MHW (ALONG WALL FACE)

APPROX. MLW 0.0

#23 Peabody Street
Rockett Management

EXISTING TIMBER FENDER PILES AND STEEL SHEETING TO BE CUT AND REMOVED AT MUDLINE

PILE SUPPORTED CONCRETE WALKWAY (SEE DETAIL THIS SHEET) (SEE SECTION SHEET 6)

6' TALL CHAIN-LINK FENCE

ANGLED PORTION OF PILE SUPPORTED WALKWAY (±50')

10'-8" WIDE REINFORCED CONCRETE WALKWAY

VEGETATED BUFFER AREA (VARIES)

FLOW
EBB
SOUTH RIVER

APPROX. MLW 0.0

2-6" Steel conduits #2347

Conduits #2348+2349

Electrolysis Prot. Cable (see plans by Mass.Elec.)

EXISTING FENCING TO BE REMOVED

PRE-CAST CONCRETE ELEVATED WALKWAY (SLOPE ±1:20) (±8+86 TO 10+00) SEE DETAIL SHEET 7

3+00 4+50 5+50 5+85.8 6+00 6+35 6+57 6+82 7+00 7+50 7+63.7 7+71.9 7+95.7 8+00 8+26.1 8+43.3 8+50 8+63.4 ±8+86 9+00 9+50 9+91 10+01

14.0 14.0

20' 15'

EXISTING CONCRETE WALL

SEE DETAIL THIS SHEET

"EAST OF CONGRESS" (PANEL #1)

BENCH/LIGHTPOLE/ TRASH RECEPTACLE LOCATION, TYP.

NEW 6' HIGH CHAIN-LINK FENCE

TRANSITION BERM TO GRADE

CONNECT NEW CHAIN-LINK FENCE TO EXISTING

MISC. STONE BARRIERS TO BE REMOVED

MHW (ALONG WALL FACE)

PROPOSED RAILING OPENING AT BRIDGE (SEE SHEET 6)

LIGHT POLE LOCATION, TYP.

±10' LANDING

GRANITE BLOCK CURB (2'x2'x6') – MAX. 3' BETWEEN BLOCK

EXISTING SIGN TO REMAIN

EXISTING LIGHT POLE

EXISTING TREE (TYP.)

Drawtenders' House (currently Salem Water Taxi)

CONGRESS STREET

MATCH LINE A-A – SEE SHEET 3

Mass. Electric Co.
Lot #34-0436

Mass. Electric Co.
Lot #34-0436

PEABODY STREET

PAVED PARKING AREA

ISSUED FOR DRAFT
NOT FOR CONSTRUCTION
DATE ISSUED: AUG. 2008
VINE ASSOCIATES, INC.

EDGE OF PROPOSED WALKWAY

PROPOSED RAILING

13'-4"

PROPOSED LIGHT POLE

PROPOSED 6' TALL CHAIN-LINK FENCE

EXISTING CONCRETE WALL TO REMAIN

EDGE OF PROPOSED WALKWAY

WALKWAY DETAIL

SCALE: 1"=5'

SOUTH RIVER

PILE SUPPORTED CONCRETE WALKWAY (SEE SECTION SHEET 6)

ANGLED PORTION OF PILE SUPPORTED WALKWAY (±50')

80'

6" (TYP)

6" (TYP)

11'-1"

11'-2" (1:12 BATTER)

11'-1"

12"x0.5" WALL STEEL PILE SPACED @12' O.C., WELDED SEAMLESS GRADE 2, CONCRETE FILLED ENTIRE LENGTH

12' O.C. @ 1:12 SLOPE (TYP)

14.6' O.C.

14.6' O.C.

1:3.5 SLOPE

14.0 14.0

3+95.5 4+16.5 4+50 4+75.6 5+00 5+50 5+85.9 6+00 6+35

NOT IN CONTRACT

TIE INTO EXISTING FENCE

EXISTING CONCRETE WALL TO REMAIN

PROPOSED LIGHT POLE

PROPOSED CHAIN-LINK FENCE

PILE SUPPORTED WALKWAY DETAIL

SCALE: 1"=20'

0 5 10
SCALE IN FEET

0 20 40
SCALE IN FEET

PROPOSED WORK PLAN

SALEM HARBORWALK
DERBY STREET TO CONGRESS STREET
SALEM, MASSACHUSETTS

Vine ASSOCIATES, INC.
372 MERRIMAC STREET NEWBURYPORT, MA 01950 tel. (978)465-1428 fax (978)465-2640
190 OLD DERBY STREET HINGHAM, MA 02043 tel. (781)749-2530 fax (781)749-2751
18 BEACH STREET MONUMENT BEACH, MA. 02553 tel. (508)743-0390 fax (508)743-0391

DES. MTT	CHK. DBV	DR. MTT	VAI FILE NO. 1117\NEW WALK
SCALE AS SHOWN	APP'D DBV	DATE AUG. 2008	SHEET 4