


SALEM, MASSACHUSETTS



CONTRACT AND SPECIFICATIONS FOR SEWER REHABILITATION PROJECT

BID # T-09

MAYOR
Kimberley Driscoll
City Hall
93 Washington Street
Salem, MA

CITY ENGINEER
David H. Knowlton, P.E.
City Hall Annex
120 Washington Street
Salem, MA

AUGUST 2017




TABLE OF CONTENTS

DIVISION 0 – GENERAL REQUIREMENTS

<u>Section</u>	<u>Title</u>
00020	Invitation to Bid
00100	Instructions to Bidders
00300	Forms for General Bid
00310	Bid Bond
00312	Statement of Bidder's Qualifications
00450	Certificate as to Corporate Bidder
00451	Certificate of Tax Compliance
00500	Agreement
00540	Notice of Award
00560	Notice to Proceed
00610	Performance Bond
00620	Payment Bond
00630	Certificate of Substantial Completion
00635	Change Order
00700	General Conditions
00800	Supplemental General Conditions
	Attachment I Massachusetts Prevailing Wage Rates
	Attachment II Massachusetts General Laws

DIVISION 1 – GENERAL REQUIREMENTS

<u>Section</u>	<u>Title</u>
01010	Summary of Work
01025	Measurement and Payment
01040	Project Coordination
01045	Cutting, Coring, and Patching
01050	Field Engineering
01060	Permits and Regulatory Requirements
01063	Miscellaneous Requirements
01080	Abbreviations and Definitions
01090	Reference Standards
01105	Rodent Control
01108	Health and Safety Procedures
01110	Environmental Protection Procedures
01200	Project Meetings
01210	General Requirements for Utility Work
01300	Submittal Procedures
01310	Construction Progress Schedules
01400	Quality Assurance
01500	Temporary Facilities and Controls
01505	Mobilization
01560	Temporary Environmental Controls
01568	Erosion Control, Sedimentation and Containment of Construction Materials

01600	Control of Materials
01610	Delivery, Storage, and Handling
01700	Contract Closeout
01710	Cleaning Up
01740	Warranties and Bonds
01850	Traffic Management

DIVISION 2 – SITEWORK

<u>Section</u>	<u>Title</u>
02010	Subsurface Investigation
02050	Demolition, Alteration, and Abandonment
02100	Site Preparation
02210	Earth Excavation, Backfill, Fill and Grading
02273	Geotextile Fabric
02498	Restoration of Disturbed Areas
02500	Paving and Surfacing
02590	Brick and Concrete Block Masonry
02622	Polyvinyl Chloride Gravity Pipe
02652	External Chemical Sealing for Manholes
02760	Pipeline Internal Inspection
02761	Bypass Flow Handling
02763	Interior Manhole Rehabilitation
02765	Sewer Line and Manhole Cleaning
02769	Cured-in-Place Pipe Liner
02770	Cured-in-Place Spot Repair

DIVISION 3 – CONCRETE

<u>Section</u>	<u>Title</u>
03315	Grout

ATTACHMENTS

Manhole Construction Detail	Map 5: Churchill Street
Maps, CCTV Photos, and Logs	Map 6: Sable and Circle Hill Road
Table of all Defects to be Repaired	Map 7: Wheatland Street
Locus Map: Sewer Rehabilitation	Map 8: Cleveland and Buchanan Road
Project Locations	Map 9: Nichols and Butler Street
Map 1: Highland Avenue and Essex	Map 10: Pope Street Easement
Street	Map 11: Washington Street
Map 2: Crescent Drive	Map 12: Buena Vista Avenue (Cross
Map 3: Liberty Street	Country Sewer)
Map 4: Oakview Avenue	

SECTION 00020

INVITATION TO BID # T-09

SEWER REHABILITATION PROJECT

Sealed Bids for the SEWER REHABILITATION PROJECT will be received by the City of Salem (the OWNER), by the City of Salem Purchasing Office, 93 Washington Street 3rd Floor, Salem, MA 01970 until 2:00 p.m. local time on September 13, 2017 at which time the Bids will be publicly opened and read aloud. Bids shall be addressed to the City of Salem Purchasing Office, 93 Washington Street 3rd Floor, Salem, MA 01970 and shall be labeled "SEWER REHABILITATION PROJECT".

The work involves the rehabilitation of sanitary sewer manhole walls, inverts, and pipe connections to eliminate infiltration from ground water and repair structural deficiencies in the system. The work includes manhole rehabilitation and sealing, pipeline cleaning and CCTV inspection, cured-in-place pipe liner of (6 to 18)-inch sewer and drain, installation of cured-in-place spot liner and pipeline spot repairs or replacement of (8 to 12)- inch sewer and drain. The estimated cost for this project is \$ 450,000.00.

Bid security in the form of a bid bond, certified checks, treasurer's or cashier's check, payable to the OWNER, is required in the amount of five percent (5%) of the total bid, in accordance with the conditions in Section 00100 – INSTRUCTIONS TO BIDDERS.

Successful bidder must furnish 100 percent Construction Performance Bond and 100 percent Construction Payment Bond, from a surety company acceptable to the Owner.

Every bid bond, every performance bond and every payment bond issued for any construction work in the Commonwealth shall be the bond of a surety company organized pursuant to Section 105 of Chapter 175 or of a surety company authorized to do business in the Commonwealth under the provisions of Section 106 of said Chapter 175 and be approved by the U. S. Department of Treasury and acceptable as sureties and reinsurers on federal bonds under Title 31 of the United States Code, sections 9304 to 9308.

Contract Documents have been prepared by New England Civil Engineering Corporation, 120 Washington Street, Suite 202E, P.O. Box 3026, Salem, MA 01970 Phone: (978) 741-7401 and may be examined and obtained at the Purchasing Office located at 93 Washington Street 3rd Floor, Salem, MA 01970, Phone: (978) 619-5695. City Hall hours are Monday through Wednesday 8:00 A.M. to 4:00 P.M., Thursday 8:00 A.M. to 7:00 P.M., and Friday 8:00 A.M. to 12:00 P.M. To obtain a copy of the Contract Documents, starting August 30, 2017 after 12:00 p.m., a \$75 refundable deposit is required. Checks shall be payable to the City of Salem. Cash will not be accepted. Drawings and other Contract Documents will be mailed, if requested, upon receipt of a street (not a P.O. Box) address and an additional check in the amount of \$25.00, payable to the City of Salem as nonrefundable postage and handling fee. Do not combine amounts into one check. Document deposits will be refunded upon return of the documents in good condition within fifteen (15) days after the opening of general bids. Drawings and Specifications must be returned to the office of the Purchasing Agent for refunds of deposits; no Drawings and Specifications will be accepted at the bid openings.

A copy of the Contract Documents is also available for examination at the City of Salem website (http://www.salem.com/Pages/SalemMA_Purchasing/index) and the Massachusetts COMMBUYS website (<https://www.commbuys.com/bso/>).

Contract time (to substantial completion of the project) is One hundred fifty (150) calendar days commencing on the effective date of the Agreement.

No Bidder may withdraw his/her Bid for a period of thirty (30) days, excluding Saturdays, Sundays, and legal holidays, after the actual date of the opening of the Bids.

Complete instructions for filing Bids are included in the Instruction to Bidders.

Minimum Wage Rates as determined by the Commissioner of Department of Labor and Industries under the provision of the Massachusetts General Laws, Chapter 149, Sections 26 to 27D, as amended, apply to this project. It is the responsibility of the Contractor, before bid opening, to request if necessary any additional information on Minimum Wage Rates for those trades people who may be employed for the proposed work under this contract.

Prevailing Wage Rates as determined by the Commissioner under the provisions of the Massachusetts General Laws, Chapter 149, sections 26 to 27H, apply to this project.

Pursuant to the applicable provisions of Chapter 149 and Chapter 30, 39M of the General Laws and over \$10,000, contracts resulting from bids issued on or after July 1, 2006, the Contractor agrees and hereby certifies that he is able to furnish labor that can work in harmony with all other elements of labor employed or to be employed on the work; that all employees to be employed at the worksite will have successfully completed a course in construction safety and health approved by the United States Occupational Safety and Health Administration that is at least 10 hours in duration at the time the employee begins work and who shall furnish documentation of successful completion of said course with the first certified payroll report for each employee; and that he will comply fully with all laws and regulations applicable to awards made subject to section 44A.

The bidding and award of the Contract shall be in full compliance with Sections 39M inclusive of Chapter 30 of the General Laws of the Commonwealth of Massachusetts as last revised.

The OWNER reserves the right to reject any or all bids and to determine which bid is, in the OWNER'S judgment, the lowest responsive bid of a bidder or group of bidders. The OWNER also reserves the right to waive any informality in any bid and to delete certain items listed in the bid as set forth therein.

City of Salem, Massachusetts

David H. Knowlton, P.E.
Director of Public Services and City Engineer

END OF SECTION 00020

SECTION 00100

INSTRUCTIONS TO BIDDERS

- Article 1. Receipt and Opening of Bids
- Article 2. Deposit on Drawings and Documents
- Article 3. Ability and Experience of Bidder
- Article 4. Information Not Guaranteed
- Article 5. Borings
- Article 6. Easements
- Article 7. Other Contracts
- Article 8. Bidders to Investigate
- Article 9. Questions Regarding Drawings and Documents
- Article 10. Blank Form for Bid
- Article 11. Alternates
- Article 12. Bid Security
- Article 13. Withdrawal of Bids
- Article 14. Right to Reject Bids
- Article 15. Comparison of Bids
- Article 16. Reduction in Scope of Work
- Article 17. Contract Bonds
- Article 18. Execution of Agreement
- Article 19. Insurance Certificates
- Article 20. Massachusetts Sales and Use Tax
- Article 21. Massachusetts Wage Rates
- Article 30. Utility Underground Plant Damage Prevention System
- Article 31. Competitive Bidding

ARTICLE 1. RECEIPT AND OPENING OF BIDS

- 1.1 Sealed Bids for the work of this Contract will be received at the time and place indicated in the Invitation to Bid.
- 1.2 OWNER may consider informal any Bid not prepared and submitted in accordance with the provisions hereof.
- 1.3 Bidders are cautioned that it is the responsibility of each individual bidder to assure that his bid is in the possession of the responsible official or his designated alternate prior to the stated time and at the place of the Bid Opening. Owner is not responsible for bids delayed by mail and/or delivery services, of any nature.
- 1.4 If forwarded by mail, the sealed envelope containing the bid should be addressed to Purchasing Agent, at 93 Washington Street 3rd Floor, Salem, MA 01970

ARTICLE 2. DEPOSIT ON DRAWINGS AND DOCUMENTS

- 2.1 Upon award of the Contract, the Contractor will be provided with one (1) reduced copy of drawings and one full size set of reproducibles from which he can make, at his own expense, full size prints necessary for execution of the Work.

ARTICLE 3. ABILITY AND EXPERIENCE OF BIDDER

- 3.1 No award will be made to any bidder who cannot satisfy the Owner that he has sufficient ability and experience in this class of work and sufficient capital and plant to enable him to prosecute and complete the Work successfully within the time named. The Owner's decision or judgment on these matters shall be final, conclusive, and binding.
- 3.2 The Owner may make such investigations as it deems necessary, and the Bidder shall furnish to the Owner, under oath if so required, all such information and data for this purpose as the Owner may request.

ARTICLE 4. INFORMATION NOT GUARANTEED

- 4.1 All information given on the Drawings or in the other Contract Documents relating to subsurface and other conditions, natural phenomena, existing pipes, and other structures is from the best sources at present available to the Owner. All such information is furnished only for the information and convenience of bidders and is not guaranteed.
- 4.2 It is agreed and understood that the Owner does not warrant or guarantee that the subsurface or other conditions, natural phenomena, existing pipes or other structures encountered during construction will be the same as those indicated on the Drawings or in the other Contract Documents.
- 4.3 It is agreed further and understood that no bidder nor Contractor shall use or be entitled to use any of the information made available to him or obtained in any examination made by him in any manner as a basis of or ground for any claim or demand against the Owner or the Engineer, arising from or by reason of any variance which may exist between the information made available and the actual subsurface or other conditions, natural phenomena, existing pipes or

other structures actually encountered during the construction work, except as may otherwise be expressly provided for in the Contract Documents.

ARTICLE 5. SUBSURFACE INVESTIGATION

- 5.1 Subsurface investigations have not been completed for this project. The Contractor shall conduct subsurface investigations at the locations indicated on the drawings, and at all locations of known or suspected utility crossings prior to beginning installation and layout of proposed utilities.
- 5.2 The Contractor shall be aware that the existing soil conditions and groundwater level are not known. Contractor shall assume that construction dewatering due to seasonal and tidally influenced groundwater, removal and disposal of unsuitable soils and rock excavation will be required during construction.

ARTICLE 6. EASEMENTS

- 6.1 On all lands, the Contractor has no rights unless he obtains them from the proper parties.
- 6.2 The Contractor shall not work on property requiring an easement until the Owner has obtained the necessary easement.
- 6.3 The Contractor shall have no claim for additional compensation or damage on account of any delay in obtaining the necessary easements.

ARTICLE 7. OTHER CONTRACTS

- 7.1 Contractor shall be aware that gas utility replacement is ongoing and will continue throughout the contract period by National Grid or their contractor. Contractor shall coordinate with National Grid to allow them access to the project site during the contract period and modify layout of proposed work to avoid conflicts with new and existing gas utilities.
- 7.2 It is essential that all parties interested in the project cooperate to the end that the entire project will be brought to a successful conclusion as rapidly as possible, but the Owner cannot guarantee that no interference or delay will be caused thereby. Interference and delay resulting from such cooperation shall not be the basis of claims against the Owner.

ARTICLE 8. BIDDERS TO INVESTIGATE

- 8.1 Bidders must satisfy themselves by personal examination of the site of the Work and by such other means as they may wish, as to the actual conditions there existing, the character and requirements of the Work, the difficulties attendant upon its execution, and the accuracy of all estimated quantities stated in the Bid.

ARTICLE 9. QUESTIONS REGARDING DRAWINGS AND DOCUMENTS

- 9.1 In general, no answer will be given to prospective bidders in reply to an oral question if the question involves an interpretation of the intent or meaning of the Drawings or other Contract Documents, or the equality or use of products or methods other than those designated or described on the Drawings or in the Specifications. Any information given to bidders other than by means of the Drawings and other Contract Documents, including Addenda, as described below, is given informally, for information and the convenience of the bidder only and is not

guaranteed. The bidder agrees that such information shall not be used as the basis of nor shall the giving of any such information entitle the bidder to assert any claim or demand against the Owner or the Engineer on account thereof.

- 9.2 To receive consideration, such questions shall be submitted in writing to Purchasing Agent, at 93 Washington Street 3rd Floor, Salem, MA 01970 at least seven days before the established date for receipt of Bids. The Engineer will neither approve nor disapprove particular products prior to the opening of Bids; such products will be considered when offered by the Contractor for incorporation into the Work, in accordance with the requirements of Section 01300 - SUBMITTAL PROCEDURES.
- 9.3 The Engineer will set forth as Addenda, which shall become a part of the Contract Documents, such questions received as above provided as in his sole judgment are appropriate or necessary and his decision regarding each. At least five days prior to the receipt of Bids, he will send a copy of these Addenda to those prospective bidders and parties known to have taken out sets of the Drawings and Contract Documents.
- 9.4 The Contractor agrees to use and base his/her bid on the products and methods designated or described in the Specifications as amended by the Addenda.

ARTICLE 10. BLANK FORM FOR BID

- 10.1 All bids must be upon the blank form for Bid annexed hereto, state the proposed price of each item of the Work, both in words and in figures, and be signed by the bidder with his business address and place of residence.

ARTICLE 11. ALTERNATES

- 11.1 Alternate Bids are not required in this contract.

ARTICLE 12. BID SECURITY

- 12.1 Each bid must be accompanied by a bid deposit in the form of a certified check on, or a treasurer's or cashier's check issued by, a responsible bank or trust company and payable to the order of the City of Salem or by a bid bond prepared on the form of BID BOND (see Section 00310) attached hereto duly executed and acknowledged by the bidder, as Principal, and by a surety company qualified to do business in the Commonwealth of Massachusetts and satisfactory to the Owner, as Surety. The bid deposit shall be in the sum of 5 percent of the value of the Bid and shall be enclosed in the sealed envelope containing the Bid.
- 12.2 Every bid bond, every performance bond and every payment bond issued for any construction work in the Commonwealth shall be the bond of a surety company organized pursuant to Section 105 of Chapter 175 or of a surety company authorized to do business in the Commonwealth under the provisions of Section 106 of said Chapter 175 and be approved by the U. S. Department of Treasury and acceptable as sureties and reinsurers on federal bonds under Title 31 of the United States Code, sections 9304 to 9308.
- 12.3 Each such check or bid bond amount may be held by the Owner as security for the fulfillment of the bidder's agreements as hereinabove set forth and as set forth in the BID. Should the bidder

fail to fulfill such agreements the bid check shall become the property of the Owner or if a bid bond was furnished the bid bond shall become payable to the Owner, as liquidated damages; otherwise, the bid check shall be returned to the bidder as hereinafter provided, or if the security is a bid bond, the bid bond shall become null and void.

- 12.4 Bid securities will be returned to all except the three lowest bidders within five days, Sundays and legal holidays excluded, after the opening of Bids, and to the three lowest bidders within five days, Sundays and legal holidays excluded, after the Owner and the accepted bidder have executed the AGREEMENT. In the event that the AGREEMENT has not been executed by both the accepted bidder and the Owner the bid security will be returned promptly to any bidder who has not been notified of the acceptance of his Bid.
- 12.5 None of the three lowest Bids shall be deemed rejected, notwithstanding acceptance of any BID, until the AGREEMENT has been executed by both the Owner and the accepted bidder.

ARTICLE 13. WITHDRAWAL OF BIDS

- 13.1 Except as hereinafter in this subsection otherwise expressly provided, once his Bid is submitted and received by the Owner for consideration and comparison with other bids similarly submitted, the bidder agrees that he may not and will not withdraw it within thirty (30) days excluding Saturdays, Sundays and legal holidays after the actual date of the opening of Bids.
- 13.2 Upon proper written request and identification, Bids may be withdrawn only as follows:
1. At any time prior to the designated time for the opening of Bids.
 2. Provided the Bid has not theretofore been accepted by the Owner, at any time subsequent to the expiration of the period during which the bidder has agreed not to withdraw his Bid.
- 13.3 Unless a Bid is withdrawn as provided above, the bidder agrees that it shall be deemed open for acceptance until the AGREEMENT has been executed by both parties thereto or until the Owner returns his Bid deposit. Notice of acceptance of a Bid shall not constitute rejection of any other Bid.

ARTICLE 14. RIGHT TO REJECT BIDS

- 14.1 The Owner reserves the right to reject any or all Bids if the Bid cost exceeds available funds approved by the City of Salem.
- 14.2 The Owner reserves the right to reject any or all Bids, should the Owner deem it to be in the public interest to do so.
- 14.3 The Owner may reject Bids which in its sole judgment are incomplete, conditional, obscure or not responsive or which contain additions not called for, erasures not properly initialed, alterations, or similar irregularities, or the Owner may waive such omissions, conditions or irregularities.

ARTICLE 15. COMPARISON OF BIDS

- 15.1 Bids will be compared on the basis of the quantities and unit and lump-sum prices stated in the BID.
- 15.2 In the event that there is a discrepancy in the Bid between the lump sum or unit prices written in words and figures, the prices written in words shall govern.
- 15.3 The Owner agrees to examine and consider each Bid submitted in consideration of the Bidder's agreements, as hereinabove set forth and as set forth in the BID.

ARTICLE 16. REDUCTION IN SCOPE OF WORK

- 16.1 The Owner reserves the right to decrease the scope of the work to be done under this Contract and to delete any work in order to bring the cost within available funds or for any other reason in the best interest of the Owner. To this end, the Owner reserves the right to reduce the quantity of any items and/or delete entire items as set forth in the BID at any time during the progress of the work. The Owner further reserves the right, at any time during the progress of the work, to restore all or part of any items previously deleted or reduced. Exercise by the Owner of the above rights shall not constitute any ground or basis of claim for damages or for anticipated profits on the work reduced or deleted.
- 16.2 The work that may be reduced or deleted specifically includes, but is limited to:

ARTICLE 17. CONTRACT BONDS

- 17.1 The Bidder whose Bid is accepted agrees to furnish the Contract Bonds in the forms which follow in Section 00610 – PERFORMANCE BOND and Section 00620 – PAYMENT BOND, each in the sum of the full amount of the Contract and duly executed by the said bidder as Principal and by a surety company qualified to do business under the laws of the Commonwealth of Massachusetts and satisfactory to the Owner, as Surety, for the faithful performance of the Contract and payment for labor and materials. The premiums for such Bonds shall be paid by the Contractor.
- 17.2 Every bid bond, every performance bond and every payment bond issued for any construction work in the Commonwealth shall be the bond of a surety company organized pursuant to Section 105 of Chapter 175 or of a surety company authorized to do business in the Commonwealth under the provisions of Section 106 of said Chapter 175 and be approved by the U. S. Department of Treasury and acceptable as sureties and reinsurers on federal bonds under Title 31 of the United States Code, sections 9304 to 9308.

ARTICLE 18. EXECUTION OF AGREEMENT

- 18.1 The Bidder whose Bid is accepted will be required and agrees to duly execute the AGREEMENT and furnish the required CONTRACT BONDS within the time limit stated in the BID after notification that the AGREEMENT is ready for signature.
- 18.2 The Bidder to whom the Contract is awarded shall comply with the provisions of Chapter 30, Section 39R of the General Laws of Massachusetts as amended to date; and as provided therein shall, prior to execution of the contract, file a statement of management on internal accounting controls and an audited financial statement for the most recent completed fiscal year. See Attachment II – MASSACHUSETTS GENERAL LAWS.

ARTICLE 19. INSURANCE CERTIFICATES

- 19.1 The Contractor will not be permitted to start any construction work until he has submitted certificates covering all insurances called for under Article 2.05 of Section 00800 – SUPPLEMENTARY CONDITIONS.

ARTICLE 20. MASSACHUSETTS SALES AND USE TAX

- 20.1 Materials and equipment purchased for permanent installation in this project will be exempt from the Massachusetts Sales and Use Tax. The exemption certificate number will be furnished to the Contractor. Each bidder shall take this exemption into account in calculating his bid for the work.

ARTICLE 21. MASSACHUSETTS WAGE RATES

- 21.1 Massachusetts Wage Rates as established pursuant to the provisions of M.G.L. Chapter 149 Section 26-27G apply to this project. The Massachusetts Wage Determination is attached to these specifications. It is the responsibility of the Contractor, before bid opening, to request, if necessary, any additional information on Massachusetts Wage Rates for those trades people who are not covered by the applicable Massachusetts Wage Decision, but who may be employed for the proposed work under this contract.

ARTICLE 30. UTILITY UNDERGROUND PLANT DAMAGE PREVENTION SYSTEM

- 30.1 All excavations within public or private ways are subject to the requirements of Massachusetts General Law, Chapter 82, Section 40 included in Part II of the Supplementary Conditions.

ARTICLE 31. COMPETITIVE BIDDING

- 31.1 The bidding and award of the Contract shall be in full compliance with Section 39 M inclusive of Chapter 30 of the General Laws of the Commonwealth of Massachusetts as last revised.

END OF SECTION 00100

SECTION 00300

FORMS FOR GENERAL BID

To the City of Salem, herein called the Owner, acting by and through its Purchasing Agent, for the SEWER REHABILITATION PROJECT.

The Undersigned, as bidder, herein referred to as singular and masculine, declares as follows:

- (1) The only parties interested in this BID as Principals are named herein;
- (2) This BID is made without collusion with any other person, firm, or corporation;
- (3) No officer, agent, or employee of the Owner is directly or indirectly interested in this BID;
- (4) He has carefully examined the site of the proposed Work and fully informed and satisfied himself as to the conditions there existing, the character and requirements of the proposed Work, the difficulties attendant upon its execution and the accuracy of all estimated quantities stated in this BID, and he has carefully read and examined the Drawings, the annexed proposed AGREEMENT and the Specifications and other Contract Documents therein referred to and knows and understands the terms and provisions thereof;
- (5) He understands that information relative to subsurface and other conditions, natural phenomena, existing pipes and other structures (surface and/or subsurface) has been furnished only for his information and convenience without any warranty or guarantee, expressed or implied, that the subsurface and/or other conditions, natural phenomena, existing pipes and other structures (surface and/or subsurface) actually encountered will be the same as those shown on the Drawings or in any of the other Contract Documents and he agrees that he shall not use or be entitled to use any such information made available to him through the Contract Documents or otherwise or obtained by him in his own examination of the site, as a basis of or ground for any claim against the Owner or the Engineer arising from or by reason of any variance which may exist between the aforesaid information made available to or acquired by him and the subsurface and/or other conditions, natural phenomena, existing pipes and other structures (surface and/or subsurface) actually encountered during the construction work, and he has made due allowance therefore in this BID;
- (6) and he understands that the quantities of work tabulated in this BID or indicated on the Drawings or in the Specifications or other Contract Documents are only approximate and are subject to increase or decrease as deemed necessary by the Engineer; and he agrees that, if this BID is accepted he will contract with the Owner, as provided in the copy of the Contract Documents deposited in the office of the Engineer, this BID form being part of said Contract Documents, and that he will perform all the work and furnish all the materials and equipment, and provide all labor, services, plant, machinery, apparatus, appliances, tools, supplies and all other things required by the Contract Documents in the manner and within the time therein prescribed and according to the requirements of the

Engineer as therein set forth, and that he will take in full payment therefore the lump sum or unit price applicable to each item of the Work as stated in the schedule below.

- (7) and he understands that the Owner reserves the right to decrease the scope of the work to be done under this Contract and to delete any work in order to bring the cost within available funds or for any other reason in the best interest of the Owner. To this end, the Owner reserves the right to reduce the quantity of any items and/or delete entire items as set forth in the BID, either prior to executing the Contract or at any time during the progress of the work. The Owner further reserves the right, at any time during the progress of the work, to restore all or part of any items previously deleted or reduced. Exercise by the Owner of the above rights shall not constitute any ground or basis of claim for damages or for anticipated profits on the work reduced or deleted.

- (8) The work that may be reduced or deleted specifically includes, but is limited to:

Item No. 5: Furnish and Install New (6 to 8)-inch PVC Sewer or Drain Pipe or Service, Including Drop Connection, All Depths

Item No. 6: Furnish and Install New (10 to 15)-inch PVC Sewer or Drain Pipe, All Depths

Item No. 7: Furnish and Install New 18-inch PVC Sewer or Drain Pipe, All Depths

Item No. 14: Heavy Cleaning of (6 to 8)-inch Sewer and Drain Pipe

Item No. 15: Heavy Cleaning of (10 to 18)-inch Sewer and Drain Pipe

Item No. 19: Furnish and Install Cured-in-Place Spot Liner in Existing (6 to 8)-inch Sewer or Drain Pipe (minimum 4-foot length)

Item No. 20: Furnish and Install Cured-in-Place Spot Liner in Existing (10 to 15)-inch Sewer or Drain Pipe (minimum 4-foot length)

Item No. 21: Furnish and Install Cured-in-Place Spot Liner in Existing 18-inch Sewer or Drain Pipe (minimum 4-foot length)

(Note: Bidders must bid on each item. All entries in the entire BID must be made clearly and in ink. In case of discrepancy between prices in writing and in figures; the writing shall govern. In case of discrepancy between the product obtained by multiplying the estimated quantity by the unit price, and the extended amount, the product obtained shall govern. In case of discrepancy between total of extended amounts and total amount of bid stated, total of items shall govern. Use the pages in this document when submitting proposal and submit contract documents intact).

Refer to Section 01025 - MEASUREMENT AND PAYMENT for Item Descriptions.

Base Bid:

Item No.	Unit	Description	Estimated Quantity	Unit Price (In Figures)	Extended Total (In Figures)
1	LS	Mobilization/Demobilization (Not to Exceed 5% of Total Bid) _____ Dollars _____ Cents Per Lump Sum	1	\$ _____	\$ _____
2	CY	Rock Excavation (Minimum) _____ Sixty _____ Dollars _____ Zero _____ Cents Per Cubic Yard	25	\$ 60.00	\$1,500.00
2A	CY	Rock Excavation (Additional) _____ Dollars _____ Cents Per Cubic Yard	25	\$ _____	
3	CY	Exploratory Excavation _____ Dollars _____ Cents Per Cubic Yard	25	\$ _____	\$ _____
4	CY	Earth Excavation and Refill Below Normal Depth _____ Dollars _____ Cents Per Cubic Yard	100	\$ _____	\$ _____
5	LF	Furnish and Install New (6 to 8)-inch PVC Sewer or Drain Pipe or Service, including drop connection, All Depths _____ Dollars _____ Cents Per Linear Foot	125	\$ _____	\$ _____

Item No.	Unit	Description	Estimated Quantity	Unit Price (In Figures)	Extended Total (In Figures)
6	LF	Furnish and Install New (10 to 15)-inch PVC Sewer or Drain Pipe, All Depths <div>_____ Dollars</div> <div>_____ Cents</div> Per Linear Foot	50	\$ _____	\$ _____
7	LF	Furnish and Install New 18-inch PVC Sewer or Drain Pipe, All Depths <div>_____ Dollars</div> <div>_____ Cents</div> Per Linear Foot	5	\$ _____	\$ _____
8	EA	Furnish and Install (6 to 8)-inch Tee Fittings, Connect to Existing (4 to 8)-inch Sewer Service Pipe, All Depths <div>_____ Dollars</div> <div>_____ Cents</div> Per Each	12	\$ _____	\$ _____
9	EA	Furnish and Install (10 to 15)-inch Tee Fittings, Connect to Existing (4 to 8)-inch Sewer Service Pipe, All Depths <div>_____ Dollars</div> <div>_____ Cents</div> Per Each	2	\$ _____	\$ _____
10	EA	Furnish and Install 18-inch Tee Fittings, Connect to Existing (4 to 8)-inch Sewer Service Pipe, All Depths <div>_____ Dollars</div> <div>_____ Cents</div> Per Each	1	\$ _____	\$ _____
11	LF	CCTV Inspection of Service Laterals from Trench or Main, All Sizes <div>_____ Dollars</div> <div>_____ Cents</div> Per Linear Foot	1000	\$ _____	\$ _____

Item No.	Unit	Description	Estimated Quantity	Unit Price (In Figures)	Extended Total (In Figures)
12	LF	Light Cleaning and CCTV Inspection of (6 to 8)-inch Sewer and Drain Pipe _____ Dollars _____ Cents Per Linear Foot	4000	\$ _____	\$ _____
13	LF	Light Cleaning and CCTV Inspection of (10 to 18)-inch Sewer and Drain Pipe _____ Dollars _____ Cents Per Linear Foot	2000	\$ _____	\$ _____
14	LF	Heavy Cleaning of (6 to 8)-inch Sewer and Drain Pipe _____ Dollars _____ Cents Per Linear Foot	1000	\$ _____	\$ _____
15	LF	Heavy Cleaning of (10 to 18)-inch Sewer and Drain Pipe _____ Dollars _____ Cents Per Linear Foot	500	\$ _____	\$ _____
16	LF	Furnish and Install Cured-in-Place Pipe Liner Existing (8 to 10)-inch Sewer or Drain Pipe _____ Dollars _____ Cents Per Linear Foot	1350	\$ _____	\$ _____
17	LF	Furnish and Install Cured-in-Place Pipe Liner in Existing (12 to 15)-inch Sewer or Drain Pipe _____ Dollars _____ Cents Per Linear Foot	800	\$ _____	\$ _____

Item No.	Unit	Description	Estimated Quantity	Unit Price (In Figures)	Extended Total (In Figures)
18	LF	Furnish and Install Cured-in-Place Pipe Liner in Existing 18-inch and non-round Sewer or Drain Pipe <div>_____ Dollars</div> <div>_____ Cents</div> Per Linear Foot	550	\$ _____	\$ _____
19	LF	Furnish and Install Cured-in-Place Spot Liner in Existing (6 to 8)-inch Sewer or Drain Pipe (minimum 4-foot length) <div>_____ Dollars</div> <div>_____ Cents</div> Per Linear Foot	100	\$ _____	\$ _____
20	LF	Furnish and Install Cured-in-Place Spot Liner in Existing (10 to 15)-inch Sewer or Drain Pipe (minimum 4-foot length) <div>_____ Dollars</div> <div>_____ Cents</div> Per Linear Foot	25	\$ _____	\$ _____
21	LF	Furnish and Install Cured-in-Place Spot Liner in Existing 18-inch Sewer or Drain Pipe (minimum 4-foot length) <div>_____ Dollars</div> <div>_____ Cents</div> Per Linear Foot	4	\$ _____	\$ _____
22	VF	Manhole Rehabilitation, Clean, Grout, Waterproof <div>_____ Dollars</div> <div>_____ Cents</div> Per Vertical Foot	15	\$ _____	\$ _____
23	EA	Manhole Rehabilitation, Replace Frame and Cover <div>_____ Dollars</div> <div>_____ Cents</div> Per Each	2	\$ _____	\$ _____

Item No.	Unit	Description	Estimated Quantity	Unit Price (In Figures)	Extended Total (In Figures)
24	EA	Manhole Rehabilitation, Build/Rebuild Invert and Bench _____ Dollars _____ Cents Per Each	13	\$ _____	\$ _____
25	VF	Reconstruct Sewer or Drain Structures _____ Dollars _____ Cents Per Vertical Foot	8	\$ _____	\$ _____
26	EA	Furnish and Deliver New Manhole or Catch Basin Castings _____ Dollars _____ Cents Per Each	2	\$ _____	\$ _____
27	EA	Furnish and Install Brick and Mortar Plugs _____ Dollars _____ Cents Per Each	2	\$ _____	\$ _____
28	SY	2-inch Temporary Bituminous Concrete Pavement _____ Dollars _____ Cents Per Square Yard	100	\$ _____	\$ _____
29	SY	4-inch Permanent Bituminous Concrete Pavement in Trenches _____ Dollars _____ Cents Per Square Yard	100	\$ _____	\$ _____

Total Amount of Base Bid (Items 1 through 29) inclusive:

\$

(Amount in figures)

(Amount in words)

Basis of award will be done on the prices bid for Base Bid (Items 1-29 inclusive).

The undersigned agrees that for extra work, if any, will be performed in accordance with Article 10 of the General Conditions of the Contract and will be paid for in accordance with Article 11 of the General Conditions of the Contract.

The bid security accompanying this BID shall be in the amount of 5 percent of the BID.

The undersigned must furnish 100 percent Construction Performance Bond and 100 percent Construction Payment Bond with a surety company acceptable to the Owner.

The bidding and award of the contract will be in full compliance with Section 39M inclusive of Chapter 30 of the General Laws of the Commonwealth of Massachusetts as last revised.

If this BID is accepted by the Owner, the undersigned agrees to complete the entire work provided to be done under the Contract. The contract to substantial completion (of all work including final paving) is 150 calendar days. Liquidated damages for each calendar day of delay shall be \$1,000.00 as stipulated in the AGREEMENT.

As provided in the Section 00100 – INSTRUCTIONS TO BIDDERS, the bidder hereby agrees that he will not withdraw this BID within thirty (30) days, excluding Saturdays, Sundays and legal holidays after the actual date of the opening of Bids and that, if the Owner shall accept this BID, the bidder will duly execute and acknowledge the AGREEMENT and furnish, duly executed and acknowledged, the required CONTRACT BONDS within ten (10) days after notification that the AGREEMENT and other Contract Documents are ready for signature.

The time period for holding bids where Federal approval is not required is thirty (30) days, Saturdays, Sundays and legal holidays excluded, after the opening of bids, and where Federal approval is required, the time period for holding bids is thirty (30) days, Saturdays, Sundays and holidays excluded after Federal approval.

Should the bidder fail to fulfill any of his agreements as hereinabove set forth, the Owner shall have the right to retain as liquidated damages the amount of the bid check or cash which shall become the Owner's property. If a bid bond was given, it is agreed that the amount thereof shall be paid as liquidated damages to the Owner by the Surety.

This BID includes Addenda number _____ (To be filled in by Bidder if Addenda are issued.)

The bidder, by submittal of this BID, agrees with the Owner that the amount of the bid security deposited with this BID fairly and reasonably represents the amount of damages the Owner will suffer due to the failure of the bidder to fulfill his agreements as above provided.

The undersigned certifies pursuant to M.G.L. Ch. 62C, Sec. 49A, under the penalties of perjury that I, to the best of my knowledge and belief, have filed all State tax returns and paid all State taxes required under law.

The undersigned certifies under penalties of perjury that this bid or proposal has been made and submitted in good faith and without collusion or fraud with any other person. As used in this certification, the word "person" shall mean any natural person, business, partnership, corporation, union, committee, club, or other organization, entity, or group of individual.

(SEAL)_____L.S.
(Name of Bidder)

By _____
(Signature and title of authorized representative)

(Telephone)

(Business address)

(Fax Number)

(City and State)

Date _____

The bidder is a corporation incorporated in the State (or Commonwealth) of _____ - a partnership - an individual. (Bidder must add and delete as necessary to make this sentence read correctly.)

(Note: If the bidder is a corporation, affix corporate seal and give below the names of its president, treasurer, and general manager if any; if a partnership, give full names and residential addresses of all partners; and if an individual, give residential address if different from business address.)

The required names and addresses of all persons interested in the foregoing Bid, as Principals, are as follows:

The bidder is requested to provide information on a minimum of three (3) projects similar to that included in the proposed Contract he has done and to give references that will enable the Owner to judge his experience, skill, and business standing.

Project Name	Contact Name	Title	Telephone No.

Add supplementary page if necessary.

CERTIFICATION OF BID

Pursuant to M.G.L. Ch. 62C, s 49A, I certify under the penalties of perjury that I, to my best knowledge and belief, have filed all state tax returns and paid all State Taxes Required under law.

The bidder by signing the bid, or contract, under penalties of perjury certifies (1) that he is able to furnish labor that can work in harmony with other elements of labor employed or to be employed on the work site; (2) that all employees to be employed at the worksite will have successfully completed a course in construction safety and health approved by the United States Occupational Safety and Health Administration that is at least 10 hours in duration at the time the employee begins work and who shall furnish documentation of successful completion of said course with the first certified payroll report for each employee; and (3) that all employees to be employed in the work subject to this bid have successfully completed a course in construction safety and health approved by the United States Occupational Safety and Health Administration that is at least 10 hours in duration. Any employee found on a worksite subject to this section without documentation of successful completion of a course in construction safety and health approved by the United States Occupational Safety and Health Administration that is at least 10 hours in duration shall be subject to immediate removal.

Ch. 30, s39 (a) The undersigned certifies under penalties of perjury that this bid is in all respects bonafide, fair and made without collusion or fraud with any other person. As use in this paragraph the "person" shall mean any natural person, joint venture, partnership, corporation or other business or legal entity.

Certification undersigned is not presently debarred from doing public construction work in the Commonwealth of Massachusetts under the provision of Section Twenty-Nine F of Chapter Twenty-Nine, or any other applicable debarment provisions of any other Chapter of the General Laws or any rule or regulation promulgated thereunder.

_____ (Date)	_____ (Name of General Bidder)
By: _____ (Signature)	
_____ (Printed Title & Name of Person Signing Bid)	
_____ (Business Address)	_____ (City, State, Zip)

CONTRACTOR'S CERTIFICATION

A contractor will not be eligible for award of a contract unless such contractor has submitted the following certification, which is deemed a part of the resulting contract:

CONTRACTOR'S CERTIFICATION

Name of the General Contractor

certifies that:

1. It intends to use the following listed construction trades in the work under contract:

2. and will obtain from each of its subcontractors and submit to the contracting or administering agency prior to the award of any subcontract under this contract the subcontractor's certification required by these bid conditions.

Signature of Authorized
Representative or Contractor

SUBCONTRACTOR'S CERTIFICATION

Prior to the award of any subcontract, regardless of tier, the prospective subcontractor must execute and submit to the General Contractor the following certification, which will be deemed a part of the resulting subcontract:

SUBCONTRACTOR'S CERTIFICATION

Name of the Subcontractor

certifies that:

1. It intends to use the following construction trades in the work under the contract:

2. and will obtain from each of its subcontractors prior to the award of any subcontract under this contract the subcontractor’s certification required by these bid conditions.

Signature of Authorized Representative of Subcontractor

END OF SECTION 00300

SECTION 00310

BID BOND

KNOW ALL MEN BY THESE PRESENTS, that we, the undersigned _____
_____, as Principal, and
_____, as Surety, are hereby held and
firmly bound unto the City of Salem, a municipality in the Commonwealth of Massachusetts in the penal
sum of _____ Dollars (\$ _____), for the payment of which, well
and truly to be made, we hereby jointly and severally bind ourselves, our heirs, executors, administrators,
successors and assigns. Signed this _____ day of _____, _____. THE CONDITION
OF THE ABOVE OBLIGATION is such that whereas the Principal has submitted to the City of Salem,
Massachusetts, a certain bid attached hereto and hereby made a part hereof to enter into a contract in
writing for the "SEWER REHABILITATION PROJECT," for the City of Salem, Massachusetts.

NOW THEREFORE,

- a. If said Bid shall be rejected, or
- b. If said Bid shall be accepted and the Principal shall execute and deliver a contract in the
Form of Contract attached hereto (properly completed in accordance with said Bid) and shall
furnish a bond for its faithful performance of said Contract, and for the payment of all
persons performing labor or furnishing materials in connection therewith, and shall in all
other respects perform the agreement created by the acceptance of said Bid,

then this obligation shall be void, otherwise the same shall remain in force and effect; it being expressly
understood and agreed that the liability of the Surety for any and all claims hereunder shall in no event
exceed the penal amount of this obligation as herein stated.

The Surety, for value received, hereby stipulates and agrees that the obligations of said Surety and its bond shall in no way be impaired or affected by any extension of the time within which the Owner may accept such bid; and said Surety does hereby waive notice of any such extension.

IN WITNESS WHEREOF, the Principal and the Surety have hereunto set their hands and seals, and such of them as are corporations have caused their corporate seals to be hereto affixed and these presents to be signed by their proper officers, the day and year first set forth above.

SEAL

(Principal)

By _____

SEAL

(Surety)

Address _____

Telephone No. _____

Fax No. _____

END OF SECTION 00310

SECTION 00312
STATEMENT OF BIDDER'S QUALIFICATIONS

A bidder will not be eligible for award of the contract unless such bidder has submitted the following statement of qualifications for the prime contractor and any proposed sub-contractor(s) and both the prime contractor and any proposed sub-contractor(s) meets the minimum requirements as described herein.

All questions must be answered and the data given must be clear and comprehensive. This statement must be notarized. If necessary, questions may be answered on separate attached sheets. The Bidder may submit any additional information it desires.

1. The names, titles, residences and Social Security numbers of all persons and parties interested in this Proposal as principals are as follows:

Note: Give the first and last names in full. In the case of corporation, give names of officers and directors; in the case of a partnership, give names of all partners.

IMPORTANT: Be sure residences and Social Security Numbers are listed below.

Name	Title	Home Address	Social Security #
<hr/>			
<hr/>			
<hr/>			
<hr/>			
<hr/>			
<hr/>			

2. When organized.

3. If a corporation, where incorporated.

Bidder's Name _____

4. How many years have you been engaged in the pipeline sealing and rehabilitation, manhole rehabilitation and waterproofing, and storm and sanitary sewer pipe replacement, under your present firm or trade name?

5. What projects similar to this one is your organization currently performing? Provide the following information:

Name and Address of Owner for Whom Work is Being Done	Whether Work Being Done as Contractor or Sub-contractor	Description of Work	Approximate Amount of Contract	Approximate Completion Date of Work
---	---	---------------------	--------------------------------	-------------------------------------

6. **Minimum Requirements for contract award eligibility:**

Provide specific information (size and complexity), including referral and contact information, for at least three (3) similar projects completed by the prime contractor (and at least three (3) similar projects completed by any proposed sub-contractor) within the past five years, that involved 1) interior manhole rehabilitation and waterproofing; 2) cured in placed lining (8 to 18)-inch diameter of a least 100-feet; 3) cured in place spot liner (6 to18)-inch; 4) Sewer or drain replacement at least 10-feet length; and 5) coordination with public and private utilities without significant delays to project progress.

Bidder's Name _____

-
7. What is the general nature of work normally performed by your company, what is your annual gross revenue (last year and projected for the next two years), what is your total current revenue commitment (in dollars)?
-
-

8. Has your present organization ever failed to complete any work awarded to it? If so, state when, where, and why.
-
-
-

9. Has your present organization ever defaulted on a contract? If so, state when, where, and why.
-
-
-

10. Submit a preliminary project schedule.

11. Describe equipment available for the performance of this contract by setting forth make, model and year, size, number, and type for each such piece of equipment (a) owned, (b) currently rented or (c) to be rented. Bidder must set forth description of all equipment it plans to use whether rented or owned.

(a) Owned

Bidder's Name _____

CITY OF SALEM

SEWER REHABILITATION PROJECT

STATEMENT OF BIDDER'S

QUALIFICATIONS

00312-3

(b) Rented

12. Background and experience of the principal member of your organization, including the officers.

13. Who will be the contractor's on site project manager? State such person's qualifications. Also list names of employees who will be participating in this contract and their qualifications (years of experience, etc.).

Bidder's Name _____

14. Who will be the contractor's full time on-site superintendent? Submit such person's resume for review by Owner/Engineer. Also, list names of employees who will be participating in this contract and their qualifications (years of experience, etc.).

15. Will you fill out a detailed financial statement and furnish any other information that may be required by the City of Salem, Massachusetts?

16. Employer Identification No. (Treasurer's No.)

17. Name, Signature, Social Security number and Title of officer preparing this proposal.

Name_____

Signature_____

Social Security Number_____Title_____

18. The undersigned hereby authorizes and requests any person, firm or corporation to furnish any information requested by the City of Salem Engineering Department, in verification of the recitals comprising this Statement of Bidder's Qualifications.

Dated at _____ this _____ day of _____, 20____
Bidder's Name _____

(Signature)

Tel. No. _____

BY _____

Title _____

State of _____)

as:

County of _____)

_____, being duly sworn,

deposes and says that he is

_____ of

(Name of Organization)

and that the answers to the foregoing questions and all statements therein contained are true and correct.

Subscribed and sworn to before me this _____ day of _____,
20_____

(Notary Public)

My commission expires _____, 20_____

END OF SECTION 00312

Bidder's Name _____

CITY OF SALEM STATEMENT OF BIDDER'S
SEWER REHABILITATION PROJECT QUALIFICATIONS
00312-6

SECTION 00450

CERTIFICATE AS TO CORPORATE BIDDER

I, _____, certify that I am the _____ of the Corporation named as bidder in the attached Bid Form; that _____, who signed said Bid Form on behalf of the bidder was then _____ of said Corporation; that I know his/her signature hereto is genuine and that said Bid Form was duly signed, sealed and executed for and in behalf said Corporation by authority of its governing body.

(Corporate Seal)

By: _____
Name – Type or Print

Signature

This Certificate must be completed where Bidder is a Corporation and should be so completed by its Clerk. In the event that the Clerk is the person signing the Proposal on behalf of the Corporation, this certificate must be completed by another Officer of the Corporation.

END OF SECTION 00450

SECTION 00451

CERTIFICATE OF TAX COMPLIANCE

Date: _____

Pursuant to M.G.L. Chapter 62C, Section 49A, I certify under the penalties of perjury that I have filed all state tax returns and paid all state taxes required under law.

Social Security Number or
Federal Identification Number

Signature of Individual or Corporate Name

By: _____
Corporate Officer (if applicable)

This form shall be submitted by all bidders.

END OF SECTION 00451

SECTION 00500

AGREEMENT

INDEX

ARTICLE 1 WORK

ARTICLE 2 ENGINEER

ARTICLE 3 CONTRACT TIMES

ARTICLE 4 CONTRACT PRICE

ARTICLE 5 PAYMENT PROCEDURES

ARTICLE 6 INTEREST

ARTICLE 7 CONTRACTOR'S REPRESENTATIONS

ARTICLE 8 CONTRACT DOCUMENTS

ARTICLE 9 MISCELLANEOUS
SECTION 00500

AGREEMENT

CITY OF SALEM, MASSACHUSETTS

IFB NO.

THIS AGREEMENT is dated as of the _____ day of _____ in the year 20____ by and between the City of Salem, Massachusetts, acting by and through its Engineering Department, duly authorized therefore, who acts herein solely for said City of Salem and without personal liability to itself, (hereinafter called OWNER) and _____ (hereinafter called CONTRACTOR).

OWNER AND CONTRACTOR, in consideration of the mutual covenants hereinafter set forth, agree as follows:

ARTICLE 1. WORK

CONTRACTOR shall complete all Work as specified or indicated in the Contract Documents. The Work is as described in Section 01010 – SUMMARY OF WORK.

ARTICLE 2. ENGINEER

The Project has been designed by New England Civil Engineering Corporation, 120 Washington St. Suite 202E, Salem, Massachusetts, who is hereinafter called ENGINEER and who is to act as OWNER'S representative, and have the rights and authority assigned to ENGINEER in the Contract Documents in connection with completion of the Work in accordance with the Contract Documents.

ARTICLE 3. CONTRACT TIMES

- 3.1 The work will be substantially complete on or before _____, 20____.
- 3.2 Liquidated Damages. OWNER and CONTRACTOR recognize that time is of the essence of this Agreement and that OWNER will suffer financial loss if the Work is not completed within the times specified in paragraph 3.1 above, plus any extensions thereof allowed in accordance with Article 12 of the General Conditions. They also recognize the delays, expense, and difficulties involved in proving the actual loss suffered by OWNER if the Work is not completed on time. Accordingly, instead of requiring any such proof, OWNER and CONTRACTOR agree that as liquidated damages for delay (but not as a penalty) CONTRACTOR shall pay OWNER One Thousand dollars (\$1,000.00) for each day that expires after the time specified in paragraph 3.1 for Substantial Completion until the Work is substantially complete.

ARTICLE 4. CONTRACT PRICE

OWNER shall pay CONTRACTOR for completion of the Work in accordance with the Contract Documents an amount in current funds equal to the prices stipulated in the CONTRACTOR's BID attached to this Agreement.

ARTICLE 5. PAYMENT PROCEDURES

CONTRACTOR shall submit Applications for Payment in accordance with Article 14 of the General Conditions. Applications for Payment will be processed by ENGINEER as provided in the General Conditions.

- 5.1 Progress Payments; Retainage. OWNER shall make progress payments on account of the Contract Price on the basis of CONTRACTOR's Applications for Payment as recommended by ENGINEER, and in accordance with the applicable Massachusetts General Law during construction as provided in paragraphs 5.1.1 and 5.2 below. All such payments will be measured by the schedule of values established in paragraph 2.07 of the General Conditions (and in the case of Unit Price Work based on the number of units completed) or, in the event there is no schedule of values, as provided in the General Requirements.
- 5.1.1 Progress payments will be made in an amount equal to 95 percent of Work completed (with the balance being retainage) but, in each case, less the aggregate of payments previously made and less such amounts as ENGINEER shall determine, or OWNER may withhold, in accordance with paragraph 14.02.B.5 of the General Conditions.
- 5.2 Final Payment. Upon final completion and acceptance of the Work in accordance with paragraph 14.07 of the General Conditions, OWNER shall pay the remainder of the Contract Price as recommended by ENGINEER as provided in said paragraph 14.07.

ARTICLE 6. INTEREST

All moneys not paid when due as provided in Article 14 of the General Conditions shall bear interest at the rate of three percentage points above the rediscount rate then charged by the Federal Reserve Bank of Boston, Massachusetts.

ARTICLE 7. CONTRACTOR'S REPRESENTATIONS

In order to induce OWNER to enter into this Agreement, CONTRACTOR makes the following representations:

- 7.1 CONTRACTOR has examined and carefully studied the Contract Documents (including the Addenda listed in paragraph 8) and the other related data identified in the Bidding Documents including "technical data."
- 7.2 CONTRACTOR has visited the site and become familiar with and is satisfied as to the general, local, and site conditions that may affect cost, progress, performance, or furnishing of the Work.
- 7.3 CONTRACTOR is familiar with and is satisfied as to all federal, state, and local Laws and Regulations that may affect cost, progress, performance, and furnishing of the Work.
- 7.4 CONTRACTOR is aware of the general nature of work to be performed by OWNER and others at the site that relates to the Work as indicated in the Contract Documents.
- 7.5 CONTRACTOR has correlated the information known to CONTRACTOR, information and observations obtained from visits to the site, reports, and drawings identified in the Contract Documents and all additional examinations, investigations, explorations, tests, studies, and data with the Contract Documents.
- 7.6 CONTRACTOR has given ENGINEER written notice of all conflicts, errors, ambiguities, or discrepancies that CONTRACTOR has discovered in the Contract Documents and the written resolution thereof by ENGINEER is acceptable to CONTRACTOR, and the Contract Documents are generally sufficient to indicate and convey understanding of all terms and conditions for performance and furnishing of the Work.

ARTICLE 8. CONTRACT DOCUMENTS

The Contract Documents which comprise the entire agreement between OWNER and CONTRACTOR concerning the Work consist of the following:

- 8.1 Invitation to Bid.
- 8.2 Instructions to Bidders.
- 8.3 Contractor's Bid.
- 8.4 This Agreement.
- 8.5 Exhibits to this Agreement (pages _____ to _____, inclusive).

- 8.6 Performance, Payment, and other Bonds.
- 8.7 General Conditions EJCDC Document C-700, 2007 edition.
- 8.8 Supplementary Conditions.
- 8.9 Specifications as listed in table of contents thereof and Attachments to the Specifications.
- 8.10 Manhole Construction Detail; Table: Table of All Defects to be Repaired; Locus Map; Map : Highland Avenue and Essex Street; Map 2: Crescent Drive; Map 3: Liberty Street; Map 4: Oakview Avenue; Map 5: Churchill Street; Map 6: Sable and Circle Hill Road; Map 7: Wheatland Street; Map 8: Cleveland and Buchanan Road; Map 9: Nichols and Butler Street; Map 10: Pope Street Easement; Map 11: Washington Street; Map 12: Buena Vista Avenue - Cross Country Sewer) and dated August 2017
- 8.11 Addenda numbers _____ to _____, inclusive.
- 8.12 The following which may be delivered or issued after the Effective Date of the Agreement and are not attached hereto: All Written Amendments and other documents amending, modifying, or supplementing the Contract Documents pursuant to paragraph 3.04 of the General Conditions.

ARTICLE 9. MISCELLANEOUS

- 9.1 Terms used in this Agreement which are defined in Article 1 of the General Conditions will have the meanings indicated in the General Conditions.
- 9.2 No assignment by a party hereto of any rights under or interests in the Contract Documents will be binding on another party hereto without the written consent of the party sought to be bound; and specifically, but without limitation, moneys that may become due and moneys that are due may not be assigned without such consent (except to the extent that the effect of this restriction may be limited by law), and unless specifically stated to the contrary in any written consent to an assignment no assignment with release or discharge the assignor from any duty or responsibility under the Contract Documents.
- 9.3 OWNER and CONTRACTOR each binds itself, its partners, successors, assigns, and legal representatives to the other party hereto, its partners, successors, assigns, and legal representatives in respect to all covenants, agreements, and obligations contained in the Contract Documents.
- 9.4 Any provision or part of the Contract Documents held to be void or unenforceable under any Law or Regulation shall be deemed stricken, and all remaining provisions shall continue to be valid and binding upon OWNER and CONTRACTOR, who agree that the Contract Documents shall be reformed to replace such stricken provision or part thereof with a valid and enforceable provision that comes as close as possible to expressing the intention of the stricken provision.
- 9.5 The contractor shall not discriminate against or exclude any person from participation herein on grounds of race, religion, color, sex, age, or national origin; and that it shall take affirmative actions to insure that applicants are employed, and that employees are treated during their employment, without regard to race, religion, color, sex, age, handicapped status, or national origin.

- 9.6 The contractor shall not participate in or cooperate with an international boycott, as defined in Section 999 (b)(3) and (4) of the Internal Revenue code 1986, as amended, or engage in conduct declared to be unlawful by Section 2 of Chapter 151E of the Massachusetts General Laws.
- 9.7 The Contractor agrees to post in conspicuous places, available to employees and applicants for employment, notices to be provided by the Massachusetts Commission Against Discrimination setting forth the provisions of this nondiscrimination clause.
- 9.8 The agreed upon Direct Labor Markup (percentage) for change orders on this project shall not exceed _____ percent.
- 9.9 The time for completion of this contract is One Hundred Fifty (150) calendar days.
- 9.10 Liquidated damages specified in this contract are \$1,000.00 per day for each calendar day beyond the contract completion date that work remains uncompleted.

IN WITNESS WHEREOF, OWNER AND CONTRACTOR have signed this Agreement in triplicate. One counterpart each has been delivered to OWNER, CONTRACTOR and ENGINEER. All portions of the Contract Documents have been signed, initialed or identified by OWNER and CONTRACTOR or identified by ENGINEER on their behalf.

This Agreement will be effective on _____, 20____ (which is the Effective Date of the Agreement).

OWNER City of Salem

CONTRACTOR _____

By: _____

Kimberley Driscoll, Mayor

By: _____

[CORPORATE SEAL]

Purchasing Agent

Attest _____

David H. Knowlton, PE,
DPS Director, City Engineer

Address For giving notices

Address for giving notices

93 Washington Street, 3rd Floor
Salem, MA 01970

Pursuant to M.G.L. c.44, s31C, I certify
that an appropriation has been made in the
total amount of the contract.

License No. _____

Agent for service of process: _____

Purchase Order # _____
Contract Amount _____

(If CONTRACTOR is a corporation, attach
evidence of authority to sign.)

Finance Director/Auditor

END OF SECTION 00500

SECTION 00540
NOTICE OF AWARD

Date: _____

TO: _____
(Bidder)

ADDRESS: _____

Contract: SEWER REHABILITATION PROJECT
Project: _____

OWNERS Contract No. _____

You are notified that your Bid dated _____ for the above Contract has been considered and that you are the apparent successful bidder for the construction of the above Contract.

The Contract Price of your contract is _____
Dollars (\$))

Three copies of the Contract Documents (except Drawings) accompany this Notice of Award. Three sets of the Drawings will be delivered separately or otherwise made available to you.

You must comply with the following conditions precedent within ten days of the date of this Notice of Award, that is by _____
(Date)

1. You must deliver to the OWNER three fully executed counterparts of the Agreement including all the Contract Documents. This includes the triplicate sets of Drawings. Each of the Contract Documents must bear your signature on the cover.
2. You must deliver with the executed Agreement the Contract Security (Bonds) and Insurance Certificate as specified in the Information for Bidders and General Conditions.
3. List other conditions precedent.

Failure to comply with these conditions within the time specified will entitle OWNER to consider your bid abandoned, to annul this Notice of Award and to declare your Bid Security forfeited.

Within ten days after you comply with those conditions, OWNER will return to you one fully signed counterpart of the Agreement with the Contract Documents attached.

City of Salem
(Owner)

By: _____
(Authorized Signature)

(Title)

Copy to ENGINEER

END OF SECTION 00540

SECTION 00560

NOTICE TO PROCEED

To: _____ Date: _____
(Contractor)

Project: SEWER REHABILITATION PROJECT,

You are hereby notified to commence the Work in accordance with the Agreement dated _____, 20____, on or before _____, 20____, and you are to complete all work within One Hundred Fifty (150) consecutive calendar days thereafter. The date of completion of all work is therefore _____, 20____.

City of Salem
(Owner)

By _____

Title _____

ACCEPTANCE OF NOTICE

Receipt of the above Notice to Proceed is hereby acknowledged, this the _____ day of _____, 20____.

By _____

Title _____

END OF SECTION 00560

SECTION 00610

PERFORMANCE BOND

We, the undersigned, _____

(Name of Contractor)

(Address of Contractor)

_____ (Corporation, Partnership, or Individual), hereinafter called Principal, and

(Name of Surety)

(Address of Surety)

hereinafter called Surety, are held and firmly bound unto the City Salem, hereinafter called Owner, in the penal sum of _____ Dollars (\$_____) in lawful money of the United States, for the payment of which sum well and truly to be made. We hereby jointly and severally bind ourselves, our heirs, executors, administrators, successors and assigns.

The condition of this obligation is such that the Principal entered into a certain contract with the Owner, dated the ____ day of _____, 20____, a copy of which is attached hereto and made a part hereof, for the project known as "SEWER REHABILITATION PROJECT," and the Principal and Surety bind themselves to the Owner for the performance of the contract.

Now, therefore, if the Principal shall well, truly and faithfully perform its duties, all the undertakings, covenants, terms, conditions, and agreements of said contract during the original term thereof, and any extensions thereof which may be granted by the Owner, with or without notice to the Surety and during the guaranty period set forth in the contract, and if it shall satisfy all claims and demands incurred under such contract, and shall fully indemnify and save harmless the Owner, its officers and agents from any and all costs and damages which it may suffer by a reason of failure to do so, and shall reimburse and repay the Owner all outlay and expense which the Owner may incur in making good any default, then this obligation shall be void; otherwise, this bond shall remain in full force and effect; provided, further, that the said Surety for value received hereby agrees that no change,

extension of time, alteration or addition to the terms of the contract or to the work to be performed thereunder of the Specifications accompanying the same shall in any way affect its obligation on this Bond, and it does hereby waive notice of any such change, extension of time, alteration or addition to the terms of the contract or to the work or to the specifications. Provided, further, that no final settlement between the Owner and the Contractor shall abridge the right of any beneficiary hereunder whose claim may be unsatisfied.

IN WITNESS WHEREOF, this instrument is executed on this ____ day of _____, 20____.

CONTRACTOR AS PRINCIPAL

SURETY

(Signature)
Name and Title:

(Signature)
Name and Title:

SEAL

SEAL

Address

Telephone No.

Fax No.

END OF SECTION 00610

SECTION 00620
PAYMENT BOND

We, the undersigned, _____
_____,
(Name of Contractor)

(Address of Contractor)

_____ (Corporation, Partnership or Individual), hereinafter called Principal, and

_____,
(Name of Surety)

_____,
(Address of Surety)

hereinafter called Surety, are held and firmly bound unto the City of Salem, hereinafter called Owner, in the penal sum of _____ Dollars (\$_____) in lawful money of the United States, for the payment of which sum well and truly to be made. We hereby jointly and severally bind ourselves, our heirs, executors, administrators, successors and assigns.

The condition of this obligation is such that the Principal entered into a certain contract with the Owner, dated the ____ day of _____ 20____, a copy of which is attached hereto and made a part hereof, for the project known as "SEWER REHABILITATION PROJECT."

Now, therefore, if the Principal shall promptly make payment to all persons, firms, subcontractors, and corporations furnishing materials for or performing labor in the prosecution of the work provided for in such contract, and any authorized extension or modification thereof, including all amounts due for all materials used in connection with the work, and all insurance premiums on said work, and for all labor performed in such work whether by subcontractor or otherwise, then this obligation shall be void; otherwise this bond is to remain in full force and effect. Provided, further, that the said Surety for value received hereby agrees that no change, extension of time, alteration or addition to the terms of the contract or to the work to be performed thereunder of the Specifications accompanying the same shall in any way affect its obligation on this Bond, and it does hereby waive notice of any such change, extension

of time, alteration or addition to the terms of the contract or to the work or to the specifications.

Provided, further, that no final settlement between the Owner and the Contractor shall abridge the right of any beneficiary hereunder whose claim may be unsatisfied.

IN WITNESS WHEREOF, this instrument is executed on this _____ day of _____, 20____.

CONTRACTOR AS PRINCIPAL

SURETY

(Signature)
Name and Title:

(Signature)
Name and Title:

SEAL

SEAL

Address

Telephone No.

Fax No.

END OF SECTION 00620

SECTION 00630

CERTIFICATE OF SUBSTANTIAL COMPLETION

DATE OF ISSUANCE _____

OWNER _____

CONTRACTOR _____

Contract: _____

Project: _____

OWNER's Contract No. _____ ENGINEER's Project No. _____

This Certificate of Substantial Completion applies to all Work under the Contract Documents or to the following specified parts thereof:

To _____
OWNER

And To _____
CONTRACTOR

The Work to which this Certificate applies has been inspected by authorized representatives of OWNER, CONTRACTOR and ENGINEER, and that Work is hereby declared to be substantially complete in accordance with the Contract Documents on

DATE OF SUBSTANTIAL COMPLETION

A tentative list of items to be completed or corrected is attached hereto. This list may not be all-inclusive, and the failure to include an item in it does not alter the responsibility of CONTRACTOR to complete all the Work in accordance with the Contract Documents. The items in the tentative list shall be completed or corrected by CONTRACTOR within _____ days of the above date of Substantial Completion.

The responsibilities between OWNER and CONTRACTOR for security, operation, safety, maintenance, heat, utilities, insurance and warranties and guarantees shall be as follows:

OWNER: _____

CONTRACTOR: _____

The following documents are attached to and made a part of this Certificate:

[For items to be attached see definition of Substantial Completion as supplemented and other specifically noted conditions precedent to achieving Substantial Completion as required by Contract Documents.]

This certificate does not constitute an acceptance of Work not in accordance with the Contract Documents nor is it a release of CONTRACTOR's obligation to complete the Work in accordance with the Contract Documents.

Executed by ENGINEER on _____
Date

ENGINEER

By: _____
(Authorized Signature)

CONTRACTOR accepts this Certificate of Substantial Completion on _____
Date

CONTRACTOR

By: _____
(Authorized Signature)

OWNER accepts this Certificate of Substantial Completion on _____
Date

OWNER

By: _____
(Authorized Signature)

END OF SECTION 00630

SECTION 00635
CHANGE ORDER

No. _____

Contract:	Date of Issuance: _____
-----------	-------------------------

OWNER:	OWNER's Contract No. _____
--------	----------------------------

CONTRACTOR:

ENGINEER: New England Civil Engineering Corp.	ENGINEER's Project No. _____
---	------------------------------

CONTRACTOR is directed to make the following changes in the Contract Documents.

1. Description of Work:
2. Purpose of Change Order:
3. Attachments: (List documents supporting change)

CHANGE IN CONTRACT PRICE	CHANGE IN CONTRACT TIME
Original Contract Price \$ _____	Original Contract Time _____ (days or date)
Previous Change Orders No. ____ to No. ____ \$ _____	Net change from previous Change Orders _____ (days)
Contract Price prior to this Change Order \$ _____	Contract Time prior to this Change Order _____ (days or date)
Net (Increase/Decrease) of this Change Order \$ _____	Net (Increase/Decrease) of this Change Order _____ (days)
Contract Price with all approved Change Orders \$ _____	Contract Time with all approved Change Orders _____ (days or date)

RECOMMENDED:

By: _____
(Engineer)

Date: _____

APPROVED:

By: _____
(Owner)

Date: _____

ACCEPTED:

By: _____
(Contractor)

Date: _____

END OF SECTION 00635

This document has important legal consequences; consultation with an attorney is encouraged with respect to its use or modification. This document should be adapted to the particular circumstances of the contemplated Project and the controlling Laws and Regulations.


**STANDARD GENERAL CONDITIONS
OF THE CONSTRUCTION CONTRACT**

Prepared by

ENGINEERS JOINT CONTRACT DOCUMENTS COMMITTEE

and

Issued and Published Jointly by



AMERICAN COUNCIL OF ENGINEERING COMPANIES

ASSOCIATED GENERAL CONTRACTORS OF AMERICA

AMERICAN SOCIETY OF CIVIL ENGINEERS

PROFESSIONAL ENGINEERS IN PRIVATE PRACTICE
A Practice Division of the
NATIONAL SOCIETY OF PROFESSIONAL ENGINEERS

Endorsed by



CONSTRUCTION SPECIFICATIONS INSTITUTE

These General Conditions have been prepared for use with the Suggested Forms of Agreement Between Owner and Contractor (EJCDC C-520 or C-525, 2007 Editions). Their provisions are interrelated and a change in one may necessitate a change in the other. Comments concerning their usage are contained in the Narrative Guide to the EJCDC Construction Documents (EJCDC C-001, 2007 Edition). For guidance in the preparation of Supplementary Conditions, see Guide to the Preparation of Supplementary Conditions (EJCDC C-800, 2007 Edition).

Copyright © 2007 National Society of Professional Engineers
1420 King Street, Alexandria, VA 22314-2794
(703) 684-2882
www.nspe.org

American Council of Engineering Companies
1015 15th Street N.W., Washington, DC 20005
(202) 347-7474
www.acec.org

American Society of Civil Engineers
1801 Alexander Bell Drive, Reston, VA 20191-4400
(800) 548-2723
www.asce.org

Associated General Contractors of America
2300 Wilson Boulevard, Suite 400, Arlington, VA 22201-3308
(703) 548-3118
www.agc.org

The copyright for this EJCDC document is owned jointly by the four
EJCDC sponsoring organizations and held in trust for their benefit by NSPE.

STANDARD GENERAL CONDITIONS OF THE
CONSTRUCTION CONTRACT

TABLE OF CONTENTS

	Page
Article 1 – Definitions and Terminology	6
1.01 Defined Terms	6
1.02 Terminology	9
Article 2 – Preliminary Matters	9
2.01 Delivery of Bonds and Evidence of Insurance	9
2.02 Copies of Documents	10
2.03 Commencement of Contract Times; Notice to Proceed	10
2.04 Starting the Work	10
2.05 Before Starting Construction	10
2.06 Preconstruction Conference; Designation of Authorized Representatives	10
2.07 Initial Acceptance of Schedules	10
Article 3 – Contract Documents: Intent, Amending, Reuse	11
3.01 Intent	11
3.02 Reference Standards	11
3.03 Reporting and Resolving Discrepancies	11
3.04 Amending and Supplementing Contract Documents	12
3.05 Reuse of Documents	12
3.06 Electronic Data	12
Article 4 – Availability of Lands; Subsurface and Physical Conditions; Hazardous Environmental Conditions; Reference Points	12
4.01 Availability of Lands	12
4.02 Subsurface and Physical Conditions	13
4.03 Differing Subsurface or Physical Conditions	13
4.04 Underground Facilities	14
4.05 Reference Points	15
4.06 Hazardous Environmental Condition at Site	15
Article 5 – Bonds and Insurance	16
5.01 Performance, Payment, and Other Bonds	16
5.02 Licensed Sureties and Insurers	17
5.03 Certificates of Insurance	17
5.04 Contractor’s Insurance	17
5.05 Owner’s Liability Insurance	18
5.06 Property Insurance	18
5.07 Waiver of Rights	19
5.08 Receipt and Application of Insurance Proceeds	20
5.09 Acceptance of Bonds and Insurance; Option to Replace	20
5.10 Partial Utilization, Acknowledgment of Property Insurer	20
Article 6 – Contractor’s Responsibilities	21
6.01 Supervision and Superintendence	21
6.02 Labor; Working Hours	21
6.03 Services, Materials, and Equipment	21
6.04 Progress Schedule	21
6.05 Substitutes and “Or-Equals”	21
6.06 Concerning Subcontractors, Suppliers, and Others	23

6.07	Patent Fees and Royalties.....	24
6.08	Permits	25
6.09	Laws and Regulations	25
6.10	Taxes.....	25
6.11	Use of Site and Other Areas.....	25
6.12	Record Documents	26
6.13	Safety and Protection.....	26
6.14	Safety Representative	27
6.15	Hazard Communication Programs	27
6.16	Emergencies.....	27
6.17	Shop Drawings and Samples.....	27
6.18	Continuing the Work.....	28
6.19	Contractor's General Warranty and Guarantee	28
6.20	Indemnification.....	29
6.21	Delegation of Professional Design Services.....	29
Article 7 – Other Work at the Site		30
7.01	Related Work at Site.....	30
7.02	Coordination	30
7.03	Legal Relationships	31
Article 8 – Owner's Responsibilities		31
8.01	Communications to Contractor	31
8.02	Replacement of Engineer	31
8.03	Furnish Data	31
8.04	Pay When Due.....	31
8.05	Lands and Easements; Reports and Tests	31
8.06	Insurance.....	31
8.07	Change Orders.....	31
8.08	Inspections, Tests, and Approvals.....	31
8.09	Limitations on Owner's Responsibilities.....	31
8.10	Undisclosed Hazardous Environmental Condition.....	31
8.11	Evidence of Financial Arrangements.....	31
8.12	Compliance with Safety Program	31
Article 9 – Engineer's Status During Construction		32
9.01	Owner's Representative	32
9.02	Visits to Site.....	32
9.03	Project Representative.....	32
9.04	Authorized Variations in Work.....	32
9.05	Rejecting Defective Work.....	32
9.06	Shop Drawings, Change Orders and Payments.....	32
9.07	Determinations for Unit Price Work.....	33
9.08	Decisions on Requirements of Contract Documents and Acceptability of Work	33
9.09	Limitations on Engineer's Authority and Responsibilities.....	33
9.10	Compliance with Safety Program	34
Article 10 – Changes in the Work; Claims		34
10.01	Authorized Changes in the Work.....	34
10.02	Unauthorized Changes in the Work.....	34
10.03	Execution of Change Orders	34
10.04	Notification to Surety	34
10.05	Claims.....	34
Article 11 – Cost of the Work; Allowances; Unit Price Work.....		35
11.01	Cost of the Work	35

11.02	Allowances	37
11.03	Unit Price Work	37
Article 12 – Change of Contract Price; Change of Contract Times		38
12.01	Change of Contract Price	38
12.02	Change of Contract Times	39
12.03	Delays	39
Article 13 – Tests and Inspections; Correction, Removal or Acceptance of Defective Work		39
13.01	Notice of Defects	39
13.02	Access to Work	39
13.03	Tests and Inspections	40
13.04	Uncovering Work	40
13.05	Owner May Stop the Work	40
13.06	Correction or Removal of Defective Work	41
13.07	Correction Period	41
13.08	Acceptance of Defective Work	41
13.09	Owner May Correct Defective Work	42
Article 14 – Payments to Contractor and Completion		42
14.01	Schedule of Values	42
14.02	Progress Payments	42
14.03	Contractor's Warranty of Title	44
14.04	Substantial Completion	44
14.05	Partial Utilization	45
14.06	Final Inspection	45
14.07	Final Payment	46
14.08	Final Completion Delayed	46
14.09	Waiver of Claims	47
Article 15 – Suspension of Work and Termination		47
15.01	Owner May Suspend Work	47
15.02	Owner May Terminate for Cause	47
15.03	Owner May Terminate For Convenience	48
15.04	Contractor May Stop Work or Terminate	48
Article 16 – Dispute Resolution		48
16.01	Methods and Procedures	48
Article 17 – Miscellaneous		49
17.01	Giving Notice	49
17.02	Computation of Times	49
17.03	Cumulative Remedies	49
17.04	Survival of Obligations	49
17.05	Controlling Law	49
17.06	Headings	49

ARTICLE 1 – DEFINITIONS AND TERMINOLOGY

1.01 *Defined Terms*

- A. Wherever used in the Bidding Requirements or Contract Documents and printed with initial capital letters, the terms listed below will have the meanings indicated which are applicable to both the singular and plural thereof. In addition to terms specifically defined, terms with initial capital letters in the Contract Documents include references to identified articles and paragraphs, and the titles of other documents or forms.
1. *Addenda*—Written or graphic instruments issued prior to the opening of Bids which clarify, correct, or change the Bidding Requirements or the proposed Contract Documents.
 2. *Agreement*—The written instrument which is evidence of the agreement between Owner and Contractor covering the Work.
 3. *Application for Payment*—The form acceptable to Engineer which is to be used by Contractor during the course of the Work in requesting progress or final payments and which is to be accompanied by such supporting documentation as is required by the Contract Documents.
 4. *Asbestos*—Any material that contains more than one percent asbestos and is friable or is releasing asbestos fibers into the air above current action levels established by the United States Occupational Safety and Health Administration.
 5. *Bid*—The offer or proposal of a Bidder submitted on the prescribed form setting forth the prices for the Work to be performed.
 6. *Bidder*—The individual or entity who submits a Bid directly to Owner.
 7. *Bidding Documents*—The Bidding Requirements and the proposed Contract Documents (including all Addenda).
 8. *Bidding Requirements*—The advertisement or invitation to bid, Instructions to Bidders, Bid security of acceptable form, if any, and the Bid Form with any supplements.
 9. *Change Order*—A document recommended by Engineer which is signed by Contractor and Owner and authorizes an addition, deletion, or revision in the Work or an adjustment in the Contract Price or the Contract Times, issued on or after the Effective Date of the Agreement.
 10. *Claim*—A demand or assertion by Owner or Contractor seeking an adjustment of Contract Price or Contract Times, or both, or other relief with respect to the terms of the Contract. A demand for money or services by a third party is not a Claim.
 11. *Contract*—The entire and integrated written agreement between the Owner and Contractor concerning the Work. The Contract supersedes prior negotiations, representations, or agreements, whether written or oral.
 12. *Contract Documents*—Those items so designated in the Agreement. Only printed or hard copies of the items listed in the Agreement are Contract Documents. Approved Shop Drawings, other Contractor submittals, and the reports and drawings of subsurface and physical conditions are not Contract Documents.
 13. *Contract Price*—The moneys payable by Owner to Contractor for completion of the Work in accordance with the Contract Documents as stated in the Agreement (subject to the provisions of Paragraph 11.03 in the case of Unit Price Work).
 14. *Contract Times*—The number of days or the dates stated in the Agreement to: (i) achieve Milestones, if any; (ii) achieve Substantial Completion; and (iii) complete the Work so that it is ready for final payment as evidenced by Engineer's written recommendation of final payment.
 15. *Contractor*—The individual or entity with whom Owner has entered into the Agreement.
 16. *Cost of the Work*—See Paragraph 11.01 for definition.
 17. *Drawings*—That part of the Contract Documents prepared or approved by Engineer which graphically shows the scope, extent, and character of the Work to be

performed by Contractor. Shop Drawings and other Contractor submittals are not Drawings as so defined.

18. *Effective Date of the Agreement*—The date indicated in the Agreement on which it becomes effective, but if no such date is indicated, it means the date on which the Agreement is signed and delivered by the last of the two parties to sign and deliver.
19. *Engineer*—The individual or entity named as such in the Agreement.
20. *Field Order*—A written order issued by Engineer which requires minor changes in the Work but which does not involve a change in the Contract Price or the Contract Times.
21. *General Requirements*—Sections of Division 1 of the Specifications.
22. *Hazardous Environmental Condition*—The presence at the Site of Asbestos, PCBs, Petroleum, Hazardous Waste, or Radioactive Material in such quantities or circumstances that may present a substantial danger to persons or property exposed thereto.
23. *Hazardous Waste*—The term Hazardous Waste shall have the meaning provided in Section 1004 of the Solid Waste Disposal Act (42 USC Section 6903) as amended from time to time.
24. *Laws and Regulations; Laws or Regulations*—Any and all applicable laws, rules, regulations, ordinances, codes, and orders of any and all governmental bodies, agencies, authorities, and courts having jurisdiction.
25. *Liens*—Charges, security interests, or encumbrances upon Project funds, real property, or personal property.
26. *Milestone*—A principal event specified in the Contract Documents relating to an intermediate completion date or time prior to Substantial Completion of all the Work.
27. *Notice of Award*—The written notice by Owner to the Successful Bidder stating that upon timely compliance by the Successful Bidder with the conditions precedent listed therein, Owner will sign and deliver the Agreement.
28. *Notice to Proceed*—A written notice given by Owner to Contractor fixing the date on which the Contract Times will commence to run and on which Contractor shall start to perform the Work under the Contract Documents.
29. *Owner*—The individual or entity with whom Contractor has entered into the Agreement and for whom the Work is to be performed.
30. *PCBs*—Polychlorinated biphenyls.
31. *Petroleum*—Petroleum, including crude oil or any fraction thereof which is liquid at standard conditions of temperature and pressure (60 degrees Fahrenheit and 14.7 pounds per square inch absolute), such as oil, petroleum, fuel oil, oil sludge, oil refuse, gasoline, kerosene, and oil mixed with other non-Hazardous Waste and crude oils.
32. *Progress Schedule*—A schedule, prepared and maintained by Contractor, describing the sequence and duration of the activities comprising the Contractor's plan to accomplish the Work within the Contract Times.
33. *Project*—The total construction of which the Work to be performed under the Contract Documents may be the whole, or a part.
34. *Project Manual*—The bound documentary information prepared for bidding and constructing the Work. A listing of the contents of the Project Manual, which may be bound in one or more volumes, is contained in the table(s) of contents.
35. *Radioactive Material*—Source, special nuclear, or byproduct material as defined by the Atomic Energy Act of 1954 (42 USC Section 2011 et seq.) as amended from time to time.
36. *Resident Project Representative*—The authorized representative of Engineer who may be assigned to the Site or any part thereof.
37. *Samples*—Physical examples of materials, equipment, or workmanship that are representative of some portion of the Work

- and which establish the standards by which such portion of the Work will be judged.
38. *Schedule of Submittals*—A schedule, prepared and maintained by Contractor, of required submittals and the time requirements to support scheduled performance of related construction activities.
39. *Schedule of Values*—A schedule, prepared and maintained by Contractor, allocating portions of the Contract Price to various portions of the Work and used as the basis for reviewing Contractor's Applications for Payment.
40. *Shop Drawings*—All drawings, diagrams, illustrations, schedules, and other data or information which are specifically prepared or assembled by or for Contractor and submitted by Contractor to illustrate some portion of the Work.
41. *Site*—Lands or areas indicated in the Contract Documents as being furnished by Owner upon which the Work is to be performed, including rights-of-way and easements for access thereto, and such other lands furnished by Owner which are designated for the use of Contractor.
42. *Specifications*—That part of the Contract Documents consisting of written requirements for materials, equipment, systems, standards and workmanship as applied to the Work, and certain administrative requirements and procedural matters applicable thereto.
43. *Subcontractor*—An individual or entity having a direct contract with Contractor or with any other Subcontractor for the performance of a part of the Work at the Site.
44. *Substantial Completion*—The time at which the Work (or a specified part thereof) has progressed to the point where, in the opinion of Engineer, the Work (or a specified part thereof) is sufficiently complete, in accordance with the Contract Documents, so that the Work (or a specified part thereof) can be utilized for the purposes for which it is intended. The terms "substantially complete" and "substantially completed" as applied to all or part of the Work refer to Substantial Completion thereof.
45. *Successful Bidder*—The Bidder submitting a responsive Bid to whom Owner makes an award.
46. *Supplementary Conditions*—That part of the Contract Documents which amends or supplements these General Conditions.
47. *Supplier*—A manufacturer, fabricator, supplier, distributor, materialman, or vendor having a direct contract with Contractor or with any Subcontractor to furnish materials or equipment to be incorporated in the Work by Contractor or Subcontractor.
48. *Underground Facilities*—All underground pipelines, conduits, ducts, cables, wires, manholes, vaults, tanks, tunnels, or other such facilities or attachments, and any encasements containing such facilities, including those that convey electricity, gases, steam, liquid petroleum products, telephone or other communications, cable television, water, wastewater, storm water, other liquids or chemicals, or traffic or other control systems.
49. *Unit Price Work*—Work to be paid for on the basis of unit prices.
50. *Work*—The entire construction or the various separately identifiable parts thereof required to be provided under the Contract Documents. Work includes and is the result of performing or providing all labor, services, and documentation necessary to produce such construction, and furnishing, installing, and incorporating all materials and equipment into such construction, all as required by the Contract Documents.
51. *Work Change Directive*—A written statement to Contractor issued on or after the Effective Date of the Agreement and signed by Owner and recommended by Engineer ordering an addition, deletion, or revision in the Work, or responding to differing or unforeseen subsurface or physical conditions under which the Work is to be performed or to emergencies. A Work Change Directive will not change the Contract Price or the Contract Times but is evidence that the parties expect that the change ordered or documented by a Work Change Directive will be incorporated in a subsequently issued Change Order following negotiations by the parties as to its

effect, if any, on the Contract Price or Contract Times.

1.02 Terminology

A. The words and terms discussed in Paragraph 1.02.B through F are not defined but, when used in the Bidding Requirements or Contract Documents, have the indicated meaning.

B. *Intent of Certain Terms or Adjectives:*

1. The Contract Documents include the terms "as allowed," "as approved," "as ordered," "as directed" or terms of like effect or import to authorize an exercise of professional judgment by Engineer. In addition, the adjectives "reasonable," "suitable," "acceptable," "proper," "satisfactory," or adjectives of like effect or import are used to describe an action or determination of Engineer as to the Work. It is intended that such exercise of professional judgment, action, or determination will be solely to evaluate, in general, the Work for compliance with the information in the Contract Documents and with the design concept of the Project as a functioning whole as shown or indicated in the Contract Documents (unless there is a specific statement indicating otherwise). The use of any such term or adjective is not intended to and shall not be effective to assign to Engineer any duty or authority to supervise or direct the performance of the Work, or any duty or authority to undertake responsibility contrary to the provisions of Paragraph 9.09 or any other provision of the Contract Documents.

C. *Day:*

1. The word "day" means a calendar day of 24 hours measured from midnight to the next midnight.

D. *Defective:*

1. The word "defective," when modifying the word "Work," refers to Work that is unsatisfactory, faulty, or deficient in that it:
 - a. does not conform to the Contract Documents; or
 - b. does not meet the requirements of any applicable inspection, reference standard,

test, or approval referred to in the Contract Documents; or

- c. has been damaged prior to Engineer's recommendation of final payment (unless responsibility for the protection thereof has been assumed by Owner at Substantial Completion in accordance with Paragraph 14.04 or 14.05).

E. *Furnish, Install, Perform, Provide:*

1. The word "furnish," when used in connection with services, materials, or equipment, shall mean to supply and deliver said services, materials, or equipment to the Site (or some other specified location) ready for use or installation and in usable or operable condition.
 2. The word "install," when used in connection with services, materials, or equipment, shall mean to put into use or place in final position said services, materials, or equipment complete and ready for intended use.
 3. The words "perform" or "provide," when used in connection with services, materials, or equipment, shall mean to furnish and install said services, materials, or equipment complete and ready for intended use.
 4. When "furnish," "install," "perform," or "provide" is not used in connection with services, materials, or equipment in a context clearly requiring an obligation of Contractor, "provide" is implied.
- F. Unless stated otherwise in the Contract Documents, words or phrases that have a well-known technical or construction industry or trade meaning are used in the Contract Documents in accordance with such recognized meaning.

ARTICLE 2 – PRELIMINARY MATTERS

2.01 *Delivery of Bonds and Evidence of Insurance*

- A. When Contractor delivers the executed counterparts of the Agreement to Owner, Contractor shall also deliver to Owner such bonds as Contractor may be required to furnish.
- B. *Evidence of Insurance:* Before any Work at the Site is started, Contractor and Owner shall each deliver to the other, with copies to each additional

insured identified in the Supplementary Conditions, certificates of insurance (and other evidence of insurance which either of them or any additional insured may reasonably request) which Contractor and Owner respectively are required to purchase and maintain in accordance with Article 5.

2.02 *Copies of Documents*

- A. Owner shall furnish to Contractor up to ten printed or hard copies of the Drawings and Project Manual. Additional copies will be furnished upon request at the cost of reproduction.

2.03 *Commencement of Contract Times; Notice to Proceed*

- A. The Contract Times will commence to run on the thirtieth day after the Effective Date of the Agreement or, if a Notice to Proceed is given, on the day indicated in the Notice to Proceed. A Notice to Proceed may be given at any time within 30 days after the Effective Date of the Agreement. In no event will the Contract Times commence to run later than the sixtieth day after the day of Bid opening or the thirtieth day after the Effective Date of the Agreement, whichever date is earlier.

2.04 *Starting the Work*

- A. Contractor shall start to perform the Work on the date when the Contract Times commence to run. No Work shall be done at the Site prior to the date on which the Contract Times commence to run.

2.05 *Before Starting Construction*

- A. *Preliminary Schedules:* Within 10 days after the Effective Date of the Agreement (unless otherwise specified in the General Requirements), Contractor shall submit to Engineer for timely review:
 - 1. a preliminary Progress Schedule indicating the times (numbers of days or dates) for starting and completing the various stages of the Work, including any Milestones specified in the Contract Documents;
 - 2. a preliminary Schedule of Submittals; and
 - 3. a preliminary Schedule of Values for all of the Work which includes quantities and prices of items which when added together equal the Contract Price and subdivides the Work into component parts in sufficient

detail to serve as the basis for progress payments during performance of the Work. Such prices will include an appropriate amount of overhead and profit applicable to each item of Work.

2.06 *Preconstruction Conference; Designation of Authorized Representatives*

- A. Before any Work at the Site is started, a conference attended by Owner, Contractor, Engineer, and others as appropriate will be held to establish a working understanding among the parties as to the Work and to discuss the schedules referred to in Paragraph 2.05.A, procedures for handling Shop Drawings and other submittals, processing Applications for Payment, and maintaining required records.
- B. At this conference Owner and Contractor each shall designate, in writing, a specific individual to act as its authorized representative with respect to the services and responsibilities under the Contract. Such individuals shall have the authority to transmit instructions, receive information, render decisions relative to the Contract, and otherwise act on behalf of each respective party.

2.07 *Initial Acceptance of Schedules*

- A. At least 10 days before submission of the first Application for Payment a conference attended by Contractor, Engineer, and others as appropriate will be held to review for acceptability to Engineer as provided below the schedules submitted in accordance with Paragraph 2.05.A. Contractor shall have an additional 10 days to make corrections and adjustments and to complete and resubmit the schedules. No progress payment shall be made to Contractor until acceptable schedules are submitted to Engineer.
 - 1. The Progress Schedule will be acceptable to Engineer if it provides an orderly progression of the Work to completion within the Contract Times. Such acceptance will not impose on Engineer responsibility for the Progress Schedule, for sequencing, scheduling, or progress of the Work, nor interfere with or relieve Contractor from Contractor's full responsibility therefor.
 - 2. Contractor's Schedule of Submittals will be acceptable to Engineer if it provides a

workable arrangement for reviewing and processing the required submittals.

3. Contractor's Schedule of Values will be acceptable to Engineer as to form and substance if it provides a reasonable allocation of the Contract Price to component parts of the Work.

ARTICLE 3 – CONTRACT DOCUMENTS: INTENT, AMENDING, REUSE

3.01 Intent

- A. The Contract Documents are complementary; what is required by one is as binding as if required by all.
- B. It is the intent of the Contract Documents to describe a functionally complete project (or part thereof) to be constructed in accordance with the Contract Documents. Any labor, documentation, services, materials, or equipment that reasonably may be inferred from the Contract Documents or from prevailing custom or trade usage as being required to produce the indicated result will be provided whether or not specifically called for, at no additional cost to Owner.
- C. Clarifications and interpretations of the Contract Documents shall be issued by Engineer as provided in Article 9.

3.02 Reference Standards

- A. Standards, Specifications, Codes, Laws, and Regulations
 1. Reference to standards, specifications, manuals, or codes of any technical society, organization, or association, or to Laws or Regulations, whether such reference be specific or by implication, shall mean the standard, specification, manual, code, or Laws or Regulations in effect at the time of opening of Bids (or on the Effective Date of the Agreement if there were no Bids), except as may be otherwise specifically stated in the Contract Documents.
 2. No provision of any such standard, specification, manual, or code, or any instruction of a Supplier, shall be effective to change the duties or responsibilities of Owner, Contractor, or Engineer, or any of their subcontractors, consultants, agents, or

employees, from those set forth in the Contract Documents. No such provision or instruction shall be effective to assign to Owner, Engineer, or any of their officers, directors, members, partners, employees, agents, consultants, or subcontractors, any duty or authority to supervise or direct the performance of the Work or any duty or authority to undertake responsibility inconsistent with the provisions of the Contract Documents.

3.03 Reporting and Resolving Discrepancies

A. Reporting Discrepancies:

1. *Contractor's Review of Contract Documents Before Starting Work:* Before undertaking each part of the Work, Contractor shall carefully study and compare the Contract Documents and check and verify pertinent figures therein and all applicable field measurements. Contractor shall promptly report in writing to Engineer any conflict, error, ambiguity, or discrepancy which Contractor discovers, or has actual knowledge of, and shall obtain a written interpretation or clarification from Engineer before proceeding with any Work affected thereby.
2. *Contractor's Review of Contract Documents During Performance of Work:* If, during the performance of the Work, Contractor discovers any conflict, error, ambiguity, or discrepancy within the Contract Documents, or between the Contract Documents and (a) any applicable Law or Regulation, (b) any standard, specification, manual, or code, or (c) any instruction of any Supplier, then Contractor shall promptly report it to Engineer in writing. Contractor shall not proceed with the Work affected thereby (except in an emergency as required by Paragraph 6.16.A) until an amendment or supplement to the Contract Documents has been issued by one of the methods indicated in Paragraph 3.04.
3. Contractor shall not be liable to Owner or Engineer for failure to report any conflict, error, ambiguity, or discrepancy in the Contract Documents unless Contractor had actual knowledge thereof.

B. Resolving Discrepancies:

1. Except as may be otherwise specifically stated in the Contract Documents, the provisions of the Contract Documents shall take precedence in resolving any conflict, error, ambiguity, or discrepancy between the provisions of the Contract Documents and:

- a. the provisions of any standard, specification, manual, or code, or the instruction of any Supplier (whether or not specifically incorporated by reference in the Contract Documents); or
- b. the provisions of any Laws or Regulations applicable to the performance of the Work (unless such an interpretation of the provisions of the Contract Documents would result in violation of such Law or Regulation).

3.04 *Amending and Supplementing Contract Documents*

- A. The Contract Documents may be amended to provide for additions, deletions, and revisions in the Work or to modify the terms and conditions thereof by either a Change Order or a Work Change Directive.
- B. The requirements of the Contract Documents may be supplemented, and minor variations and deviations in the Work may be authorized, by one or more of the following ways:
 1. A Field Order;
 2. Engineer's approval of a Shop Drawing or Sample (subject to the provisions of Paragraph 6.17.D.3); or
 3. Engineer's written interpretation or clarification.

3.05 *Reuse of Documents*

- A. Contractor and any Subcontractor or Supplier shall not:
 1. have or acquire any title to or ownership rights in any of the Drawings, Specifications, or other documents (or copies of any thereof) prepared by or bearing the seal of Engineer or its consultants, including electronic media editions; or
 2. reuse any such Drawings, Specifications, other documents, or copies thereof on

extensions of the Project or any other project without written consent of Owner and Engineer and specific written verification or adaptation by Engineer.

- B. The prohibitions of this Paragraph 3.05 will survive final payment, or termination of the Contract. Nothing herein shall preclude Contractor from retaining copies of the Contract Documents for record purposes.

3.06 *Electronic Data*

- A. Unless otherwise stated in the Supplementary Conditions, the data furnished by Owner or Engineer to Contractor, or by Contractor to Owner or Engineer, that may be relied upon are limited to the printed copies (also known as hard copies). Files in electronic media format of text, data, graphics, or other types are furnished only for the convenience of the receiving party. Any conclusion or information obtained or derived from such electronic files will be at the user's sole risk. If there is a discrepancy between the electronic files and the hard copies, the hard copies govern.
- B. Because data stored in electronic media format can deteriorate or be modified inadvertently or otherwise without authorization of the data's creator, the party receiving electronic files agrees that it will perform acceptance tests or procedures within 60 days, after which the receiving party shall be deemed to have accepted the data thus transferred. Any errors detected within the 60-day acceptance period will be corrected by the transferring party.
- C. When transferring documents in electronic media format, the transferring party makes no representations as to long term compatibility, usability, or readability of documents resulting from the use of software application packages, operating systems, or computer hardware differing from those used by the data's creator.

ARTICLE 4 – AVAILABILITY OF LANDS; SUBSURFACE AND PHYSICAL CONDITIONS; HAZARDOUS ENVIRONMENTAL CONDITIONS; REFERENCE POINTS

4.01 *Availability of Lands*

- A. Owner shall furnish the Site. Owner shall notify Contractor of any encumbrances or restrictions not of general application but specifically related to

use of the Site with which Contractor must comply in performing the Work. Owner will obtain in a timely manner and pay for easements for permanent structures or permanent changes in existing facilities. If Contractor and Owner are unable to agree on entitlement to or on the amount or extent, if any, of any adjustment in the Contract Price or Contract Times, or both, as a result of any delay in Owner's furnishing the Site or a part thereof, Contractor may make a Claim therefor as provided in Paragraph 10.05.

B. Upon reasonable written request, Owner shall furnish Contractor with a current statement of record legal title and legal description of the lands upon which the Work is to be performed and Owner's interest therein as necessary for giving notice of or filing a mechanic's or construction lien against such lands in accordance with applicable Laws and Regulations.

C. Contractor shall provide for all additional lands and access thereto that may be required for temporary construction facilities or storage of materials and equipment.

4.02 *Subsurface and Physical Conditions*

A. *Reports and Drawings:* The Supplementary Conditions identify:

1. those reports known to Owner of explorations and tests of subsurface conditions at or contiguous to the Site; and
2. those drawings known to Owner of physical conditions relating to existing surface or subsurface structures at the Site (except Underground Facilities).

B. *Limited Reliance by Contractor on Technical Data Authorized:* Contractor may rely upon the accuracy of the "technical data" contained in such reports and drawings, but such reports and drawings are not Contract Documents. Such "technical data" is identified in the Supplementary Conditions. Except for such reliance on such "technical data," Contractor may not rely upon or make any claim against Owner or Engineer, or any of their officers, directors, members, partners, employees, agents, consultants, or subcontractors with respect to:

1. the completeness of such reports and drawings for Contractor's purposes, including, but not limited to, any aspects of

the means, methods, techniques, sequences, and procedures of construction to be employed by Contractor, and safety precautions and programs incident thereto; or

2. other data, interpretations, opinions, and information contained in such reports or shown or indicated in such drawings; or
3. any Contractor interpretation of or conclusion drawn from any "technical data" or any such other data, interpretations, opinions, or information.

4.03 *Differing Subsurface or Physical Conditions*

A. *Notice:* If Contractor believes that any subsurface or physical condition that is uncovered or revealed either:

1. is of such a nature as to establish that any "technical data" on which Contractor is entitled to rely as provided in Paragraph 4.02 is materially inaccurate; or
2. is of such a nature as to require a change in the Contract Documents; or
3. differs materially from that shown or indicated in the Contract Documents; or
4. is of an unusual nature, and differs materially from conditions ordinarily encountered and generally recognized as inherent in work of the character provided for in the Contract Documents;

then Contractor shall, promptly after becoming aware thereof and before further disturbing the subsurface or physical conditions or performing any Work in connection therewith (except in an emergency as required by Paragraph 6.16.A), notify Owner and Engineer in writing about such condition. Contractor shall not further disturb such condition or perform any Work in connection therewith (except as aforesaid) until receipt of written order to do so.

B. *Engineer's Review:* After receipt of written notice as required by Paragraph 4.03.A, Engineer will promptly review the pertinent condition, determine the necessity of Owner's obtaining additional exploration or tests with respect thereto, and advise Owner in writing (with a copy to Contractor) of Engineer's findings and conclusions.

C. *Possible Price and Times Adjustments:*

1. The Contract Price or the Contract Times, or both, will be equitably adjusted to the extent that the existence of such differing subsurface or physical condition causes an increase or decrease in Contractor's cost of, or time required for, performance of the Work; subject, however, to the following:
 - a. such condition must meet any one or more of the categories described in Paragraph 4.03.A; and
 - b. with respect to Work that is paid for on a unit price basis, any adjustment in Contract Price will be subject to the provisions of Paragraphs 9.07 and 11.03.
2. Contractor shall not be entitled to any adjustment in the Contract Price or Contract Times if:
 - a. Contractor knew of the existence of such conditions at the time Contractor made a final commitment to Owner with respect to Contract Price and Contract Times by the submission of a Bid or becoming bound under a negotiated contract; or
 - b. the existence of such condition could reasonably have been discovered or revealed as a result of any examination, investigation, exploration, test, or study of the Site and contiguous areas required by the Bidding Requirements or Contract Documents to be conducted by or for Contractor prior to Contractor's making such final commitment; or
 - c. Contractor failed to give the written notice as required by Paragraph 4.03.A.
3. If Owner and Contractor are unable to agree on entitlement to or on the amount or extent, if any, of any adjustment in the Contract Price or Contract Times, or both, a Claim may be made therefor as provided in Paragraph 10.05. However, neither Owner or Engineer, or any of their officers, directors, members, partners, employees, agents, consultants, or subcontractors shall be liable to Contractor for any claims, costs, losses, or damages (including but not limited to all fees and charges of engineers, architects, attorneys, and other professionals and all court or

arbitration or other dispute resolution costs) sustained by Contractor on or in connection with any other project or anticipated project.

4.04 *Underground Facilities*

A. *Shown or Indicated:* The information and data shown or indicated in the Contract Documents with respect to existing Underground Facilities at or contiguous to the Site is based on information and data furnished to Owner or Engineer by the owners of such Underground Facilities, including Owner, or by others. Unless it is otherwise expressly provided in the Supplementary Conditions:

1. Owner and Engineer shall not be responsible for the accuracy or completeness of any such information or data provided by others; and
2. the cost of all of the following will be included in the Contract Price, and Contractor shall have full responsibility for:
 - a. reviewing and checking all such information and data;
 - b. locating all Underground Facilities shown or indicated in the Contract Documents;
 - c. coordination of the Work with the owners of such Underground Facilities, including Owner, during construction; and
 - d. the safety and protection of all such Underground Facilities and repairing any damage thereto resulting from the Work.

B. *Not Shown or Indicated:*

1. If an Underground Facility is uncovered or revealed at or contiguous to the Site which was not shown or indicated, or not shown or indicated with reasonable accuracy in the Contract Documents, Contractor shall, promptly after becoming aware thereof and before further disturbing conditions affected thereby or performing any Work in connection therewith (except in an emergency as required by Paragraph 6.16.A), identify the owner of such Underground Facility and give written notice to that owner and to Owner and Engineer. Engineer will promptly review the Underground Facility and determine the

extent, if any, to which a change is required in the Contract Documents to reflect and document the consequences of the existence or location of the Underground Facility. During such time, Contractor shall be responsible for the safety and protection of such Underground Facility.

2. If Engineer concludes that a change in the Contract Documents is required, a Work Change Directive or a Change Order will be issued to reflect and document such consequences. An equitable adjustment shall be made in the Contract Price or Contract Times, or both, to the extent that they are attributable to the existence or location of any Underground Facility that was not shown or indicated or not shown or indicated with reasonable accuracy in the Contract Documents and that Contractor did not know of and could not reasonably have been expected to be aware of or to have anticipated. If Owner and Contractor are unable to agree on entitlement to or on the amount or extent, if any, of any such adjustment in Contract Price or Contract Times, Owner or Contractor may make a Claim therefor as provided in Paragraph 10.05.

4.05 *Reference Points*

- A. Owner shall provide engineering surveys to establish reference points for construction which in Engineer's judgment are necessary to enable Contractor to proceed with the Work. Contractor shall be responsible for laying out the Work, shall protect and preserve the established reference points and property monuments, and shall make no changes or relocations without the prior written approval of Owner. Contractor shall report to Engineer whenever any reference point or property monument is lost or destroyed or requires relocation because of necessary changes in grades or locations, and shall be responsible for the accurate replacement or relocation of such reference points or property monuments by professionally qualified personnel.

4.06 *Hazardous Environmental Condition at Site*

- A. *Reports and Drawings:* The Supplementary Conditions identify those reports and drawings known to Owner relating to Hazardous Environmental Conditions that have been identified at the Site.

- B. *Limited Reliance by Contractor on Technical Data Authorized:* Contractor may rely upon the accuracy of the "technical data" contained in such reports and drawings, but such reports and drawings are not Contract Documents. Such "technical data" is identified in the Supplementary Conditions. Except for such reliance on such "technical data," Contractor may not rely upon or make any claim against Owner or Engineer, or any of their officers, directors, members, partners, employees, agents, consultants, or subcontractors with respect to:

1. the completeness of such reports and drawings for Contractor's purposes, including, but not limited to, any aspects of the means, methods, techniques, sequences and procedures of construction to be employed by Contractor and safety precautions and programs incident thereto; or
2. other data, interpretations, opinions and information contained in such reports or shown or indicated in such drawings; or
3. any Contractor interpretation of or conclusion drawn from any "technical data" or any such other data, interpretations, opinions or information.

- C. Contractor shall not be responsible for any Hazardous Environmental Condition uncovered or revealed at the Site which was not shown or indicated in Drawings or Specifications or identified in the Contract Documents to be within the scope of the Work. Contractor shall be responsible for a Hazardous Environmental Condition created with any materials brought to the Site by Contractor, Subcontractors, Suppliers, or anyone else for whom Contractor is responsible.

- D. If Contractor encounters a Hazardous Environmental Condition or if Contractor or anyone for whom Contractor is responsible creates a Hazardous Environmental Condition, Contractor shall immediately: (i) secure or otherwise isolate such condition; (ii) stop all Work in connection with such condition and in any area affected thereby (except in an emergency as required by Paragraph 6.16.A); and (iii) notify Owner and Engineer (and promptly thereafter confirm such notice in writing). Owner shall promptly consult with Engineer concerning the necessity for Owner to retain a qualified expert to evaluate such condition or take corrective action,

if any. Promptly after consulting with Engineer, Owner shall take such actions as are necessary to permit Owner to timely obtain required permits and provide Contractor the written notice required by Paragraph 4.06.E.

E. Contractor shall not be required to resume Work in connection with such condition or in any affected area until after Owner has obtained any required permits related thereto and delivered written notice to Contractor: (i) specifying that such condition and any affected area is or has been rendered safe for the resumption of Work; or (ii) specifying any special conditions under which such Work may be resumed safely. If Owner and Contractor cannot agree as to entitlement to or on the amount or extent, if any, of any adjustment in Contract Price or Contract Times, or both, as a result of such Work stoppage or such special conditions under which Work is agreed to be resumed by Contractor, either party may make a Claim therefor as provided in Paragraph 10.05.

F. If after receipt of such written notice Contractor does not agree to resume such Work based on a reasonable belief it is unsafe, or does not agree to resume such Work under such special conditions, then Owner may order the portion of the Work that is in the area affected by such condition to be deleted from the Work. If Owner and Contractor cannot agree as to entitlement to or on the amount or extent, if any, of an adjustment in Contract Price or Contract Times as a result of deleting such portion of the Work, then either party may make a Claim therefor as provided in Paragraph 10.05. Owner may have such deleted portion of the Work performed by Owner's own forces or others in accordance with Article 7.

G. To the fullest extent permitted by Laws and Regulations, Owner shall indemnify and hold harmless Contractor, Subcontractors, and Engineer, and the officers, directors, members, partners, employees, agents, consultants, and subcontractors of each and any of them from and against all claims, costs, losses, and damages (including but not limited to all fees and charges of engineers, architects, attorneys, and other professionals and all court or arbitration or other dispute resolution costs) arising out of or relating to a Hazardous Environmental Condition, provided that such Hazardous Environmental Condition: (i) was not shown or indicated in the Drawings or Specifications or identified in the Contract Documents to be included within the scope of the Work, and (ii) was not created by

Contractor or by anyone for whom Contractor is responsible. Nothing in this Paragraph 4.06.G shall obligate Owner to indemnify any individual or entity from and against the consequences of that individual's or entity's own negligence.

H. To the fullest extent permitted by Laws and Regulations, Contractor shall indemnify and hold harmless Owner and Engineer, and the officers, directors, members, partners, employees, agents, consultants, and subcontractors of each and any of them from and against all claims, costs, losses, and damages (including but not limited to all fees and charges of engineers, architects, attorneys, and other professionals and all court or arbitration or other dispute resolution costs) arising out of or relating to a Hazardous Environmental Condition created by Contractor or by anyone for whom Contractor is responsible. Nothing in this Paragraph 4.06.H shall obligate Contractor to indemnify any individual or entity from and against the consequences of that individual's or entity's own negligence.

I. The provisions of Paragraphs 4.02, 4.03, and 4.04 do not apply to a Hazardous Environmental Condition uncovered or revealed at the Site.

ARTICLE 5 – BONDS AND INSURANCE

5.01 *Performance, Payment, and Other Bonds*

A. Contractor shall furnish performance and payment bonds, each in an amount at least equal to the Contract Price as security for the faithful performance and payment of all of Contractor's obligations under the Contract Documents. These bonds shall remain in effect until one year after the date when final payment becomes due or until completion of the correction period specified in Paragraph 13.07, whichever is later, except as provided otherwise by Laws or Regulations or by the Contract Documents. Contractor shall also furnish such other bonds as are required by the Contract Documents.

B. All bonds shall be in the form prescribed by the Contract Documents except as provided otherwise by Laws or Regulations, and shall be executed by such sureties as are named in the list of "Companies Holding Certificates of Authority as Acceptable Sureties on Federal Bonds and as Acceptable Reinsuring Companies" as published in Circular 570 (amended) by the Financial Management Service, Surety Bond Branch, U.S. Department of the Treasury. All bonds signed by

an agent or attorney-in-fact must be accompanied by a certified copy of that individual's authority to bind the surety. The evidence of authority shall show that it is effective on the date the agent or attorney-in-fact signed each bond.

- C. If the surety on any bond furnished by Contractor is declared bankrupt or becomes insolvent or its right to do business is terminated in any state where any part of the Project is located or it ceases to meet the requirements of Paragraph 5.01.B, Contractor shall promptly notify Owner and Engineer and shall, within 20 days after the event giving rise to such notification, provide another bond and surety, both of which shall comply with the requirements of Paragraphs 5.01.B and 5.02.

5.02 *Licensed Sureties and Insurers*

- A. All bonds and insurance required by the Contract Documents to be purchased and maintained by Owner or Contractor shall be obtained from surety or insurance companies that are duly licensed or authorized in the jurisdiction in which the Project is located to issue bonds or insurance policies for the limits and coverages so required. Such surety and insurance companies shall also meet such additional requirements and qualifications as may be provided in the Supplementary Conditions.

5.03 *Certificates of Insurance*

- A. Contractor shall deliver to Owner, with copies to each additional insured and loss payee identified in the Supplementary Conditions, certificates of insurance (and other evidence of insurance requested by Owner or any other additional insured) which Contractor is required to purchase and maintain.
- B. Owner shall deliver to Contractor, with copies to each additional insured and loss payee identified in the Supplementary Conditions, certificates of insurance (and other evidence of insurance requested by Contractor or any other additional insured) which Owner is required to purchase and maintain.
- C. Failure of Owner to demand such certificates or other evidence of Contractor's full compliance with these insurance requirements or failure of Owner to identify a deficiency in compliance from the evidence provided shall not be construed as a waiver of Contractor's obligation to maintain such insurance.

- D. Owner does not represent that insurance coverage and limits established in this Contract necessarily will be adequate to protect Contractor.

- E. The insurance and insurance limits required herein shall not be deemed as a limitation on Contractor's liability under the indemnities granted to Owner in the Contract Documents.

5.04 *Contractor's Insurance*

- A. Contractor shall purchase and maintain such insurance as is appropriate for the Work being performed and as will provide protection from claims set forth below which may arise out of or result from Contractor's performance of the Work and Contractor's other obligations under the Contract Documents, whether it is to be performed by Contractor, any Subcontractor or Supplier, or by anyone directly or indirectly employed by any of them to perform any of the Work, or by anyone for whose acts any of them may be liable:

1. claims under workers' compensation, disability benefits, and other similar employee benefit acts;
2. claims for damages because of bodily injury, occupational sickness or disease, or death of Contractor's employees;
3. claims for damages because of bodily injury, sickness or disease, or death of any person other than Contractor's employees;
4. claims for damages insured by reasonably available personal injury liability coverage which are sustained:
 - a. by any person as a result of an offense directly or indirectly related to the employment of such person by Contractor, or
 - b. by any other person for any other reason;
5. claims for damages, other than to the Work itself, because of injury to or destruction of tangible property wherever located, including loss of use resulting therefrom; and
6. claims for damages because of bodily injury or death of any person or property damage arising out of the ownership, maintenance or use of any motor vehicle.

B. The policies of insurance required by this Paragraph 5.04 shall:

1. with respect to insurance required by Paragraphs 5.04.A.3 through 5.04.A.6 inclusive, be written on an occurrence basis, include as additional insureds (subject to any customary exclusion regarding professional liability) Owner and Engineer, and any other individuals or entities identified in the Supplementary Conditions, all of whom shall be listed as additional insureds, and include coverage for the respective officers, directors, members, partners, employees, agents, consultants, and subcontractors of each and any of all such additional insureds, and the insurance afforded to these additional insureds shall provide primary coverage for all claims covered thereby;
2. include at least the specific coverages and be written for not less than the limits of liability provided in the Supplementary Conditions or required by Laws or Regulations, whichever is greater;
3. include contractual liability insurance covering Contractor's indemnity obligations under Paragraphs 6.11 and 6.20;
4. contain a provision or endorsement that the coverage afforded will not be canceled, materially changed or renewal refused until at least 30 days prior written notice has been given to Owner and Contractor and to each other additional insured identified in the Supplementary Conditions to whom a certificate of insurance has been issued (and the certificates of insurance furnished by the Contractor pursuant to Paragraph 5.03 will so provide);
5. remain in effect at least until final payment and at all times thereafter when Contractor may be correcting, removing, or replacing defective Work in accordance with Paragraph 13.07; and
6. include completed operations coverage:
 - a. Such insurance shall remain in effect for two years after final payment.
 - b. Contractor shall furnish Owner and each other additional insured identified in the Supplementary Conditions, to whom a

certificate of insurance has been issued, evidence satisfactory to Owner and any such additional insured of continuation of such insurance at final payment and one year thereafter.

5.05 *Owner's Liability Insurance*

- A. In addition to the insurance required to be provided by Contractor under Paragraph 5.04, Owner, at Owner's option, may purchase and maintain at Owner's expense Owner's own liability insurance as will protect Owner against claims which may arise from operations under the Contract Documents.

5.06 *Property Insurance*

- A. Unless otherwise provided in the Supplementary Conditions, Owner shall purchase and maintain property insurance upon the Work at the Site in the amount of the full replacement cost thereof (subject to such deductible amounts as may be provided in the Supplementary Conditions or required by Laws and Regulations). This insurance shall:
 1. include the interests of Owner, Contractor, Subcontractors, and Engineer, and any other individuals or entities identified in the Supplementary Conditions, and the officers, directors, members, partners, employees, agents, consultants, and subcontractors of each and any of them, each of whom is deemed to have an insurable interest and shall be listed as a loss payee;
 2. be written on a Builder's Risk "all-risk" policy form that shall at least include insurance for physical loss or damage to the Work, temporary buildings, falsework, and materials and equipment in transit, and shall insure against at least the following perils or causes of loss: fire, lightning, extended coverage, theft, vandalism and malicious mischief, earthquake, collapse, debris removal, demolition occasioned by enforcement of Laws and Regulations, water damage (other than that caused by flood), and such other perils or causes of loss as may be specifically required by the Supplementary Conditions.
 3. include expenses incurred in the repair or replacement of any insured property

(including but not limited to fees and charges of engineers and architects);

4. cover materials and equipment stored at the Site or at another location that was agreed to in writing by Owner prior to being incorporated in the Work, provided that such materials and equipment have been included in an Application for Payment recommended by Engineer;
 5. allow for partial utilization of the Work by Owner;
 6. include testing and startup; and
 7. be maintained in effect until final payment is made unless otherwise agreed to in writing by Owner, Contractor, and Engineer with 30 days written notice to each other loss payee to whom a certificate of insurance has been issued.
- B. Owner shall purchase and maintain such equipment breakdown insurance or additional property insurance as may be required by the Supplementary Conditions or Laws and Regulations which will include the interests of Owner, Contractor, Subcontractors, and Engineer, and any other individuals or entities identified in the Supplementary Conditions, and the officers, directors, members, partners, employees, agents, consultants and subcontractors of each and any of them, each of whom is deemed to have an insurable interest and shall be listed as a loss payee.
- C. All the policies of insurance (and the certificates or other evidence thereof) required to be purchased and maintained in accordance with this Paragraph 5.06 will contain a provision or endorsement that the coverage afforded will not be canceled or materially changed or renewal refused until at least 30 days prior written notice has been given to Owner and Contractor and to each other loss payee to whom a certificate of insurance has been issued and will contain waiver provisions in accordance with Paragraph 5.07.
- D. Owner shall not be responsible for purchasing and maintaining any property insurance specified in this Paragraph 5.06 to protect the interests of Contractor, Subcontractors, or others in the Work to the extent of any deductible amounts that are identified in the Supplementary Conditions. The risk of loss within such identified deductible

amount will be borne by Contractor, Subcontractors, or others suffering any such loss, and if any of them wishes property insurance coverage within the limits of such amounts, each may purchase and maintain it at the purchaser's own expense.

- E. If Contractor requests in writing that other special insurance be included in the property insurance policies provided under this Paragraph 5.06, Owner shall, if possible, include such insurance, and the cost thereof will be charged to Contractor by appropriate Change Order. Prior to commencement of the Work at the Site, Owner shall in writing advise Contractor whether or not such other insurance has been procured by Owner.

5.07 *Waiver of Rights*

- A. Owner and Contractor intend that all policies purchased in accordance with Paragraph 5.06 will protect Owner, Contractor, Subcontractors, and Engineer, and all other individuals or entities identified in the Supplementary Conditions as loss payees (and the officers, directors, members, partners, employees, agents, consultants, and subcontractors of each and any of them) in such policies and will provide primary coverage for all losses and damages caused by the perils or causes of loss covered thereby. All such policies shall contain provisions to the effect that in the event of payment of any loss or damage the insurers will have no rights of recovery against any of the insureds or loss payees thereunder. Owner and Contractor waive all rights against each other and their respective officers, directors, members, partners, employees, agents, consultants and subcontractors of each and any of them for all losses and damages caused by, arising out of or resulting from any of the perils or causes of loss covered by such policies and any other property insurance applicable to the Work; and, in addition, waive all such rights against Subcontractors and Engineer, and all other individuals or entities identified in the Supplementary Conditions as loss payees (and the officers, directors, members, partners, employees, agents, consultants, and subcontractors of each and any of them) under such policies for losses and damages so caused. None of the above waivers shall extend to the rights that any party making such waiver may have to the proceeds of insurance held by Owner as trustee or otherwise payable under any policy so issued.

B. Owner waives all rights against Contractor, Subcontractors, and Engineer, and the officers, directors, members, partners, employees, agents, consultants and subcontractors of each and any of them for:

1. loss due to business interruption, loss of use, or other consequential loss extending beyond direct physical loss or damage to Owner's property or the Work caused by, arising out of, or resulting from fire or other perils whether or not insured by Owner; and

2. loss or damage to the completed Project or part thereof caused by, arising out of, or resulting from fire or other insured peril or cause of loss covered by any property insurance maintained on the completed Project or part thereof by Owner during partial utilization pursuant to Paragraph 14.05, after Substantial Completion pursuant to Paragraph 14.04, or after final payment pursuant to Paragraph 14.07.

C. Any insurance policy maintained by Owner covering any loss, damage or consequential loss referred to in Paragraph 5.07.B shall contain provisions to the effect that in the event of payment of any such loss, damage, or consequential loss, the insurers will have no rights of recovery against Contractor, Subcontractors, or Engineer, and the officers, directors, members, partners, employees, agents, consultants and subcontractors of each and any of them.

5.08 *Receipt and Application of Insurance Proceeds*

A. Any insured loss under the policies of insurance required by Paragraph 5.06 will be adjusted with Owner and made payable to Owner as fiduciary for the loss payees, as their interests may appear, subject to the requirements of any applicable mortgage clause and of Paragraph 5.08.B. Owner shall deposit in a separate account any money so received and shall distribute it in accordance with such agreement as the parties in interest may reach. If no other special agreement is reached, the damaged Work shall be repaired or replaced, the moneys so received applied on account thereof, and the Work and the cost thereof covered by an appropriate Change Order.

B. Owner as fiduciary shall have power to adjust and settle any loss with the insurers unless one of the parties in interest shall object in writing within 15 days after the occurrence of loss to Owner's

exercise of this power. If such objection be made, Owner as fiduciary shall make settlement with the insurers in accordance with such agreement as the parties in interest may reach. If no such agreement among the parties in interest is reached, Owner as fiduciary shall adjust and settle the loss with the insurers and, if required in writing by any party in interest, Owner as fiduciary shall give bond for the proper performance of such duties.

5.09 *Acceptance of Bonds and Insurance; Option to Replace*

A. If either Owner or Contractor has any objection to the coverage afforded by or other provisions of the bonds or insurance required to be purchased and maintained by the other party in accordance with Article 5 on the basis of non-conformance with the Contract Documents, the objecting party shall so notify the other party in writing within 10 days after receipt of the certificates (or other evidence requested) required by Paragraph 2.01.B. Owner and Contractor shall each provide to the other such additional information in respect of insurance provided as the other may reasonably request. If either party does not purchase or maintain all of the bonds and insurance required of such party by the Contract Documents, such party shall notify the other party in writing of such failure to purchase prior to the start of the Work, or of such failure to maintain prior to any change in the required coverage. Without prejudice to any other right or remedy, the other party may elect to obtain equivalent bonds or insurance to protect such other party's interests at the expense of the party who was required to provide such coverage, and a Change Order shall be issued to adjust the Contract Price accordingly.

5.10 *Partial Utilization, Acknowledgment of Property Insurer*

A. If Owner finds it necessary to occupy or use a portion or portions of the Work prior to Substantial Completion of all the Work as provided in Paragraph 14.05, no such use or occupancy shall commence before the insurers providing the property insurance pursuant to Paragraph 5.06 have acknowledged notice thereof and in writing effected any changes in coverage necessitated thereby. The insurers providing the property insurance shall consent by endorsement on the policy or policies, but the property insurance shall not be canceled or permitted to lapse on account of any such partial use or occupancy.

ARTICLE 6 – CONTRACTOR’S RESPONSIBILITIES

6.01 *Supervision and Superintendence*

A. Contractor shall supervise, inspect, and direct the Work competently and efficiently, devoting such attention thereto and applying such skills and expertise as may be necessary to perform the Work in accordance with the Contract Documents. Contractor shall be solely responsible for the means, methods, techniques, sequences, and procedures of construction. Contractor shall not be responsible for the negligence of Owner or Engineer in the design or specification of a specific means, method, technique, sequence, or procedure of construction which is shown or indicated in and expressly required by the Contract Documents.

B. At all times during the progress of the Work, Contractor shall assign a competent resident superintendent who shall not be replaced without written notice to Owner and Engineer except under extraordinary circumstances.

6.02 *Labor; Working Hours*

A. Contractor shall provide competent, suitably qualified personnel to survey and lay out the Work and perform construction as required by the Contract Documents. Contractor shall at all times maintain good discipline and order at the Site.

B. Except as otherwise required for the safety or protection of persons or the Work or property at the Site or adjacent thereto, and except as otherwise stated in the Contract Documents, all Work at the Site shall be performed during regular working hours. Contractor will not permit the performance of Work on a Saturday, Sunday, or any legal holiday without Owner’s written consent (which will not be unreasonably withheld) given after prior written notice to Engineer.

6.03 *Services, Materials, and Equipment*

A. Unless otherwise specified in the Contract Documents, Contractor shall provide and assume full responsibility for all services, materials, equipment, labor, transportation, construction equipment and machinery, tools, appliances, fuel, power, light, heat, telephone, water, sanitary facilities, temporary facilities, and all other facilities and incidentals necessary for the performance, testing, start-up, and completion of the Work.

B. All materials and equipment incorporated into the Work shall be as specified or, if not specified, shall be of good quality and new, except as otherwise provided in the Contract Documents. All special warranties and guarantees required by the Specifications shall expressly run to the benefit of Owner. If required by Engineer, Contractor shall furnish satisfactory evidence (including reports of required tests) as to the source, kind, and quality of materials and equipment.

C. All materials and equipment shall be stored, applied, installed, connected, erected, protected, used, cleaned, and conditioned in accordance with instructions of the applicable Supplier, except as otherwise may be provided in the Contract Documents.

6.04 *Progress Schedule*

A. Contractor shall adhere to the Progress Schedule established in accordance with Paragraph 2.07 as it may be adjusted from time to time as provided below.

1. Contractor shall submit to Engineer for acceptance (to the extent indicated in Paragraph 2.07) proposed adjustments in the Progress Schedule that will not result in changing the Contract Times. Such adjustments will comply with any provisions of the General Requirements applicable thereto.

2. Proposed adjustments in the Progress Schedule that will change the Contract Times shall be submitted in accordance with the requirements of Article 12. Adjustments in Contract Times may only be made by a Change Order.

6.05 *Substitutes and “Or-Equals”*

A. Whenever an item of material or equipment is specified or described in the Contract Documents by using the name of a proprietary item or the name of a particular Supplier, the specification or description is intended to establish the type, function, appearance, and quality required. Unless the specification or description contains or is followed by words reading that no like, equivalent, or “or-equal” item or no substitution is permitted, other items of material or equipment or material or equipment of other Suppliers may be

submitted to Engineer for review under the circumstances described below.

1. *"Or-Equal" Items:* If in Engineer's sole discretion an item of material or equipment proposed by Contractor is functionally equal to that named and sufficiently similar so that no change in related Work will be required, it may be considered by Engineer as an "or-equal" item, in which case review and approval of the proposed item may, in Engineer's sole discretion, be accomplished without compliance with some or all of the requirements for approval of proposed substitute items. For the purposes of this Paragraph 6.05.A.1, a proposed item of material or equipment will be considered functionally equal to an item so named if:

a. in the exercise of reasonable judgment Engineer determines that:

- 1) it is at least equal in materials of construction, quality, durability, appearance, strength, and design characteristics;
- 2) it will reliably perform at least equally well the function and achieve the results imposed by the design concept of the completed Project as a functioning whole; and
- 3) it has a proven record of performance and availability of responsive service.

b. Contractor certifies that, if approved and incorporated into the Work:

- 1) there will be no increase in cost to the Owner or increase in Contract Times; and
- 2) it will conform substantially to the detailed requirements of the item named in the Contract Documents.

2. *Substitute Items:*

a. If in Engineer's sole discretion an item of material or equipment proposed by Contractor does not qualify as an "or-equal" item under Paragraph 6.05.A.1, it will be considered a proposed substitute item.

b. Contractor shall submit sufficient information as provided below to allow Engineer to determine if the item of material or equipment proposed is essentially equivalent to that named and an acceptable substitute therefor. Requests for review of proposed substitute items of material or equipment will not be accepted by Engineer from anyone other than Contractor.

c. The requirements for review by Engineer will be as set forth in Paragraph 6.05.A.2.d, as supplemented by the General Requirements, and as Engineer may decide is appropriate under the circumstances.

d. Contractor shall make written application to Engineer for review of a proposed substitute item of material or equipment that Contractor seeks to furnish or use. The application:

1) shall certify that the proposed substitute item will:

- a) perform adequately the functions and achieve the results called for by the general design,
- b) be similar in substance to that specified, and
- c) be suited to the same use as that specified;

2) will state:

- a) the extent, if any, to which the use of the proposed substitute item will prejudice Contractor's achievement of Substantial Completion on time,
- b) whether use of the proposed substitute item in the Work will require a change in any of the Contract Documents (or in the provisions of any other direct contract with Owner for other work on the Project) to adapt the design to the proposed substitute item, and

- c) whether incorporation or use of the proposed substitute item in connection with the Work is subject to payment of any license fee or royalty;
 - 3) will identify:
 - a) all variations of the proposed substitute item from that specified, and
 - b) available engineering, sales, maintenance, repair, and replacement services; and
 - 4) shall contain an itemized estimate of all costs or credits that will result directly or indirectly from use of such substitute item, including costs of redesign and claims of other contractors affected by any resulting change.
- 6.06
- B. *Substitute Construction Methods or Procedures:*** If a specific means, method, technique, sequence, or procedure of construction is expressly required by the Contract Documents, Contractor may furnish or utilize a substitute means, method, technique, sequence, or procedure of construction approved by Engineer. Contractor shall submit sufficient information to allow Engineer, in Engineer's sole discretion, to determine that the substitute proposed is equivalent to that expressly called for by the Contract Documents. The requirements for review by Engineer will be similar to those provided in Paragraph 6.05.A.2.
- C. *Engineer's Evaluation:*** Engineer will be allowed a reasonable time within which to evaluate each proposal or submittal made pursuant to Paragraphs 6.05.A and 6.05.B. Engineer may require Contractor to furnish additional data about the proposed substitute item. Engineer will be the sole judge of acceptability. No "or equal" or substitute will be ordered, installed or utilized until Engineer's review is complete, which will be evidenced by a Change Order in the case of a substitute and an approved Shop Drawing for an "or equal." Engineer will advise Contractor in writing of any negative determination.
- D. *Special Guarantee:*** Owner may require Contractor to furnish at Contractor's expense a special performance guarantee or other surety with respect to any substitute.
- E. *Engineer's Cost Reimbursement:*** Engineer will record Engineer's costs in evaluating a substitute proposed or submitted by Contractor pursuant to Paragraphs 6.05.A.2 and 6.05.B. Whether or not Engineer approves a substitute so proposed or submitted by Contractor, Contractor shall reimburse Owner for the reasonable charges of Engineer for evaluating each such proposed substitute. Contractor shall also reimburse Owner for the reasonable charges of Engineer for making changes in the Contract Documents (or in the provisions of any other direct contract with Owner) resulting from the acceptance of each proposed substitute.
- F. *Contractor's Expense:*** Contractor shall provide all data in support of any proposed substitute or "or-equal" at Contractor's expense.
- 6.06 *Concerning Subcontractors, Suppliers, and Others***
- A.** Contractor shall not employ any Subcontractor, Supplier, or other individual or entity (including those acceptable to Owner as indicated in Paragraph 6.06.B), whether initially or as a replacement, against whom Owner may have reasonable objection. Contractor shall not be required to employ any Subcontractor, Supplier, or other individual or entity to furnish or perform any of the Work against whom Contractor has reasonable objection.
- B.** If the Supplementary Conditions require the identity of certain Subcontractors, Suppliers, or other individuals or entities to be submitted to Owner in advance for acceptance by Owner by a specified date prior to the Effective Date of the Agreement, and if Contractor has submitted a list thereof in accordance with the Supplementary Conditions, Owner's acceptance (either in writing or by failing to make written objection thereto by the date indicated for acceptance or objection in the Bidding Documents or the Contract Documents) of any such Subcontractor, Supplier, or other individual or entity so identified may be revoked on the basis of reasonable objection after due investigation. Contractor shall submit an acceptable replacement for the rejected Subcontractor, Supplier, or other individual or entity, and the Contract Price will be adjusted by the difference in the cost occasioned by such replacement, and an appropriate Change Order will be issued. No acceptance by Owner of any such Subcontractor, Supplier, or other individual or entity, whether initially or as a replacement,

shall constitute a waiver of any right of Owner or Engineer to reject defective Work.

- C. Contractor shall be fully responsible to Owner and Engineer for all acts and omissions of the Subcontractors, Suppliers, and other individuals or entities performing or furnishing any of the Work just as Contractor is responsible for Contractor's own acts and omissions. Nothing in the Contract Documents:

1. shall create for the benefit of any such Subcontractor, Supplier, or other individual or entity any contractual relationship between Owner or Engineer and any such Subcontractor, Supplier or other individual or entity; nor
2. shall create any obligation on the part of Owner or Engineer to pay or to see to the payment of any moneys due any such Subcontractor, Supplier, or other individual or entity except as may otherwise be required by Laws and Regulations.

- D. Contractor shall be solely responsible for scheduling and coordinating the Work of Subcontractors, Suppliers, and other individuals or entities performing or furnishing any of the Work under a direct or indirect contract with Contractor.

- E. Contractor shall require all Subcontractors, Suppliers, and such other individuals or entities performing or furnishing any of the Work to communicate with Engineer through Contractor.

- F. The divisions and sections of the Specifications and the identifications of any Drawings shall not control Contractor in dividing the Work among Subcontractors or Suppliers or delineating the Work to be performed by any specific trade.

- G. All Work performed for Contractor by a Subcontractor or Supplier will be pursuant to an appropriate agreement between Contractor and the Subcontractor or Supplier which specifically binds the Subcontractor or Supplier to the applicable terms and conditions of the Contract Documents for the benefit of Owner and Engineer. Whenever any such agreement is with a Subcontractor or Supplier who is listed as a loss payee on the property insurance provided in Paragraph 5.06, the agreement between the Contractor and the Subcontractor or Supplier will contain provisions whereby the Subcontractor or Supplier waives all rights against Owner, Contractor, Engineer, and

all other individuals or entities identified in the Supplementary Conditions to be listed as insureds or loss payees (and the officers, directors, members, partners, employees, agents, consultants, and subcontractors of each and any of them) for all losses and damages caused by, arising out of, relating to, or resulting from any of the perils or causes of loss covered by such policies and any other property insurance applicable to the Work. If the insurers on any such policies require separate waiver forms to be signed by any Subcontractor or Supplier, Contractor will obtain the same.

6.07 *Patent Fees and Royalties*

- A. Contractor shall pay all license fees and royalties and assume all costs incident to the use in the performance of the Work or the incorporation in the Work of any invention, design, process, product, or device which is the subject of patent rights or copyrights held by others. If a particular invention, design, process, product, or device is specified in the Contract Documents for use in the performance of the Work and if, to the actual knowledge of Owner or Engineer, its use is subject to patent rights or copyrights calling for the payment of any license fee or royalty to others, the existence of such rights shall be disclosed by Owner in the Contract Documents.

- B. To the fullest extent permitted by Laws and Regulations, Owner shall indemnify and hold harmless Contractor, and its officers, directors, members, partners, employees, agents, consultants, and subcontractors from and against all claims, costs, losses, and damages (including but not limited to all fees and charges of engineers, architects, attorneys, and other professionals, and all court or arbitration or other dispute resolution costs) arising out of or relating to any infringement of patent rights or copyrights incident to the use in the performance of the Work or resulting from the incorporation in the Work of any invention, design, process, product, or device specified in the Contract Documents, but not identified as being subject to payment of any license fee or royalty to others required by patent rights or copyrights.

- C. To the fullest extent permitted by Laws and Regulations, Contractor shall indemnify and hold harmless Owner and Engineer, and the officers, directors, members, partners, employees, agents, consultants and subcontractors of each and any of them from and against all claims, costs, losses,

and damages (including but not limited to all fees and charges of engineers, architects, attorneys, and other professionals and all court or arbitration or other dispute resolution costs) arising out of or relating to any infringement of patent rights or copyrights incident to the use in the performance of the Work or resulting from the incorporation in the Work of any invention, design, process, product, or device not specified in the Contract Documents.

6.08 *Permits*

- A. Unless otherwise provided in the Supplementary Conditions, Contractor shall obtain and pay for all construction permits and licenses. Owner shall assist Contractor, when necessary, in obtaining such permits and licenses. Contractor shall pay all governmental charges and inspection fees necessary for the prosecution of the Work which are applicable at the time of opening of Bids, or, if there are no Bids, on the Effective Date of the Agreement. Owner shall pay all charges of utility owners for connections for providing permanent service to the Work.

6.09 *Laws and Regulations*

- A. Contractor shall give all notices required by and shall comply with all Laws and Regulations applicable to the performance of the Work. Except where otherwise expressly required by applicable Laws and Regulations, neither Owner nor Engineer shall be responsible for monitoring Contractor's compliance with any Laws or Regulations.
- B. If Contractor performs any Work knowing or having reason to know that it is contrary to Laws or Regulations, Contractor shall bear all claims, costs, losses, and damages (including but not limited to all fees and charges of engineers, architects, attorneys, and other professionals and all court or arbitration or other dispute resolution costs) arising out of or relating to such Work. However, it shall not be Contractor's responsibility to make certain that the Specifications and Drawings are in accordance with Laws and Regulations, but this shall not relieve Contractor of Contractor's obligations under Paragraph 3.03.
- C. Changes in Laws or Regulations not known at the time of opening of Bids (or, on the Effective Date of the Agreement if there were no Bids) having an effect on the cost or time of performance of the

Work shall be the subject of an adjustment in Contract Price or Contract Times. If Owner and Contractor are unable to agree on entitlement to or on the amount or extent, if any, of any such adjustment, a Claim may be made therefor as provided in Paragraph 10.05.

6.10 *Taxes*

- A. Contractor shall pay all sales, consumer, use, and other similar taxes required to be paid by Contractor in accordance with the Laws and Regulations of the place of the Project which are applicable during the performance of the Work.

6.11 *Use of Site and Other Areas*

A. *Limitation on Use of Site and Other Areas:*

1. Contractor shall confine construction equipment, the storage of materials and equipment, and the operations of workers to the Site and other areas permitted by Laws and Regulations, and shall not unreasonably encumber the Site and other areas with construction equipment or other materials or equipment. Contractor shall assume full responsibility for any damage to any such land or area, or to the owner or occupant thereof, or of any adjacent land or areas resulting from the performance of the Work.
2. Should any claim be made by any such owner or occupant because of the performance of the Work, Contractor shall promptly settle with such other party by negotiation or otherwise resolve the claim by arbitration or other dispute resolution proceeding or at law.
3. To the fullest extent permitted by Laws and Regulations, Contractor shall indemnify and hold harmless Owner and Engineer, and the officers, directors, members, partners, employees, agents, consultants and subcontractors of each and any of them from and against all claims, costs, losses, and damages (including but not limited to all fees and charges of engineers, architects, attorneys, and other professionals and all court or arbitration or other dispute resolution costs) arising out of or relating to any claim or action, legal or equitable, brought by any such owner or occupant against Owner, Engineer, or any other party indemnified hereunder to the extent caused by or based upon Contractor's performance of the Work.

- B. *Removal of Debris During Performance of the Work:* During the progress of the Work Contractor shall keep the Site and other areas free from accumulations of waste materials, rubbish, and other debris. Removal and disposal of such waste materials, rubbish, and other debris shall conform to applicable Laws and Regulations.
- C. *Cleaning:* Prior to Substantial Completion of the Work Contractor shall clean the Site and the Work and make it ready for utilization by Owner. At the completion of the Work Contractor shall remove from the Site all tools, appliances, construction equipment and machinery, and surplus materials and shall restore to original condition all property not designated for alteration by the Contract Documents.
- D. *Loading Structures:* Contractor shall not load nor permit any part of any structure to be loaded in any manner that will endanger the structure, nor shall Contractor subject any part of the Work or adjacent property to stresses or pressures that will endanger it.

6.12 *Record Documents*

- A. Contractor shall maintain in a safe place at the Site one record copy of all Drawings, Specifications, Addenda, Change Orders, Work Change Directives, Field Orders, and written interpretations and clarifications in good order and annotated to show changes made during construction. These record documents together with all approved Samples and a counterpart of all approved Shop Drawings will be available to Engineer for reference. Upon completion of the Work, these record documents, Samples, and Shop Drawings will be delivered to Engineer for Owner.

6.13 *Safety and Protection*

- A. Contractor shall be solely responsible for initiating, maintaining and supervising all safety precautions and programs in connection with the Work. Such responsibility does not relieve Subcontractors of their responsibility for the safety of persons or property in the performance of their work, nor for compliance with applicable safety Laws and Regulations. Contractor shall take all necessary precautions for the safety of, and shall provide the necessary protection to prevent damage, injury or loss to:

- 1. all persons on the Site or who may be affected by the Work;
 - 2. all the Work and materials and equipment to be incorporated therein, whether in storage on or off the Site; and
 - 3. other property at the Site or adjacent thereto, including trees, shrubs, lawns, walks, pavements, roadways, structures, utilities, and Underground Facilities not designated for removal, relocation, or replacement in the course of construction.
- B. Contractor shall comply with all applicable Laws and Regulations relating to the safety of persons or property, or to the protection of persons or property from damage, injury, or loss; and shall erect and maintain all necessary safeguards for such safety and protection. Contractor shall notify owners of adjacent property and of Underground Facilities and other utility owners when prosecution of the Work may affect them, and shall cooperate with them in the protection, removal, relocation, and replacement of their property.
 - C. Contractor shall comply with the applicable requirements of Owner's safety programs, if any. The Supplementary Conditions identify any Owner's safety programs that are applicable to the Work.
 - D. Contractor shall inform Owner and Engineer of the specific requirements of Contractor's safety program with which Owner's and Engineer's employees and representatives must comply while at the Site.
 - E. All damage, injury, or loss to any property referred to in Paragraph 6.13.A.2 or 6.13.A.3 caused, directly or indirectly, in whole or in part, by Contractor, any Subcontractor, Supplier, or any other individual or entity directly or indirectly employed by any of them to perform any of the Work, or anyone for whose acts any of them may be liable, shall be remedied by Contractor (except damage or loss attributable to the fault of Drawings or Specifications or to the acts or omissions of Owner or Engineer or anyone employed by any of them, or anyone for whose acts any of them may be liable, and not attributable, directly or indirectly, in whole or in part, to the fault or negligence of Contractor or any Subcontractor, Supplier, or other individual or

entity directly or indirectly employed by any of them).

- F. Contractor's duties and responsibilities for safety and for protection of the Work shall continue until such time as all the Work is completed and Engineer has issued a notice to Owner and Contractor in accordance with Paragraph 14.07.B that the Work is acceptable (except as otherwise expressly provided in connection with Substantial Completion).

6.14 *Safety Representative*

- A. Contractor shall designate a qualified and experienced safety representative at the Site whose duties and responsibilities shall be the prevention of accidents and the maintaining and supervising of safety precautions and programs.

6.15 *Hazard Communication Programs*

- A. Contractor shall be responsible for coordinating any exchange of material safety data sheets or other hazard communication information required to be made available to or exchanged between or among employers at the Site in accordance with Laws or Regulations.

6.16 *Emergencies*

- A. In emergencies affecting the safety or protection of persons or the Work or property at the Site or adjacent thereto, Contractor is obligated to act to prevent threatened damage, injury, or loss. Contractor shall give Engineer prompt written notice if Contractor believes that any significant changes in the Work or variations from the Contract Documents have been caused thereby or are required as a result thereof. If Engineer determines that a change in the Contract Documents is required because of the action taken by Contractor in response to such an emergency, a Work Change Directive or Change Order will be issued.

6.17 *Shop Drawings and Samples*

- A. Contractor shall submit Shop Drawings and Samples to Engineer for review and approval in accordance with the accepted Schedule of Submittals (as required by Paragraph 2.07). Each submittal will be identified as Engineer may require.

1. *Shop Drawings:*

- a. Submit number of copies specified in the General Requirements.
- b. Data shown on the Shop Drawings will be complete with respect to quantities, dimensions, specified performance and design criteria, materials, and similar data to show Engineer the services, materials, and equipment Contractor proposes to provide and to enable Engineer to review the information for the limited purposes required by Paragraph 6.17.D.

2. *Samples:*

- a. Submit number of Samples specified in the Specifications.
- b. Clearly identify each Sample as to material, Supplier, pertinent data such as catalog numbers, the use for which intended and other data as Engineer may require to enable Engineer to review the submittal for the limited purposes required by Paragraph 6.17.D.

- B. Where a Shop Drawing or Sample is required by the Contract Documents or the Schedule of Submittals, any related Work performed prior to Engineer's review and approval of the pertinent submittal will be at the sole expense and responsibility of Contractor.

C. *Submittal Procedures:*

- 1. Before submitting each Shop Drawing or Sample, Contractor shall have:
 - a. reviewed and coordinated each Shop Drawing or Sample with other Shop Drawings and Samples and with the requirements of the Work and the Contract Documents;
 - b. determined and verified all field measurements, quantities, dimensions, specified performance and design criteria, installation requirements, materials, catalog numbers, and similar information with respect thereto;
 - c. determined and verified the suitability of all materials offered with respect to the

indicated application, fabrication, shipping, handling, storage, assembly, and installation pertaining to the performance of the Work; and

- d. determined and verified all information relative to Contractor's responsibilities for means, methods, techniques, sequences, and procedures of construction, and safety precautions and programs incident thereto.
2. Each submittal shall bear a stamp or specific written certification that Contractor has satisfied Contractor's obligations under the Contract Documents with respect to Contractor's review and approval of that submittal.
3. With each submittal, Contractor shall give Engineer specific written notice of any variations that the Shop Drawing or Sample may have from the requirements of the Contract Documents. This notice shall be both a written communication separate from the Shop Drawings or Sample submittal; and, in addition, by a specific notation made on each Shop Drawing or Sample submitted to Engineer for review and approval of each such variation.

D. Engineer's Review:

1. Engineer will provide timely review of Shop Drawings and Samples in accordance with the Schedule of Submittals acceptable to Engineer. Engineer's review and approval will be only to determine if the items covered by the submittals will, after installation or incorporation in the Work, conform to the information given in the Contract Documents and be compatible with the design concept of the completed Project as a functioning whole as indicated by the Contract Documents.
2. Engineer's review and approval will not extend to means, methods, techniques, sequences, or procedures of construction (except where a particular means, method, technique, sequence, or procedure of construction is specifically and expressly called for by the Contract Documents) or to safety precautions or programs incident thereto. The review and approval of a separate item as such will not indicate

approval of the assembly in which the item functions.

3. Engineer's review and approval shall not relieve Contractor from responsibility for any variation from the requirements of the Contract Documents unless Contractor has complied with the requirements of Paragraph 6.17.C.3 and Engineer has given written approval of each such variation by specific written notation thereof incorporated in or accompanying the Shop Drawing or Sample. Engineer's review and approval shall not relieve Contractor from responsibility for complying with the requirements of Paragraph 6.17.C.1.

E. Resubmittal Procedures:

1. Contractor shall make corrections required by Engineer and shall return the required number of corrected copies of Shop Drawings and submit, as required, new Samples for review and approval. Contractor shall direct specific attention in writing to revisions other than the corrections called for by Engineer on previous submittals.

Continuing the Work

- A. Contractor shall carry on the Work and adhere to the Progress Schedule during all disputes or disagreements with Owner. No Work shall be delayed or postponed pending resolution of any disputes or disagreements, except as permitted by Paragraph 15.04 or as Owner and Contractor may otherwise agree in writing.

Contractor's General Warranty and Guarantee

- A. Contractor warrants and guarantees to Owner that all Work will be in accordance with the Contract Documents and will not be defective. Engineer and its officers, directors, members, partners, employees, agents, consultants, and subcontractors shall be entitled to rely on representation of Contractor's warranty and guarantee.
- B. Contractor's warranty and guarantee hereunder excludes defects or damage caused by:
 1. abuse, modification, or improper maintenance or operation by persons other than Contractor, Subcontractors, Suppliers, or any other

individual or entity for whom Contractor is responsible; or

2. normal wear and tear under normal usage.
- C. Contractor's obligation to perform and complete the Work in accordance with the Contract Documents shall be absolute. None of the following will constitute an acceptance of Work that is not in accordance with the Contract Documents or a release of Contractor's obligation to perform the Work in accordance with the Contract Documents:
 1. observations by Engineer;
 2. recommendation by Engineer or payment by Owner of any progress or final payment;
 3. the issuance of a certificate of Substantial Completion by Engineer or any payment related thereto by Owner;
 4. use or occupancy of the Work or any part thereof by Owner;
 5. any review and approval of a Shop Drawing or Sample submittal or the issuance of a notice of acceptability by Engineer;
 6. any inspection, test, or approval by others; or
 7. any correction of defective Work by Owner.

6.20 *Indemnification*

- A. To the fullest extent permitted by Laws and Regulations, Contractor shall indemnify and hold harmless Owner and Engineer, and the officers, directors, members, partners, employees, agents, consultants and subcontractors of each and any of them from and against all claims, costs, losses, and damages (including but not limited to all fees and charges of engineers, architects, attorneys, and other professionals and all court or arbitration or other dispute resolution costs) arising out of or relating to the performance of the Work, provided that any such claim, cost, loss, or damage is attributable to bodily injury, sickness, disease, or death, or to injury to or destruction of tangible property (other than the Work itself), including the loss of use resulting therefrom but only to the extent caused by any negligent act or omission of Contractor, any Subcontractor, any Supplier, or any individual or entity directly or indirectly employed by any of them to perform any of the

Work or anyone for whose acts any of them may be liable .

- B. In any and all claims against Owner or Engineer or any of their officers, directors, members, partners, employees, agents, consultants, or subcontractors by any employee (or the survivor or personal representative of such employee) of Contractor, any Subcontractor, any Supplier, or any individual or entity directly or indirectly employed by any of them to perform any of the Work, or anyone for whose acts any of them may be liable, the indemnification obligation under Paragraph 6.20.A shall not be limited in any way by any limitation on the amount or type of damages, compensation, or benefits payable by or for Contractor or any such Subcontractor, Supplier, or other individual or entity under workers' compensation acts, disability benefit acts, or other employee benefit acts.
- C. The indemnification obligations of Contractor under Paragraph 6.20.A shall not extend to the liability of Engineer and Engineer's officers, directors, members, partners, employees, agents, consultants and subcontractors arising out of:
 1. the preparation or approval of, or the failure to prepare or approve maps, Drawings, opinions, reports, surveys, Change Orders, designs, or Specifications; or
 2. giving directions or instructions, or failing to give them, if that is the primary cause of the injury or damage.

6.21 *Delegation of Professional Design Services*

- A. Contractor will not be required to provide professional design services unless such services are specifically required by the Contract Documents for a portion of the Work or unless such services are required to carry out Contractor's responsibilities for construction means, methods, techniques, sequences and procedures. Contractor shall not be required to provide professional services in violation of applicable law.
- B. If professional design services or certifications by a design professional related to systems, materials or equipment are specifically required of Contractor by the Contract Documents, Owner and Engineer will specify all performance and design criteria that such services must satisfy. Contractor shall cause such services or

certifications to be provided by a properly licensed professional, whose signature and seal shall appear on all drawings, calculations, specifications, certifications, Shop Drawings and other submittals prepared by such professional. Shop Drawings and other submittals related to the Work designed or certified by such professional, if prepared by others, shall bear such professional's written approval when submitted to Engineer.

- C. Owner and Engineer shall be entitled to rely upon the adequacy, accuracy and completeness of the services, certifications or approvals performed by such design professionals, provided Owner and Engineer have specified to Contractor all performance and design criteria that such services must satisfy.
- D. Pursuant to this Paragraph 6.21, Engineer's review and approval of design calculations and design drawings will be only for the limited purpose of checking for conformance with performance and design criteria given and the design concept expressed in the Contract Documents. Engineer's review and approval of Shop Drawings and other submittals (except design calculations and design drawings) will be only for the purpose stated in Paragraph 6.17.D.1.
- E. Contractor shall not be responsible for the adequacy of the performance or design criteria required by the Contract Documents.

ARTICLE 7 – OTHER WORK AT THE SITE

7.01 *Related Work at Site*

- A. Owner may perform other work related to the Project at the Site with Owner's employees, or through other direct contracts therefor, or have other work performed by utility owners. If such other work is not noted in the Contract Documents, then:
 - 1. written notice thereof will be given to Contractor prior to starting any such other work; and
 - 2. if Owner and Contractor are unable to agree on entitlement to or on the amount or extent, if any, of any adjustment in the Contract Price or Contract Times that should be allowed as a result of such other work, a Claim may be made therefor as provided in Paragraph 10.05.

B. Contractor shall afford each other contractor who is a party to such a direct contract, each utility owner, and Owner, if Owner is performing other work with Owner's employees, proper and safe access to the Site, provide a reasonable opportunity for the introduction and storage of materials and equipment and the execution of such other work, and properly coordinate the Work with theirs. Contractor shall do all cutting, fitting, and patching of the Work that may be required to properly connect or otherwise make its several parts come together and properly integrate with such other work. Contractor shall not endanger any work of others by cutting, excavating, or otherwise altering such work; provided, however, that Contractor may cut or alter others' work with the written consent of Engineer and the others whose work will be affected. The duties and responsibilities of Contractor under this Paragraph are for the benefit of such utility owners and other contractors to the extent that there are comparable provisions for the benefit of Contractor in said direct contracts between Owner and such utility owners and other contractors.

- C. If the proper execution or results of any part of Contractor's Work depends upon work performed by others under this Article 7, Contractor shall inspect such other work and promptly report to Engineer in writing any delays, defects, or deficiencies in such other work that render it unavailable or unsuitable for the proper execution and results of Contractor's Work. Contractor's failure to so report will constitute an acceptance of such other work as fit and proper for integration with Contractor's Work except for latent defects and deficiencies in such other work.

7.02 *Coordination*

- A. If Owner intends to contract with others for the performance of other work on the Project at the Site, the following will be set forth in Supplementary Conditions:
 - 1. the individual or entity who will have authority and responsibility for coordination of the activities among the various contractors will be identified;
 - 2. the specific matters to be covered by such authority and responsibility will be itemized; and
 - 3. the extent of such authority and responsibilities will be provided.

- B. Unless otherwise provided in the Supplementary Conditions, Owner shall have sole authority and responsibility for such coordination.

Contractor copies of reports of explorations and tests of subsurface conditions and drawings of physical conditions relating to existing surface or subsurface structures at the Site.

7.03 *Legal Relationships*

- A. Paragraphs 7.01.A and 7.02 are not applicable for utilities not under the control of Owner.
- B. Each other direct contract of Owner under Paragraph 7.01.A shall provide that the other contractor is liable to Owner and Contractor for the reasonable direct delay and disruption costs incurred by Contractor as a result of the other contractor's wrongful actions or inactions.
- C. Contractor shall be liable to Owner and any other contractor under direct contract to Owner for the reasonable direct delay and disruption costs incurred by such other contractor as a result of Contractor's wrongful action or inactions.

8.06 *Insurance*

- A. Owner's responsibilities, if any, with respect to purchasing and maintaining liability and property insurance are set forth in Article 5.

8.07 *Change Orders*

- A. Owner is obligated to execute Change Orders as indicated in Paragraph 10.03.

8.08 *Inspections, Tests, and Approvals*

- A. Owner's responsibility with respect to certain inspections, tests, and approvals is set forth in Paragraph 13.03.B.

ARTICLE 8 – OWNER'S RESPONSIBILITIES

8.09 *Limitations on Owner's Responsibilities*

8.01 *Communications to Contractor*

- A. Except as otherwise provided in these General Conditions, Owner shall issue all communications to Contractor through Engineer.

8.02 *Replacement of Engineer*

- A. In case of termination of the employment of Engineer, Owner shall appoint an engineer to whom Contractor makes no reasonable objection, whose status under the Contract Documents shall be that of the former Engineer.

8.03 *Furnish Data*

- A. Owner shall promptly furnish the data required of Owner under the Contract Documents.

8.04 *Pay When Due*

- A. Owner shall make payments to Contractor when they are due as provided in Paragraphs 14.02.C and 14.07.C.

8.05 *Lands and Easements; Reports and Tests*

- A. Owner's duties with respect to providing lands and easements and providing engineering surveys to establish reference points are set forth in Paragraphs 4.01 and 4.05. Paragraph 4.02 refers to Owner's identifying and making available to

- A. The Owner shall not supervise, direct, or have control or authority over, nor be responsible for, Contractor's means, methods, techniques, sequences, or procedures of construction, or the safety precautions and programs incident thereto, or for any failure of Contractor to comply with Laws and Regulations applicable to the performance of the Work. Owner will not be responsible for Contractor's failure to perform the Work in accordance with the Contract Documents.

8.10 *Undisclosed Hazardous Environmental Condition*

- A. Owner's responsibility in respect to an undisclosed Hazardous Environmental Condition is set forth in Paragraph 4.06.

8.11 *Evidence of Financial Arrangements*

- A. Upon request of Contractor, Owner shall furnish Contractor reasonable evidence that financial arrangements have been made to satisfy Owner's obligations under the Contract Documents.

8.12 *Compliance with Safety Program*

- A. While at the Site, Owner's employees and representatives shall comply with the specific applicable requirements of Contractor's safety programs of which Owner has been informed pursuant to Paragraph 6.13.D.

ARTICLE 9 – ENGINEER’S STATUS DURING CONSTRUCTION

9.01 *Owner’s Representative*

- A. Engineer will be Owner’s representative during the construction period. The duties and responsibilities and the limitations of authority of Engineer as Owner’s representative during construction are set forth in the Contract Documents.

9.02 *Visits to Site*

- A. Engineer will make visits to the Site at intervals appropriate to the various stages of construction as Engineer deems necessary in order to observe as an experienced and qualified design professional the progress that has been made and the quality of the various aspects of Contractor’s executed Work. Based on information obtained during such visits and observations, Engineer, for the benefit of Owner, will determine, in general, if the Work is proceeding in accordance with the Contract Documents. Engineer will not be required to make exhaustive or continuous inspections on the Site to check the quality or quantity of the Work. Engineer’s efforts will be directed toward providing for Owner a greater degree of confidence that the completed Work will conform generally to the Contract Documents. On the basis of such visits and observations, Engineer will keep Owner informed of the progress of the Work and will endeavor to guard Owner against defective Work.
- B. Engineer’s visits and observations are subject to all the limitations on Engineer’s authority and responsibility set forth in Paragraph 9.09. Particularly, but without limitation, during or as a result of Engineer’s visits or observations of Contractor’s Work, Engineer will not supervise, direct, control, or have authority over or be responsible for Contractor’s means, methods, techniques, sequences, or procedures of construction, or the safety precautions and programs incident thereto, or for any failure of Contractor to comply with Laws and Regulations applicable to the performance of the Work.

9.03 *Project Representative*

- A. If Owner and Engineer agree, Engineer will furnish a Resident Project Representative to assist Engineer in providing more extensive observation of the Work. The authority and responsibilities of

any such Resident Project Representative and assistants will be as provided in the Supplementary Conditions, and limitations on the responsibilities thereof will be as provided in Paragraph 9.09. If Owner designates another representative or agent to represent Owner at the Site who is not Engineer’s consultant, agent or employee, the responsibilities and authority and limitations thereon of such other individual or entity will be as provided in the Supplementary Conditions.

9.04 *Authorized Variations in Work*

- A. Engineer may authorize minor variations in the Work from the requirements of the Contract Documents which do not involve an adjustment in the Contract Price or the Contract Times and are compatible with the design concept of the completed Project as a functioning whole as indicated by the Contract Documents. These may be accomplished by a Field Order and will be binding on Owner and also on Contractor, who shall perform the Work involved promptly. If Owner or Contractor believes that a Field Order justifies an adjustment in the Contract Price or Contract Times, or both, and the parties are unable to agree on entitlement to or on the amount or extent, if any, of any such adjustment, a Claim may be made therefor as provided in Paragraph 10.05.

9.05 *Rejecting Defective Work*

- A. Engineer will have authority to reject Work which Engineer believes to be defective, or that Engineer believes will not produce a completed Project that conforms to the Contract Documents or that will prejudice the integrity of the design concept of the completed Project as a functioning whole as indicated by the Contract Documents. Engineer will also have authority to require special inspection or testing of the Work as provided in Paragraph 13.04, whether or not the Work is fabricated, installed, or completed.

9.06 *Shop Drawings, Change Orders and Payments*

- A. In connection with Engineer’s authority, and limitations thereof, as to Shop Drawings and Samples, see Paragraph 6.17.
- B. In connection with Engineer’s authority, and limitations thereof, as to design calculations and design drawings submitted in response to a

delegation of professional design services, if any, see Paragraph 6.21.

- C. In connection with Engineer's authority as to Change Orders, see Articles 10, 11, and 12.
- D. In connection with Engineer's authority as to Applications for Payment, see Article 14.

9.07 *Determinations for Unit Price Work*

- A. Engineer will determine the actual quantities and classifications of Unit Price Work performed by Contractor. Engineer will review with Contractor the Engineer's preliminary determinations on such matters before rendering a written decision thereon (by recommendation of an Application for Payment or otherwise). Engineer's written decision thereon will be final and binding (except as modified by Engineer to reflect changed factual conditions or more accurate data) upon Owner and Contractor, subject to the provisions of Paragraph 10.05.

9.08 *Decisions on Requirements of Contract Documents and Acceptability of Work*

- A. Engineer will be the initial interpreter of the requirements of the Contract Documents and judge of the acceptability of the Work thereunder. All matters in question and other matters between Owner and Contractor arising prior to the date final payment is due relating to the acceptability of the Work, and the interpretation of the requirements of the Contract Documents pertaining to the performance of the Work, will be referred initially to Engineer in writing within 30 days of the event giving rise to the question.
- B. Engineer will, with reasonable promptness, render a written decision on the issue referred. If Owner or Contractor believes that any such decision entitles them to an adjustment in the Contract Price or Contract Times or both, a Claim may be made under Paragraph 10.05. The date of Engineer's decision shall be the date of the event giving rise to the issues referenced for the purposes of Paragraph 10.05.B.
- C. Engineer's written decision on the issue referred will be final and binding on Owner and Contractor, subject to the provisions of Paragraph 10.05.
- D. When functioning as interpreter and judge under this Paragraph 9.08, Engineer will not show

partiality to Owner or Contractor and will not be liable in connection with any interpretation or decision rendered in good faith in such capacity.

9.09 *Limitations on Engineer's Authority and Responsibilities*

- A. Neither Engineer's authority or responsibility under this Article 9 or under any other provision of the Contract Documents nor any decision made by Engineer in good faith either to exercise or not exercise such authority or responsibility or the undertaking, exercise, or performance of any authority or responsibility by Engineer shall create, impose, or give rise to any duty in contract, tort, or otherwise owed by Engineer to Contractor, any Subcontractor, any Supplier, any other individual or entity, or to any surety for or employee or agent of any of them.
- B. Engineer will not supervise, direct, control, or have authority over or be responsible for Contractor's means, methods, techniques, sequences, or procedures of construction, or the safety precautions and programs incident thereto, or for any failure of Contractor to comply with Laws and Regulations applicable to the performance of the Work. Engineer will not be responsible for Contractor's failure to perform the Work in accordance with the Contract Documents.
- C. Engineer will not be responsible for the acts or omissions of Contractor or of any Subcontractor, any Supplier, or of any other individual or entity performing any of the Work.
- D. Engineer's review of the final Application for Payment and accompanying documentation and all maintenance and operating instructions, schedules, guarantees, bonds, certificates of inspection, tests and approvals, and other documentation required to be delivered by Paragraph 14.07.A will only be to determine generally that their content complies with the requirements of, and in the case of certificates of inspections, tests, and approvals that the results certified indicate compliance with, the Contract Documents.
- E. The limitations upon authority and responsibility set forth in this Paragraph 9.09 shall also apply to the Resident Project Representative, if any, and assistants, if any.

9.10 *Compliance with Safety Program*

- A. While at the Site, Engineer's employees and representatives shall comply with the specific applicable requirements of Contractor's safety programs of which Engineer has been informed pursuant to Paragraph 6.13.D.

ARTICLE 10 – CHANGES IN THE WORK; CLAIMS

10.01 *Authorized Changes in the Work*

- A. Without invalidating the Contract and without notice to any surety, Owner may, at any time or from time to time, order additions, deletions, or revisions in the Work by a Change Order, or a Work Change Directive. Upon receipt of any such document, Contractor shall promptly proceed with the Work involved which will be performed under the applicable conditions of the Contract Documents (except as otherwise specifically provided).
- B. If Owner and Contractor are unable to agree on entitlement to, or on the amount or extent, if any, of an adjustment in the Contract Price or Contract Times, or both, that should be allowed as a result of a Work Change Directive, a Claim may be made therefor as provided in Paragraph 10.05.

10.02 *Unauthorized Changes in the Work*

- A. Contractor shall not be entitled to an increase in the Contract Price or an extension of the Contract Times with respect to any work performed that is not required by the Contract Documents as amended, modified, or supplemented as provided in Paragraph 3.04, except in the case of an emergency as provided in Paragraph 6.16 or in the case of uncovering Work as provided in Paragraph 13.04.D.

10.03 *Execution of Change Orders*

- A. Owner and Contractor shall execute appropriate Change Orders recommended by Engineer covering:
 - 1. changes in the Work which are: (i) ordered by Owner pursuant to Paragraph 10.01.A, (ii) required because of acceptance of defective Work under Paragraph 13.08.A or Owner's correction of defective Work under Paragraph 13.09, or (iii) agreed to by the parties;

- 2. changes in the Contract Price or Contract Times which are agreed to by the parties, including any undisputed sum or amount of time for Work actually performed in accordance with a Work Change Directive; and
- 3. changes in the Contract Price or Contract Times which embody the substance of any written decision rendered by Engineer pursuant to Paragraph 10.05; provided that, in lieu of executing any such Change Order, an appeal may be taken from any such decision in accordance with the provisions of the Contract Documents and applicable Laws and Regulations, but during any such appeal, Contractor shall carry on the Work and adhere to the Progress Schedule as provided in Paragraph 6.18.A.

10.04 *Notification to Surety*

- A. If the provisions of any bond require notice to be given to a surety of any change affecting the general scope of the Work or the provisions of the Contract Documents (including, but not limited to, Contract Price or Contract Times), the giving of any such notice will be Contractor's responsibility. The amount of each applicable bond will be adjusted to reflect the effect of any such change.

10.05 *Claims*

- A. *Engineer's Decision Required:* All Claims, except those waived pursuant to Paragraph 14.09, shall be referred to the Engineer for decision. A decision by Engineer shall be required as a condition precedent to any exercise by Owner or Contractor of any rights or remedies either may otherwise have under the Contract Documents or by Laws and Regulations in respect of such Claims.
- B. *Notice:* Written notice stating the general nature of each Claim shall be delivered by the claimant to Engineer and the other party to the Contract promptly (but in no event later than 30 days) after the start of the event giving rise thereto. The responsibility to substantiate a Claim shall rest with the party making the Claim. Notice of the amount or extent of the Claim, with supporting data shall be delivered to the Engineer and the other party to the Contract within 60 days after the start of such event (unless Engineer allows additional time for claimant to submit additional

or more accurate data in support of such Claim). A Claim for an adjustment in Contract Price shall be prepared in accordance with the provisions of Paragraph 12.01.B. A Claim for an adjustment in Contract Times shall be prepared in accordance with the provisions of Paragraph 12.02.B. Each Claim shall be accompanied by claimant's written statement that the adjustment claimed is the entire adjustment to which the claimant believes it is entitled as a result of said event. The opposing party shall submit any response to Engineer and the claimant within 30 days after receipt of the claimant's last submittal (unless Engineer allows additional time).

- C. *Engineer's Action:* Engineer will review each Claim and, within 30 days after receipt of the last submittal of the claimant or the last submittal of the opposing party, if any, take one of the following actions in writing:
1. deny the Claim in whole or in part;
 2. approve the Claim; or
 3. notify the parties that the Engineer is unable to resolve the Claim if, in the Engineer's sole discretion, it would be inappropriate for the Engineer to do so. For purposes of further resolution of the Claim, such notice shall be deemed a denial.
- D. In the event that Engineer does not take action on a Claim within said 30 days, the Claim shall be deemed denied.
- E. Engineer's written action under Paragraph 10.05.C or denial pursuant to Paragraphs 10.05.C.3 or 10.05.D will be final and binding upon Owner and Contractor, unless Owner or Contractor invoke the dispute resolution procedure set forth in Article 16 within 30 days of such action or denial.
- F. No Claim for an adjustment in Contract Price or Contract Times will be valid if not submitted in accordance with this Paragraph 10.05.

ARTICLE 11 – COST OF THE WORK; ALLOWANCES; UNIT PRICE WORK

11.01 *Cost of the Work*

- A. *Costs Included:* The term Cost of the Work means the sum of all costs, except those excluded in Paragraph 11.01.B, necessarily incurred and

paid by Contractor in the proper performance of the Work. When the value of any Work covered by a Change Order or when a Claim for an adjustment in Contract Price is determined on the basis of Cost of the Work, the costs to be reimbursed to Contractor will be only those additional or incremental costs required because of the change in the Work or because of the event giving rise to the Claim. Except as otherwise may be agreed to in writing by Owner, such costs shall be in amounts no higher than those prevailing in the locality of the Project, shall not include any of the costs itemized in Paragraph 11.01.B, and shall include only the following items:

1. Payroll costs for employees in the direct employ of Contractor in the performance of the Work under schedules of job classifications agreed upon by Owner and Contractor. Such employees shall include, without limitation, superintendents, foremen, and other personnel employed full time on the Work. Payroll costs for employees not employed full time on the Work shall be apportioned on the basis of their time spent on the Work. Payroll costs shall include, but not be limited to, salaries and wages plus the cost of fringe benefits, which shall include social security contributions, unemployment, excise, and payroll taxes, workers' compensation, health and retirement benefits, bonuses, sick leave, vacation and holiday pay applicable thereto. The expenses of performing Work outside of regular working hours, on Saturday, Sunday, or legal holidays, shall be included in the above to the extent authorized by Owner.
2. Cost of all materials and equipment furnished and incorporated in the Work, including costs of transportation and storage thereof, and Suppliers' field services required in connection therewith. All cash discounts shall accrue to Contractor unless Owner deposits funds with Contractor with which to make payments, in which case the cash discounts shall accrue to Owner. All trade discounts, rebates and refunds and returns from sale of surplus materials and equipment shall accrue to Owner, and Contractor shall make provisions so that they may be obtained.
3. Payments made by Contractor to Subcontractors for Work performed by Subcontractors. If required by Owner, Contractor shall obtain competitive bids from

subcontractors acceptable to Owner and Contractor and shall deliver such bids to Owner, who will then determine, with the advice of Engineer, which bids, if any, will be acceptable. If any subcontract provides that the Subcontractor is to be paid on the basis of Cost of the Work plus a fee, the Subcontractor's Cost of the Work and fee shall be determined in the same manner as Contractor's Cost of the Work and fee as provided in this Paragraph 11.01.

4. Costs of special consultants (including but not limited to engineers, architects, testing laboratories, surveyors, attorneys, and accountants) employed for services specifically related to the Work.

5. Supplemental costs including the following:

- a. The proportion of necessary transportation, travel, and subsistence expenses of Contractor's employees incurred in discharge of duties connected with the Work.
- b. Cost, including transportation and maintenance, of all materials, supplies, equipment, machinery, appliances, office, and temporary facilities at the Site, and hand tools not owned by the workers, which are consumed in the performance of the Work, and cost, less market value, of such items used but not consumed which remain the property of Contractor.
- c. Rentals of all construction equipment and machinery, and the parts thereof whether rented from Contractor or others in accordance with rental agreements approved by Owner with the advice of Engineer, and the costs of transportation, loading, unloading, assembly, dismantling, and removal thereof. All such costs shall be in accordance with the terms of said rental agreements. The rental of any such equipment, machinery, or parts shall cease when the use thereof is no longer necessary for the Work.
- d. Sales, consumer, use, and other similar taxes related to the Work, and for which Contractor is liable, as imposed by Laws and Regulations.

- e. Deposits lost for causes other than negligence of Contractor, any Subcontractor, or anyone directly or indirectly employed by any of them or for whose acts any of them may be liable, and royalty payments and fees for permits and licenses.

- f. Losses and damages (and related expenses) caused by damage to the Work, not compensated by insurance or otherwise, sustained by Contractor in connection with the performance of the Work (except losses and damages within the deductible amounts of property insurance established in accordance with Paragraph 5.06.D), provided such losses and damages have resulted from causes other than the negligence of Contractor, any Subcontractor, or anyone directly or indirectly employed by any of them or for whose acts any of them may be liable. Such losses shall include settlements made with the written consent and approval of Owner. No such losses, damages, and expenses shall be included in the Cost of the Work for the purpose of determining Contractor's fee.

- g. The cost of utilities, fuel, and sanitary facilities at the Site.

- h. Minor expenses such as telegrams, long distance telephone calls, telephone service at the Site, express and courier services, and similar petty cash items in connection with the Work.

- i. The costs of premiums for all bonds and insurance Contractor is required by the Contract Documents to purchase and maintain.

- B. *Costs Excluded:* The term Cost of the Work shall not include any of the following items:

1. Payroll costs and other compensation of Contractor's officers, executives, principals (of partnerships and sole proprietorships), general managers, safety managers, engineers, architects, estimators, attorneys, auditors, accountants, purchasing and contracting agents, expeditors, timekeepers, clerks, and other personnel employed by Contractor, whether at the Site or in Contractor's principal or branch office for

general administration of the Work and not specifically included in the agreed upon schedule of job classifications referred to in Paragraph 11.01.A.1 or specifically covered by Paragraph 11.01.A.4, all of which are to be considered administrative costs covered by the Contractor's fee.

2. Expenses of Contractor's principal and branch offices other than Contractor's office at the Site.
3. Any part of Contractor's capital expenses, including interest on Contractor's capital employed for the Work and charges against Contractor for delinquent payments.
4. Costs due to the negligence of Contractor, any Subcontractor, or anyone directly or indirectly employed by any of them or for whose acts any of them may be liable, including but not limited to, the correction of defective Work, disposal of materials or equipment wrongly supplied, and making good any damage to property.
5. Other overhead or general expense costs of any kind and the costs of any item not specifically and expressly included in Paragraphs 11.01.A.

C. *Contractor's Fee:* When all the Work is performed on the basis of cost-plus, Contractor's fee shall be determined as set forth in the Agreement. When the value of any Work covered by a Change Order or when a Claim for an adjustment in Contract Price is determined on the basis of Cost of the Work, Contractor's fee shall be determined as set forth in Paragraph 12.01.C.

D. *Documentation:* Whenever the Cost of the Work for any purpose is to be determined pursuant to Paragraphs 11.01.A and 11.01.B, Contractor will establish and maintain records thereof in accordance with generally accepted accounting practices and submit in a form acceptable to Engineer an itemized cost breakdown together with supporting data.

11.02 Allowances

- A. It is understood that Contractor has included in the Contract Price all allowances so named in the Contract Documents and shall cause the Work so covered to be performed for such sums and by

such persons or entities as may be acceptable to Owner and Engineer.

B. *Cash Allowances:*

1. Contractor agrees that:
 - a. the cash allowances include the cost to Contractor (less any applicable trade discounts) of materials and equipment required by the allowances to be delivered at the Site, and all applicable taxes; and
 - b. Contractor's costs for unloading and handling on the Site, labor, installation, overhead, profit, and other expenses contemplated for the cash allowances have been included in the Contract Price and not in the allowances, and no demand for additional payment on account of any of the foregoing will be valid.

C. *Contingency Allowance:*

1. Contractor agrees that a contingency allowance, if any, is for the sole use of Owner to cover unanticipated costs.

D. Prior to final payment, an appropriate Change Order will be issued as recommended by Engineer to reflect actual amounts due Contractor on account of Work covered by allowances, and the Contract Price shall be correspondingly adjusted.

11.03 Unit Price Work

- A. Where the Contract Documents provide that all or part of the Work is to be Unit Price Work, initially the Contract Price will be deemed to include for all Unit Price Work an amount equal to the sum of the unit price for each separately identified item of Unit Price Work times the estimated quantity of each item as indicated in the Agreement.
- B. The estimated quantities of items of Unit Price Work are not guaranteed and are solely for the purpose of comparison of Bids and determining an initial Contract Price. Determinations of the actual quantities and classifications of Unit Price Work performed by Contractor will be made by Engineer subject to the provisions of Paragraph 9.07.

- C. Each unit price will be deemed to include an amount considered by Contractor to be adequate to cover Contractor's overhead and profit for each separately identified item.
- D. Owner or Contractor may make a Claim for an adjustment in the Contract Price in accordance with Paragraph 10.05 if:
 - 1. the quantity of any item of Unit Price Work performed by Contractor differs materially and significantly from the estimated quantity of such item indicated in the Agreement; and
 - 2. there is no corresponding adjustment with respect to any other item of Work; and
 - 3. Contractor believes that Contractor is entitled to an increase in Contract Price as a result of having incurred additional expense or Owner believes that Owner is entitled to a decrease in Contract Price and the parties are unable to agree as to the amount of any such increase or decrease.
- 3. where the Work involved is not covered by unit prices contained in the Contract Documents and agreement to a lump sum is not reached under Paragraph 12.01.B.2, on the basis of the Cost of the Work (determined as provided in Paragraph 11.01) plus a Contractor's fee for overhead and profit (determined as provided in Paragraph 12.01.C).
- C. *Contractor's Fee:* The Contractor's fee for overhead and profit shall be determined as follows:
 - 1. a mutually acceptable fixed fee; or
 - 2. if a fixed fee is not agreed upon, then a fee based on the following percentages of the various portions of the Cost of the Work:
 - a. for costs incurred under Paragraphs 11.01.A.1 and 11.01.A.2, the Contractor's fee shall be 15 percent;
 - b. for costs incurred under Paragraph 11.01.A.3, the Contractor's fee shall be five percent;
 - c. where one or more tiers of subcontracts are on the basis of Cost of the Work plus a fee and no fixed fee is agreed upon, the intent of Paragraphs 12.01.C.2.a and 12.01.C.2.b is that the Subcontractor who actually performs the Work, at whatever tier, will be paid a fee of 15 percent of the costs incurred by such Subcontractor under Paragraphs 11.01.A.1 and 11.01.A.2 and that any higher tier Subcontractor and Contractor will each be paid a fee of five percent of the amount paid to the next lower tier Subcontractor;
 - d. no fee shall be payable on the basis of costs itemized under Paragraphs 11.01.A.4, 11.01.A.5, and 11.01.B;
 - e. the amount of credit to be allowed by Contractor to Owner for any change which results in a net decrease in cost will be the amount of the actual net decrease in cost plus a deduction in Contractor's fee by an amount equal to five percent of such net decrease; and

ARTICLE 12 – CHANGE OF CONTRACT PRICE; CHANGE OF CONTRACT TIMES

12.01 *Change of Contract Price*

- A. The Contract Price may only be changed by a Change Order. Any Claim for an adjustment in the Contract Price shall be based on written notice submitted by the party making the Claim to the Engineer and the other party to the Contract in accordance with the provisions of Paragraph 10.05.
- B. The value of any Work covered by a Change Order or of any Claim for an adjustment in the Contract Price will be determined as follows:
 - 1. where the Work involved is covered by unit prices contained in the Contract Documents, by application of such unit prices to the quantities of the items involved (subject to the provisions of Paragraph 11.03); or
 - 2. where the Work involved is not covered by unit prices contained in the Contract Documents, by a mutually agreed lump sum (which may include an allowance for overhead and profit not necessarily in accordance with Paragraph 12.01.C.2); or

- f. when both additions and credits are involved in any one change, the adjustment in Contractor's fee shall be computed on the basis of the net change in accordance with Paragraphs 12.01.C.2.a through 12.01.C.2.e, inclusive.

12.02 *Change of Contract Times*

- A. The Contract Times may only be changed by a Change Order. Any Claim for an adjustment in the Contract Times shall be based on written notice submitted by the party making the Claim to the Engineer and the other party to the Contract in accordance with the provisions of Paragraph 10.05.
- B. Any adjustment of the Contract Times covered by a Change Order or any Claim for an adjustment in the Contract Times will be determined in accordance with the provisions of this Article 12.

12.03 *Delays*

- A. Where Contractor is prevented from completing any part of the Work within the Contract Times due to delay beyond the control of Contractor, the Contract Times will be extended in an amount equal to the time lost due to such delay if a Claim is made therefor as provided in Paragraph 12.02.A. Delays beyond the control of Contractor shall include, but not be limited to, acts or neglect by Owner, acts or neglect of utility owners or other contractors performing other work as contemplated by Article 7, fires, floods, epidemics, abnormal weather conditions, or acts of God.
- B. If Owner, Engineer, or other contractors or utility owners performing other work for Owner as contemplated by Article 7, or anyone for whom Owner is responsible, delays, disrupts, or interferes with the performance or progress of the Work, then Contractor shall be entitled to an equitable adjustment in the Contract Price or the Contract Times, or both. Contractor's entitlement to an adjustment of the Contract Times is conditioned on such adjustment being essential to Contractor's ability to complete the Work within the Contract Times.
- C. If Contractor is delayed in the performance or progress of the Work by fire, flood, epidemic, abnormal weather conditions, acts of God, acts or failures to act of utility owners not under the

control of Owner, or other causes not the fault of and beyond control of Owner and Contractor, then Contractor shall be entitled to an equitable adjustment in Contract Times, if such adjustment is essential to Contractor's ability to complete the Work within the Contract Times. Such an adjustment shall be Contractor's sole and exclusive remedy for the delays described in this Paragraph 12.03.C.

- D. Owner, Engineer, and their officers, directors, members, partners, employees, agents, consultants, or subcontractors shall not be liable to Contractor for any claims, costs, losses, or damages (including but not limited to all fees and charges of engineers, architects, attorneys, and other professionals and all court or arbitration or other dispute resolution costs) sustained by Contractor on or in connection with any other project or anticipated project.
- E. Contractor shall not be entitled to an adjustment in Contract Price or Contract Times for delays within the control of Contractor. Delays attributable to and within the control of a Subcontractor or Supplier shall be deemed to be delays within the control of Contractor.

ARTICLE 13 – TESTS AND INSPECTIONS; CORRECTION, REMOVAL OR ACCEPTANCE OF DEFECTIVE WORK

13.01 *Notice of Defects*

- A. Prompt notice of all defective Work of which Owner or Engineer has actual knowledge will be given to Contractor. Defective Work may be rejected, corrected, or accepted as provided in this Article 13.

13.02 *Access to Work*

- A. Owner, Engineer, their consultants and other representatives and personnel of Owner, independent testing laboratories, and governmental agencies with jurisdictional interests will have access to the Site and the Work at reasonable times for their observation, inspection, and testing. Contractor shall provide them proper and safe conditions for such access and advise them of Contractor's safety procedures and programs so that they may comply therewith as applicable.

13.03 *Tests and Inspections*

- A. Contractor shall give Engineer timely notice of readiness of the Work for all required inspections, tests, or approvals and shall cooperate with inspection and testing personnel to facilitate required inspections or tests.
- B. Owner shall employ and pay for the services of an independent testing laboratory to perform all inspections, tests, or approvals required by the Contract Documents except:
 - 1. for inspections, tests, or approvals covered by Paragraphs 13.03.C and 13.03.D below;
 - 2. that costs incurred in connection with tests or inspections conducted pursuant to Paragraph 13.04.B shall be paid as provided in Paragraph 13.04.C; and
 - 3. as otherwise specifically provided in the Contract Documents.
- C. If Laws or Regulations of any public body having jurisdiction require any Work (or part thereof) specifically to be inspected, tested, or approved by an employee or other representative of such public body, Contractor shall assume full responsibility for arranging and obtaining such inspections, tests, or approvals, pay all costs in connection therewith, and furnish Engineer the required certificates of inspection or approval.
- D. Contractor shall be responsible for arranging and obtaining and shall pay all costs in connection with any inspections, tests, or approvals required for Owner's and Engineer's acceptance of materials or equipment to be incorporated in the Work; or acceptance of materials, mix designs, or equipment submitted for approval prior to Contractor's purchase thereof for incorporation in the Work. Such inspections, tests, or approvals shall be performed by organizations acceptable to Owner and Engineer.
- E. If any Work (or the work of others) that is to be inspected, tested, or approved is covered by Contractor without written concurrence of Engineer, Contractor shall, if requested by Engineer, uncover such Work for observation.
- F. Uncovering Work as provided in Paragraph 13.03.E shall be at Contractor's expense unless Contractor has given Engineer timely notice of Contractor's intention to cover the same and

Engineer has not acted with reasonable promptness in response to such notice.

13.04 *Uncovering Work*

- A. If any Work is covered contrary to the written request of Engineer, it must, if requested by Engineer, be uncovered for Engineer's observation and replaced at Contractor's expense.
- B. If Engineer considers it necessary or advisable that covered Work be observed by Engineer or inspected or tested by others, Contractor, at Engineer's request, shall uncover, expose, or otherwise make available for observation, inspection, or testing as Engineer may require, that portion of the Work in question, furnishing all necessary labor, material, and equipment.
- C. If it is found that the uncovered Work is defective, Contractor shall pay all claims, costs, losses, and damages (including but not limited to all fees and charges of engineers, architects, attorneys, and other professionals and all court or arbitration or other dispute resolution costs) arising out of or relating to such uncovering, exposure, observation, inspection, and testing, and of satisfactory replacement or reconstruction (including but not limited to all costs of repair or replacement of work of others); and Owner shall be entitled to an appropriate decrease in the Contract Price. If the parties are unable to agree as to the amount thereof, Owner may make a Claim therefor as provided in Paragraph 10.05.
- D. If the uncovered Work is not found to be defective, Contractor shall be allowed an increase in the Contract Price or an extension of the Contract Times, or both, directly attributable to such uncovering, exposure, observation, inspection, testing, replacement, and reconstruction. If the parties are unable to agree as to the amount or extent thereof, Contractor may make a Claim therefor as provided in Paragraph 10.05.

13.05 *Owner May Stop the Work*

- A. If the Work is defective, or Contractor fails to supply sufficient skilled workers or suitable materials or equipment, or fails to perform the Work in such a way that the completed Work will conform to the Contract Documents, Owner may order Contractor to stop the Work, or any portion thereof, until the cause for such order has been eliminated; however, this right of Owner to stop

the Work shall not give rise to any duty on the part of Owner to exercise this right for the benefit of Contractor, any Subcontractor, any Supplier, any other individual or entity, or any surety for, or employee or agent of any of them.

13.06 *Correction or Removal of Defective Work*

- A. Promptly after receipt of written notice, Contractor shall correct all defective Work, whether or not fabricated, installed, or completed, or, if the Work has been rejected by Engineer, remove it from the Project and replace it with Work that is not defective. Contractor shall pay all claims, costs, losses, and damages (including but not limited to all fees and charges of engineers, architects, attorneys, and other professionals and all court or arbitration or other dispute resolution costs) arising out of or relating to such correction or removal (including but not limited to all costs of repair or replacement of work of others).
- B. When correcting defective Work under the terms of this Paragraph 13.06 or Paragraph 13.07, Contractor shall take no action that would void or otherwise impair Owner's special warranty and guarantee, if any, on said Work.

13.07 *Correction Period*

- A. If within one year after the date of Substantial Completion (or such longer period of time as may be prescribed by the terms of any applicable special guarantee required by the Contract Documents) or by any specific provision of the Contract Documents, any Work is found to be defective, or if the repair of any damages to the land or areas made available for Contractor's use by Owner or permitted by Laws and Regulations as contemplated in Paragraph 6.11.A is found to be defective, Contractor shall promptly, without cost to Owner and in accordance with Owner's written instructions:

- 1. repair such defective land or areas; or
- 2. correct such defective Work; or
- 3. if the defective Work has been rejected by Owner, remove it from the Project and replace it with Work that is not defective, and
- 4. satisfactorily correct or repair or remove and replace any damage to other Work, to the work of others or other land or areas resulting therefrom.

B. If Contractor does not promptly comply with the terms of Owner's written instructions, or in an emergency where delay would cause serious risk of loss or damage, Owner may have the defective Work corrected or repaired or may have the rejected Work removed and replaced. All claims, costs, losses, and damages (including but not limited to all fees and charges of engineers, architects, attorneys, and other professionals and all court or arbitration or other dispute resolution costs) arising out of or relating to such correction or repair or such removal and replacement (including but not limited to all costs of repair or replacement of work of others) will be paid by Contractor.

C. In special circumstances where a particular item of equipment is placed in continuous service before Substantial Completion of all the Work, the correction period for that item may start to run from an earlier date if so provided in the Specifications.

D. Where defective Work (and damage to other Work resulting therefrom) has been corrected or removed and replaced under this Paragraph 13.07, the correction period hereunder with respect to such Work will be extended for an additional period of one year after such correction or removal and replacement has been satisfactorily completed.

E. Contractor's obligations under this Paragraph 13.07 are in addition to any other obligation or warranty. The provisions of this Paragraph 13.07 shall not be construed as a substitute for, or a waiver of, the provisions of any applicable statute of limitation or repose.

13.08 *Acceptance of Defective Work*

- A. If, instead of requiring correction or removal and replacement of defective Work, Owner (and, prior to Engineer's recommendation of final payment, Engineer) prefers to accept it, Owner may do so. Contractor shall pay all claims, costs, losses, and damages (including but not limited to all fees and charges of engineers, architects, attorneys, and other professionals and all court or arbitration or other dispute resolution costs) attributable to Owner's evaluation of and determination to accept such defective Work (such costs to be approved by Engineer as to reasonableness) and for the diminished value of the Work to the extent not otherwise paid by Contractor pursuant to this sentence. If any such acceptance occurs prior to

Engineer's recommendation of final payment, a Change Order will be issued incorporating the necessary revisions in the Contract Documents with respect to the Work, and Owner shall be entitled to an appropriate decrease in the Contract Price, reflecting the diminished value of Work so accepted. If the parties are unable to agree as to the amount thereof, Owner may make a Claim therefor as provided in Paragraph 10.05. If the acceptance occurs after such recommendation, an appropriate amount will be paid by Contractor to Owner.

13.09 *Owner May Correct Defective Work*

- A. If Contractor fails within a reasonable time after written notice from Engineer to correct defective Work, or to remove and replace rejected Work as required by Engineer in accordance with Paragraph 13.06.A, or if Contractor fails to perform the Work in accordance with the Contract Documents, or if Contractor fails to comply with any other provision of the Contract Documents, Owner may, after seven days written notice to Contractor, correct, or remedy any such deficiency.
- B. In exercising the rights and remedies under this Paragraph 13.09, Owner shall proceed expeditiously. In connection with such corrective or remedial action, Owner may exclude Contractor from all or part of the Site, take possession of all or part of the Work and suspend Contractor's services related thereto, take possession of Contractor's tools, appliances, construction equipment and machinery at the Site, and incorporate in the Work all materials and equipment stored at the Site or for which Owner has paid Contractor but which are stored elsewhere. Contractor shall allow Owner, Owner's representatives, agents and employees, Owner's other contractors, and Engineer and Engineer's consultants access to the Site to enable Owner to exercise the rights and remedies under this Paragraph.
- C. All claims, costs, losses, and damages (including but not limited to all fees and charges of engineers, architects, attorneys, and other professionals and all court or arbitration or other dispute resolution costs) incurred or sustained by Owner in exercising the rights and remedies under this Paragraph 13.09 will be charged against Contractor, and a Change Order will be issued incorporating the necessary revisions in the Contract Documents with respect to the Work;

and Owner shall be entitled to an appropriate decrease in the Contract Price. If the parties are unable to agree as to the amount of the adjustment, Owner may make a Claim therefor as provided in Paragraph 10.05. Such claims, costs, losses and damages will include but not be limited to all costs of repair, or replacement of work of others destroyed or damaged by correction, removal, or replacement of Contractor's defective Work.

- D. Contractor shall not be allowed an extension of the Contract Times because of any delay in the performance of the Work attributable to the exercise by Owner of Owner's rights and remedies under this Paragraph 13.09.

ARTICLE 14 – PAYMENTS TO CONTRACTOR AND COMPLETION

14.01 *Schedule of Values*

- A. The Schedule of Values established as provided in Paragraph 2.07.A will serve as the basis for progress payments and will be incorporated into a form of Application for Payment acceptable to Engineer. Progress payments on account of Unit Price Work will be based on the number of units completed.

14.02 *Progress Payments*

A. Applications for Payments:

- 1. At least 20 days before the date established in the Agreement for each progress payment (but not more often than once a month), Contractor shall submit to Engineer for review an Application for Payment filled out and signed by Contractor covering the Work completed as of the date of the Application and accompanied by such supporting documentation as is required by the Contract Documents. If payment is requested on the basis of materials and equipment not incorporated in the Work but delivered and suitably stored at the Site or at another location agreed to in writing, the Application for Payment shall also be accompanied by a bill of sale, invoice, or other documentation warranting that Owner has received the materials and equipment free and clear of all Liens and evidence that the materials and equipment are covered by appropriate property insurance or other arrangements to

protect Owner's interest therein, all of which must be satisfactory to Owner.

2. Beginning with the second Application for Payment, each Application shall include an affidavit of Contractor stating that all previous progress payments received on account of the Work have been applied on account to discharge Contractor's legitimate obligations associated with prior Applications for Payment.
3. The amount of retainage with respect to progress payments will be as stipulated in the Agreement.

B. Review of Applications:

1. Engineer will, within 10 days after receipt of each Application for Payment, either indicate in writing a recommendation of payment and present the Application to Owner or return the Application to Contractor indicating in writing Engineer's reasons for refusing to recommend payment. In the latter case, Contractor may make the necessary corrections and resubmit the Application.
2. Engineer's recommendation of any payment requested in an Application for Payment will constitute a representation by Engineer to Owner, based on Engineer's observations of the executed Work as an experienced and qualified design professional, and on Engineer's review of the Application for Payment and the accompanying data and schedules, that to the best of Engineer's knowledge, information and belief:
 - a. the Work has progressed to the point indicated;
 - b. the quality of the Work is generally in accordance with the Contract Documents (subject to an evaluation of the Work as a functioning whole prior to or upon Substantial Completion, the results of any subsequent tests called for in the Contract Documents, a final determination of quantities and classifications for Unit Price Work under Paragraph 9.07, and any other qualifications stated in the recommendation); and
 - c. the conditions precedent to Contractor's being entitled to such payment appear to have been fulfilled in so far as it is Engineer's responsibility to observe the Work.
3. By recommending any such payment Engineer will not thereby be deemed to have represented that:
 - a. inspections made to check the quality or the quantity of the Work as it has been performed have been exhaustive, extended to every aspect of the Work in progress, or involved detailed inspections of the Work beyond the responsibilities specifically assigned to Engineer in the Contract Documents; or
 - b. there may not be other matters or issues between the parties that might entitle Contractor to be paid additionally by Owner or entitle Owner to withhold payment to Contractor.
4. Neither Engineer's review of Contractor's Work for the purposes of recommending payments nor Engineer's recommendation of any payment, including final payment, will impose responsibility on Engineer:
 - a. to supervise, direct, or control the Work, or
 - b. for the means, methods, techniques, sequences, or procedures of construction, or the safety precautions and programs incident thereto, or
 - c. for Contractor's failure to comply with Laws and Regulations applicable to Contractor's performance of the Work, or
 - d. to make any examination to ascertain how or for what purposes Contractor has used the moneys paid on account of the Contract Price, or
 - e. to determine that title to any of the Work, materials, or equipment has passed to Owner free and clear of any Liens.
5. Engineer may refuse to recommend the whole or any part of any payment if, in Engineer's opinion, it would be incorrect to make the

representations to Owner stated in Paragraph 14.02.B.2. Engineer may also refuse to recommend any such payment or, because of subsequently discovered evidence or the results of subsequent inspections or tests, revise or revoke any such payment recommendation previously made, to such extent as may be necessary in Engineer's opinion to protect Owner from loss because:

- a. the Work is defective, or completed Work has been damaged, requiring correction or replacement;
- b. the Contract Price has been reduced by Change Orders;
- c. Owner has been required to correct defective Work or complete Work in accordance with Paragraph 13.09; or
- d. Engineer has actual knowledge of the occurrence of any of the events enumerated in Paragraph 15.02.A.

enumerated in Paragraphs 14.02.B.5.a through 14.02.B.5.c or Paragraph 15.02.A.

2. If Owner refuses to make payment of the full amount recommended by Engineer, Owner will give Contractor immediate written notice (with a copy to Engineer) stating the reasons for such action and promptly pay Contractor any amount remaining after deduction of the amount so withheld. Owner shall promptly pay Contractor the amount so withheld, or any adjustment thereto agreed to by Owner and Contractor, when Contractor remedies the reasons for such action.
3. Upon a subsequent determination that Owner's refusal of payment was not justified, the amount wrongfully withheld shall be treated as an amount due as determined by Paragraph 14.02.C.1 and subject to interest as provided in the Agreement.

14.03 *Contractor's Warranty of Title*

C. *Payment Becomes Due:*

1. Ten days after presentation of the Application for Payment to Owner with Engineer's recommendation, the amount recommended will (subject to the provisions of Paragraph 14.02.D) become due, and when due will be paid by Owner to Contractor.

- A. Contractor warrants and guarantees that title to all Work, materials, and equipment covered by any Application for Payment, whether incorporated in the Project or not, will pass to Owner no later than the time of payment free and clear of all Liens.

14.04 *Substantial Completion*

D. *Reduction in Payment:*

1. Owner may refuse to make payment of the full amount recommended by Engineer because:
 - a. claims have been made against Owner on account of Contractor's performance or furnishing of the Work;
 - b. Liens have been filed in connection with the Work, except where Contractor has delivered a specific bond satisfactory to Owner to secure the satisfaction and discharge of such Liens;
 - c. there are other items entitling Owner to a set-off against the amount recommended; or
 - d. Owner has actual knowledge of the occurrence of any of the events

- A. When Contractor considers the entire Work ready for its intended use Contractor shall notify Owner and Engineer in writing that the entire Work is substantially complete (except for items specifically listed by Contractor as incomplete) and request that Engineer issue a certificate of Substantial Completion.
- B. Promptly after Contractor's notification, Owner, Contractor, and Engineer shall make an inspection of the Work to determine the status of completion. If Engineer does not consider the Work substantially complete, Engineer will notify Contractor in writing giving the reasons therefor.
- C. If Engineer considers the Work substantially complete, Engineer will deliver to Owner a tentative certificate of Substantial Completion which shall fix the date of Substantial Completion. There shall be attached to the certificate a tentative list of items to be completed or corrected before final payment. Owner shall have seven days after receipt of the tentative certificate during which to

make written objection to Engineer as to any provisions of the certificate or attached list. If, after considering such objections, Engineer concludes that the Work is not substantially complete, Engineer will, within 14 days after submission of the tentative certificate to Owner, notify Contractor in writing, stating the reasons therefor. If, after consideration of Owner's objections, Engineer considers the Work substantially complete, Engineer will, within said 14 days, execute and deliver to Owner and Contractor a definitive certificate of Substantial Completion (with a revised tentative list of items to be completed or corrected) reflecting such changes from the tentative certificate as Engineer believes justified after consideration of any objections from Owner.

- D. At the time of delivery of the tentative certificate of Substantial Completion, Engineer will deliver to Owner and Contractor a written recommendation as to division of responsibilities pending final payment between Owner and Contractor with respect to security, operation, safety, and protection of the Work, maintenance, heat, utilities, insurance, and warranties and guarantees. Unless Owner and Contractor agree otherwise in writing and so inform Engineer in writing prior to Engineer's issuing the definitive certificate of Substantial Completion, Engineer's aforesaid recommendation will be binding on Owner and Contractor until final payment.
- E. Owner shall have the right to exclude Contractor from the Site after the date of Substantial Completion subject to allowing Contractor reasonable access to remove its property and complete or correct items on the tentative list.

14.05 *Partial Utilization*

- A. Prior to Substantial Completion of all the Work, Owner may use or occupy any substantially completed part of the Work which has specifically been identified in the Contract Documents, or which Owner, Engineer, and Contractor agree constitutes a separately functioning and usable part of the Work that can be used by Owner for its intended purpose without significant interference with Contractor's performance of the remainder of the Work, subject to the following conditions:
 - 1. Owner at any time may request Contractor in writing to permit Owner to use or occupy any such part of the Work which Owner believes to be ready for its intended use and

substantially complete. If and when Contractor agrees that such part of the Work is substantially complete, Contractor, Owner, and Engineer will follow the procedures of Paragraph 14.04.A through D for that part of the Work.

- 2. Contractor at any time may notify Owner and Engineer in writing that Contractor considers any such part of the Work ready for its intended use and substantially complete and request Engineer to issue a certificate of Substantial Completion for that part of the Work.
- 3. Within a reasonable time after either such request, Owner, Contractor, and Engineer shall make an inspection of that part of the Work to determine its status of completion. If Engineer does not consider that part of the Work to be substantially complete, Engineer will notify Owner and Contractor in writing giving the reasons therefor. If Engineer considers that part of the Work to be substantially complete, the provisions of Paragraph 14.04 will apply with respect to certification of Substantial Completion of that part of the Work and the division of responsibility in respect thereof and access thereto.
- 4. No use or occupancy or separate operation of part of the Work may occur prior to compliance with the requirements of Paragraph 5.10 regarding property insurance.

14.06 *Final Inspection*

- A. Upon written notice from Contractor that the entire Work or an agreed portion thereof is complete, Engineer will promptly make a final inspection with Owner and Contractor and will notify Contractor in writing of all particulars in which this inspection reveals that the Work is incomplete or defective. Contractor shall immediately take such measures as are necessary to complete such Work or remedy such deficiencies.

14.07 *Final Payment*

A. *Application for Payment:*

1. After Contractor has, in the opinion of Engineer, satisfactorily completed all corrections identified during the final inspection and has delivered, in accordance with the Contract Documents, all maintenance and operating instructions, schedules, guarantees, bonds, certificates or other evidence of insurance, certificates of inspection, marked-up record documents (as provided in Paragraph 6.12), and other documents, Contractor may make application for final payment following the procedure for progress payments.
2. The final Application for Payment shall be accompanied (except as previously delivered) by:
 - a. all documentation called for in the Contract Documents, including but not limited to the evidence of insurance required by Paragraph 5.04.B.6;
 - b. consent of the surety, if any, to final payment;
 - c. a list of all Claims against Owner that Contractor believes are unsettled; and
 - d. complete and legally effective releases or waivers (satisfactory to Owner) of all Lien rights arising out of or Liens filed in connection with the Work.
3. In lieu of the releases or waivers of Liens specified in Paragraph 14.07.A.2 and as approved by Owner, Contractor may furnish receipts or releases in full and an affidavit of Contractor that: (i) the releases and receipts include all labor, services, material, and equipment for which a Lien could be filed; and (ii) all payrolls, material and equipment bills, and other indebtedness connected with the Work for which Owner might in any way be responsible, or which might in any way result in liens or other burdens on Owner's property, have been paid or otherwise satisfied. If any Subcontractor or Supplier fails to furnish such a release or receipt in full, Contractor may furnish a bond or other collateral satisfactory to Owner to indemnify Owner against any Lien.

B. *Engineer's Review of Application and Acceptance:*

1. If, on the basis of Engineer's observation of the Work during construction and final inspection, and Engineer's review of the final Application for Payment and accompanying documentation as required by the Contract Documents, Engineer is satisfied that the Work has been completed and Contractor's other obligations under the Contract Documents have been fulfilled, Engineer will, within ten days after receipt of the final Application for Payment, indicate in writing Engineer's recommendation of payment and present the Application for Payment to Owner for payment. At the same time Engineer will also give written notice to Owner and Contractor that the Work is acceptable subject to the provisions of Paragraph 14.09. Otherwise, Engineer will return the Application for Payment to Contractor, indicating in writing the reasons for refusing to recommend final payment, in which case Contractor shall make the necessary corrections and resubmit the Application for Payment.

C. *Payment Becomes Due:*

1. Thirty days after the presentation to Owner of the Application for Payment and accompanying documentation, the amount recommended by Engineer, less any sum Owner is entitled to set off against Engineer's recommendation, including but not limited to liquidated damages, will become due and will be paid by Owner to Contractor.

14.08 *Final Completion Delayed*

- A. If, through no fault of Contractor, final completion of the Work is significantly delayed, and if Engineer so confirms, Owner shall, upon receipt of Contractor's final Application for Payment (for Work fully completed and accepted) and recommendation of Engineer, and without terminating the Contract, make payment of the balance due for that portion of the Work fully completed and accepted. If the remaining balance to be held by Owner for Work not fully completed or corrected is less than the retainage stipulated in the Agreement, and if bonds have been furnished as required in Paragraph 5.01, the written consent of the surety to the payment of the balance due for that portion of the Work fully completed and

accepted shall be submitted by Contractor to Engineer with the Application for such payment. Such payment shall be made under the terms and conditions governing final payment, except that it shall not constitute a waiver of Claims.

14.09 *Waiver of Claims*

A. The making and acceptance of final payment will constitute:

1. a waiver of all Claims by Owner against Contractor, except Claims arising from unsettled Liens, from defective Work appearing after final inspection pursuant to Paragraph 14.06, from failure to comply with the Contract Documents or the terms of any special guarantees specified therein, or from Contractor's continuing obligations under the Contract Documents; and
2. a waiver of all Claims by Contractor against Owner other than those previously made in accordance with the requirements herein and expressly acknowledged by Owner in writing as still unsettled.

ARTICLE 15 – SUSPENSION OF WORK AND TERMINATION

15.01 *Owner May Suspend Work*

A. At any time and without cause, Owner may suspend the Work or any portion thereof for a period of not more than 90 consecutive days by notice in writing to Contractor and Engineer which will fix the date on which Work will be resumed. Contractor shall resume the Work on the date so fixed. Contractor shall be granted an adjustment in the Contract Price or an extension of the Contract Times, or both, directly attributable to any such suspension if Contractor makes a Claim therefor as provided in Paragraph 10.05.

15.02 *Owner May Terminate for Cause*

A. The occurrence of any one or more of the following events will justify termination for cause:

1. Contractor's persistent failure to perform the Work in accordance with the Contract Documents (including, but not limited to, failure to supply sufficient skilled workers or suitable materials or equipment or failure to adhere to the Progress Schedule established

under Paragraph 2.07 as adjusted from time to time pursuant to Paragraph 6.04);

2. Contractor's disregard of Laws or Regulations of any public body having jurisdiction;

3. Contractor's repeated disregard of the authority of Engineer; or

4. Contractor's violation in any substantial way of any provisions of the Contract Documents.

B. If one or more of the events identified in Paragraph 15.02.A occur, Owner may, after giving Contractor (and surety) seven days written notice of its intent to terminate the services of Contractor:

1. exclude Contractor from the Site, and take possession of the Work and of all Contractor's tools, appliances, construction equipment, and machinery at the Site, and use the same to the full extent they could be used by Contractor (without liability to Contractor for trespass or conversion);

2. incorporate in the Work all materials and equipment stored at the Site or for which Owner has paid Contractor but which are stored elsewhere; and

3. complete the Work as Owner may deem expedient.

C. If Owner proceeds as provided in Paragraph 15.02.B, Contractor shall not be entitled to receive any further payment until the Work is completed. If the unpaid balance of the Contract Price exceeds all claims, costs, losses, and damages (including but not limited to all fees and charges of engineers, architects, attorneys, and other professionals and all court or arbitration or other dispute resolution costs) sustained by Owner arising out of or relating to completing the Work, such excess will be paid to Contractor. If such claims, costs, losses, and damages exceed such unpaid balance, Contractor shall pay the difference to Owner. Such claims, costs, losses, and damages incurred by Owner will be reviewed by Engineer as to their reasonableness and, when so approved by Engineer, incorporated in a Change Order. When exercising any rights or remedies under this Paragraph, Owner shall not be required to obtain the lowest price for the Work performed.

D. Notwithstanding Paragraphs 15.02.B and 15.02.C, Contractor's services will not be terminated if Contractor begins within seven days of receipt of notice of intent to terminate to correct its failure to perform and proceeds diligently to cure such failure within no more than 30 days of receipt of said notice.

E. Where Contractor's services have been so terminated by Owner, the termination will not affect any rights or remedies of Owner against Contractor then existing or which may thereafter accrue. Any retention or payment of moneys due Contractor by Owner will not release Contractor from liability.

F. If and to the extent that Contractor has provided a performance bond under the provisions of Paragraph 5.01.A, the termination procedures of that bond shall supersede the provisions of Paragraphs 15.02.B and 15.02.C.

15.03 *Owner May Terminate For Convenience*

A. Upon seven days written notice to Contractor and Engineer, Owner may, without cause and without prejudice to any other right or remedy of Owner, terminate the Contract. In such case, Contractor shall be paid for (without duplication of any items):

1. completed and acceptable Work executed in accordance with the Contract Documents prior to the effective date of termination, including fair and reasonable sums for overhead and profit on such Work;
2. expenses sustained prior to the effective date of termination in performing services and furnishing labor, materials, or equipment as required by the Contract Documents in connection with uncompleted Work, plus fair and reasonable sums for overhead and profit on such expenses;
3. all claims, costs, losses, and damages (including but not limited to all fees and charges of engineers, architects, attorneys, and other professionals and all court or arbitration or other dispute resolution costs) incurred in settlement of terminated contracts with Subcontractors, Suppliers, and others; and
4. reasonable expenses directly attributable to termination.

B. Contractor shall not be paid on account of loss of anticipated profits or revenue or other economic loss arising out of or resulting from such termination.

15.04 *Contractor May Stop Work or Terminate*

A. If, through no act or fault of Contractor, (i) the Work is suspended for more than 90 consecutive days by Owner or under an order of court or other public authority, or (ii) Engineer fails to act on any Application for Payment within 30 days after it is submitted, or (iii) Owner fails for 30 days to pay Contractor any sum finally determined to be due, then Contractor may, upon seven days written notice to Owner and Engineer, and provided Owner or Engineer do not remedy such suspension or failure within that time, terminate the Contract and recover from Owner payment on the same terms as provided in Paragraph 15.03.

B. In lieu of terminating the Contract and without prejudice to any other right or remedy, if Engineer has failed to act on an Application for Payment within 30 days after it is submitted, or Owner has failed for 30 days to pay Contractor any sum finally determined to be due, Contractor may, seven days after written notice to Owner and Engineer, stop the Work until payment is made of all such amounts due Contractor, including interest thereon. The provisions of this Paragraph 15.04 are not intended to preclude Contractor from making a Claim under Paragraph 10.05 for an adjustment in Contract Price or Contract Times or otherwise for expenses or damage directly attributable to Contractor's stopping the Work as permitted by this Paragraph.

ARTICLE 16 – DISPUTE RESOLUTION

16.01 *Methods and Procedures*

A. Either Owner or Contractor may request mediation of any Claim submitted to Engineer for a decision under Paragraph 10.05 before such decision becomes final and binding. The mediation will be governed by the Construction Industry Mediation Rules of the American Arbitration Association in effect as of the Effective Date of the Agreement. The request for mediation shall be submitted in writing to the American Arbitration Association and the other party to the Contract. Timely submission of the request shall stay the effect of Paragraph 10.05.E.

- B. Owner and Contractor shall participate in the mediation process in good faith. The process shall be concluded within 60 days of filing of the request. The date of termination of the mediation shall be determined by application of the mediation rules referenced above.
- C. If the Claim is not resolved by mediation, Engineer's action under Paragraph 10.05.C or a denial pursuant to Paragraphs 10.05.C.3 or 10.05.D shall become final and binding 30 days after termination of the mediation unless, within that time period, Owner or Contractor:

1. elects in writing to invoke any dispute resolution process provided for in the Supplementary Conditions; or
2. agrees with the other party to submit the Claim to another dispute resolution process; or
3. gives written notice to the other party of the intent to submit the Claim to a court of competent jurisdiction.

ARTICLE 17 – MISCELLANEOUS

17.01 *Giving Notice*

- A. Whenever any provision of the Contract Documents requires the giving of written notice, it will be deemed to have been validly given if:
1. delivered in person to the individual or to a member of the firm or to an officer of the corporation for whom it is intended; or
 2. delivered at or sent by registered or certified mail, postage prepaid, to the last business address known to the giver of the notice.

17.02 *Computation of Times*

- A. When any period of time is referred to in the Contract Documents by days, it will be computed to exclude the first and include the last day of such period. If the last day of any such period falls on a Saturday or Sunday or on a day made a legal holiday by the law of the applicable jurisdiction, such day will be omitted from the computation.

17.03 *Cumulative Remedies*

- A. The duties and obligations imposed by these General Conditions and the rights and remedies

available hereunder to the parties hereto are in addition to, and are not to be construed in any way as a limitation of, any rights and remedies available to any or all of them which are otherwise imposed or available by Laws or Regulations, by special warranty or guarantee, or by other provisions of the Contract Documents. The provisions of this Paragraph will be as effective as if repeated specifically in the Contract Documents in connection with each particular duty, obligation, right, and remedy to which they apply.

17.04 *Survival of Obligations*

- A. All representations, indemnifications, warranties, and guarantees made in, required by, or given in accordance with the Contract Documents, as well as all continuing obligations indicated in the Contract Documents, will survive final payment, completion, and acceptance of the Work or termination or completion of the Contract or termination of the services of Contractor.

17.05 *Controlling Law*

- A. This Contract is to be governed by the law of the state in which the Project is located.

17.06 *Headings*

- A. Article and paragraph headings are inserted for convenience only and do not constitute parts of these General Conditions.

SECTION 00800

SUPPLEMENTARY CONDITIONS

These Supplementary Conditions amend or supplement the Standard General Conditions of the Construction Contract (EJCDC No. C-100, 2007 Edition) and other provisions of the Contract Documents as indicated below. All provisions which are not specifically amended or supplemented hereby remain in full force and effect.

ARTICLE 1. DEFINITIONS AND TERMINOLOGY

SC-1.01.A.12

Add the following language at the beginning of the definition entitled "Contract Documents" in the General Conditions:

The Invitation to Bid, Instructions to Bidders, and Specifications Divisions 0, 1, 2, 3...

SC-1.01.A.29

Add the following language to the definition entitled "Owner" in the General Conditions:

The term "Owner" shall mean the City of Salem, Massachusetts acting through its Engineering Department.

SC-1.01.A.44

Delete the definition of Substantial Completion in the General Conditions in its entirety and add the following in its place:

The Work required by the Contract has been completed except for work having a Contract Price of less than one percent of the then adjusted total contract price, or substantially all of the Work has been completed and opened to Owner's use except for minor incomplete or unsatisfactory work items that do not materially impair the usefulness of the Work required by the Contract.

ARTICLE 2. PRELIMINARY MATTERS

SC-2.01.B

Delete paragraph 2.01.B of the General Conditions in its entirety and insert the following in its place:

2.01.B Before any work at the site is started, Contractor shall deliver to Owner, with a copy to Engineer and each additional insured in Article 5, certificates of insurance (and other evidence of insurance requested by Owner) which Contractor is required to purchase and maintain in accordance with the requirements of Article 5.

2.01.B.1 Contractor shall include and identify on the certificate of insurance, indemnification as required by Article 6.20 of the General Conditions (Section 00700).

SC-2.02

Delete paragraph 2.02A of the General Conditions in its entirety and insert the following in its place:

2.02.A Owner shall furnish to contractor up to two (2) printed or hard copies of the Drawings and Project Manual, additional copies will be furnished upon request at the cost of reproduction.

SC-2.03

Delete paragraph 2.03 of the General Conditions in its entirety and insert the following in its place:

2.03.A The Contract Time will commence to run on the effective date of the Agreement.

ARTICLE 3. CONTRACT DOCUMENTS: INTENT, AMENDING, REUSE

SC-3.01

Add the following new paragraphs immediately after paragraph 3.01.A of the General Conditions which is to read as follows:

3.01.A.1 Each and every provision of law and clause required by law to be inserted in the Contract shall be deemed to be inserted herein, and the Contract shall be read and enforced as though they were included herein. If through mistake or otherwise any such provision is not inserted, or is not correctly inserted, then upon the application of either party, the Contract shall forthwith be physically amended to make such insertion.

3.01.A.2 Sections of Division 1 - General Requirements govern the execution of the work of all sections of the specifications.

ARTICLE 4. AVAILABILITY OF LANDS; SUBSURFACE AND PHYSICAL CONDITIONS; HAZARDOUS ENVIRONMENTAL CONDITIONS; REFERENCE POINTS

SC-4.01.A

Add the followings new paragraph immediately after paragraph 4.01A of the General Conditions which is to read as follows:

1. If all lands and right-of-ways are not obtained as herein contemplated before construction begins, Contractor shall begin the Work upon such land and right-of-ways as Owner has previously required.

SC-4.03.3

Add the followings new paragraph immediately after paragraph 4.03C.3 of the General Conditions which is to read as follows:

D. Adjust resulting from subsurface or latent physical conditions will be in accordance with Massachusetts General Law Chapter 30, Section 39N included in Massachusetts General Laws, located in Attachments of this specification document.

SC-4.03.3

Add the followings new paragraph immediately after paragraph 4.05.A of the General Conditions which is to read as follows:

B. Engineer may check the lines, elevations, reference marks, batter boards, etc., set by Contractor, and Contractor shall correct any errors disclosed by such check. Such a check shall not be considered as approval of Contractor's work and shall not relieve Contractor of the

responsibility for accurate construction of the entire Work. Contractor shall furnish personnel to assist Engineer in checking lines and grades.

ARTICLE 5. BONDS AND INSURANCE

SC-5.01

Add the following new paragraph immediately after paragraph 5.01.A of the General Conditions which is to read as follows:

The Surety Company providing the bonds shall have a rating A or better within the Best Key Rating Guide and be licensed by the Massachusetts Division of Insurance. The Contractor shall pay the premiums for such Bonds.

5.01.B

Amend the following paragraph 5.01.A of the General Conditions which is to read as follows:

Every bid bond, every performance bond and every payment bond issued for any construction work in the commonwealth shall be the bond of a surety company organized pursuant to Section 105 of Chapter 175 or of a surety company authorized to do business in Commonwealth under the provisions of Section 106 of said Chapter 175 and be approved by the U. S. Department of Treasury and acceptable as sureties and reinsurers on federal bonds under Title 31 of the United States Code, sections 9304 to 9308.

5.03.E

Add 2 new paragraphs immediately after paragraph 5.03E of the General Conditions which are to read as follows:

F. Contractor shall provide evidence of its insurance coverage on the ACORD certificate of insurance form and shall include the following statement in its entirety in the section of the form entitled "Description of Operations/Locations/Vehicles/Special Items".

The City of Salem and New England Civil Engineering Corp. and their officers, directors, partners, employees and other consultants and subcontractors are named as additional insureds with respect to the insured's Commercial General Liability and Automobile Liability Insurance Policies. All insurers waive all rights of subrogation against the City of Salem and New England Civil Engineering Corp., their officers, directors, partners, employees, and other consultants and subcontractors. All insurance is primary for all claims covered thereby. Commercial General Liability Insurance includes contractual liability coverage.

SC-5.04

The limits of liability for the insurance required by paragraph 5.04 of the General Conditions shall provide the following coverages for not less than the following amounts or greater where required by Laws and Regulations:

5.04.A.1 and 5.04.A.2 Worker's Compensation, etc. under paragraphs 5.04.A.1 and 5.04.A.2 of the General Conditions:

- (1) Worker's Compensation as required by the laws of the Commonwealth of Massachusetts, and at a minimum of \$100,000.

- | | | |
|-----|-------------------------|---|
| (2) | Employer's Liability | \$1,000,000 |
| | Including at a minimum: | \$500,000 Each Accident
\$500,000 Disease per Employee |

5.04.A.3, 5.04.A.4, and 5.04.A.5 Contractor's Liability Insurance under paragraphs 5.04.A.3 through 5.04.A.5 of the General Conditions which shall also include completed operations and product liability coverages and eliminate the exclusion with respect to property under the care, custody, and control of Contractor. These policies shall name the Owner, the Engineer, as additional insured:

- | | | |
|-----|--|----------------------------|
| (1) | General Aggregate

(Except Products--Completed Operations) |

\$1,000,000 |
| (2) | Products--Completed Operations Aggregate | \$1,000,000 |
| (3) | Personal and Advertising Injury (Per Person/ Organization) | \$1,000,000 |
| (4) | Each Occurrence (Bodily Injury and Property Damage) | \$1,000,000 |
| (5) | Property Damage liability insurance including Collapse, and Underground coverages. If blasting is to be used, also include explosion coverage. | \$1,000,000 |
| (6) | General Aggregate
Each Occurrence | \$2,000,000
\$1,000,000 |
| (7) | Umbrella Liability | \$1,000,000 |

5.04.A.6 Automobile Liability:

- | | | |
|-----|-----------------------|--|
| (1) | Bodily Injury: | \$1,000,000 Each Person

\$1,000,000 Each Accident |
| | Property Damage: | \$1,000,000 Each Accident |
| | or | |
| (2) | Combined Single Limit | |

(Bodily Injury and Property Damage): \$2,000,000 Each Accident

SC-5.04.B.4 The Contractual Liability coverage required by paragraph 5.04.B.4 in the General Conditions shall provide coverage for not less than the following amounts:

- | | | |
|-----|---|-------------|
| (1) | General Aggregate | \$2,000,000 |
| (2) | Each Occurrence (Bodily Injury and Property Damage) | \$1,000,000 |

SC-5.04.B.6

Add two new paragraphs immediately after paragraph 5.04.B.6.b of the General Conditions which is to read as follows:

7. Contractor may purchase and maintain excess liability insurance in the umbrella form in order to satisfy the minimum amounts required for the insurance to be purchased and maintained in accordance with paragraph 5.04. Evidence of such excess liability insurance shall be delivered to Owner in accordance with paragraph 2.01B in the form of certificate indicating the policy numbers and minimum coverage amounts of all underlying insurance. The umbrella liability insurance shall have a combined single limit of not less than \$5,000,000.

8. Contactor shall list the Owner and Engineer as additional insured parties on all policies. All policies required by this paragraph 5.04 shall contain provisions to the effect that the insurer(s) waive all rights of subrogation against the Owner, Engineer and their officers, directors, partners, employees and other consultants and subcontractors of each and any of them.

SC-5.05

Delete paragraph 5.05 of the General Conditions in its entirety and insert the following in its place:

5.05.A Contractor shall purchase and maintain a separate Owner's Protective Liability policy, issued to OWNER at the expense of Contractor, including Owner and Engineer as named insured. This insurance shall provide coverage for not less than the following amounts:

- | | | |
|----------|------------------|---|
| 5.05.A.1 | Bodily Injury: | \$1,000,000 Each Occurrence |
| 5.05.A.2 | Property Damage: | \$1,000,000 Each Occurrence
\$1,000,000 Annual Aggregate |

SC-5.05.A

Add the following new paragraph immediately after paragraph 5.05.A.2 of the General Conditions which is to read as follows:

B. Contactor shall list the Owner and Engineer as additional insured parties on all policies. All policies required by this paragraph 5.05 shall contain provisions to the effect that the insurer(s) waive all rights of subrogation against the Owner, Engineer and their officers, directors, partners, employees and other consultants and subcontractors of each and any of them.

SC-5.06

Delete paragraph 5.06 of the General Conditions in its entirety.

SC-5.09.A

Delete paragraph 5.09.A of the General Conditions in its entirety and replace with the following:

A. If Owner has any objection to the coverage afforded by or other provisions of the insurance required to be purchased and maintained by Contractor in accordance with this Article 5 on the basis of its not complying with the Contract Documents, Owner will notify Contractor in writing thereof within ten days of the date of delivery of such certificates to Owner in accordance with paragraph 2.01. Contractor will provide such additional information in respect of insurance provided by Contractor as Owner may reasonably request.

ARTICLE 6. CONTRACTOR'S RESPONSIBILITIES

SC-6.02

Add the following 2 paragraphs immediately after paragraph 6.02.B of the General Conditions which are to read as follows:

C. Regular working hours are defined as 8 hours per day, Monday through Friday, excluding holidays, between the hours of 7:00 A.M. and 4:00 P.M. Requests to work other than regular working hours shall be submitted to the Engineer not less than 48 hours prior to any proposed weekend work or scheduled extended work weeks. Occasional unscheduled overtime on weekdays may be permitted provided two hours notice is given to the Engineer.

D. Contractor shall reimburse the Owner for additional engineering and/or inspection costs incurred as a result of overtime work in excess of the regular working hours stipulated in Article SC-6.02.C. At Owner's opinion, overtime costs may either be deducted from the Contractor's monthly payment request or deducted from the Contractor's retention prior to release of final payment. Overtime costs for the Owner's personnel shall be based on the individual's current overtime wage rate. Overtime costs for personnel employed by the Engineer or Owner's independent testing laboratory shall be calculated in accordance with the terms of their respective contracts with the Owner.

SC-6.02.B

Add the following new paragraphs immediately after paragraph 6.02.B of the General Conditions which are to read as follows:

C. This agreement is subject to the applicable provisions of the Contract Work Hours and Safety Standards Act, Public Law 87-581, 87th Congress. No Contractor or Subcontractor contracting for any part of the Work shall require or permit any laborer or mechanic to be employed on the Work in excess of forty hours in any work week unless such labor or mechanic receives compensation at a rate not less than one and one-half times that person's basic rate of pay for all hours worked in excess of forty hours in such work week.

D. Contractor shall employ only competent persons to do the work and whenever Owner shall notify Contractor, in writing, that any person on the Work appears to be incompetent, disorderly, or otherwise unsatisfactory, such person shall be removed from the Project and shall not again be employed on it except with the consent of the Owner.

E. Contractor and Subcontractor shall, insofar as practicable, give preference in the hiring of workers for the Project to qualified local residents with first preference being given to citizens of

the United States who have served in the armed forces of the United States and have been honorably discharged therefrom or released from active duty therein.

F. Contractor and all Subcontractors shall comply with the Massachusetts Prevailing Wage law as contained in M.G.L. chapter 149 sections 26-27 which are included in Section 01069 – Massachusetts General Laws, located in Division 1 of this specification document.

SC-6.06.A

Delete paragraphs 6.06.A and 6.06.B of the General Conditions in their entirety and replace with the following:

A. Contractor shall not employ any Subcontractor, Supplier or other person or organization, (including those who are to furnish the principal items of materials or equipment), whether initially or as substitute, against whom Owner may have reasonable objection. Acceptance of any Subcontractor, other person or organization by Owner shall not constitute a waiver of any right of Owner to reject defective Work. Contractor shall not be required to employ and Subcontractor, other person or organization against whom Contractor has reasonable objection.

B. Not used.

SC-6.06.D

Add the following new subparagraph as follows:

6.06.D.1 Owner or Engineer may furnish to any such Subcontractor, Supplier, or other person or organization, to the extent practicable, information about amounts paid to Contractor in accordance with Contractor's Applications for Payment on account of the particular Subcontractor's, Suppliers, other person's, or other organization's Work.

SC-6.08

Add the following language at the end of Paragraph 6.08.A of the General Conditions:

SC-6.10

Add the following language at the end of paragraph 6.10.A of the General Conditions:

6.10.A.1 The materials and supplies to be used in the Work under this Contract are exempt from the Sales and Use Tax of the Commonwealth of Massachusetts. Contractor shall obtain the proper certificates, maintain the necessary records, and otherwise comply with all applicable requirements governing the exemption from sales tax.

SC-6.16.A

Delete the last sentence in paragraph 6.16.A of the General Conditions in its entirety and replace with the following:

If Engineer determines that the incident giving rise to the emergency action was not the responsibility of the Contractor and that a change in the Contract Documents is required because of the action taken by the Contractor in response to such an emergency, a Work Change Directive or Change Order will be issued.

SC-6.17

Add the following new paragraph immediately after paragraph 6.17.E of the General Conditions, which is to read as follows:

6.17.F The accuracy of all such information submitted by the Contractor is the responsibility of the Contractor. In reviewing Shop Drawings, Samples and similar submittals, the Engineer shall be entitled to rely upon the Contractor's representation that such information is correct and accurate.

SC-6-19.A

Add the following new paragraph immediately after paragraph 6.19.A of the General Conditions which is to read as follows:

B. The Contractor guarantees that the Work and Services to be performed under the Contract, and all workmanship, materials and equipment performed, furnished, used or installed in the construction of the same shall be free from defects and flaws, and shall be performed and furnished in strict accordance with the Drawings, Specifications, and other Contract Documents, that the strength of all parts of all manufactured equipment shall be adequate and as specified and that the performance test requirements of the Contract shall be fulfilled. This guarantee shall be for a period of one year from and after the date of completion and acceptance of the Work as stated in the final estimate. If part of the Work is accepted accordance with that subsection of this AGREEMENT titled "Partial Acceptance," the guarantee for that part of the Work shall be for a period of one year from the date fixed for such acceptance.

1. If at any time within the said period of guarantee any part of the Work requires repairing, correction or replacement, the Owner may notify the Contractor in writing to make the required repairs, correction or replacements. If the Contractor neglects to commence making such repairs, corrections or replacements to the satisfaction of the Owner within seven (7) days from the date of receipt of such notice, or having commenced fails to prosecute such Work with diligence, the Owner may employ other persons to make said repairs, corrections or replacements, and charge the costs, including compensation for additional professional services, to the Contractor.

2. The Contractor's guarantee under this clause, 6.19.B, is in addition to the Contractor's express or implied warranties under this Agreement and State law and in no way diminish any other rights that the Owner may have against the Contractor.

SC-6.19.C and D

Renumber 6.19.B and 6.19.C of the General Conditions to read 6.19.C and 6.19.D

SC-6.19D

Add the following new paragraphs immediately after paragraph 6.19.D of the General Conditions which is to read as follows:

E. Manufacturer's Guaranty/Warranty

1. The Contractor shall obtain the following guaranty/warranty from the manufacturer of all major pieces of equipment furnished and installed on this Project. Such guaranty/warranty shall be for the benefit of Owner and be furnished in writing by the manufacturer. The Contractor's and manufacturer's obligations under this provision are in addition to other

express or implied warranties under the Contract Documents and under the law and in no way diminish any other right that the Owner may have against the Contractor or manufacturer for faulty material, equipment or work. The warranty period shall not be interpreted as a limitation on the time in which the Owner can enforce such other duties, obligations, rights, or remedies.

2. The manufacturer warrants and guarantees for a period of one year from the date of Substantial Completion, or such longer period that may be specified in the Contract Documents, that all materials and equipment furnished and installed shall be free from flaws, defects in material and workmanship and shall be in conformance with the Contract Documents.

SC-6.20.A

Delete paragraphs 6.20.A of the General Conditions in its entirety and replace with the following:

A. To the fullest extent permitted by Laws and Regulations, Contractor shall defend, indemnify and hold harmless Owner, Engineer and the officers, directors, members, partners, employees, agents, consultants and subcontractors of each and any of them from and against all claims, costs, losses and damages (including but not limited to all fees and charges of engineers, architects, attorneys and other professionals and all court or arbitration or other dispute resolution costs) arising out of or relating to the performance of the Work, provided that any such claim, cost or loss or damage:

1. is attributable to bodily injury, sickness, disease or death or to injury to or destruction of tangible property (other than Work itself), including the loss of use resulting therefrom; and
2. is caused in whole or in part by any negligent act or omission of Contractor, any Subcontractor, any Supplier, or any individual or entity directly or indirectly employed by any of them to perform any of the Work or anyone for whose acts any of them may be liable, regardless of whether or not caused in part by any negligence or omission of an individual or entity indemnified hereunder or whether liability is imposed upon such indemnified party by Laws and Regulations regardless of the negligence of any such indemnified party unless caused by the sole negligence of a party indemnified hereunder. If through the acts of neglect on the part of Contractor, any other contractor or any Subcontractor shall suffer loss or damage on the Work, Contractor shall settle with such other contractor or Subcontractor by agreement or arbitration if such other contractor or Subcontractor will so settle. If such other contractor or Subcontractor shall assert any claim against Owner and/or Engineer, or the officers, directors, members, partners, employees, agents, consultants and subcontractors of each on account of any damage alleged to have been sustained, Owner shall notify Contractor, who shall defend, indemnify and save harmless Owner, Engineer, and the officers, directors, members, partners, employees, agents, consultants and subcontractors of each against any such claims.

SC-6.20.C

Delete paragraphs 6.20.C, C.1 and C.2 of the General Conditions in their entirety.

SC-6.21.E

Delete paragraph 6.21.E of the General Conditions in its entirety and replace with the following:

E. Contractors shall not be responsible for the adequacy of the performance criteria or design criteria contained in the Contract Documents.

SC-6.21.E

Add the following new paragraph immediately after paragraph 6.21.E of the General Conditions which is to read as follows:

SC-6.22 Definitions; Contract Provisions; Management and Financial Statements; Enforcement

A. Contractor shall comply with all applicable provisions of Chapter 30, Section 39R of the Massachusetts General Laws regarding Contractor's records which is included in Section 01069 – Massachusetts General Laws, located in Division 1 of this specification document.

ARTICLE 7. OTHER WORK AT THE SITE

ARTICLE 8. OWNER'S RESPONSIBILITIES

SC-8.06

Delete paragraph 8.06 of the General Conditions in its entirety.

ARTICLE 9. ENGINEER'S STATUS DURING CONSTRUCTION

SC-9.03

Add the following new paragraph immediately after paragraph 9.03.A of the General Conditions as follows:

9.03.A.1 Engineer will furnish a Resident Project Representative and assistants to assist ENGINEER in observing the performance of the work. The duties and responsibilities of the Resident Project Representative will be as enumerated in a document entitled "Duties, Responsibilities, and Limitations of the Authority of Resident Project Representative" and will be made available to Contractor at the start of his work.

SC-9.04

Add the following new paragraph immediately after paragraph 9.04.A of the General Conditions which is to read as follows:

9.04.A.1 ENGINEER'S interpretations will be made in accordance with Massachusetts General Law, Chapter 30, Section 39P.

ARTICLE 10. CHANGES IN THE WORK; CLAIMS

SC-10.01.A

Add the following new paragraph immediately after paragraph 10.01A of the General Conditions, which is to read as follows:

10.01.A.1 Upon request of the Owner or the Engineer, the Contractor shall without cost to the Owner submit to the Engineer, in such form as the Engineer may require, an accurate written estimate of the cost of any such proposed extra Work or change. The estimate shall indicate the quantity and unit cost of each item of materials, and the number of hours of work and hourly rate for each class of labor, as well as the description and amounts of all other costs chargeable under

the terms of this Article. Unit labor costs for the installation of each item of materials shall be shown if required by the Engineer. The contractor shall promptly revise and resubmit such estimate if the Engineer determines that it is not in compliance with the requirements of this Article, or that it contains errors of fact or mathematical errors. If required by the Engineer, in order to establish the exact cost of new Work added or previously required Work omitted, the Contractor shall obtain and furnish to the Engineer bona fide proposals from recognized suppliers for furnishing any material included in such Work. Such estimates shall be furnished promptly so as to occasion no delay in the Work, and shall be furnished at the Contractor's expense. The Contractor shall state in the estimate any extension of time required for the competition of the Work if the change or extra work is ordered.

SC-10.05.B

Replace paragraph 10.05.B of the General Conditions with the following paragraph:

10.05.B *Notice*: Written notice stating the general nature of each Claim shall be delivered by the claimant to Engineer and the other party to the Contract promptly (but in no event later than 7 calendar days) after the start of the event giving rise thereto. The responsibility to substantiate the Claim shall rest with the party making the Claim. Notice of the amount or extent of the Claim, with supporting data, shall be delivered to the Engineer and the other party to the Contract within 14 calendar days after the start of such event (unless Engineer allows additional time for claimant to submit additional or more accurate data in support of such Claim). A Claim for an adjustment in Contract Price shall be prepared in accordance with the provisions of Paragraph 12.01.B. A Claim for an adjustment in Contract Times shall be prepared in accordance with the provisions of Paragraph 12.02.B. Each Claim shall be accompanied by claimant's written statement that the adjustment claimed in the entire adjustment to which the claimant believes it is entitled as a result of said event. The opposing party shall submit any response to Engineer and claimant within 30 days after receipt of the claimant's last submittal (unless Engineer allows additional time).

ARTICLE 11. COST OF THE WORK; ALLOWANCES; UNIT PRICE WORK

SC-11.01

In the second sentence of paragraph 11.01.A.1 delete the word "superintendents".

SC-11.02

Delete paragraph 11.02 of the General Conditions in its entirety.

SC-11.3.D

Delete paragraph 11.03.D of the General Conditions in its entirety and replace with the following:

D. The unit price of an item of Unit Price Work shall be subject to re-evaluation and adjustment under the following conditions:

1. if the total cost of a particular item of Unit Price Work amounts to 5 percent or more of the Contract Price and the variation in the quantity of that particular item of Unit Price Work performed by Contractor differs by more than 15 percent from the estimated quantity of such item indicated in the Agreement; and
2. if there is no corresponding adjustment with respect to any other item of Work; and

3. if Contractor believes that Contractor has incurred additional expense as a result thereof; or if Owner believes that the quantity variation entitles Owner to an adjustment in the unit price, either Owner or Contractor may make a claim of an adjustment in the Unit Price for that quantity by which the actual quantity exceeds 115% of the estimated quantity in accordance with Article 10.05 if the parties are unable to agree as to the effect of any such variations in the quantity of Unit Price Work performed.

ARTICLE 12. CHANGE OF CONTRACT PRICE; CHANGE OF CONTRACT TIMES

SC-12.01.C.2.b

In the second line of paragraph 12.01.C.2.b, before the semicolon add the following words “based on subcontractor’s Cost of the Work”;

ARTICLE 13. TESTS AND INSPECTIONS; CORRECTION, REMOVAL OR ACCEPTANCE OF DEFECTIVE WORK

SC-13.05.A

Add the following new paragraph immediately after paragraph 13.05.A of the General Conditions to read as follows:

B. If Owner stops Work under paragraph 13.05.A Contractor shall not be entitled to any extension of Contract Time or increase in Contract Price.

SC-13.07.A

Delete paragraph 13.07.A of the General Conditions in its entirety and replace with the following:

If within one year after the date of Substantial Completion or such longer period of time as may be prescribed by Laws or Regulations or by the terms of any applicable special guarantee required by the Contract Documents or by any specific provision of the Contract Documents, any work is found to be defective, Contractor shall promptly, without cost to Owner and in accordance with Owner’s written instructions: (i) correct such defective work, or, if it has been rejected by Owner, remove it from the site and replace with work that is not defective, and (ii) satisfactory correct or remove and replace any damage to other work or the work of others therefrom. If Contractor does not begin the repairs within ten (10) days of receipt of written notification and promptly comply with the terms of Owner’s written instructions, or in an emergency where delay would cause serious risk, loss or damage, Owner may have the defective work corrected or the rejected work removed and replaced, and all claims, costs, losses, and damages caused by or resulting from such removal and replacement (including but not limited to all costs of repair or replacement of work of others) will be paid by Contractor.

ARTICLE 14. PAYMENTS TO CONTRACTOR AND COMPLETION

SC-14.02.A.3

Add the following new paragraph immediately after paragraph 14.02.A.3 of the General Conditions which is to read as follows:

1. Contractor shall furnish evidence that payment received on the basis of materials and equipment not incorporated and suitably stored, has in fact been paid to the respective supplier(s) within sixty days of payment by Owner. Failure to provide such evidence of payment may result in the

withdrawal of previous approval(s) and removal of the cost of related materials and equipment from the next submitted Application for Payment.

SC-14.02.B.1

Delete paragraph 14.02.B.1 of the General Conditions in its entirety and replace with the following:

1. Progress Payments will be made in accordance with Massachusetts General Law Chapter 30, Section 39G, which is included in Massachusetts General Laws, located in Attachments of this specification document.

ARTICLE 15. SUSPENSION OF WORK AND TERMINATION

SC-15.01.A

Delete paragraph 15.01.A of the General Conditions in its entirety and replace with the following:

- A. Owner may order, at any time and without cause, suspension of the Work in accordance with Massachusetts General Law Chapter 30, Section 39O, which is included in Section 01069 – Massachusetts General Laws, located in Division 1 of this specification document.

SC-15.02.A.4

Add the following new paragraph immediately after paragraph 15.02.A.4 of the General Conditions which is to read as follows

5. If Contractor abandons the Work, or sublets this Contract or any part thereof, without the previous written consent of Owner, or if the Contract or any claim thereunder shall be assigned by Contractor otherwise than as herein specified;

ARTICLE 16. DISPUTE RESOLUTION

SC-16.01.A

Delete the paragraph 16.01.A of the General Conditions in its entirety and replace with the following:

Either Owner or Contractor may request mediation of any Claim submitted to Engineer for a decision under paragraph 10.05 when such decision becomes final and binding. The mediation will be governed by the Construction Industry Mediation Rules of the American Arbitration Association in effect as of the Effective Date of this Agreement. The request for mediation shall be submitted in writing to the American Arbitration Association and the other party to the Contract.

SC-16.01C.3

Add the following new paragraph immediately after paragraph 16.01.C of the General Conditions to read as follows:

- D. Contractor shall carry on the Work and maintain the progress schedule during the dispute resolution proceedings unless otherwise agreed in writing by Owner and Contractor.

ARTICLE 17. MISCELLANEOUS

SC-17.06

Add the following new paragraphs immediately after paragraph 17.05 of the General Conditions to read as follows:

A. The Contractor shall not assign the whole or any part of this Contract or any moneys due or to become due hereunder until thirty (30) days prior notice in writing has been given to the Owner or the intention to assign, which notice shall state the identity and address of the prospective assignee. No assignment shall be made without Owner's prior written consent. Such consent shall not be unreasonably withheld. In case the Contractor assigns all or any part of the moneys due or to become due under this Contract, the instrument of assignment shall contain a clause substantially to the effect that it is agreed that the right of the assignee in and to any moneys due or to become due to the Contractor shall be subject to prior claims of all persons, firms and corporations of services rendered or materials supplied for the performance of the work called for in this Contract.

SC-17.07

Add the following new paragraph immediately after paragraph 17.06 of the General Conditions as follows:

SC-17.07 Legal Address of Contractor

17.07.A Contractor's business address and his office at or near the site of the Work are both hereby designated as places to which communications shall be delivered. The depositing of any letter, notice, or other communication in a postpaid wrapper directed to the Contractor's business address in a post office box regularly maintained by the Post Office Department or the delivery at either designated address of any letter, notice, or other communication by mail or otherwise shall be deemed sufficient service thereof upon Contractor, and the date of such service shall be the date of receipt. The first-named address may be changed at any time by an instrument in writing, executed and acknowledged by Contractor and delivered to Engineer. Service of any notice, letter, or other communication upon the Contractor personally shall likewise be deemed sufficient service.

SC-17.07 Liability

It is understood and agreed that members of the Owner and the Engineer or any agent or employees of the Owner signing this Agreement shall not be personally liable hereunder for any actions incurred in connection with this Agreement

SC-17.08 State Statutes and Regulations

See Massachusetts General Laws in Attachments for further modifications of the General Conditions due to State Statutes and Regulations.

CS-17.09 If any provisions of this Agreement shall be invalid or unenforceable to any extent or in any application, then the remainder of this Agreement and of such terms and conditions, except to such extent or such application, shall not be affected thereby, and each and every term and condition of this Agreement shall be valid and enforced to the fullest extent and in the broadest application permitted by law.

END OF SECTION 00800



CHARLES D. BAKER
Governor

KARYN E. POLITO
Lt. Governor

THE COMMONWEALTH OF MASSACHUSETTS
EXECUTIVE OFFICE OF LABOR AND WORKFORCE DEVELOPMENT
DEPARTMENT OF LABOR STANDARDS

Prevailing Wage Rates

**As determined by the Director under the provisions of the
Massachusetts General Laws, Chapter 149, Sections 26 to 27H**

ROSALIN ACOSTA
Secretary
WILLIAM D MCKINNEY
Director

Awarding Authority: City of Salem

Contract Number: **City/Town:** SALEM

Description of Work: T-09 Sewer Rehabilitation Project is for sewer rehabilitation including cured-in-place pipe lining, manhole reconstruction and waterproofing, and sewer pipe replacement and spot repairs.

Job Location: Various locations within city streets & easements

Information about Prevailing Wage Schedules for Awarding Authorities and Contractors

- This wage schedule applies only to the specific project referenced at the top of this page and uniquely identified by the "Wage Request Number" on all pages of this schedule.
- An Awarding Authority must request an updated wage schedule from the Department of Labor Standards ("DLS") if it has not opened bids or selected a contractor within 90 days of the date of issuance of the wage schedule. For CM AT RISK projects (bid pursuant to G.L. c.149A), the earlier of: (a) the execution date of the GMP Amendment, or (b) the bid for the first construction scope of work must be within 90-days of the wage schedule issuance date.
- The wage schedule shall be incorporated in any advertisement or call for bids for the project as required by M.G.L. c. 149, § 27. The wage schedule shall be made a part of the contract awarded for the project. The wage schedule must be posted in a conspicuous place at the work site for the life of the project in accordance with M.G.L. c. 149 § 27. The wages listed on the wage schedule must be paid to employees performing construction work on the project whether they are employed by the prime contractor, a filed sub-bidder, or any sub-contractor.
- All apprentices working on the project are required to be registered with the Massachusetts Department of Labor Standards, Division of Apprentice Standards (DLS/DAS). Apprentice must keep his/her apprentice identification card on his/her person during all work hours on the project. An apprentice registered with DAS may be paid the lower apprentice wage rate at the applicable step as provided on the prevailing wage schedule. **Any apprentice not registered with DLS/DAS regardless of whether or not they are registered with any other federal, state, local, or private agency must be paid the journeyworker's rate for the trade.**
- The wage rates will remain in effect for the duration of the project, except in the case of multi-year public construction projects. For construction projects lasting longer than one year, awarding authorities must request an updated wage schedule. Awarding authorities are required to request these updates no later than two weeks before the anniversary of the date the contract was executed by the awarding authority and the general contractor. For multi-year CM AT RISK projects, awarding authority must request an annual update no later than two weeks before the anniversary date, determined as the earlier of: (a) the execution date of the GMP Amendment, or (b) the execution date of the first amendment to permit procurement of construction services. Contractors are required to obtain the wage schedules from awarding authorities, and to pay no less than these rates to covered workers. The annual update requirement is not applicable to 27F "rental of equipment" contracts.
- Every contractor or subcontractor which performs construction work on the project is required to submit weekly payroll reports and a Statement of Compliance directly to the awarding authority by mail or email and keep them on file for three years. Each weekly payroll report must contain: the employee's name, address, occupational classification, hours worked, and wages paid. Do not submit weekly payroll reports to DLS. A sample of a payroll reporting form may be obtained at <http://www.mass.gov/dols/pw>.
- Contractors with questions about the wage rates or classifications included on the wage schedule have an affirmative obligation to inquire with DLS at (617) 626-6953.
- Employees not receiving the prevailing wage rate set forth on the wage schedule may report the violation to the Fair Labor Division of the office of the Attorney General at (617) 727-3465.
- Failure of a contractor or subcontractor to pay the prevailing wage rates listed on the wage schedule to all employees who perform construction work on the project is a violation of the law and subjects the contractor or subcontractor to civil and

Classification	Effective Date	Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
Construction						
(2 AXLE) DRIVER - EQUIPMENT <i>TEAMSTERS JOINT COUNCIL NO. 10 ZONE B</i>	12/01/2016	\$32.15	\$10.91	\$10.89	\$0.00	\$53.95
(3 AXLE) DRIVER - EQUIPMENT <i>TEAMSTERS JOINT COUNCIL NO. 10 ZONE B</i>	12/01/2016	\$32.22	\$10.91	\$10.89	\$0.00	\$54.02
(4 & 5 AXLE) DRIVER - EQUIPMENT <i>TEAMSTERS JOINT COUNCIL NO. 10 ZONE B</i>	12/01/2016	\$32.34	\$10.91	\$10.89	\$0.00	\$54.14
ADS/SUBMERSIBLE PILOT <i>PILE DRIVER LOCAL 56 (ZONE 1)</i>	08/01/2015	\$88.29	\$9.80	\$19.23	\$0.00	\$117.32
For apprentice rates see "Apprentice- PILE DRIVER"						
AIR TRACK OPERATOR <i>LABORERS - ZONE 2</i>	06/01/2017	\$33.15	\$7.60	\$13.50	\$0.00	\$54.25
	12/01/2017	\$33.78	\$7.60	\$13.50	\$0.00	\$54.88
	06/01/2018	\$34.62	\$7.60	\$13.50	\$0.00	\$55.72
	12/01/2018	\$35.46	\$7.60	\$13.50	\$0.00	\$56.56
	06/01/2019	\$36.33	\$7.60	\$13.50	\$0.00	\$57.43
	12/01/2019	\$37.19	\$7.60	\$13.50	\$0.00	\$58.29
For apprentice rates see "Apprentice- LABORER"						
ASBESTOS REMOVER - PIPE / MECH. EQUIPT. <i>HEAT & FROST INSULATORS LOCAL 6 (BOSTON)</i>	06/01/2017	\$34.90	\$11.50	\$7.10	\$0.00	\$53.50
	12/01/2017	\$35.90	\$11.50	\$7.10	\$0.00	\$54.50
	06/01/2018	\$36.90	\$11.50	\$7.10	\$0.00	\$55.50
	12/01/2018	\$37.90	\$11.50	\$7.10	\$0.00	\$56.50
	06/01/2019	\$38.90	\$11.50	\$7.10	\$0.00	\$57.50
	12/01/2019	\$39.90	\$11.50	\$7.10	\$0.00	\$58.50
	06/01/2020	\$40.90	\$11.50	\$7.10	\$0.00	\$59.50
	12/01/2020	\$41.90	\$11.50	\$7.10	\$0.00	\$60.50
ASPHALT RAKER <i>LABORERS - ZONE 2</i>	06/01/2017	\$32.65	\$7.60	\$13.50	\$0.00	\$53.75
	12/01/2017	\$33.28	\$7.60	\$13.50	\$0.00	\$54.38
	06/01/2018	\$34.12	\$7.60	\$13.50	\$0.00	\$55.22
	12/01/2018	\$34.96	\$7.60	\$13.50	\$0.00	\$56.06
	06/01/2019	\$35.83	\$7.60	\$13.50	\$0.00	\$56.93
	12/01/2019	\$36.69	\$7.60	\$13.50	\$0.00	\$57.79
For apprentice rates see "Apprentice- LABORER"						
ASPHALT/CONCRETE/CRUSHER PLANT-ON SITE <i>OPERATING ENGINEERS LOCAL 4</i>	06/01/2017	\$46.38	\$10.00	\$15.25	\$0.00	\$71.63
	12/01/2017	\$47.38	\$10.00	\$15.25	\$0.00	\$72.63
For apprentice rates see "Apprentice- OPERATING ENGINEERS"						
BACKHOE/FRONT-END LOADER <i>OPERATING ENGINEERS LOCAL 4</i>	06/01/2017	\$46.38	\$10.00	\$15.25	\$0.00	\$71.63
	12/01/2017	\$47.38	\$10.00	\$15.25	\$0.00	\$72.63
For apprentice rates see "Apprentice- OPERATING ENGINEERS"						
BARCO-TYPE JUMPING TAMPER <i>LABORERS - ZONE 2</i>	06/01/2017	\$32.65	\$7.60	\$13.50	\$0.00	\$53.75
	12/01/2017	\$33.28	\$7.60	\$13.50	\$0.00	\$54.38
	06/01/2018	\$34.12	\$7.60	\$13.50	\$0.00	\$55.22
	12/01/2018	\$34.96	\$7.60	\$13.50	\$0.00	\$56.06
	06/01/2019	\$35.83	\$7.60	\$13.50	\$0.00	\$56.93
	12/01/2019	\$36.69	\$7.60	\$13.50	\$0.00	\$57.79
For apprentice rates see "Apprentice- LABORER"						

Classification	Effective Date	Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
BLOCK PAVER, RAMMER / CURB SETTER <i>LABORERS - ZONE 2</i>	06/01/2017	\$33.15	\$7.60	\$13.50	\$0.00	\$54.25
	12/01/2017	\$33.78	\$7.60	\$13.50	\$0.00	\$54.88
	06/01/2018	\$34.62	\$7.60	\$13.50	\$0.00	\$55.72
	12/01/2018	\$35.46	\$7.60	\$13.50	\$0.00	\$56.56
	06/01/2019	\$36.33	\$7.60	\$13.50	\$0.00	\$57.43
	12/01/2019	\$37.19	\$7.60	\$13.50	\$0.00	\$58.29

For apprentice rates see "Apprentice- LABORER"

BOILER MAKER <i>BOILERMAKERS LOCAL 29</i>	01/01/2017	\$42.92	\$6.97	\$16.21	\$0.00	\$66.10
--	------------	---------	--------	---------	--------	---------

Apprentice - *BOILERMAKER - Local 29*

Effective Date - 01/01/2017

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	65	\$27.90	\$6.97	\$10.54	\$0.00	\$45.41
2	65	\$27.90	\$6.97	\$10.54	\$0.00	\$45.41
3	70	\$30.04	\$6.97	\$11.35	\$0.00	\$48.36
4	75	\$32.19	\$6.97	\$12.16	\$0.00	\$51.32
5	80	\$34.34	\$6.97	\$12.97	\$0.00	\$54.28
6	85	\$36.48	\$6.97	\$13.78	\$0.00	\$57.23
7	90	\$38.63	\$6.97	\$14.59	\$0.00	\$60.19
8	95	\$40.77	\$6.97	\$15.40	\$0.00	\$63.14

Notes:

Apprentice to Journeyworker Ratio:1:5

BRICK/STONE/ARTIFICIAL MASONRY (INCL. MASONRY WATERPROOFING) <i>BRICKLAYERS LOCAL 3 (LYNN)</i>	08/01/2017	\$52.06	\$10.75	\$19.35	\$0.00	\$82.16
	02/01/2018	\$52.74	\$10.75	\$19.35	\$0.00	\$82.84
	08/01/2018	\$54.09	\$10.75	\$19.48	\$0.00	\$84.32
	02/01/2019	\$54.73	\$10.75	\$19.48	\$0.00	\$84.96
	08/01/2019	\$56.08	\$10.75	\$19.62	\$0.00	\$86.45
	02/01/2020	\$56.72	\$10.75	\$19.62	\$0.00	\$87.09
	08/01/2020	\$58.07	\$10.75	\$19.77	\$0.00	\$88.59
	02/01/2021	\$58.71	\$10.75	\$19.77	\$0.00	\$89.23
	08/01/2021	\$60.11	\$10.75	\$19.93	\$0.00	\$90.79
	02/01/2022	\$60.70	\$10.75	\$19.93	\$0.00	\$91.38

Classification	Effective Date	Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
----------------	----------------	-----------	--------	---------	---------------------------	------------

Apprentice - BRICK/PLASTER/CEMENT MASON - Local 3 Lynn

Effective Date - 08/01/2017

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	50	\$26.03	\$10.75	\$19.35	\$0.00	\$56.13
2	60	\$31.24	\$10.75	\$19.35	\$0.00	\$61.34
3	70	\$36.44	\$10.75	\$19.35	\$0.00	\$66.54
4	80	\$41.65	\$10.75	\$19.35	\$0.00	\$71.75
5	90	\$46.85	\$10.75	\$19.35	\$0.00	\$76.95

Effective Date - 02/01/2018

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	50	\$26.37	\$10.75	\$19.35	\$0.00	\$56.47
2	60	\$31.64	\$10.75	\$19.35	\$0.00	\$61.74
3	70	\$36.92	\$10.75	\$19.35	\$0.00	\$67.02
4	80	\$42.19	\$10.75	\$19.35	\$0.00	\$72.29
5	90	\$47.47	\$10.75	\$19.35	\$0.00	\$77.57

Notes:

Apprentice to Journeyworker Ratio:1:5

BULLDOZER/GRADER/SCRAPER	06/01/2017	\$45.93	\$10.00	\$15.25	\$0.00	\$71.18
OPERATING ENGINEERS LOCAL 4	12/01/2017	\$46.92	\$10.00	\$15.25	\$0.00	\$72.17
For apprentice rates see "Apprentice- OPERATING ENGINEERS"						
CAISSON & UNDERPINNING BOTTOM MAN	12/01/2016	\$37.45	\$7.60	\$14.35	\$0.00	\$59.40
LABORERS - FOUNDATION AND MARINE						
For apprentice rates see "Apprentice- LABORER"						
CAISSON & UNDERPINNING LABORER	12/01/2016	\$36.30	\$7.60	\$14.35	\$0.00	\$58.25
LABORERS - FOUNDATION AND MARINE						
For apprentice rates see "Apprentice- LABORER"						
CAISSON & UNDERPINNING TOP MAN	12/01/2016	\$36.30	\$7.60	\$14.35	\$0.00	\$58.25
LABORERS - FOUNDATION AND MARINE						
For apprentice rates see "Apprentice- LABORER"						
CARBIDE CORE DRILL OPERATOR	06/01/2017	\$32.65	\$7.60	\$13.50	\$0.00	\$53.75
LABORERS - ZONE 2	12/01/2017	\$33.28	\$7.60	\$13.50	\$0.00	\$54.38
	06/01/2018	\$34.12	\$7.60	\$13.50	\$0.00	\$55.22
	12/01/2018	\$34.96	\$7.60	\$13.50	\$0.00	\$56.06
	06/01/2019	\$35.83	\$7.60	\$13.50	\$0.00	\$56.93
	12/01/2019	\$36.69	\$7.60	\$13.50	\$0.00	\$57.79
For apprentice rates see "Apprentice- LABORER"						
CARPENTER	03/01/2017	\$38.77	\$9.90	\$17.00	\$0.00	\$65.67
CARPENTERS -ZONE 2 (Eastern Massachusetts)	09/01/2017	\$39.28	\$9.90	\$17.50	\$0.00	\$66.68
	03/01/2018	\$40.28	\$9.90	\$17.50	\$0.00	\$67.68
	09/01/2018	\$41.32	\$9.90	\$17.50	\$0.00	\$68.72
	03/01/2019	\$42.35	\$9.90	\$17.50	\$0.00	\$69.75

Classification

Effective Date Base Wage Health Pension Supplemental Unemployment Total Rate

Apprentice - CARPENTER - Zone 2 Eastern MA

Effective Date - 03/01/2017

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	50	\$19.39	\$9.90	\$1.68	\$0.00	\$30.97
2	60	\$23.26	\$9.90	\$1.68	\$0.00	\$34.84
3	70	\$27.14	\$9.90	\$12.21	\$0.00	\$49.25
4	75	\$29.08	\$9.90	\$12.21	\$0.00	\$51.19
5	80	\$31.02	\$9.90	\$13.89	\$0.00	\$54.81
6	80	\$31.02	\$9.90	\$13.89	\$0.00	\$54.81
7	90	\$34.89	\$9.90	\$15.57	\$0.00	\$60.36
8	90	\$34.89	\$9.90	\$15.57	\$0.00	\$60.36

Effective Date - 09/01/2017

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	50	\$19.64	\$9.90	\$1.73	\$0.00	\$31.27
2	60	\$23.57	\$9.90	\$1.73	\$0.00	\$35.20
3	70	\$27.50	\$9.90	\$12.31	\$0.00	\$49.71
4	75	\$29.46	\$9.90	\$12.31	\$0.00	\$51.67
5	80	\$31.42	\$9.90	\$14.04	\$0.00	\$55.36
6	80	\$31.42	\$9.90	\$14.04	\$0.00	\$55.36
7	90	\$35.35	\$9.90	\$15.77	\$0.00	\$61.02
8	90	\$35.35	\$9.90	\$15.77	\$0.00	\$61.02

Notes:

Apprentice to Journeyworker Ratio:1:5

CEMENT MASONRY/PLASTERING	07/01/2017	\$47.40	\$12.20	\$19.41	\$1.30	\$80.31
BRICKLAYERS LOCAL 3 (LYNN)	01/01/2018	\$48.17	\$12.20	\$19.41	\$1.30	\$81.08
	07/01/2018	\$49.56	\$12.20	\$19.41	\$1.30	\$82.47
	01/01/2019	\$50.30	\$12.20	\$19.41	\$1.30	\$83.21
	07/01/2019	\$51.69	\$12.20	\$19.41	\$1.30	\$84.60
	01/01/2020	\$52.44	\$12.20	\$19.41	\$1.30	\$85.35

Classification
Effective Date
Base Wage
Health
Pension
**Supplemental
Unemployment**
Total Rate
Apprentice - CEMENT MASONRY/PLASTERING - Eastern Mass (Lynn)
Effective Date - 07/01/2017

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	50	\$23.70	\$12.20	\$12.41	\$0.00	\$48.31
2	60	\$28.44	\$12.20	\$14.41	\$1.30	\$56.35
3	65	\$30.81	\$12.20	\$15.41	\$1.30	\$59.72
4	70	\$33.18	\$12.20	\$16.41	\$1.30	\$63.09
5	75	\$35.55	\$12.20	\$17.41	\$1.30	\$66.46
6	80	\$37.92	\$12.20	\$18.41	\$1.30	\$69.83
7	90	\$42.66	\$12.20	\$19.41	\$1.30	\$75.57

Effective Date - 01/01/2018

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	50	\$24.09	\$12.20	\$12.41	\$0.00	\$48.70
2	60	\$28.90	\$12.20	\$14.41	\$1.30	\$56.81
3	65	\$31.31	\$12.20	\$15.41	\$1.30	\$60.22
4	70	\$33.72	\$12.20	\$16.41	\$1.30	\$63.63
5	75	\$36.13	\$12.20	\$17.41	\$1.30	\$67.04
6	80	\$38.54	\$12.20	\$18.41	\$1.30	\$70.45
7	90	\$43.35	\$12.20	\$19.41	\$1.30	\$76.26

Notes:

Steps 3,4 are 500 hrs. All other steps are 1,000 hrs.

Apprentice to Journeyworker Ratio:1:3

CHAIN SAW OPERATOR	06/01/2017	\$32.65	\$7.60	\$13.50	\$0.00	\$53.75
LABORERS - ZONE 2	12/01/2017	\$33.28	\$7.60	\$13.50	\$0.00	\$54.38
	06/01/2018	\$34.12	\$7.60	\$13.50	\$0.00	\$55.22
	12/01/2018	\$34.96	\$7.60	\$13.50	\$0.00	\$56.06
	06/01/2019	\$35.83	\$7.60	\$13.50	\$0.00	\$56.93
	12/01/2019	\$36.69	\$7.60	\$13.50	\$0.00	\$57.79
For apprentice rates see "Apprentice- LABORER"						
CLAM SHELLS/SLURRY BUCKETS/HEADING MACHINES	06/01/2017	\$47.38	\$10.00	\$15.25	\$0.00	\$72.63
OPERATING ENGINEERS LOCAL 4	12/01/2017	\$48.38	\$10.00	\$15.25	\$0.00	\$73.63
For apprentice rates see "Apprentice- OPERATING ENGINEERS"						
COMPRESSOR OPERATOR	06/01/2017	\$31.86	\$10.00	\$15.25	\$0.00	\$57.11
OPERATING ENGINEERS LOCAL 4	12/01/2017	\$32.55	\$10.00	\$15.25	\$0.00	\$57.80
For apprentice rates see "Apprentice- OPERATING ENGINEERS"						
DELEADER (BRIDGE)	01/01/2017	\$51.41	\$7.85	\$16.10	\$0.00	\$75.36
PAINTERS LOCAL 35 - ZONE 2						

Classification	Effective Date	Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
----------------	----------------	-----------	--------	---------	------------------------------	------------

Apprentice - PAINTER Local 35 - BRIDGES/TANKS

Effective Date - 01/01/2017

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	50	\$25.71	\$7.85	\$0.00	\$0.00	\$33.56
2	55	\$28.28	\$7.85	\$3.66	\$0.00	\$39.79
3	60	\$30.85	\$7.85	\$3.99	\$0.00	\$42.69
4	65	\$33.42	\$7.85	\$4.32	\$0.00	\$45.59
5	70	\$35.99	\$7.85	\$14.11	\$0.00	\$57.95
6	75	\$38.56	\$7.85	\$14.44	\$0.00	\$60.85
7	80	\$41.13	\$7.85	\$14.77	\$0.00	\$63.75
8	90	\$46.27	\$7.85	\$15.44	\$0.00	\$69.56

Notes:

Steps are 750 hrs.

Apprentice to Journeyworker Ratio:1:1

DEMO: ADZEMAN LABORERS - ZONE 2	06/01/2017	\$37.00	\$7.60	\$14.65	\$0.00	\$59.25
	12/01/2017	\$37.85	\$7.60	\$14.65	\$0.00	\$60.10
	06/01/2018	\$38.80	\$7.60	\$14.65	\$0.00	\$61.05
	12/01/2018	\$39.75	\$7.60	\$14.65	\$0.00	\$62.00
	06/01/2019	\$40.75	\$7.60	\$14.65	\$0.00	\$63.00
	12/01/2019	\$41.75	\$7.60	\$14.65	\$0.00	\$64.00
For apprentice rates see "Apprentice- LABORER"						
DEMO: BACKHOE/LOADER/HAMMER OPERATOR LABORERS - ZONE 2	06/01/2017	\$38.00	\$7.60	\$14.65	\$0.00	\$60.25
	12/01/2017	\$38.85	\$7.60	\$14.65	\$0.00	\$61.10
	06/01/2018	\$39.80	\$7.60	\$14.65	\$0.00	\$62.05
	12/01/2018	\$40.75	\$7.60	\$14.65	\$0.00	\$63.00
	06/01/2019	\$41.75	\$7.60	\$14.65	\$0.00	\$64.00
	12/01/2019	\$42.75	\$7.60	\$14.65	\$0.00	\$65.00
For apprentice rates see "Apprentice- LABORER"						
DEMO: BURNERS LABORERS - ZONE 2	06/01/2017	\$37.75	\$7.60	\$14.65	\$0.00	\$60.00
	12/01/2017	\$38.60	\$7.60	\$14.65	\$0.00	\$60.85
	06/01/2018	\$39.55	\$7.60	\$14.65	\$0.00	\$61.80
	12/01/2018	\$40.50	\$7.60	\$14.65	\$0.00	\$62.75
	06/01/2019	\$41.50	\$7.60	\$14.65	\$0.00	\$63.75
	12/01/2019	\$42.50	\$7.60	\$14.65	\$0.00	\$64.75
For apprentice rates see "Apprentice- LABORER"						
DEMO: CONCRETE CUTTER/SAWYER LABORERS - ZONE 2	06/01/2017	\$38.00	\$7.60	\$14.65	\$0.00	\$60.25
	12/01/2017	\$38.85	\$7.60	\$14.65	\$0.00	\$61.10
	06/01/2018	\$39.80	\$7.60	\$14.65	\$0.00	\$62.05
	12/01/2018	\$40.75	\$7.60	\$14.65	\$0.00	\$63.00
	06/01/2019	\$41.75	\$7.60	\$14.65	\$0.00	\$64.00
	12/01/2019	\$42.75	\$7.60	\$14.65	\$0.00	\$65.00
For apprentice rates see "Apprentice- LABORER"						

Classification	Effective Date	Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
DEMO: JACKHAMMER OPERATOR <i>LABORERS - ZONE 2</i>	06/01/2017	\$37.75	\$7.60	\$14.65	\$0.00	\$60.00
	12/01/2017	\$38.60	\$7.60	\$14.65	\$0.00	\$60.85
	06/01/2018	\$39.55	\$7.60	\$14.65	\$0.00	\$61.80
	12/01/2018	\$40.50	\$7.60	\$14.65	\$0.00	\$62.75
	06/01/2019	\$41.50	\$7.60	\$14.65	\$0.00	\$63.75
	12/01/2019	\$42.50	\$7.60	\$14.65	\$0.00	\$64.75
For apprentice rates see "Apprentice- LABORER"						
DEMO: WRECKING LABORER <i>LABORERS - ZONE 2</i>	06/01/2017	\$37.00	\$7.60	\$14.65	\$0.00	\$59.25
	12/01/2017	\$37.85	\$7.60	\$14.65	\$0.00	\$60.10
	06/01/2018	\$38.80	\$7.60	\$14.65	\$0.00	\$61.05
	12/01/2018	\$39.75	\$7.60	\$14.65	\$0.00	\$62.00
	06/01/2019	\$40.75	\$7.60	\$14.65	\$0.00	\$63.00
	12/01/2019	\$41.75	\$7.60	\$14.65	\$0.00	\$64.00
For apprentice rates see "Apprentice- LABORER"						
DIRECTIONAL DRILL MACHINE OPERATOR <i>OPERATING ENGINEERS LOCAL 4</i>	06/01/2017	\$45.93	\$10.00	\$15.25	\$0.00	\$71.18
	12/01/2017	\$46.92	\$10.00	\$15.25	\$0.00	\$72.17
For apprentice rates see "Apprentice- OPERATING ENGINEERS"						
DIVER <i>PILE DRIVER LOCAL 56 (ZONE 1)</i>	08/01/2015	\$58.86	\$9.80	\$19.23	\$0.00	\$87.89
For apprentice rates see "Apprentice- PILE DRIVER"						
DIVER TENDER <i>PILE DRIVER LOCAL 56 (ZONE 1)</i>	08/01/2015	\$42.04	\$9.80	\$19.23	\$0.00	\$71.07
For apprentice rates see "Apprentice- PILE DRIVER"						
DIVER TENDER (EFFLUENT) <i>PILE DRIVER LOCAL 56 (ZONE 1)</i>	08/01/2015	\$63.06	\$9.80	\$19.23	\$0.00	\$92.09
For apprentice rates see "Apprentice- PILE DRIVER"						
DIVER/SLURRY (EFFLUENT) <i>PILE DRIVER LOCAL 56 (ZONE 1)</i>	08/01/2015	\$88.23	\$9.80	\$19.23	\$0.00	\$117.26
For apprentice rates see "Apprentice- PILE DRIVER"						
DRAWBRIDGE OPERATOR (Construction) <i>ELECTRICIANS LOCAL 103</i>	03/01/2017	\$48.33	\$13.00	\$17.45	\$0.00	\$78.78
	09/01/2017	\$49.28	\$13.00	\$17.48	\$0.00	\$79.76
	03/01/2018	\$50.15	\$13.00	\$17.85	\$0.00	\$81.00
	09/01/2018	\$51.34	\$13.00	\$17.89	\$0.00	\$82.23
	03/01/2019	\$52.53	\$13.00	\$17.93	\$0.00	\$83.46
For apprentice rates see "Apprentice- ELECTRICIAN"						
ELECTRICIAN <i>ELECTRICIANS LOCAL 103</i>	03/01/2017	\$48.33	\$13.00	\$17.45	\$0.00	\$78.78
	09/01/2017	\$49.28	\$13.00	\$17.48	\$0.00	\$79.76
	03/01/2018	\$50.15	\$13.00	\$17.85	\$0.00	\$81.00
	09/01/2018	\$51.34	\$13.00	\$17.89	\$0.00	\$82.23
	03/01/2019	\$52.53	\$13.00	\$17.93	\$0.00	\$83.46

Classification

**Effective Date Base Wage Health Pension Supplemental
Unemployment Total Rate**

Apprentice - *ELECTRICIAN - Local 103*

Effective Date - 03/01/2017

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	40	\$19.33	\$13.00	\$0.58	\$0.00	\$32.91
2	40	\$19.33	\$13.00	\$0.58	\$0.00	\$32.91
3	45	\$21.75	\$13.00	\$13.37	\$0.00	\$48.12
4	45	\$21.75	\$13.00	\$13.37	\$0.00	\$48.12
5	50	\$24.17	\$13.00	\$13.75	\$0.00	\$50.92
6	55	\$26.58	\$13.00	\$14.11	\$0.00	\$53.69
7	60	\$29.00	\$13.00	\$14.48	\$0.00	\$56.48
8	65	\$31.41	\$13.00	\$14.85	\$0.00	\$59.26
9	70	\$33.83	\$13.00	\$15.22	\$0.00	\$62.05
10	75	\$36.25	\$13.00	\$15.60	\$0.00	\$64.85

Effective Date - 09/01/2017

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	40	\$19.71	\$13.00	\$0.59	\$0.00	\$33.30
2	40	\$19.71	\$13.00	\$0.59	\$0.00	\$33.30
3	45	\$22.18	\$13.00	\$13.39	\$0.00	\$48.57
4	45	\$22.18	\$13.00	\$13.39	\$0.00	\$48.57
5	50	\$24.64	\$13.00	\$13.76	\$0.00	\$51.40
6	55	\$27.10	\$13.00	\$14.12	\$0.00	\$54.22
7	60	\$29.57	\$13.00	\$14.50	\$0.00	\$57.07
8	65	\$32.03	\$13.00	\$14.87	\$0.00	\$59.90
9	70	\$34.50	\$13.00	\$15.25	\$0.00	\$62.75
10	75	\$36.96	\$13.00	\$15.62	\$0.00	\$65.58

Notes: :

App Prior 1/1/03; 30/35/40/45/50/55/65/70/75/80

Apprentice to Journeyworker Ratio:2:3***

ELEVATOR CONSTRUCTOR	01/01/2017	\$55.86	\$15.28	\$15.71	\$0.00	\$86.85
<i>ELEVATOR CONSTRUCTORS LOCAL 4</i>						

Classification	Effective Date	Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
Apprentice - ELEVATOR CONSTRUCTOR - Local 4						
Effective Date - 01/01/2017						
Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	50	\$27.93	\$15.28	\$0.00	\$0.00	\$43.21
2	55	\$30.72	\$15.28	\$15.71	\$0.00	\$61.71
3	65	\$36.31	\$15.28	\$15.71	\$0.00	\$67.30
4	70	\$39.10	\$15.28	\$15.71	\$0.00	\$70.09
5	80	\$44.69	\$15.28	\$15.71	\$0.00	\$75.68
Notes: Steps 1-2 are 6 mos.; Steps 3-5 are 1 year						
Apprentice to Journeyworker Ratio:1:1						
ELEVATOR CONSTRUCTOR HELPER <i>ELEVATOR CONSTRUCTORS LOCAL 4</i>	01/01/2017	\$39.10	\$15.28	\$15.71	\$0.00	\$70.09
For apprentice rates see "Apprentice - ELEVATOR CONSTRUCTOR"						
FENCE & GUARD RAIL ERECTOR <i>LABORERS - ZONE 2</i>	06/01/2017	\$32.65	\$7.60	\$13.50	\$0.00	\$53.75
	12/01/2017	\$33.28	\$7.60	\$13.50	\$0.00	\$54.38
	06/01/2018	\$34.12	\$7.60	\$13.50	\$0.00	\$55.22
	12/01/2018	\$34.96	\$7.60	\$13.50	\$0.00	\$56.06
	06/01/2019	\$35.83	\$7.60	\$13.50	\$0.00	\$56.93
	12/01/2019	\$36.69	\$7.60	\$13.50	\$0.00	\$57.79
For apprentice rates see "Apprentice- LABORER"						
FIELD ENG.INST.PERSON-BLDG,SITE,HVY/HWY <i>OPERATING ENGINEERS LOCAL 4</i>	05/01/2017	\$42.15	\$10.00	\$15.25	\$0.00	\$67.40
	11/01/2017	\$42.88	\$10.00	\$15.25	\$0.00	\$68.13
	05/01/2018	\$43.59	\$10.00	\$15.25	\$0.00	\$68.84
For apprentice rates see "Apprentice- OPERATING ENGINEERS"						
FIELD ENG.PARTY CHIEF-BLDG,SITE,HVY/HWY <i>OPERATING ENGINEERS LOCAL 4</i>	05/01/2017	\$43.61	\$10.00	\$15.25	\$0.00	\$68.86
	11/01/2017	\$44.34	\$10.00	\$15.25	\$0.00	\$69.59
	05/01/2018	\$45.06	\$10.00	\$15.25	\$0.00	\$70.31
For apprentice rates see "Apprentice- OPERATING ENGINEERS"						
FIELD ENG.ROD PERSON-BLDG,SITE,HVY/HWY <i>OPERATING ENGINEERS LOCAL 4</i>	05/01/2017	\$22.41	\$10.00	\$15.25	\$0.00	\$47.66
	11/01/2017	\$22.83	\$10.00	\$15.25	\$0.00	\$48.08
	05/01/2018	\$23.26	\$10.00	\$15.25	\$0.00	\$48.51
For apprentice rates see "Apprentice- OPERATING ENGINEERS"						
FIRE ALARM INSTALLER <i>ELECTRICIANS LOCAL 103</i>	03/01/2017	\$48.33	\$13.00	\$17.45	\$0.00	\$78.78
	09/01/2017	\$49.28	\$13.00	\$17.48	\$0.00	\$79.76
	03/01/2018	\$50.15	\$13.00	\$17.85	\$0.00	\$81.00
	09/01/2018	\$51.34	\$13.00	\$17.89	\$0.00	\$82.23
	03/01/2019	\$52.53	\$13.00	\$17.93	\$0.00	\$83.46
For apprentice rates see "Apprentice- ELECTRICIAN"						
FIRE ALARM REPAIR / MAINTENANCE <i>LOCAL 103</i> / COMMISSIONING <i>ELECTRICIANS</i>	03/01/2017	\$36.25	\$13.00	\$15.60	\$0.00	\$64.85
	09/01/2017	\$36.96	\$13.00	\$15.62	\$0.00	\$65.58
	03/01/2018	\$37.61	\$13.00	\$15.93	\$0.00	\$66.54
	09/01/2018	\$38.51	\$13.00	\$15.96	\$0.00	\$67.47
	03/01/2019	\$39.40	\$13.00	\$15.98	\$0.00	\$68.38

Issue Date: 08/24/2017	Wage Request Number:		20170824-010		Page 10 of 32	

Classification	Effective Date	Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
For apprentice rates see "Apprentice- TELECOMMUNICATIONS TECHNICIAN"						
FIREMAN (ASST. ENGINEER)	06/01/2017	\$38.49	\$10.00	\$15.25	\$0.00	\$63.74
OPERATING ENGINEERS LOCAL 4	12/01/2017	\$39.32	\$10.00	\$15.25	\$0.00	\$64.57
For apprentice rates see "Apprentice- OPERATING ENGINEERS"						
FLAGGER & SIGNALER	06/01/2017	\$20.50	\$7.60	\$13.50	\$0.00	\$41.60
LABORERS - ZONE 2	12/01/2017	\$21.50	\$7.60	\$13.50	\$0.00	\$42.60
	06/01/2018	\$21.50	\$7.60	\$13.50	\$0.00	\$42.60
	12/01/2018	\$22.50	\$7.60	\$13.50	\$0.00	\$43.60
	06/01/2019	\$22.50	\$7.60	\$13.50	\$0.00	\$43.60
	12/01/2019	\$23.50	\$7.60	\$13.50	\$0.00	\$44.60
For apprentice rates see "Apprentice- LABORER"						
FLOORCOVERER	03/01/2016	\$42.13	\$9.80	\$17.62	\$0.00	\$69.55
FLOORCOVERERS LOCAL 2168 ZONE I						

Apprentice - FLOORCOVERER - Local 2168 Zone I

Effective Date - 03/01/2016

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	50	\$21.07	\$9.80	\$1.79	\$0.00	\$32.66
2	55	\$23.17	\$9.80	\$1.79	\$0.00	\$34.76
3	60	\$25.28	\$9.80	\$12.25	\$0.00	\$47.33
4	65	\$27.38	\$9.80	\$12.25	\$0.00	\$49.43
5	70	\$29.49	\$9.80	\$14.04	\$0.00	\$53.33
6	75	\$31.60	\$9.80	\$14.04	\$0.00	\$55.44
7	80	\$33.70	\$9.80	\$15.83	\$0.00	\$59.33
8	85	\$35.81	\$9.80	\$15.83	\$0.00	\$61.44

Notes:

Steps are 750 hrs.

Apprentice to Journeyworker Ratio:1:1

FORK LIFT/CHERRY PICKER	06/01/2017	\$46.38	\$10.00	\$15.25	\$0.00	\$71.63
OPERATING ENGINEERS LOCAL 4	12/01/2017	\$47.38	\$10.00	\$15.25	\$0.00	\$72.63
For apprentice rates see "Apprentice- OPERATING ENGINEERS"						
GENERATOR/LIGHTING PLANT/HEATERS	06/01/2017	\$31.86	\$10.00	\$15.25	\$0.00	\$57.11
OPERATING ENGINEERS LOCAL 4	12/01/2017	\$32.55	\$10.00	\$15.25	\$0.00	\$57.80
For apprentice rates see "Apprentice- OPERATING ENGINEERS"						
GLAZIER (GLASS PLANK/AIR BARRIER/INTERIOR SYSTEMS)	01/01/2017	\$40.91	\$7.85	\$16.10	\$0.00	\$64.86
GLAZIERS LOCAL 35 (ZONE 2)						

Apprentice - GLAZIER - Local 35 Zone 2
Effective Date - 01/01/2017

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	50	\$20.46	\$7.85	\$0.00	\$0.00	\$28.31
2	55	\$22.50	\$7.85	\$3.66	\$0.00	\$34.01
3	60	\$24.55	\$7.85	\$3.99	\$0.00	\$36.39
4	65	\$26.59	\$7.85	\$4.32	\$0.00	\$38.76
5	70	\$28.64	\$7.85	\$14.11	\$0.00	\$50.60
6	75	\$30.68	\$7.85	\$14.44	\$0.00	\$52.97
7	80	\$32.73	\$7.85	\$14.77	\$0.00	\$55.35
8	90	\$36.82	\$7.85	\$15.44	\$0.00	\$60.11

Notes:
Steps are 750 hrs.

Apprentice to Journeyworker Ratio:1:1

HOISTING ENGINEER/CRANES/GRADALLS	06/01/2017	\$46.38	\$10.00	\$15.25	\$0.00	\$71.63
OPERATING ENGINEERS LOCAL 4	12/01/2017	\$47.38	\$10.00	\$15.25	\$0.00	\$72.63

Classification	Effective Date	Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
----------------	----------------	-----------	--------	---------	------------------------------	------------

Apprentice - OPERATING ENGINEERS - Local 4

Effective Date - 06/01/2017

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	55	\$25.51	\$10.00	\$0.00	\$0.00	\$35.51
2	60	\$27.83	\$10.00	\$15.25	\$0.00	\$53.08
3	65	\$30.15	\$10.00	\$15.25	\$0.00	\$55.40
4	70	\$32.47	\$10.00	\$15.25	\$0.00	\$57.72
5	75	\$34.79	\$10.00	\$15.25	\$0.00	\$60.04
6	80	\$37.10	\$10.00	\$15.25	\$0.00	\$62.35
7	85	\$39.42	\$10.00	\$15.25	\$0.00	\$64.67
8	90	\$41.74	\$10.00	\$15.25	\$0.00	\$66.99

Effective Date - 12/01/2017

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	55	\$26.06	\$10.00	\$0.00	\$0.00	\$36.06
2	60	\$28.43	\$10.00	\$15.25	\$0.00	\$53.68
3	65	\$30.80	\$10.00	\$15.25	\$0.00	\$56.05
4	70	\$33.17	\$10.00	\$15.25	\$0.00	\$58.42
5	75	\$35.54	\$10.00	\$15.25	\$0.00	\$60.79
6	80	\$37.90	\$10.00	\$15.25	\$0.00	\$63.15
7	85	\$40.27	\$10.00	\$15.25	\$0.00	\$65.52
8	90	\$42.64	\$10.00	\$15.25	\$0.00	\$67.89

Notes:

Apprentice to Journeyworker Ratio:1:6

HVAC (DUCTWORK) <i>SHEETMETAL WORKERS LOCAL 17 - A</i>	08/01/2017	\$43.83	\$11.45	\$24.03	\$2.38	\$81.69
	02/01/2018	\$44.98	\$11.45	\$24.03	\$2.38	\$82.84
For apprentice rates see "Apprentice- SHEET METAL WORKER"						
HVAC (ELECTRICAL CONTROLS) <i>ELECTRICIANS LOCAL 103</i>	03/01/2017	\$48.33	\$13.00	\$17.45	\$0.00	\$78.78
	09/01/2017	\$49.28	\$13.00	\$17.48	\$0.00	\$79.76
	03/01/2018	\$50.15	\$13.00	\$17.85	\$0.00	\$81.00
	09/01/2018	\$51.34	\$13.00	\$17.89	\$0.00	\$82.23
	03/01/2019	\$52.53	\$13.00	\$17.93	\$0.00	\$83.46
For apprentice rates see "Apprentice- ELECTRICIAN"						
HVAC (TESTING AND BALANCING - AIR) <i>SHEETMETAL WORKERS LOCAL 17 - A</i>	08/01/2017	\$43.83	\$11.45	\$24.03	\$2.38	\$81.69
	02/01/2018	\$44.98	\$11.45	\$24.03	\$2.38	\$82.84
For apprentice rates see "Apprentice- SHEET METAL WORKER"						
HVAC (TESTING AND BALANCING -WATER) <i>PIPEFITTERS LOCAL 537 (Local 138)</i>	03/01/2017	\$48.86	\$9.70	\$16.14	\$0.00	\$74.70
For apprentice rates see "Apprentice- PIPEFITTER" or "PLUMBER/PIPEFITTER"						
HVAC MECHANIC <i>PIPEFITTERS LOCAL 537 (Local 138)</i>	03/01/2017	\$48.86	\$9.70	\$16.14	\$0.00	\$74.70
For apprentice rates see "Apprentice- PIPEFITTER" or "PLUMBER/PIPEFITTER"						

Classification	Effective Date	Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
HYDRAULIC DRILLS <i>LABORERS - ZONE 2</i>	06/01/2017	\$33.15	\$7.60	\$13.50	\$0.00	\$54.25
	12/01/2017	\$33.78	\$7.60	\$13.50	\$0.00	\$54.88
	06/01/2018	\$34.62	\$7.60	\$13.50	\$0.00	\$55.72
	12/01/2018	\$35.46	\$7.60	\$13.50	\$0.00	\$56.56
	06/01/2019	\$36.33	\$7.60	\$13.50	\$0.00	\$57.43
	12/01/2019	\$37.19	\$7.60	\$13.50	\$0.00	\$58.29

For apprentice rates see "Apprentice- LABORER"

INSULATOR (PIPES & TANKS) <i>HEAT & FROST INSULATORS LOCAL 6 (BOSTON)</i>	09/01/2016	\$45.09	\$11.75	\$14.20	\$0.00	\$71.04
	09/01/2017	\$47.09	\$11.75	\$14.20	\$0.00	\$73.04
	09/01/2018	\$49.34	\$11.75	\$14.20	\$0.00	\$75.29
	09/01/2019	\$51.84	\$11.75	\$14.20	\$0.00	\$77.79

Apprentice - ASBESTOS INSULATOR (Pipes & Tanks) - Local 6 Boston

Effective Date - 09/01/2016

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	50	\$22.55	\$11.75	\$10.45	\$0.00	\$44.75
2	60	\$27.05	\$11.75	\$11.20	\$0.00	\$50.00
3	70	\$31.56	\$11.75	\$11.95	\$0.00	\$55.26
4	80	\$36.07	\$11.75	\$12.70	\$0.00	\$60.52

Effective Date - 09/01/2017

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	50	\$23.55	\$11.75	\$10.45	\$0.00	\$45.75
2	60	\$28.25	\$11.75	\$11.20	\$0.00	\$51.20
3	70	\$32.96	\$11.75	\$11.95	\$0.00	\$56.66
4	80	\$37.67	\$11.75	\$12.70	\$0.00	\$62.12

Notes:

Steps are 1 year

Apprentice to Journeyworker Ratio:1:4

IRONWORKER/WELDER <i>IRONWORKERS LOCAL 7 (BOSTON AREA)</i>	03/16/2017	\$44.65	\$7.80	\$20.85	\$0.00	\$73.30
---	------------	---------	--------	---------	--------	---------

Apprentice - IRONWORKER - Local 7 Boston

Effective Date - 03/16/2017

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	60	\$26.79	\$7.80	\$20.85	\$0.00	\$55.44
2	70	\$31.26	\$7.80	\$20.85	\$0.00	\$59.91
3	75	\$33.49	\$7.80	\$20.85	\$0.00	\$62.14
4	80	\$35.72	\$7.80	\$20.85	\$0.00	\$64.37
5	85	\$37.95	\$7.80	\$20.85	\$0.00	\$66.60
6	90	\$40.19	\$7.80	\$20.85	\$0.00	\$68.84

Notes:

** Structural 1:6; Ornamental 1:4

Apprentice to Journeyworker Ratio:**

JACKHAMMER & PAVING BREAKER OPERATOR	06/01/2017	\$32.65	\$7.60	\$13.50	\$0.00	\$53.75
LABORERS - ZONE 2	12/01/2017	\$33.28	\$7.60	\$13.50	\$0.00	\$54.38
	06/01/2018	\$34.12	\$7.60	\$13.50	\$0.00	\$55.22
	12/01/2018	\$34.96	\$7.60	\$13.50	\$0.00	\$56.06
	06/01/2019	\$35.83	\$7.60	\$13.50	\$0.00	\$56.93
	12/01/2019	\$36.69	\$7.60	\$13.50	\$0.00	\$57.79

For apprentice rates see "Apprentice- LABORER"

LABORER	06/01/2017	\$32.40	\$7.60	\$13.50	\$0.00	\$53.50
LABORERS - ZONE 2	12/01/2017	\$33.03	\$7.60	\$13.50	\$0.00	\$54.13
	06/01/2018	\$33.87	\$7.60	\$13.50	\$0.00	\$54.97
	12/01/2018	\$34.71	\$7.60	\$13.50	\$0.00	\$55.81
	06/01/2019	\$35.58	\$7.60	\$13.50	\$0.00	\$56.68
	12/01/2019	\$36.44	\$7.60	\$13.50	\$0.00	\$57.54

Classification
Effective Date
Base Wage
Health
Pension
**Supplemental
Unemployment**
Total Rate
Apprentice - LABORER - Zone 2
Effective Date - 06/01/2017

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	60	\$19.44	\$7.60	\$13.50	\$0.00	\$40.54
2	70	\$22.68	\$7.60	\$13.50	\$0.00	\$43.78
3	80	\$25.92	\$7.60	\$13.50	\$0.00	\$47.02
4	90	\$29.16	\$7.60	\$13.50	\$0.00	\$50.26

Effective Date - 12/01/2017

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	60	\$19.82	\$7.60	\$13.50	\$0.00	\$40.92
2	70	\$23.12	\$7.60	\$13.50	\$0.00	\$44.22
3	80	\$26.42	\$7.60	\$13.50	\$0.00	\$47.52
4	90	\$29.73	\$7.60	\$13.50	\$0.00	\$50.83

Notes:
Apprentice to Journeyworker Ratio:1:5
LABORER: CARPENTER TENDER
LABORERS - ZONE 2

06/01/2017	\$32.40	\$7.60	\$13.50	\$0.00	\$53.50
12/01/2017	\$33.03	\$7.60	\$13.50	\$0.00	\$54.13
06/01/2018	\$33.87	\$7.60	\$13.50	\$0.00	\$54.97
12/01/2018	\$34.71	\$7.60	\$13.50	\$0.00	\$55.81
06/01/2019	\$35.58	\$7.60	\$13.50	\$0.00	\$56.68
12/01/2019	\$36.44	\$7.60	\$13.50	\$0.00	\$57.54

For apprentice rates see "Apprentice- LABORER"

LABORER: CEMENT FINISHER TENDER
LABORERS - ZONE 2

06/01/2017	\$32.40	\$7.60	\$13.50	\$0.00	\$53.50
12/01/2017	\$33.03	\$7.60	\$13.50	\$0.00	\$54.13
06/01/2018	\$33.87	\$7.60	\$13.50	\$0.00	\$54.97
12/01/2018	\$34.71	\$7.60	\$13.50	\$0.00	\$55.81
06/01/2019	\$35.58	\$7.60	\$13.50	\$0.00	\$56.68
12/01/2019	\$36.44	\$7.60	\$13.50	\$0.00	\$57.54

For apprentice rates see "Apprentice- LABORER"

LABORER: HAZARDOUS WASTE/ASBESTOS REMOVER
LABORERS - ZONE 2

06/01/2017	\$32.60	\$7.60	\$13.45	\$0.00	\$53.65
12/01/2017	\$33.23	\$7.60	\$13.45	\$0.00	\$54.28
06/01/2018	\$34.07	\$7.60	\$13.45	\$0.00	\$55.12
12/01/2018	\$34.91	\$7.60	\$13.45	\$0.00	\$55.96
06/01/2019	\$35.78	\$7.60	\$13.45	\$0.00	\$56.83
12/01/2019	\$36.64	\$7.60	\$13.45	\$0.00	\$57.69

For apprentice rates see "Apprentice- LABORER"

Classification	Effective Date	Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
LABORER: MASON TENDER <i>LABORERS - ZONE 2</i>	06/01/2017	\$32.65	\$7.60	\$13.50	\$0.00	\$53.75
	12/01/2017	\$33.28	\$7.60	\$13.50	\$0.00	\$54.38
	06/01/2018	\$34.12	\$7.60	\$13.50	\$0.00	\$55.22
	12/01/2018	\$34.96	\$7.60	\$13.50	\$0.00	\$56.06
	06/01/2019	\$35.83	\$7.60	\$13.50	\$0.00	\$56.93
	12/01/2019	\$36.69	\$7.60	\$13.50	\$0.00	\$57.79
For apprentice rates see "Apprentice- LABORER"						
LABORER: MULTI-TRADE TENDER <i>LABORERS - ZONE 2</i>	06/01/2017	\$32.40	\$7.60	\$13.50	\$0.00	\$53.50
	12/01/2017	\$33.03	\$7.60	\$13.50	\$0.00	\$54.13
	06/01/2018	\$33.87	\$7.60	\$13.50	\$0.00	\$54.97
	12/01/2018	\$34.71	\$7.60	\$13.50	\$0.00	\$55.81
	06/01/2019	\$35.58	\$7.60	\$13.50	\$0.00	\$56.68
	12/01/2019	\$36.44	\$7.60	\$13.50	\$0.00	\$57.54
For apprentice rates see "Apprentice- LABORER"						
LABORER: TREE REMOVER <i>LABORERS - ZONE 2</i>	06/01/2017	\$32.40	\$7.60	\$13.50	\$0.00	\$53.50
	12/01/2017	\$33.03	\$7.60	\$13.50	\$0.00	\$54.13
	06/01/2018	\$33.87	\$7.60	\$13.50	\$0.00	\$54.97
	12/01/2018	\$34.71	\$7.60	\$13.50	\$0.00	\$55.81
	06/01/2019	\$35.58	\$7.60	\$13.50	\$0.00	\$56.68
	12/01/2019	\$36.44	\$7.60	\$13.50	\$0.00	\$57.54
This classification applies to all tree work associated with the removal of standing trees, and trimming and removal of branches and limbs when the work is not done for a utility company for the purpose of operation, maintenance or repair of utility company equipment. For apprentice rates see "Apprentice- LABORER"						
LASER BEAM OPERATOR <i>LABORERS - ZONE 2</i>	06/01/2017	\$32.65	\$7.60	\$13.50	\$0.00	\$53.75
	12/01/2017	\$33.28	\$7.60	\$13.50	\$0.00	\$54.38
	06/01/2018	\$34.12	\$7.60	\$13.50	\$0.00	\$55.22
	12/01/2018	\$34.96	\$7.60	\$13.50	\$0.00	\$56.06
	06/01/2019	\$35.83	\$7.60	\$13.50	\$0.00	\$56.93
	12/01/2019	\$36.69	\$7.60	\$13.50	\$0.00	\$57.79
For apprentice rates see "Apprentice- LABORER"						
MARBLE & TILE FINISHERS <i>BRICKLAYERS LOCAL 3 - MARBLE & TILE</i>	02/01/2017	\$38.78	\$10.75	\$17.67	\$0.00	\$67.20

Apprentice - MARBLE & TILE FINISHER - Local 3 Marble & Tile

Effective Date - 02/01/2017

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	50	\$19.39	\$10.75	\$17.67	\$0.00	\$47.81
2	60	\$23.27	\$10.75	\$17.67	\$0.00	\$51.69
3	70	\$27.15	\$10.75	\$17.67	\$0.00	\$55.57
4	80	\$31.02	\$10.75	\$17.67	\$0.00	\$59.44
5	90	\$34.90	\$10.75	\$17.67	\$0.00	\$63.32

Notes:

Apprentice to Journeyworker Ratio:1:3

MARBLE MASONS, TILELAYERS & TERRAZZO MECH <i>BRICKLAYERS LOCAL 3 - MARBLE & TILE</i>	02/01/2017	\$50.80	\$10.75	\$19.22	\$0.00	\$80.77
---	------------	---------	---------	---------	--------	---------

Classification
Effective Date
Base Wage
Health
Pension
**Supplemental
Unemployment**
Total Rate
Apprentice - MARBLE-TILE-TERRAZZO MECHANIC - Local 3 Marble & Tile
Effective Date - 02/01/2017

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	50	\$25.40	\$10.75	\$19.22	\$0.00	\$55.37
2	60	\$30.48	\$10.75	\$19.22	\$0.00	\$60.45
3	70	\$35.56	\$10.75	\$19.22	\$0.00	\$65.53
4	80	\$40.64	\$10.75	\$19.22	\$0.00	\$70.61
5	90	\$45.72	\$10.75	\$19.22	\$0.00	\$75.69

Notes:
Apprentice to Journeyworker Ratio:1:5

MECH. SWEEPER OPERATOR (ON CONST. SITES)	06/01/2017	\$45.93	\$10.00	\$15.25	\$0.00	\$71.18
OPERATING ENGINEERS LOCAL 4	12/01/2017	\$46.92	\$10.00	\$15.25	\$0.00	\$72.17

For apprentice rates see "Apprentice- OPERATING ENGINEERS"

MECHANICS MAINTENANCE	06/01/2017	\$45.93	\$10.00	\$15.25	\$0.00	\$71.18
OPERATING ENGINEERS LOCAL 4	12/01/2017	\$46.92	\$10.00	\$15.25	\$0.00	\$72.17

For apprentice rates see "Apprentice- OPERATING ENGINEERS"

MILLWRIGHT (Zone 1)	04/01/2017	\$38.62	\$9.90	\$18.50	\$0.00	\$67.02
MILLWRIGHTS LOCAL 1121 - Zone 1	10/01/2017	\$39.52	\$9.90	\$18.50	\$0.00	\$67.92
	04/01/2018	\$40.42	\$9.90	\$18.50	\$0.00	\$68.82
	10/01/2018	\$41.32	\$9.90	\$18.50	\$0.00	\$69.72
	04/01/2019	\$42.22	\$9.90	\$18.50	\$0.00	\$70.62

Apprentice - MILLWRIGHT - Local 1121 Zone 1
Effective Date - 04/01/2017

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	55	\$21.24	\$9.90	\$5.31	\$0.00	\$36.45
2	65	\$25.10	\$9.90	\$15.13	\$0.00	\$50.13
3	75	\$28.97	\$9.90	\$16.10	\$0.00	\$54.97
4	85	\$32.83	\$9.90	\$17.06	\$0.00	\$59.79

Effective Date - 10/01/2017

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	55	\$21.74	\$9.90	\$5.31	\$0.00	\$36.95
2	65	\$25.69	\$9.90	\$15.13	\$0.00	\$50.72
3	75	\$29.64	\$9.90	\$16.10	\$0.00	\$55.64
4	85	\$33.59	\$9.90	\$17.06	\$0.00	\$60.55

Notes:

Steps are 2,000 hours

Apprentice to Journeyworker Ratio:1:5

Classification	Effective Date	Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
MORTAR MIXER <i>LABORERS - ZONE 2</i>	06/01/2017	\$32.65	\$7.60	\$13.50	\$0.00	\$53.75
	12/01/2017	\$33.28	\$7.60	\$13.50	\$0.00	\$54.38
	06/01/2018	\$34.12	\$7.60	\$13.50	\$0.00	\$55.22
	12/01/2018	\$34.96	\$7.60	\$13.50	\$0.00	\$56.06
	06/01/2019	\$35.83	\$7.60	\$13.50	\$0.00	\$56.93
	12/01/2019	\$36.69	\$7.60	\$13.50	\$0.00	\$57.79
For apprentice rates see "Apprentice- LABORER"						
OILER (OTHER THAN TRUCK CRANES,GRADALLS) <i>OPERATING ENGINEERS LOCAL 4</i>	06/01/2017	\$23.47	\$10.00	\$15.25	\$0.00	\$48.72
	12/01/2017	\$23.99	\$10.00	\$15.25	\$0.00	\$49.24
For apprentice rates see "Apprentice- OPERATING ENGINEERS"						
OILER (TRUCK CRANES, GRADALLS) <i>OPERATING ENGINEERS LOCAL 4</i>	06/01/2017	\$27.54	\$10.00	\$15.25	\$0.00	\$52.79
	12/01/2017	\$28.15	\$10.00	\$15.25	\$0.00	\$53.40
For apprentice rates see "Apprentice- OPERATING ENGINEERS"						
OTHER POWER DRIVEN EQUIPMENT - CLASS II <i>OPERATING ENGINEERS LOCAL 4</i>	06/01/2017	\$45.93	\$10.00	\$15.25	\$0.00	\$71.18
	12/01/2017	\$46.92	\$10.00	\$15.25	\$0.00	\$72.17
For apprentice rates see "Apprentice- OPERATING ENGINEERS"						
PAINTER (BRIDGES/TANKS) <i>PAINTERS LOCAL 35 - ZONE 2</i>	01/01/2017	\$51.41	\$7.85	\$16.10	\$0.00	\$75.36

Apprentice - PAINTER Local 35 - BRIDGES/TANKS

Effective Date - 01/01/2017

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	50	\$25.71	\$7.85	\$0.00	\$0.00	\$33.56
2	55	\$28.28	\$7.85	\$3.66	\$0.00	\$39.79
3	60	\$30.85	\$7.85	\$3.99	\$0.00	\$42.69
4	65	\$33.42	\$7.85	\$4.32	\$0.00	\$45.59
5	70	\$35.99	\$7.85	\$14.11	\$0.00	\$57.95
6	75	\$38.56	\$7.85	\$14.44	\$0.00	\$60.85
7	80	\$41.13	\$7.85	\$14.77	\$0.00	\$63.75
8	90	\$46.27	\$7.85	\$15.44	\$0.00	\$69.56

Notes:

Steps are 750 hrs.

Apprentice to Journeyworker Ratio:1:1

PAINTER (SPRAY OR SANDBLAST, NEW) *	01/01/2017	\$42.31	\$7.85	\$16.10	\$0.00	\$66.26
-------------------------------------	------------	---------	--------	---------	--------	---------

* If 30% or more of surfaces to be painted are new construction,
NEW paint rate shall be used.*PAINTERS LOCAL 35 - ZONE 2*

Classification

Effective Date Base Wage Health Pension Supplemental Unemployment Total Rate

Apprentice - PAINTER Local 35 Zone 2 - Spray/Sandblast - New
Effective Date - 01/01/2017

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	50	\$21.16	\$7.85	\$0.00	\$0.00	\$29.01
2	55	\$23.27	\$7.85	\$3.66	\$0.00	\$34.78
3	60	\$25.39	\$7.85	\$3.99	\$0.00	\$37.23
4	65	\$27.50	\$7.85	\$4.32	\$0.00	\$39.67
5	70	\$29.62	\$7.85	\$14.11	\$0.00	\$51.58
6	75	\$31.73	\$7.85	\$14.44	\$0.00	\$54.02
7	80	\$33.85	\$7.85	\$14.77	\$0.00	\$56.47
8	90	\$38.08	\$7.85	\$15.44	\$0.00	\$61.37

Notes:

Steps are 750 hrs.

Apprentice to Journeyworker Ratio:1:1

PAINTER (SPRAY OR SANDBLAST, REPAINT)	01/01/2017	\$40.37	\$7.85	\$16.10	\$0.00	\$64.32
---------------------------------------	------------	---------	--------	---------	--------	---------

PAINTERS LOCAL 35 - ZONE 2
Apprentice - PAINTER Local 35 Zone 2 - Spray/Sandblast - Repaint
Effective Date - 01/01/2017

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	50	\$20.19	\$7.85	\$0.00	\$0.00	\$28.04
2	55	\$22.20	\$7.85	\$3.66	\$0.00	\$33.71
3	60	\$24.22	\$7.85	\$3.99	\$0.00	\$36.06
4	65	\$26.24	\$7.85	\$4.32	\$0.00	\$38.41
5	70	\$28.26	\$7.85	\$14.11	\$0.00	\$50.22
6	75	\$30.28	\$7.85	\$14.44	\$0.00	\$52.57
7	80	\$32.30	\$7.85	\$14.77	\$0.00	\$54.92
8	90	\$36.33	\$7.85	\$15.44	\$0.00	\$59.62

Notes:

Steps are 750 hrs.

Apprentice to Journeyworker Ratio:1:1

PAINTER (TRAFFIC MARKINGS)	06/01/2017	\$32.40	\$7.60	\$13.50	\$0.00	\$53.50
	12/01/2017	\$33.03	\$7.60	\$13.50	\$0.00	\$54.13
	06/01/2018	\$33.87	\$7.60	\$13.50	\$0.00	\$54.97
	12/01/2018	\$34.71	\$7.60	\$13.50	\$0.00	\$55.81
	06/01/2019	\$35.58	\$7.60	\$13.50	\$0.00	\$56.68
	12/01/2019	\$36.44	\$7.60	\$13.50	\$0.00	\$57.54

For Apprentice rates see "Apprentice- LABORER"

PAINTER / TAPER (BRUSH, NEW) *	01/01/2017	\$40.91	\$7.85	\$16.10	\$0.00	\$64.86
--------------------------------	------------	---------	--------	---------	--------	---------

* If 30% or more of surfaces to be painted are new construction,
NEW paint rate shall be used. *PAINTERS LOCAL 35 - ZONE 2*

Classification	Effective Date	Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
----------------	----------------	-----------	--------	---------	------------------------------	------------

Apprentice - PAINTER - Local 35 Zone 2 - BRUSH NEW

Effective Date - 01/01/2017

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	50	\$20.46	\$7.85	\$0.00	\$0.00	\$28.31
2	55	\$22.50	\$7.85	\$3.66	\$0.00	\$34.01
3	60	\$24.55	\$7.85	\$3.99	\$0.00	\$36.39
4	65	\$26.59	\$7.85	\$4.32	\$0.00	\$38.76
5	70	\$28.64	\$7.85	\$14.11	\$0.00	\$50.60
6	75	\$30.68	\$7.85	\$14.44	\$0.00	\$52.97
7	80	\$32.73	\$7.85	\$14.77	\$0.00	\$55.35
8	90	\$36.82	\$7.85	\$15.44	\$0.00	\$60.11

Notes:

Steps are 750 hrs.

Apprentice to Journeyworker Ratio:1:1

PAINTER / TAPER (BRUSH, REPAINT)	01/01/2017	\$38.97	\$7.85	\$16.10	\$0.00	\$62.92
<i>PAINTERS LOCAL 35 - ZONE 2</i>						

Apprentice - PAINTER Local 35 Zone 2 - BRUSH REPAINT

Effective Date - 01/01/2017

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	50	\$19.49	\$7.85	\$0.00	\$0.00	\$27.34
2	55	\$21.43	\$7.85	\$3.66	\$0.00	\$32.94
3	60	\$23.38	\$7.85	\$3.99	\$0.00	\$35.22
4	65	\$25.33	\$7.85	\$4.32	\$0.00	\$37.50
5	70	\$27.28	\$7.85	\$14.11	\$0.00	\$49.24
6	75	\$29.23	\$7.85	\$14.44	\$0.00	\$51.52
7	80	\$31.18	\$7.85	\$14.77	\$0.00	\$53.80
8	90	\$35.07	\$7.85	\$15.44	\$0.00	\$58.36

Notes:

Steps are 750 hrs.

Apprentice to Journeyworker Ratio:1:1

PANEL & PICKUP TRUCKS DRIVER	12/01/2012	\$30.28	\$9.07	\$8.00	\$0.00	\$47.35
<i>TEAMSTERS JOINT COUNCIL NO. 10 ZONE B</i>						

PIER AND DOCK CONSTRUCTOR (UNDERPINNING AND DECK)	08/01/2015	\$42.04	\$9.80	\$19.23	\$0.00	\$71.07
<i>PILE DRIVER LOCAL 56 (ZONE 1)</i>						
For apprentice rates see "Apprentice- PILE DRIVER"						

PILE DRIVER	08/01/2015	\$42.04	\$9.80	\$19.23	\$0.00	\$71.07
<i>PILE DRIVER LOCAL 56 (ZONE 1)</i>						

Classification

Effective Date

Base Wage

Health

Pension

Supplemental
Unemployment

Total Rate

Apprentice - PILE DRIVER - Local 56 Zone 1**Effective Date - 08/01/2015**

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	50	\$21.02	\$9.80	\$19.23	\$0.00	\$50.05
2	60	\$25.22	\$9.80	\$19.23	\$0.00	\$54.25
3	70	\$29.43	\$9.80	\$19.23	\$0.00	\$58.46
4	75	\$31.53	\$9.80	\$19.23	\$0.00	\$60.56
5	80	\$33.63	\$9.80	\$19.23	\$0.00	\$62.66
6	80	\$33.63	\$9.80	\$19.23	\$0.00	\$62.66
7	90	\$37.84	\$9.80	\$19.23	\$0.00	\$66.87
8	90	\$37.84	\$9.80	\$19.23	\$0.00	\$66.87

Notes:**Apprentice to Journeyworker Ratio:1:3****PIPEFITTER & STEAMFITTER***PIPEFITTERS LOCAL 537 (Local 138)*

03/01/2017

\$48.86

\$9.70

\$16.14

\$0.00

\$74.70

Apprentice - PIPEFITTER Local 537 (Local 138)**Effective Date - 03/01/2017**

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	40	\$19.54	\$9.70	\$5.50	\$0.00	\$34.74
2	45	\$21.99	\$9.70	\$16.14	\$0.00	\$47.83
3	60	\$29.32	\$9.70	\$16.14	\$0.00	\$55.16
4	70	\$34.20	\$9.70	\$16.14	\$0.00	\$60.04
5	80	\$39.09	\$9.70	\$16.14	\$0.00	\$64.93

Notes:

** 1:3; 3:15; 1:10 thereafter / Steps are 1 yr.

Refrig/AC Mechanic **1:1;1:2;2:4;3:6;4:8;5:10;6:12;7:14;8:17;9:20;10:23(Max)

Apprentice to Journeyworker Ratio:****PIPELAYER***LABORERS - ZONE 2*

06/01/2017

\$32.65

\$7.60

\$13.50

\$0.00

\$53.75

12/01/2017

\$33.28

\$7.60

\$13.50

\$0.00

\$54.38

06/01/2018

\$34.12

\$7.60

\$13.50

\$0.00

\$55.22

12/01/2018

\$34.96

\$7.60

\$13.50

\$0.00

\$56.06

06/01/2019

\$35.83

\$7.60

\$13.50

\$0.00

\$56.93

12/01/2019

\$36.69

\$7.60

\$13.50

\$0.00

\$57.79

For apprentice rates see "Apprentice- LABORER"

PLUMBER*PLUMBERS & GASFITTERS LOCAL 12 (Local 138)*

03/01/2017

\$48.61

\$11.32

\$15.46

\$0.00

\$75.39

Classification	Effective Date	Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
----------------	----------------	-----------	--------	---------	------------------------------	------------

Apprentice - PLUMBER/GASFITTER - Local 12 (Local 138)

Effective Date - 03/01/2017

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	35	\$17.01	\$11.32	\$5.74	\$0.00	\$34.07
2	40	\$19.44	\$11.32	\$6.49	\$0.00	\$37.25
3	55	\$26.74	\$11.32	\$8.73	\$0.00	\$46.79
4	65	\$31.60	\$11.32	\$10.23	\$0.00	\$53.15
5	75	\$36.46	\$11.32	\$11.72	\$0.00	\$59.50

Notes:

Steps are 1 yr
Step 4 with lic\$55.65 Step5 with lic\$61.89

Apprentice to Journeyworker Ratio:1:5

PNEUMATIC CONTROLS (TEMP.) <i>PIPEFITTERS LOCAL 537 (Local 138)</i>	03/01/2017	\$48.86	\$9.70	\$16.14	\$0.00	\$74.70
--	------------	---------	--------	---------	--------	---------

For apprentice rates see "Apprentice- PIPEFITTER" or "PLUMBER/PIPEFITTER"

PNEUMATIC DRILL/TOOL OPERATOR <i>LABORERS - ZONE 2</i>	06/01/2017	\$32.65	\$7.60	\$13.50	\$0.00	\$53.75
	12/01/2017	\$33.28	\$7.60	\$13.50	\$0.00	\$54.38
	06/01/2018	\$34.12	\$7.60	\$13.50	\$0.00	\$55.22
	12/01/2018	\$34.96	\$7.60	\$13.50	\$0.00	\$56.06
	06/01/2019	\$35.83	\$7.60	\$13.50	\$0.00	\$56.93
	12/01/2019	\$36.69	\$7.60	\$13.50	\$0.00	\$57.79

For apprentice rates see "Apprentice- LABORER"

POWDERMAN & BLASTER <i>LABORERS - ZONE 2</i>	06/01/2017	\$33.40	\$7.60	\$13.50	\$0.00	\$54.50
	12/01/2017	\$34.03	\$7.60	\$13.50	\$0.00	\$55.13
	06/01/2018	\$34.87	\$7.60	\$13.50	\$0.00	\$55.97
	12/01/2018	\$35.71	\$7.60	\$13.50	\$0.00	\$56.81
	06/01/2019	\$36.58	\$7.60	\$13.50	\$0.00	\$57.68
	12/01/2019	\$37.44	\$7.60	\$13.50	\$0.00	\$58.54

For apprentice rates see "Apprentice- LABORER"

POWER SHOVEL/DERRICK/TRENCHING MACHINE <i>OPERATING ENGINEERS LOCAL 4</i>	06/01/2017	\$46.38	\$10.00	\$15.25	\$0.00	\$71.63
	12/01/2017	\$47.38	\$10.00	\$15.25	\$0.00	\$72.63

For apprentice rates see "Apprentice- OPERATING ENGINEERS"

PUMP OPERATOR (CONCRETE) <i>OPERATING ENGINEERS LOCAL 4</i>	06/01/2017	\$46.38	\$10.00	\$15.25	\$0.00	\$71.63
	12/01/2017	\$47.38	\$10.00	\$15.25	\$0.00	\$72.63

For apprentice rates see "Apprentice- OPERATING ENGINEERS"

PUMP OPERATOR (DEWATERING, OTHER) <i>OPERATING ENGINEERS LOCAL 4</i>	06/01/2017	\$31.86	\$10.00	\$15.25	\$0.00	\$57.11
	12/01/2017	\$32.55	\$10.00	\$15.25	\$0.00	\$57.80

For apprentice rates see "Apprentice- OPERATING ENGINEERS"

READY-MIX CONCRETE DRIVER <i>TEAMSTERS LOCAL 42</i>	05/01/2017	\$24.21	\$8.49	\$11.54	\$0.00	\$44.24
	04/30/2018	\$24.21	\$8.49	\$11.96	\$0.00	\$44.66
	05/01/2018	\$24.24	\$8.49	\$12.46	\$0.00	\$45.19
	04/30/2019	\$24.24	\$8.49	\$12.92	\$0.00	\$45.65

RECLAIMERS <i>OPERATING ENGINEERS LOCAL 4</i>	06/01/2017	\$45.93	\$10.00	\$15.25	\$0.00	\$71.18
	12/01/2017	\$46.92	\$10.00	\$15.25	\$0.00	\$72.17

For apprentice rates see "Apprentice- OPERATING ENGINEERS"

Classification	Effective Date	Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
RESIDENTIAL WOOD FRAME (All Other Work) <i>CARPENTERS -ZONE 2 (Residential Wood)</i>	06/01/2016	\$25.32	\$9.80	\$16.82	\$0.00	\$51.94
RESIDENTIAL WOOD FRAME CARPENTER **	04/01/2017	\$26.31	\$7.07	\$7.18	\$0.00	\$40.56
** The Residential Wood Frame Carpenter classification applies only to the construction of new, wood frame residences that do not exceed four stories including the basement. <i>CARPENTERS -ZONE 2 (Residential Wood)</i>	10/01/2017	\$26.93	\$7.07	\$7.18	\$0.00	\$41.18
	04/01/2018	\$27.35	\$7.07	\$7.18	\$0.00	\$41.60
	10/01/2018	\$27.77	\$7.07	\$7.18	\$0.00	\$42.02
	04/01/2019	\$28.20	\$7.07	\$7.18	\$0.00	\$42.45
	10/01/2019	\$28.63	\$7.07	\$7.18	\$0.00	\$42.88

As of 9/1/09 Carpentry work on wood-frame residential WEATHERIZATION projects shall be paid the RESIDENTIAL WOOD FRAME CARPENTER rate.

Apprentice - CARPENTER (Residential Wood Frame) - Zone 2

Effective Date - 04/01/2017

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	60	\$15.79	\$7.07	\$0.00	\$0.00	\$22.86
2	60	\$15.79	\$7.07	\$0.00	\$0.00	\$22.86
3	65	\$17.10	\$7.07	\$7.18	\$0.00	\$31.35
4	70	\$18.42	\$7.07	\$7.18	\$0.00	\$32.67
5	75	\$19.73	\$7.07	\$7.18	\$0.00	\$33.98
6	80	\$21.05	\$7.07	\$7.18	\$0.00	\$35.30
7	85	\$22.36	\$7.07	\$7.18	\$0.00	\$36.61
8	90	\$23.68	\$7.07	\$7.18	\$0.00	\$37.93

Effective Date - 10/01/2017

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	60	\$16.16	\$7.07	\$0.00	\$0.00	\$23.23
2	60	\$16.16	\$7.07	\$0.00	\$0.00	\$23.23
3	65	\$17.50	\$7.07	\$7.18	\$0.00	\$31.75
4	70	\$18.85	\$7.07	\$7.18	\$0.00	\$33.10
5	75	\$20.20	\$7.07	\$7.18	\$0.00	\$34.45
6	80	\$21.54	\$7.07	\$7.18	\$0.00	\$35.79
7	85	\$22.89	\$7.07	\$7.18	\$0.00	\$37.14
8	90	\$24.24	\$7.07	\$7.18	\$0.00	\$38.49

Notes:

Apprentice to Journeyworker Ratio:1:5

RIDE-ON MOTORIZED BUGGY OPERATOR <i>LABORERS - ZONE 2</i>	06/01/2017	\$32.65	\$7.60	\$13.50	\$0.00	\$53.75
	12/01/2017	\$33.28	\$7.60	\$13.50	\$0.00	\$54.38
	06/01/2018	\$34.12	\$7.60	\$13.50	\$0.00	\$55.22
	12/01/2018	\$34.96	\$7.60	\$13.50	\$0.00	\$56.06
	06/01/2019	\$35.83	\$7.60	\$13.50	\$0.00	\$56.93
	12/01/2019	\$36.69	\$7.60	\$13.50	\$0.00	\$57.79

For apprentice rates see "Apprentice- LABORER"

ROLLER/SPREADER/MULCHING MACHINE <i>OPERATING ENGINEERS LOCAL 4</i>	06/01/2017	\$45.93	\$10.00	\$15.25	\$0.00	\$71.18
	12/01/2017	\$46.92	\$10.00	\$15.25	\$0.00	\$72.17

Classification	Effective Date	Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
For apprentice rates see "Apprentice- OPERATING ENGINEERS"						
ROOFER (Inc.Roofers Waterproofing &Roofers Damproofg) ROOFERS LOCAL 33	08/01/2017	\$41.36	\$11.20	\$14.80	\$0.00	\$67.36
	02/01/2018	\$42.51	\$11.20	\$14.80	\$0.00	\$68.51
	08/01/2018	\$43.61	\$11.20	\$14.80	\$0.00	\$69.61
	02/01/2019	\$44.76	\$11.20	\$14.80	\$0.00	\$70.76

Apprentice - ROOFER - Local 33

Effective Date - 08/01/2017

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	50	\$20.68	\$11.20	\$3.44	\$0.00	\$35.32
2	60	\$24.82	\$11.20	\$14.80	\$0.00	\$50.82
3	65	\$26.88	\$11.20	\$14.80	\$0.00	\$52.88
4	75	\$31.02	\$11.20	\$14.80	\$0.00	\$57.02
5	85	\$35.16	\$11.20	\$14.80	\$0.00	\$61.16

Effective Date - 02/01/2018

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	50	\$21.26	\$11.20	\$3.44	\$0.00	\$35.90
2	60	\$25.51	\$11.20	\$14.80	\$0.00	\$51.51
3	65	\$27.63	\$11.20	\$14.80	\$0.00	\$53.63
4	75	\$31.88	\$11.20	\$14.80	\$0.00	\$57.88
5	85	\$36.13	\$11.20	\$14.80	\$0.00	\$62.13

Notes: ** 1:5, 2:6-10, the 1:10; Reroofing: 1:4, then 1:1
Step 1 is 2000 hrs.; Steps 2-5 are 1000 hrs.
(Hot Pitch Mechanics' receive \$1.00 hr. above ROOFER)

Apprentice to Journeyworker Ratio:**

ROOFER SLATE / TILE / PRECAST CONCRETE ROOFERS LOCAL 33	08/01/2017	\$41.61	\$11.20	\$14.80	\$0.00	\$67.61
	02/01/2018	\$42.76	\$11.20	\$14.80	\$0.00	\$68.76
	08/01/2018	\$43.86	\$11.20	\$14.80	\$0.00	\$69.86
	02/01/2019	\$45.01	\$11.20	\$14.80	\$0.00	\$71.01
For apprentice rates see "Apprentice- ROOFER"						
SHEETMETAL WORKER SHEETMETAL WORKERS LOCAL 17 - A	08/01/2017	\$43.83	\$11.45	\$24.03	\$2.38	\$81.69
	02/01/2018	\$44.98	\$11.45	\$24.03	\$2.38	\$82.84

Classification

Effective Date Base Wage Health Pension Supplemental
Unemployment Total Rate

Apprentice - SHEET METAL WORKER - Local 17-A
Effective Date - 08/01/2017

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	40	\$17.53	\$11.45	\$5.61	\$0.00	\$34.59
2	40	\$17.53	\$11.45	\$5.61	\$0.00	\$34.59
3	45	\$19.72	\$11.45	\$10.76	\$1.26	\$43.19
4	45	\$19.72	\$11.45	\$10.76	\$1.26	\$43.19
5	50	\$21.92	\$11.45	\$11.71	\$1.35	\$46.43
6	50	\$21.92	\$11.45	\$11.96	\$1.36	\$46.69
7	60	\$26.30	\$11.45	\$13.61	\$1.54	\$52.90
8	65	\$28.49	\$11.45	\$14.56	\$1.64	\$56.14
9	75	\$32.87	\$11.45	\$16.47	\$1.82	\$62.61
10	85	\$37.26	\$11.45	\$17.87	\$2.00	\$68.58

Effective Date - 02/01/2018

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	40	\$17.99	\$11.45	\$5.24	\$0.00	\$34.68
2	40	\$17.99	\$11.45	\$5.24	\$0.00	\$34.68
3	45	\$20.24	\$11.45	\$10.31	\$1.27	\$43.27
4	45	\$20.24	\$11.45	\$10.31	\$1.27	\$43.27
5	50	\$22.49	\$11.45	\$11.21	\$1.37	\$46.52
6	50	\$22.49	\$11.45	\$11.46	\$1.38	\$46.78
7	60	\$26.99	\$11.45	\$13.02	\$1.56	\$53.02
8	65	\$29.24	\$11.45	\$13.93	\$1.67	\$56.29
9	75	\$33.74	\$11.45	\$15.74	\$1.85	\$62.78
10	85	\$38.23	\$11.45	\$17.05	\$2.03	\$68.76

Notes:

Steps are 6 mos.

Apprentice to Journeyworker Ratio:1:4

SIGN ERECTOR	06/01/2013	\$25.81	\$7.07	\$7.05	\$0.00	\$39.93
PAINTERS LOCAL 35 - ZONE 2						

Classification
Effective Date
Base Wage
Health
Pension
**Supplemental
Unemployment**
Total Rate
Apprentice - SIGN ERECTOR - Local 35 Zone 2
Effective Date - 06/01/2013

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	50	\$12.91	\$7.07	\$0.00	\$0.00	\$19.98
2	55	\$14.20	\$7.07	\$2.45	\$0.00	\$23.72
3	60	\$15.49	\$7.07	\$2.45	\$0.00	\$25.01
4	65	\$16.78	\$7.07	\$2.45	\$0.00	\$26.30
5	70	\$18.07	\$7.07	\$7.05	\$0.00	\$32.19
6	75	\$19.36	\$7.07	\$7.05	\$0.00	\$33.48
7	80	\$20.65	\$7.07	\$7.05	\$0.00	\$34.77
8	85	\$21.94	\$7.07	\$7.05	\$0.00	\$36.06
9	90	\$23.23	\$7.07	\$7.05	\$0.00	\$37.35

Notes:

Steps are 4 mos.

Apprentice to Journeyworker Ratio:1:1

SPECIALIZED EARTH MOVING EQUIP < 35 TONS TEAMSTERS JOINT COUNCIL NO. 10 ZONE B	12/01/2016	\$32.44	\$10.91	\$10.89	\$0.00	\$54.24
---	------------	---------	---------	---------	--------	---------

SPECIALIZED EARTH MOVING EQUIP > 35 TONS TEAMSTERS JOINT COUNCIL NO. 10 ZONE B	12/01/2016	\$32.73	\$10.91	\$10.89	\$0.00	\$54.53
---	------------	---------	---------	---------	--------	---------

SPRINKLER FITTER SPRINKLER FITTERS LOCAL 550 - (Section B) Zone 2	03/01/2017	\$50.47	\$8.77	\$17.20	\$0.00	\$76.44
--	------------	---------	--------	---------	--------	---------

Apprentice - SPRINKLER FITTER - Local 550 (Section B) Zone 2
Effective Date - 03/01/2017

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	35	\$17.66	\$8.77	\$8.70	\$0.00	\$35.13
2	40	\$20.19	\$8.77	\$8.70	\$0.00	\$37.66
3	45	\$22.71	\$8.77	\$8.70	\$0.00	\$40.18
4	50	\$25.24	\$8.77	\$8.70	\$0.00	\$42.71
5	55	\$27.76	\$8.77	\$8.70	\$0.00	\$45.23
6	60	\$30.28	\$8.77	\$10.20	\$0.00	\$49.25
7	65	\$32.81	\$8.77	\$10.20	\$0.00	\$51.78
8	70	\$35.33	\$8.77	\$10.20	\$0.00	\$54.30
9	75	\$37.85	\$8.77	\$10.20	\$0.00	\$56.82
10	80	\$40.38	\$8.77	\$10.20	\$0.00	\$59.35

Notes: Apprentice entered prior 9/30/10:

40/45/50/55/60/65/70/75/80/85

Steps are 850 hours

Apprentice to Journeyworker Ratio:1:3

STEAM BOILER OPERATOR OPERATING ENGINEERS LOCAL 4	06/01/2017	\$45.93	\$10.00	\$15.25	\$0.00	\$71.18
--	------------	---------	---------	---------	--------	---------

	12/01/2017	\$46.92	\$10.00	\$15.25	\$0.00	\$72.17
--	------------	---------	---------	---------	--------	---------

For apprentice rates see "Apprentice- OPERATING ENGINEERS"

Classification	Effective Date	Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
TAMPERS, SELF-PROPELLED OR TRACTOR DRAWN <i>OPERATING ENGINEERS LOCAL 4</i>	06/01/2017	\$45.93	\$10.00	\$15.25	\$0.00	\$71.18
	12/01/2017	\$46.92	\$10.00	\$15.25	\$0.00	\$72.17
For apprentice rates see "Apprentice- OPERATING ENGINEERS"						
TELECOMMUNICATION TECHNICIAN <i>ELECTRICIANS LOCAL 103</i>	03/01/2017	\$36.25	\$13.00	\$15.60	\$0.00	\$64.85
	09/01/2017	\$36.96	\$13.00	\$15.62	\$0.00	\$65.58
	03/01/2018	\$37.61	\$13.00	\$15.93	\$0.00	\$66.54
	09/01/2018	\$38.51	\$13.00	\$15.96	\$0.00	\$67.47
	03/01/2019	\$39.40	\$13.00	\$15.98	\$0.00	\$68.38

Apprentice - TELECOMMUNICATION TECHNICIAN - Local 103

Effective Date - 03/01/2017

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	40	\$14.50	\$13.00	\$0.44	\$0.00	\$27.94
2	40	\$14.50	\$13.00	\$0.44	\$0.00	\$27.94
3	45	\$16.31	\$13.00	\$12.54	\$0.00	\$41.85
4	45	\$16.31	\$13.00	\$12.54	\$0.00	\$41.85
5	50	\$18.13	\$13.00	\$12.81	\$0.00	\$43.94
6	55	\$19.94	\$13.00	\$13.09	\$0.00	\$46.03
7	60	\$21.75	\$13.00	\$13.37	\$0.00	\$48.12
8	65	\$23.56	\$13.00	\$13.65	\$0.00	\$50.21
9	70	\$25.38	\$13.00	\$13.93	\$0.00	\$52.31
10	75	\$27.19	\$13.00	\$14.21	\$0.00	\$54.40

Effective Date - 09/01/2017

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	40	\$14.78	\$13.00	\$0.44	\$0.00	\$28.22
2	40	\$14.78	\$13.00	\$0.44	\$0.00	\$28.22
3	45	\$16.63	\$13.00	\$12.55	\$0.00	\$42.18
4	45	\$16.63	\$13.00	\$12.55	\$0.00	\$42.18
5	50	\$18.48	\$13.00	\$12.82	\$0.00	\$44.30
6	55	\$20.33	\$13.00	\$13.10	\$0.00	\$46.43
7	60	\$22.18	\$13.00	\$13.39	\$0.00	\$48.57
8	65	\$24.02	\$13.00	\$13.66	\$0.00	\$50.68
9	70	\$25.87	\$13.00	\$13.95	\$0.00	\$52.82
10	75	\$27.72	\$13.00	\$14.22	\$0.00	\$54.94

Notes:

Apprentice to Journeyworker Ratio:1:1

TERRAZZO FINISHERS <i>BRICKLAYERS LOCAL 3 - MARBLE & TILE</i>	02/01/2017	\$49.70	\$10.75	\$19.22	\$0.00	\$79.67
--	------------	---------	---------	---------	--------	---------

Classification	Effective Date	Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
----------------	----------------	-----------	--------	---------	---------------------------	------------

Apprentice - TERRAZZO FINISHER - Local 3 Marble & Tile

Effective Date - 02/01/2017

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	50	\$24.85	\$10.75	\$19.22	\$0.00	\$54.82
2	60	\$29.82	\$10.75	\$19.22	\$0.00	\$59.79
3	70	\$34.79	\$10.75	\$19.22	\$0.00	\$64.76
4	80	\$39.76	\$10.75	\$19.22	\$0.00	\$69.73
5	90	\$44.73	\$10.75	\$19.22	\$0.00	\$74.70

Notes:

Apprentice to Journeyworker Ratio:1:3

TEST BORING DRILLER <i>LABORERS - FOUNDATION AND MARINE</i>	12/01/2016	\$37.70	\$7.60	\$14.35	\$0.00	\$59.65
For apprentice rates see "Apprentice- LABORER"						
TEST BORING DRILLER HELPER <i>LABORERS - FOUNDATION AND MARINE</i>	12/01/2016	\$36.42	\$7.60	\$14.35	\$0.00	\$58.37
For apprentice rates see "Apprentice- LABORER"						
TEST BORING LABORER <i>LABORERS - FOUNDATION AND MARINE</i>	12/01/2016	\$36.30	\$7.60	\$14.35	\$0.00	\$58.25
For apprentice rates see "Apprentice- LABORER"						
TRACTORS/PORTABLE STEAM GENERATORS <i>OPERATING ENGINEERS LOCAL 4</i>	06/01/2017	\$45.93	\$10.00	\$15.25	\$0.00	\$71.18
	12/01/2017	\$46.92	\$10.00	\$15.25	\$0.00	\$72.17
For apprentice rates see "Apprentice- OPERATING ENGINEERS"						
TRAILERS FOR EARTH MOVING EQUIPMENT <i>TEAMSTERS JOINT COUNCIL NO. 10 ZONE B</i>	12/01/2016	\$33.02	\$10.91	\$10.89	\$0.00	\$54.82
TUNNEL WORK - COMPRESSED AIR <i>LABORERS (COMPRESSED AIR)</i>	12/01/2016	\$48.58	\$7.60	\$14.75	\$0.00	\$70.93
For apprentice rates see "Apprentice- LABORER"						
TUNNEL WORK - COMPRESSED AIR (HAZ. WASTE) <i>LABORERS (COMPRESSED AIR)</i>	12/01/2016	\$50.58	\$7.60	\$14.75	\$0.00	\$72.93
For apprentice rates see "Apprentice- LABORER"						
TUNNEL WORK - FREE AIR <i>LABORERS (FREE AIR TUNNEL)</i>	12/01/2016	\$40.65	\$7.60	\$14.75	\$0.00	\$63.00
For apprentice rates see "Apprentice- LABORER"						
TUNNEL WORK - FREE AIR (HAZ. WASTE) <i>LABORERS (FREE AIR TUNNEL)</i>	12/01/2016	\$42.65	\$7.60	\$14.75	\$0.00	\$65.00
For apprentice rates see "Apprentice- LABORER"						
VAC-HAUL <i>TEAMSTERS JOINT COUNCIL NO. 10 ZONE B</i>	12/01/2016	\$32.44	\$10.91	\$10.89	\$0.00	\$54.24
WAGON DRILL OPERATOR <i>LABORERS - ZONE 2</i>	06/01/2017	\$32.65	\$7.60	\$13.50	\$0.00	\$53.75
	12/01/2017	\$33.28	\$7.60	\$13.50	\$0.00	\$54.38
	06/01/2018	\$34.12	\$7.60	\$13.50	\$0.00	\$55.22
	12/01/2018	\$34.96	\$7.60	\$13.50	\$0.00	\$56.06
	06/01/2019	\$35.83	\$7.60	\$13.50	\$0.00	\$56.93
	12/01/2019	\$36.69	\$7.60	\$13.50	\$0.00	\$57.79
For apprentice rates see "Apprentice- LABORER"						

Classification	Effective Date	Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
WASTE WATER PUMP OPERATOR <i>OPERATING ENGINEERS LOCAL 4</i>	06/01/2017	\$46.38	\$10.00	\$15.25	\$0.00	\$71.63
	12/01/2017	\$47.38	\$10.00	\$15.25	\$0.00	\$72.63
For apprentice rates see "Apprentice- OPERATING ENGINEERS"						
WATER METER INSTALLER <i>PLUMBERS & GASFITTERS LOCAL 12 (Local 138)</i>	03/01/2017	\$48.61	\$11.32	\$15.46	\$0.00	\$75.39
For apprentice rates see "Apprentice- PLUMBER/PIPEFITTER" or "PLUMBER/GASFITTER"						
Outside Electrical - East						
CABLE TECHNICIAN (Power Zone) <i>OUTSIDE ELECTRICAL WORKERS - EAST LOCAL 104</i>	08/28/2016	\$26.61	\$7.50	\$1.80	\$0.00	\$35.91
	09/03/2017	\$27.14	\$7.75	\$1.81	\$0.00	\$36.70
For apprentice rates see "Apprentice- LINEMAN"						
CABLEMAN (Underground Ducts & Cables) <i>OUTSIDE ELECTRICAL WORKERS - EAST LOCAL 104</i>	08/28/2016	\$37.70	\$7.50	\$8.87	\$0.00	\$54.07
	09/03/2017	\$38.45	\$7.75	\$9.53	\$0.00	\$55.73
For apprentice rates see "Apprentice- LINEMAN"						
DRIVER / GROUNDMAN CDL <i>OUTSIDE ELECTRICAL WORKERS - EAST LOCAL 104</i>	08/28/2016	\$31.05	\$7.50	\$8.89	\$0.00	\$47.44
	09/03/2017	\$31.66	\$7.75	\$9.44	\$0.00	\$48.85
For apprentice rates see "Apprentice- LINEMAN"						
DRIVER / GROUNDMAN -Inexperienced (<2000 Hrs) <i>OUTSIDE ELECTRICAL WORKERS - EAST LOCAL 104</i>	08/28/2016	\$24.39	\$7.50	\$1.73	\$0.00	\$33.62
	09/03/2017	\$24.88	\$7.75	\$1.75	\$0.00	\$34.38
For apprentice rates see "Apprentice- LINEMAN"						
EQUIPMENT OPERATOR (Class A CDL) <i>OUTSIDE ELECTRICAL WORKERS - EAST LOCAL 104</i>	08/28/2016	\$37.70	\$7.50	\$12.95	\$0.00	\$58.15
	09/03/2017	\$38.45	\$7.75	\$13.61	\$0.00	\$59.81
For apprentice rates see "Apprentice- LINEMAN"						
EQUIPMENT OPERATOR (Class B CDL) <i>OUTSIDE ELECTRICAL WORKERS - EAST LOCAL 104</i>	08/28/2016	\$33.26	\$7.50	\$9.63	\$0.00	\$50.39
	09/03/2017	\$33.92	\$7.75	\$10.21	\$0.00	\$51.88
For apprentice rates see "Apprentice- LINEMAN"						
GROUNDMAN <i>OUTSIDE ELECTRICAL WORKERS - EAST LOCAL 104</i>	08/28/2016	\$24.39	\$7.50	\$1.73	\$0.00	\$33.62
	09/03/2017	\$24.88	\$7.75	\$1.75	\$0.00	\$34.38
For apprentice rates see "Apprentice- LINEMAN"						
GROUNDMAN -Inexperienced (<2000 Hrs.) <i>OUTSIDE ELECTRICAL WORKERS - EAST LOCAL 104</i>	08/28/2016	\$19.96	\$7.50	\$1.60	\$0.00	\$29.06
	09/03/2017	\$20.35	\$7.75	\$1.61	\$0.00	\$29.71
For apprentice rates see "Apprentice- LINEMAN"						
JOURNEYMAN LINEMAN <i>OUTSIDE ELECTRICAL WORKERS - EAST LOCAL 104</i>	08/28/2016	\$44.35	\$7.50	\$15.83	\$0.00	\$67.68
	09/03/2017	\$45.23	\$7.75	\$16.61	\$0.00	\$69.59

Classification	Effective Date	Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
----------------	----------------	-----------	--------	---------	---------------------------	------------

Apprentice - LINEMAN (Outside Electrical) - East Local 104

Effective Date - 08/28/2016

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	60	\$26.61	\$7.50	\$3.30	\$0.00	\$37.41
2	65	\$28.83	\$7.50	\$3.36	\$0.00	\$39.69
3	70	\$31.05	\$7.50	\$3.43	\$0.00	\$41.98
4	75	\$33.26	\$7.50	\$5.00	\$0.00	\$45.76
5	80	\$35.48	\$7.50	\$5.06	\$0.00	\$48.04
6	85	\$37.70	\$7.50	\$5.13	\$0.00	\$50.33
7	90	\$39.92	\$7.50	\$7.20	\$0.00	\$54.62

Effective Date - 09/03/2017

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	60	\$27.14	\$7.75	\$3.31	\$0.00	\$38.20
2	65	\$29.40	\$7.75	\$3.38	\$0.00	\$40.53
3	70	\$31.66	\$7.75	\$3.45	\$0.00	\$42.86
4	75	\$33.92	\$7.75	\$5.02	\$0.00	\$46.69
5	80	\$36.18	\$7.75	\$5.09	\$0.00	\$49.02
6	85	\$38.45	\$7.75	\$5.15	\$0.00	\$51.35
7	90	\$40.71	\$7.75	\$7.22	\$0.00	\$55.68

Notes:

Apprentice to Journeyworker Ratio:1:2

TELEDATA CABLE SPLICER OUTSIDE ELECTRICAL WORKERS - EAST LOCAL 104	01/01/2016	\$28.98	\$4.25	\$3.12	\$0.00	\$36.35
---	------------	---------	--------	--------	--------	---------

TELEDATA LINEMAN/EQUIPMENT OPERATOR OUTSIDE ELECTRICAL WORKERS - EAST LOCAL 104	01/01/2016	\$27.31	\$4.25	\$3.07	\$0.00	\$34.63
--	------------	---------	--------	--------	--------	---------

TELEDATA WIREMAN/INSTALLER/TECHNICIAN OUTSIDE ELECTRICAL WORKERS - EAST LOCAL 104	01/01/2016	\$27.31	\$4.25	\$3.07	\$0.00	\$34.63
--	------------	---------	--------	--------	--------	---------

TREE TRIMMER OUTSIDE ELECTRICAL WORKERS - EAST LOCAL 104	01/31/2016	\$18.51	\$3.55	\$0.00	\$0.00	\$22.06
---	------------	---------	--------	--------	--------	---------

This classification applies only to tree work done: (a) for a utility company, R.E.A. cooperative, or railroad or coal mining company, and (b) for the purpose of operating, maintaining, or repairing the utility company's equipment, and (c) by a person who is using hand or mechanical cutting methods and is not on the ground. This classification does not apply to wholesale tree removal.

TREE TRIMMER GROUNDMAN OUTSIDE ELECTRICAL WORKERS - EAST LOCAL 104	01/31/2016	\$16.32	\$3.55	\$0.00	\$0.00	\$19.87
---	------------	---------	--------	--------	--------	---------

This classification applies only to tree work done: (a) for a utility company, R.E.A. cooperative, or railroad or coal mining company, and (b) for the purpose of operating, maintaining, or repairing the utility company's equipment, and (c) by a person who is using hand or mechanical cutting methods and is on the ground. This classification does not apply to wholesale tree removal.

Classification	Effective Date	Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
----------------	----------------	-----------	--------	---------	------------------------------	------------

Additional Apprentice Information:

Minimum wage rates for apprentices employed on public works projects are listed above as a percentage of the pre-determined hourly wage rate established by the Commissioner under the provisions of the M.G.L. c. 149, ss. 26-27D. Apprentice ratios are established by the Division of Apprenticeship Training pursuant to M.G.L. c. 23, ss. 11E-11L.

All apprentices must be registered with the Division of Apprenticeship Training in accordance with M.G.L. c. 23, ss. 11E-11L.

All steps are six months (1000 hours.)
 Ratios are expressed in allowable number of apprentices to journeymen or fraction thereof, unless otherwise specified.

- ** Multiple ratios are listed in the comment field.
- *** APP to JM; 1:1, 2:2, 2:3, 3:4, 4:4, 4:5, 4:6, 5:7, 6:7, 6:8, 6:9, 7:10, 8:10, 8:11, 8:12, 9:13, 10:13, 10:14, etc.
- **** APP to JM; 1:1, 1:2, 2:3, 2:4, 3:5, 4:6, 4:7, 5:8, 6:9, 6:10, 7:11, 8:12, 8:13, 9:14, 10:15, 10:16, etc.

ATTACHMENT II

MASSACHUSETTS GENERAL LAWS

The following statutes regulating construction contracts for public work projects are hereby inserted in this contract in accordance with Massachusetts General Law:

M.G.L. c.30 s 39F – Payment to Subcontractor
M.G.L. c.30 s 39I – Deviation from Plans and Specifications
M.G.L. c.30 s 39J – No Arbitrary Decisions are Final
M.G.L. c.30 s 39L – Construction Work by Foreign Corporations
M.G.L. c.30 s 39M(b) – Substitution of Equal Products
M.G.L. c.30 s 39N – Differing Site Conditions
M.G.L. c.30 s 39O – Equitable Adjustments for Delay
M.G.L. c.30 s 39P – Decisions on Interpretation of Specifications
M.G.L. c.30 s 39R – Contractor’s Records
M.G.L. c.149 s 34 – Limitations on Hours of Work
M.G.L. c.149 s 44J – Advertising Invitation to Bid
M.G.L. c.82 s 40 – Excavations; Notice; Penalties

MASSACHUSETTS GENERAL LAWS

M.G.L. c.30 s 39F

Section 39F. (1) Every contract awarded pursuant to sections forty-four A to L, inclusive, of chapter one hundred and forty-nine shall contain the following subparagraphs (a) through (i) and every contract awarded pursuant to section thirty-nine M of chapter thirty shall contain the following subparagraphs (a) through (h) and in each case those subparagraphs shall be binding between the general contractor and each subcontractor.

(a) Forthwith after the general contractor receives payment on account of a periodic estimate, the general contractor shall pay to each subcontractor the amount paid for the labor performed and the materials furnished by that subcontractor, less any amount specified in any court proceedings barring such payment and also less any amount claimed due from the subcontractor by the general contractor.

(b) Not later than the sixty-fifth day after each subcontractor substantially completes his work in accordance with the plans and specifications, the entire balance due under the subcontract less amounts retained by the awarding authority as the estimated cost of completing the incomplete and unsatisfactory items of work, shall be due the subcontractor; and the awarding authority shall pay that amount to the general contractor. The general contractor shall forthwith pay to the subcontractor the full amount received from the awarding authority less any amount specified in any court proceedings barring such payment and also less any amount claimed due from the subcontractor by the general contractor.

(c) Each payment made by the awarding authority to the general contractor pursuant to subparagraphs (a) and (b) of this paragraph for the labor performed and the materials furnished by a subcontractor shall be made to the general contractor for the account of that subcontractor; and the awarding authority shall take reasonable steps to compel the general contractor to make each such payment to each such subcontractor. If the awarding authority has received a demand for direct payment from a subcontractor for any amount which has already been included in a payment to the general contractor or which is to be included in a payment to the general contractor for payment to the subcontractor as provided in subparagraphs (a) and (b), the awarding authority shall act upon the demand as provided in this section.

(d) If, within seventy days after the subcontractor has substantially completed the subcontract work, the subcontractor has not received from the general contractor the balance due under the subcontract including any amount due for extra labor and materials furnished to the general contractor, less any amount retained by the awarding authority as the estimated cost of completing the incomplete and unsatisfactory items of work, the subcontractor may demand direct payment of that balance from the awarding authority. The demand shall be by a sworn statement delivered to or sent by certified mail to the awarding authority, and a copy shall be delivered to or sent by certified mail to the general contractor at the same time. The demand shall contain a detailed breakdown of the balance due under the subcontract and also a statement of the status of completion of the subcontract work. Any demand made after substantial completion of the subcontract work shall be valid even if delivered or mailed prior to the seventieth day after the subcontractor has substantially completed the subcontract work. Within ten days after the subcontractor has delivered or so mailed the demand to the awarding authority and delivered or so mailed a copy to the general contractor, the general contractor may reply to the demand. The reply shall be by a sworn statement delivered to or sent by certified mail to the awarding authority and a copy shall be delivered to or sent by certified mail to the subcontractor at the same time. The reply shall contain a detailed breakdown of the balance due under the subcontract including any amount due for extra labor

and materials furnished to the general contractor and of the amount due for each claim made by the general contractor against the subcontractor.

(e) Within fifteen days after receipt of the demand by the awarding authority, but in no event prior to the seventieth day after substantial completion of the subcontract work, the awarding authority shall make direct payment to the subcontractor of the balance due under the subcontract including any amount due for extra labor and materials furnished to the general contractor, less any amount (i) retained by the awarding authority as the estimated cost of completing the incomplete or unsatisfactory items of work, (ii) specified in any court proceedings barring such payment, or (iii) disputed by the general contractor in the sworn reply; provided, that the awarding authority shall not deduct from a direct payment any amount as provided in part (iii) if the reply is not sworn to, or for which the sworn reply does not contain the detailed breakdown required by subparagraph (d). The awarding authority shall make further direct payments to the subcontractor forthwith after the removal of the basis for deductions from direct payments made as provided in parts (i) and (ii) of this subparagraph.

(f) The awarding authority shall forthwith deposit the amount deducted from a direct payment as provided in part (iii) of subparagraph (e) in an interest-bearing joint account in the names of the general contractor and the subcontractor in a bank in Massachusetts selected by the awarding authority or agreed upon by the general contractor and the subcontractor and shall notify the general contractor and the subcontractor of the date of the deposit and the bank receiving the deposit. The bank shall pay the amount in the account, including accrued interest, as provided in an agreement between the general contractor and the subcontractor or as determined by decree of a court of competent jurisdiction.

(g) All direct payments and all deductions from demands for direct payments deposited in an interest-bearing account or accounts in a bank pursuant to subparagraph (f) shall be made out of amounts payable to the general contractor at the time of receipt of a demand for direct payment from a subcontractor and out of amounts which later become payable to the general contractor and in the order of receipt of such demands from subcontractors. All direct payments shall discharge the obligation of the awarding authority to the general contractor to the extent of such payment.

(h) The awarding authority shall deduct from payments to a general contractor amounts which, together with the deposits in interest-bearing accounts pursuant to subparagraph (f), are sufficient to satisfy all unpaid balances of demands for direct payment received from subcontractors. All such amounts shall be earmarked for such direct payments, and the subcontractors shall have a right in such deductions prior to any claims against such amounts by creditors of the general contractor.

(i) If the subcontractor does not receive payment as provided in subparagraph (a) or if the general contractor does not submit a periodic estimate for the value of the labor or materials performed or furnished by the subcontractor and the subcontractor does not receive payment for same when due less the deductions provided for in subparagraph (a), the subcontractor may demand direct payment by following the procedure in subparagraph (d) and the general contractor may file a sworn reply as provided in that same subparagraph. A demand made after the first day of the month following that for which the subcontractor performed or furnished the labor and materials for which the subcontractor seeks payment shall be valid even if delivered or mailed prior to the time payment was due on a periodic estimate from the general contractor. Thereafter the awarding authority shall proceed as provided in subparagraph (e), (f), (g) and (h).

(2) Any assignment by a subcontractor of the rights under this section to a surety company furnishing a bond under the provisions of section twenty-nine of chapter one hundred forty-

nine shall be invalid. The assignment and subrogation rights of the surety to amounts included in a demand for direct payment which are in the possession of the awarding authority or which are on deposit pursuant to subparagraph (f) of paragraph (1) shall be subordinate to the rights of all subcontractors who are entitled to be paid under this section and who have not been paid in full.

(3) "Subcontractor" as used in this section (i) for contracts awarded as provided in sections forty-four A to forty-four H, inclusive, of chapter one hundred forty-nine shall mean a person who files a sub-bid and receives a subcontract as a result of that filed sub-bid or who is approved by the awarding authority in writing as a person performing labor or both performing labor and furnishing materials pursuant to a contract with the general contractor, (ii) for contracts awarded as provided in paragraph (a) of section thirty-nine M of chapter thirty shall mean a person approved by the awarding authority in writing as a person performing labor or both performing labor and furnishing materials pursuant to a contract with the general contractor, and (iii) for contracts with the commonwealth not awarded as provided in forty-four A to forty-four H, inclusive, of chapter one hundred forty-nine shall also mean a person contracting with the general contractor to supply materials used or employed in a public works project for a price in excess of five thousand dollars.

(4) A general contractor or a subcontractor shall enforce a claim to any portion of the amount of a demand for direct payment deposited as provided in subparagraph (f) of paragraph 1 by a petition in equity in the superior court against the other and the bank shall not be a necessary party. A subcontractor shall enforce a claim for direct payment or a right to require a deposit as provided in subparagraph (f) of paragraph 1 by a petition in equity in the superior court against the awarding authority and the general contractor shall not be a necessary party. Upon motion of any party the court shall advance for speedy trial any petition filed as provided in this paragraph. Sections fifty-nine and fifty-nine B of chapter two hundred thirty-one shall apply to such petitions. The court shall enter an interlocutory decree upon which execution shall issue for any part of a claim found due pursuant to sections fifty-nine and fifty-nine B and, upon motion of any party, shall advance for speedy trial the petition to collect the remainder of the claim. Any party aggrieved by such interlocutory decree shall have the right to appeal therefrom as from a final decree. The court shall not consolidate for trial the petition of any subcontractor with the petition of one or more subcontractors or the same general contract unless the court finds that a substantial portion of the evidence of the same events during the course of construction (other than the fact that the claims sought to be consolidated arise under the same general contract) is applicable to the petitions sought to be consolidated and that such consolidation will prevent unnecessary duplication of evidence. A decree in any such proceeding shall not include interest on the disputed amount deposited in excess of the interest earned for the period of any such deposit. No person except a subcontractor filing a demand for direct payment for which no funds due the general contractor are available for direct payment shall have a right to file a petition in court of equity against the awarding authority claiming a demand for direct payment is premature and such subcontractor must file the petition before the awarding authority has made a direct payment to the subcontractor and has made a deposit of the disputed portion as provided in part (iii) of subparagraph (e) and in subparagraph (f) of paragraph (1).

(5) In any petition to collect any claim for which a subcontractor has filed a demand for direct payment the court shall, upon motion of the general contractor, reduce by the amount of any deposit of a disputed amount by the awarding authority as provided in part (iii) of subparagraph (e) and in subparagraph (f) of paragraph (1) any amount held under a trustee writ or pursuant to a restraining order or injunction.

M.G.L. c.30 s 39I

Section 39I. Every contractor having a contract for the construction, alteration, maintenance, repair or demolition of, or addition to, any public building or public works for the commonwealth, or of any political subdivision thereof, shall perform all the work required by such contract in conformity with the plans and specifications contained therein. No wilful and substantial deviation from said plans and specifications shall be made unless authorized in writing by the awarding authority or by the engineer or architect in charge of the work who is duly authorized by the awarding authority to approve such deviations. In order to avoid delays in the prosecution of the work required by such contract such deviation from the plans or specifications may be authorized by a written order of the awarding authority or such engineer or architect so authorized to approve such deviation. Within thirty days thereafter, such written order shall be confirmed by a certificate of the awarding authority stating: (1) If such deviation involves any substitution or elimination of materials, fixtures or equipment, the reasons why such materials, fixtures or equipment were included in the first instance and the reasons for substitution or elimination, and, if the deviation is of any other nature, the reasons for such deviation, giving justification therefor; (2) that the specified deviation does not materially injure the project as a whole; (3) that either the work substituted for the work specified is of the same cost and quality, or that an equitable adjustment has been agreed upon between the contracting agency and the contractor and the amount in dollars of said adjustment; and (4) that the deviation is in the best interest of the contracting authority.

Such certificate shall be signed under the penalties of perjury and shall be a permanent part of the file record of the work contracted for.

Whoever violates any provision of this section wilfully and with intent to defraud shall be punished by a fine of not more than five thousand dollars or by imprisonment for not more than six months, or both.

M.G.L. c.30 s 39J

Section 39J. Notwithstanding any contrary provision of any contract for the construction, reconstruction, alteration, remodeling, repair or demolition of any public building or public works by the commonwealth, or by any county, city, town, district, board, commission or other public body, when the amount of the contract is more than five thousand dollars in the case of the commonwealth and more than two thousand dollars in the case of any county, city, town, district, board, commission or other public body, a decision, by the contracting body or by any administrative board, official or agency, or by any architect or engineer, on a dispute, whether of fact or of law, arising under said contract shall not be final or conclusive if such decision is made in bad faith, fraudulently, capriciously, or arbitrarily is unsupported by substantial evidence, or is based upon error of law.

M.G.L. c.30 s 39L

Section 39L. The commonwealth and every county, city, town, district, board, commission or other public body which, as the awarding authority, requests proposals, bids or sub-bids for any work in the construction, reconstruction, alteration, remodeling, repair or demolition of any public building or other public works (1) shall not enter into a contract for the work with, and shall not approve as a subcontractor furnishing labor and materials for a part of the work, a foreign corporation which has not filed with the awarding authority a certificate of the state

secretary stating that the corporation has complied with requirements of section 15.03 of subdivision A of Part 15 of chapter 156D and the date of compliance, and further has filed all annual reports required by section 16.22 of subdivision B of Part 16 of said chapter 156D, and (2) shall report to the state secretary and to the department of corporations and taxation any foreign corporation performing work under such contract or subcontract, and any person, other than a corporation, performing work under such contract or subcontract, and residing or having a principal place of business outside the commonwealth.

M.G.L. c.30 s 39M(b)

Section 39M. (b) Specifications for such contracts, and specifications for contracts awarded pursuant to the provisions of said sections forty-four A to forty-four L of said chapter one hundred and forty-nine, shall be written to provide for full competition for each item of material to be furnished under the contract; except, however, that said specifications may be otherwise written for sound reasons in the public interest stated in writing in the public records of the awarding authority or promptly given in writing by the awarding authority to anyone making a written request therefor, in either instance such writing to be prepared after reasonable investigation. Every such contract shall provide that an item equal to that named or described in the said specifications may be furnished; and an item shall be considered equal to the item so named or described if, in the opinion of the awarding authority: (1) it is at least equal in quality, durability, appearance, strength and design, (2) it will perform at least equally the function imposed by the general design for the public work being contracted for or the material being purchased, and (3) it conforms substantially, even with deviations, to the detailed requirements for the item in the said specifications. For each item of material the specifications shall provide for either a minimum of three named brands of material or a description of material which can be met by a minimum of three manufacturers or producers, and for the equal of any one of said name or described materials.

M.G.L. c.30 s 39N

Section 39N. Every contract subject to section forty-four A of chapter one hundred and forty-nine or subject to section thirty-nine M of chapter thirty shall contain the following paragraph in its entirety and an awarding authority may adopt reasonable rules or regulations in conformity with that paragraph concerning the filing, investigation and settlement of such claims:

If, during the progress of the work, the contractor or the awarding authority discovers that the actual subsurface or latent physical conditions encountered at the site differ substantially or materially from those shown on the plans or indicated in the contract documents either the contractor or the contracting authority may request an equitable adjustment in the contract price of the contract applying to work affected by the differing site conditions. A request for such an adjustment shall be in writing and shall be delivered by the party making such claim to the other party as soon as possible after such conditions are discovered. Upon receipt of such a claim from a contractor, or upon its own initiative, the contracting authority shall make an investigation of such physical conditions, and, if they differ substantially or materially from those shown on the plans or indicated in the contract documents or from those ordinarily encountered and generally recognized as inherent in work of the character provided for in the plans and contract documents and are of such a nature as to cause an increase or decrease in the cost of performance of the work or a change in the construction methods required for the performance of the work which results in an increase or decrease in

the cost of the work, the contracting authority shall make an equitable adjustment in the contract price and the contract shall be modified in writing accordingly.

M.G.L. c.30 s 39O

Section 39O. Every contract subject to the provisions of section thirty-nine M of this chapter or subject to section forty-four A of chapter one hundred forty-nine shall contain the following provisions (a) and (b) in their entirety and, in the event a suspension, delay, interruption or failure to act of the awarding authority increases the cost of performance to any subcontractor, that subcontractor shall have the same rights against the general contractor for payment for an increase in the cost of his performance as provisions (a) and (b) give the general contractor against the awarding authority, but nothing in provisions (a) and (b) shall in any way change, modify or alter any other rights which the general contractor or the subcontractor may have against each other.

(a) The awarding authority may order the general contractor in writing to suspend, delay, or interrupt all or any part of the work for such period of time as it may determine to be appropriate for the convenience of the awarding authority; provided however, that if there is a suspension, delay or interruption for fifteen days or more or due to a failure of the awarding authority to act within the time specified in this contract, the awarding authority shall make an adjustment in the contract price for any increase in the cost of performance of this contract but shall not include any profit to the general contractor on such increase; and provided further, that the awarding authority shall not make any adjustment in the contract price under this provision for any suspension, delay, interruption or failure to act to the extent that such is due to any cause for which this contract provides for an equitable adjustment of the contract price under any other contract provisions.

(b) The general contractor must submit the amount of a claim under provision (a) to the awarding authority in writing as soon as practicable after the end of the suspension, delay, interruption or failure to act and, in any event, not later than the date of final payment under this contract and, except for costs due to a suspension order, the awarding authority shall not approve any costs in the claim incurred more than twenty days before the general contractor notified the awarding authority in writing of the act or failure to act involved in the claim.

M.G.L. c.30 s 39P

Section 39P. Every contract subject to section thirty-nine M of this chapter or section forty-four A of chapter one hundred forty-nine which requires the awarding authority, any official, its architect or engineer to make a decision on interpretation of the specifications, approval of equipment, material or any other approval, or progress of the work, shall require that the decision be made promptly and, in any event, no later than thirty days after the written submission for decision; but if such decision requires extended investigation and study, the awarding authority, the official, architect or engineer shall, within thirty days after the receipt of the submission, give the party making the submission written notice of the reasons why the decision cannot be made within the thirty day period and the date by which the decision will be made.

M.G.L. c.30 s 39R

Section 39R. (a) The words defined herein shall have the meaning stated below whenever they appear in this section:

(1) "Contractor" means any person, corporation, partnership, joint venture, sole proprietorship, or other entity awarded a contract pursuant to sections thirty-eight A 1/2 to thirty-eight O, inclusive, of chapter seven and any contract awarded or executed pursuant to section eleven C of chapter twenty-five A, section thirty-nine M of chapter thirty, or sections forty-four A to forty-four H, inclusive, of chapter one hundred and forty-nine, which is for an amount or estimated amount greater than one hundred thousand dollars.

(2) "Contract" means any contract awarded or executed pursuant to sections thirty-eight A 1/2 to thirty-eight O, inclusive, of chapter seven and any contract awarded or executed pursuant to section eleven C of chapter twenty-five A, section thirty-nine M of chapter thirty, or sections forty-four A through forty-four H, inclusive, of chapter one hundred and forty-nine, which is for amount or estimated amount greater than one hundred thousand dollars.

(3) "Records" means books of original entry, accounts, checks, bank statements and all other banking documents, correspondence, memoranda, invoices, computer printouts, tapes, discs, papers and other documents or transcribed information of any type, whether expressed in ordinary or machine language.

(4) "Independent Certified Public Accountant" means a person duly registered in good standing and entitled to practice as a certified public accountant under the laws of the place of his residence or principal office and who is in fact independent. In determining whether an accountant is independent with respect to a particular person, appropriate consideration should be given to all relationships between the accountant and that person or any affiliate thereof. Determination of an accountant's independence shall not be confined to the relationships existing in connection with the filing of reports with the awarding authority.

(5) "Audit", when used in regard to financial statements, means an examination of records by an independent certified public accountant in accordance with generally accepted accounting principles and auditing standards for the purpose of expressing a *certified* opinion thereon, or, in the alternative, a qualified opinion or a declination to express an opinion for stated reasons.

(6) "Accountant's Report", when used in regard to financial statements, means a document in which an independent certified public accountant indicates the scope of the audit which he has made and sets forth his opinion regarding the financial statements taken as a whole with a listing of noted exceptions and qualifications, or an assertion to the effect that an overall opinion cannot be expressed. When an overall opinion cannot be expressed the reason therefor shall be stated. An accountant's report shall include as a part thereof a signed statement by the responsible corporate officer attesting that management has fully disclosed all material facts to the independent certified public accountant, and that the audited financial statement is a true and complete statement of the financial condition of the contractor.

(7) "Management", when used herein, means the chief executive officers, partners, principals or other person or persons primarily responsible for the financial and operational policies and practices of the contractor.

(8) Accounting terms, unless otherwise defined herein, shall have a meaning in accordance with generally accepted accounting principles and auditing standards.

(b) Subsection (a)(2) hereof notwithstanding, every agreement or contract awarded or executed pursuant to sections thirty-eight A 1/2 to thirty-eight O, inclusive, of chapter seven, or eleven C of chapter twenty-five A, and pursuant to section thirty-nine M of chapter thirty or to section forty-four A through H, inclusive, of chapter one hundred and forty-nine, shall provide that:

(1) The contractor shall make, and keep for at least six years after final payment, books, records, and accounts which in reasonable detail accurately and fairly reflect the transactions and dispositions of the contractor, and

(2) until the expiration of six years after final payment, the office of inspector general, and the commissioner of capital asset management and maintenance shall have the right to examine any books, documents, papers or records of the contractor or of his subcontractors that directly pertain to, and involve transactions relating to, the contractor or his subcontractors, and

(3) if the agreement is a contract as defined herein, the contractor shall describe any change in the method of maintaining records or recording transactions which materially affect any statements filed with the awarding authority, including in his description the date of the change and reasons therefor, and shall accompany said description with a letter from the contractor's independent certified public accountant approving or otherwise commenting on the changes, and

(4) if the agreement is a contract as defined herein, the contractor has filed a statement of management on internal accounting controls as set forth in paragraph (c) below prior to the execution of the contract, and

(5) if the agreement is a contract as defined herein, the contractor has filed prior to the execution of the contracts and will continue to file annually, an audited financial statement for the most recent completed fiscal year as set forth in paragraph (d) below.

(c) Every contractor awarded a contract shall file with the awarding authority a statement of management as to whether the system of internal accounting controls of the contractor and its subsidiaries reasonably assures that:

(1) transactions are executed in accordance with management's general and specific authorization;

(2) transactions are recorded as necessary

i. to permit preparation of financial statements in conformity with generally accepted accounting principles, and

ii. to maintain accountability for assets;

(3) access to assets is permitted only in accordance with management's general or specific authorization; and

(4) the recorded accountability for assets is compared with the existing assets at reasonable intervals and appropriate action was taken with respect to any difference.

Every contractor awarded a contract shall also file with the awarding authority a statement prepared and signed by an independent certified public accountant, stating that he has examined the statement of management on internal accounting controls, and expressing an opinion as to

(1) whether the representations of management in response to this paragraph and paragraph (b) above are consistent with the result of management's evaluation of the system of internal accounting controls; and

(2) whether such representations of management are, in addition, reasonable with respect to transactions and assets in amounts which would be material when measured in relation to the applicant's financial statements.

(d) Every contractor awarded a contract by the commonwealth or by any political subdivision thereof shall annually file with the commissioner of capital asset management and maintenance during the term of the contract a financial statement prepared by an independent certified public accountant on the basis of an audit by such accountant. The final statement filed shall include the date of final payment. All statements shall be accompanied

by an accountant's report. Such statements shall be made available to the awarding authority upon request.

(e) The office of inspector general, the commissioner of capital asset management and maintenance and any other awarding authority shall enforce the provisions of this section. The commissioner of capital asset management and maintenance may after providing an opportunity for the inspector general and other interested parties to comment, promulgate pursuant to the provisions of chapter thirty A such rules, regulations and guidelines as are necessary to effectuate the purposes of this section. Such rules, regulations and guidelines may be applicable to all awarding authorities. A contractor's failure to satisfy any of the requirements of this section may be grounds for debarment pursuant to section forty-four C of chapter one hundred and forty-nine.

(f) Records and statements required to be made, kept or filed under the provisions of this section shall not be public records as defined in section seven of chapter four and shall not be open to public inspection; provided, however, that such records and statements shall be made available pursuant to the provisions of clause (2) of paragraph (b).

M.G.L. c.149 s 34

Section 34. Every contract, except for the purchase of material or supplies, involving the employment of laborers, workmen, mechanics, foremen or inspectors, to which the commonwealth or any county or any town, subject to section thirty, is a party, shall contain a stipulation that no laborer, workman, mechanic, foreman or inspector working within the commonwealth, in the employ of the contractor, sub-contractor or other person doing or contracting to do the whole or a part of the work contemplated by the contract, shall be required or permitted to work more than eight hours in any one day or more than forty-eight hours in any one week, or more than six days in any one week, except in cases of emergency, or, in case any town subject to section thirty-one is a party to such a contract, more than eight hours in any one day, except as aforesaid; provided, that in contracts entered into by the department of highways for the construction or reconstruction of highways there may be inserted in said stipulation a provision that said department, or any contractor or sub-contractor for said department, may employ laborers, workmen, mechanics, foremen and inspectors for more than eight hours in any one day in such construction or reconstruction when, in the opinion of the commissioner of labor and industries, public necessity so requires. Every such contract not containing the aforesaid stipulation shall be null and void.

M.G.L. c.149 s 44J

Section 44J. (1) No public agency or authority of the commonwealth or any political subdivision thereof shall award any contract for which competitive bids are required pursuant to section forty-four A of this chapter or section thirty-nine M of chapter thirty, or for which competitive proposals are required pursuant to subsection (4) of section forty-four E of this chapter or section eleven C of chapter twenty-five A, unless a notice inviting bids or proposals therefor shall have been posted no less than one week prior to the time specified in such notice for the receipt of said bids or proposals in a conspicuous place in or near the offices of the awarding authority, and shall have remained posted until the time so specified, and unless such notice shall also have been published at least once not less than two weeks prior to the time so specified in the central register published by the secretary of state pursuant to section twenty A of chapter nine and in a newspaper of general circulation in the locality of the proposed project. Said notice shall also be published at such other times and in

such other newspapers or trade periodicals as the commissioner of capital asset management and maintenance may require, having regard to the locality of the work involved.

(2) Said notice shall specify the time and place where plans and specifications of the proposed work may be had; the time and place of submission of general bids; and the time and place for opening of the general bids. For contracts subject to the provisions of sections forty-four A to H, inclusive, of this chapter, said notice shall also specify the time and place for submission of filed sub-bids, where required pursuant to section forty-four F; and the time and place for opening of said filed sub-bids.

Said notice shall also provide sufficient facts concerning the nature and scope of such project, the type and elements of construction, and such other information as will assist applicants in deciding to bid on such contract.

(3) No contract or preliminary plans and specifications shall be split or divided for the purpose of evading the provisions of this section.

(4) General bids and filed sub-bids for any contract subject to this section shall be in writing and shall be opened in public at the time and place specified in the posted or published notice, and after being so opened shall be open to public inspection.

(5) The provisions of this section shall not apply to any transaction between the commonwealth and any public service corporation.

(6) The provisions of this section may be waived in cases of extreme emergency involving the health and safety of the people and their property, upon the written approval of said commissioner. The written approval shall contain a description of the circumstances and the reasons for the commissioner's determination.

(7) Whoever violates any provision of this section shall be punished by a fine of not more than ten thousand dollars or by imprisonment in the state prison for not more than three years or in a jail or house of correction for not more than two and one-half years, or by both said fine and imprisonment; and in the event of final conviction, said person shall be incapable of holding any office of honor, trust or profit under the commonwealth or under any county, district or municipal agency.

Each and every person who shall cause or conspire to cause any contract or preliminary plans and specifications to be split or divided for the purpose of evading the provisions of this section shall forfeit and pay to the commonwealth, a political subdivision thereof or other awarding authority subject to this section, the sum of not more than five thousand dollars and, in addition, such person or persons shall pay, apportioned among them, double the amount of damages which the commonwealth or political subdivision thereof or other awarding authority may have sustained by reason of the doing of such act, together with the costs of the action.

(8) If an awarding authority rejects all general bids or does not receive any general bids, and advertises for a second opening of general bids with the original filed sub-bids as set forth in subsection (1) of section forty-four E the notice for receipt of such general bids may be published in the central register and elsewhere as required not less than one week prior to the time specified for such second opening of general bids.

(9) No request for proposals or invitation for bids issued under sections 38A1/2 to 38O, inclusive, of chapter 7, section 11C of chapter 25A, section 39M of chapter 30, this section and sections 44A to 44H, inclusive, shall be advertised if the awarding authority's cost estimate is greater than 1 year old.

M.G.L. c.82 s 40

Section 40. The following words, as used in this section and sections 40A to 40E, inclusive, shall have the following meanings:—

“Company”, natural gas pipeline company, petroleum or petroleum products pipeline company, public utility company, cable television company, and municipal utility company or department that supply gas, electricity, telephone, communication or cable television services or private water companies within the city or town where such excavation is to be made.

“Description of excavation location”, such description shall include the name of the city or town, street, way, or route number where appropriate, the name of the streets at the nearest intersection to the excavation, the number of the buildings closest to the excavation or any other description, including landmarks, utility pole numbers or other information which will accurately define the location of the excavation.

“Emergency”, a condition in which the safety of the public is in imminent danger, such as a threat to life or health or where immediate correction is required to maintain or restore essential public utility service.

“Excavation”, an operation for the purpose of movement or removal of earth, rock or the materials in the ground including, but not limited to, digging, blasting, augering, backfilling, test boring, drilling, pile driving, grading, plowing in, hammering, pulling in, jacking in, trenching, tunneling and demolition of structures, excluding excavation by tools manipulated only by human power for gardening purposes and use of blasting for quarrying purposes.

“Excavator”, any entity including, but not limited to, a person, partnership, joint venture, trust, corporation, association, public utility, company or state or local government body which performs excavation operations.

“Premark”, to delineate the general scope of the excavation or boring on the paved surface of the ground using white paint, or stakes or other suitable white markings on nonpaved surfaces. No premarking shall be acceptable if such marks can reasonably interfere with traffic or pedestrian control or are misleading to the general public. Premarking shall not be required of any continuous excavation that is over 500 feet in length.

“Safety zone”, a zone designated on the surface by the use of standard color-coded markings which contains the width of the facilities plus not more than 18 inches on each side.

“Standard color-coded markings”, red - electric power lines, cables, conduit or light cables; yellow - gas, oil, street petroleum, or other gaseous materials; orange - communications cables or conduit, alarm or signal lines; blue - water, irrigation and slurry lines; green - sewer and drain lines; white - premark of proposed excavation.

“System”, the underground plant damage prevention system as defined in section 76D of chapter 164.

PRICE ADJUSTMENTS FOR CERTAIN MATERIALS IN CONSTRUCTION
PROJECTS
MGL CHAPTER 30, SECTION 38A

On November 20, 2013, the Massachusetts Legislature passed a bill (Chapter 150 of the Acts of 2013) requiring that water and sewer projects bid under MGL Chapter 30 Section 39M include price adjustment clauses for **fuel** (both diesel and gasoline), **liquid asphalt** and **portland cement** contained in cast in place concrete for all projects that are advertised for bid after January 1, 2014.

The inclusion of these clauses in the construction contract is the responsibility of the awarding authority, and as such, MassDEP does not dictate what language should be used in the contract. MassDEP will, however, review the contracts to verify that price adjustment clauses have been included.

Awarding Authorities may find value from researching the *price adjustment* information on the Massachusetts Department of Transportation (MassDOT) website at <http://www.mhd.state.ma.us/default.asp?pgid=content/fuelPrices&sid=about> . MassDOT requires the use of price adjustment clauses in all of its contracts, and since 2008 has been requiring cities and towns utilizing Chapter 90 road construction funds to also include price adjustment clauses. Because of this, many cities and towns may already have drafted appropriate price adjustment language. This language would be suitable for use in SRF funded contracts. The MassDOT website has extensive information on price adjustments and required contract language for MassDOT contracts.

Attached below is the new Chapter 30, Section 38A language and the contract language that MassDOT uses in its construction contracts. The MassDOT contract language is presented as a possible starting point for borrowers that have not drafted price adjustment clauses. The LGU should consult with their legal and contract staff as appropriate in developing the price adjustment clauses.

Chapter 150 of the Acts of 2013
An Act Relative to Price Adjustment for Certain Materials in Construction Projects

Whereas, the deferred operation of this act would tend to defeat its purpose, which is to establish forthwith certain price adjustments, therefore it is hereby declared to be an emergency law, necessary for the immediate preservation of the public convenience.

Be it enacted by the Senate and House of Representatives in General Court assembled, and by the authority of the same as follows:

SECTION 1. Chapter 30 of the General Laws is hereby amended by inserting after section 38 the following section:-

Section 38A. Contracts for road and bridge projects awarded as a result of a proposal or invitation for bids under section 39M shall include a price adjustment clause for each of the following materials: fuel, both diesel and gasoline; asphalt; concrete; and steel. Contracts for water and sewer projects awarded as a result of a proposal or invitation for bids under said section 39M shall include a price adjustment clause for fuel, both diesel and gasoline; liquid asphalt; and *portland* cement contained in cast-in-place concrete. A base price for each material shall be set by the awarding authority or agency and shall be included in the bid documents at the time the project is advertised. The awarding authority or agency shall also identify in the bid documents the price index to be used for each material. The price adjustment clause shall provide for a contract adjustment to be made on a monthly basis when the monthly cost change exceeds plus or minus 5 per cent.

SECTION 2. Section 1 shall apply to projects which are advertised for bid after January 1, 2014.

Approved, November 25, 2013.

MassDOT Price Adjustment Clauses

DOCUMENT 00811
SPECIAL PROVISIONS
MONTHLY PRICE ADJUSTMENT FOR HOT MIX ASPHALT (HMA)
MIXTURES
ENGLISH UNITS
Revised: 02/02/2009

This provision applies to all projects using greater than 100 tons of hot mix asphalt (HMA) mixtures containing liquid asphalt cement as stipulated in the Notice to Contractors section of the bid documents.

The Price Adjustment will be based on the variance in price for the liquid asphalt component only from the Base Price to the Period Price. It shall not include transportation or other charges. This Price Adjustment will occur on a monthly basis.

Base Price

The Base Price of liquid asphalt on a project as listed in the Notice to Contractors section of the bid documents is a fixed price determined at the time of bid by the Department by using the same method as for the determination of the Period Price detailed below.

Period Price

Please note that, starting December 15, 2008, two sets of period prices will be posted each month on the MassHighway website at <http://www.mhd.state.ma.us/>. They will be labeled “New Asphalt Period Price Method” and “Old Asphalt Period Price Method”.

New Asphalt Period Price Method

The "New Asphalt Period Price Method" is for contracts bid after December 15, 2008 and will show the Period Price of liquid asphalt for each monthly period as determined by MassHighway using the average selling price per standard ton of PG64-28 paving grade (primary binder classification) asphalt, FOB manufacturer's terminal, as listed under the "East Coast Market - New England, Boston, Massachusetts area" section of the Poten & Partners, Inc. "Asphalt Weekly Monitor". This average selling price is listed in the issue having a publication date of the second Friday of the month and will be posted as the Period Price for that month. MassHighway will post this Period Price on this website within two (2) business days following their receipt of the relevant issue of the "Asphalt Weekly Monitor". Poten and Partners has granted MassHighway the right to publish this specific asphalt price information sourced from the Asphalt Weekly Monitor.

Old Asphalt Period Price Method

The "Old Asphalt Period Price Method" Period Price will be for contracts bid on or before December 15, 2008 and will contain liquid asphalt prices as determined by the old or previous method. These prices will continue to be posted on MassHighway's website until all contracts using the "Old Asphalt Period Price Method" Period Price have been closed.

New and Old Asphalt Period Price Methods

The paragraphs below apply to both the New and the Old Asphalt Period Price Methods.

The Contract Price of the hot mix asphalt mixture will be paid under the respective item in the Contract. The price adjustment, as herein provided, upwards or downwards, will be made after the work has been performed, using the monthly period price for the month during which the work was performed.

The Price Adjustment applies only to the actual virgin liquid asphalt content in the mixture placed on the job in accordance with the Standard Specifications for Highways and Bridges, Division III, Section M3.11.03.

The Price Adjustment will be a separate payment item. It will be determined by multiplying the number of tons of hot mix asphalt mixtures placed during each monthly period times the liquid asphalt content percentage times the variance in price between Base Price and Period Price of liquid asphalt.

This Price Adjustment will be paid only if the variance from the Base Price is 5% or more for a monthly period. The complete adjustment will be paid in all cases with no deduction of the 5% from either upward or downward adjustments.

No Price Adjustment will be allowed beyond the Completion Date of this Contract, unless there is a Department approved extension of time.

***** END OF DOCUMENT *****

DOCUMENT 00812
SPECIAL PROVISIONS
MONTHLY PRICE ADJUSTMENT FOR DIESEL FUEL AND GASOLINE –
ENGLISH UNITS
Revised: 01/26/2009

This monthly fuel price adjustment is inserted in this contract because the national and worldwide energy situation has made the future cost of fuel unpredictable. This adjustment will provide for either additional compensation to the Contractor or repayment to the Commonwealth, depending on an increase or decrease in the average price of diesel fuel or gasoline.

This adjustment will be based on fuel usage factors for various items of work developed by the Highway Research Board in Circular 158, dated July 1974. These factors will be multiplied by the quantities of work done in each item during each monthly period and further multiplied by the variance in price from the Base Price to the Period Price.

The Base Price of Diesel Fuel and Gasoline will be the price as indicated in the Department's web site (www.mhd.state.ma.us) for the month in which the contract was bid, which includes State Tax.

The Period Price will be the average of prices charged to the State, including State Tax for the bulk purchases made\ during each month.

This adjustment will be effected only if the variance from the Base Price is 5% or more for a monthly period. The complete adjustment will be paid in all cases with no deduction of the 5% from either upward or downward adjustments.

No adjustment will be paid for work done beyond the extended completion date of any contract.

Any adjustment (increase or decrease) to estimated quantities made to each item at the time of final payment will have the fuel price adjustment figured at the average period price for the entire term of the project for the difference of quantity.

The fuel price adjustment will apply only to the following items of work at the fuel factors shown:

ITEMS COVERED	FUEL FACTORS	
	Diesel	Gasoline
Excavation: and Borrow Work: Items 120, 120.1, 121, 123, 124, 125, 127, 129.3, 140, 140.1, 141, 142, 143, 144., 150, 150.1, 151 and 151.1 (Both Factors used)	0.29 Gallons / CY	0.15 Gallons / CY

Surfacing Work: All Items containing Hot Mix Asphalt	2.90 Gallons / Ton	Does Not Apply
--	--------------------	----------------

***** END OF DOCUMENT *****

DOCUMENT 00814
SPECIAL PROVISIONS
PRICE ADJUSTMENT FOR PORTLAND CEMENT CONCRETE MIXES
January 12, 2009

This provision applies to all projects using greater than 100 Cubic Yards (76 Cubic Meters) of Portland cement concrete containing Portland cement as stipulated in the Notice to Contractors section of the Bid Documents. This Price Adjustment will occur on a monthly basis.

The Price Adjustment will be based on the variance in price for the Portland cement component only from the Base Price to the Period Price. It shall not include transportation or other charges.

The Base Price of Portland cement on a project is a fixed price determined at the time of bid by the Department by using the same method as for the determination of the Period Price (see below) and found in the Notice to Contractors.

The Period Price of Portland cement will be determined by using the latest published price, in dollars per ton (U.S.), for Portland cement (Type I) quoted for Boston, U.S.A. in the **Construction Economics** section of *ENR Engineering News-Record* magazine or at the ENR website <http://www.enr.com> under **Construction Economics**. The Period Price will be posted on the MassHighway website the Wednesday immediately following the publishing of the monthly price in ENR, which is normally the first week of the month.

The Contract Price of the Portland cement concrete mix will be paid under the respective item in the Contract. The price adjustment, as herein provided, upwards or downwards, will be made after the work has been performed, using the monthly period price for the month during which the work was performed.

The price adjustment applies only to the actual Portland cement content in the mix placed on the job in accordance with the Standard Specifications for Highways and Bridges, Division III, Section M4.02.01.

No adjustments will be made for any cement replacement materials such as fly ash or ground granulated blast furnace slag.

The Price Adjustment will be a separate payment item. It will be determined by multiplying the number of cubic yards of Portland cement concrete placed during each monthly period times the Portland cement content percentage times the variance in price between the Base Price and Period Price of Portland cement.

This Price Adjustment will be paid only if the variance from the Base Price is 5% or more for a monthly period. The complete adjustment will be paid in all cases with no deduction of the 5% from either upward or downward adjustments.

No Price Adjustment will be allowed beyond the Completion Date of this Contract, unless there is a Department-approved extension of time.

END OF DOCUMENT

SECTION 01010

SUMMARY OF WORK

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 1 Specification Sections, apply to this section.

1.2 LOCATION OF WORK

- A. The work of this Contract is located in the City of Salem within and adjacent to several municipal roadways and sewer easements including but not limited to: Highland Avenue, Essex Street, Crescent Drive, Liberty Street, Oakview Avenue, Churchill Street, Sable Road, Circle Hill Road, Wheatland Street, Cleveland Road, Buchanan Road, Nichols Street, Butler Street, Pope Street, Proctor Street, Buena Vista and Washington Street.

1.3 SUMMARY

- A. Furnish all labor, materials, equipment, and incidentals required to perform the work associated with the SEWER REHABILITATION PROJECT as indicated on the Drawings and Attachments and specified herein.
- B. The Work includes, but is not necessarily limited to, the following major items:
 - 1. Sewer rehabilitation including approximately 2,600 linear feet of (8 to 18)-inch cured-in-place pipeliner and rehabilitation (includes egg shaped concrete pipe), 125-foot pipeline spot repairs utilizing cured-in-place spot liners or excavated pipe replacement, 50-vertical feet of manhole sealing and waterproofing, and installation of one PVC inside drop in sewer manhole.
 - 2. Cleaning and CCTV inspecting approximately 6,000 linear feet of sewer and drain pipe and services.
 - 3. The work shall also conform to such additional Drawings and addenda to these Specifications and Drawings as may be published or exhibited prior to the opening of bid proposals and to such drawings in explanation of details, or as may be furnished by the Engineer from time to time during the construction.
- C. Work and materials which are necessary in the construction but which are not specifically referred to in the Specification, or shown on the Drawings, but

implied by the Contract shall be furnished by the Contractor at his own cost and expense and shall be such as will correspond with the general character of the work as may be determined by the Engineer, whose decisions as to the necessity for and character of such work and materials shall be final and conclusive. It is the intent of these Specifications to produce a complete, operational and finished project whether shown in every detail or not.

1.4 WORK SEQUENCE:

- A. The Contractors shall submit a Work Sequencing Plan to the Engineer for review prior to beginning any construction activity, unless otherwise approved by the Engineer.
- B. Contractor shall schedule construction activities to account for variable flows in pipes due to weather and tidal conditions as well as high and variable groundwater levels due to tidal impacts.
- C. Contractor shall be aware that all pipes may convey both sanitary flows and stormwater flows and may also receive saline inflows during higher tide conditions.
- D. Contractor shall be aware that this project will be completed simultaneously with other construction projects so contractor will be required to provide weekly updates to project schedule timelines, attend weekly project meetings, and coordinate construction scheduling and activities to allow access to work zones and job site for all contractors.

1.5 CONTRACTOR'S USE OF PREMISES:

- A. Contractor shall limit the use of the premises for the performance of the Work and storage of materials and equipment.
- B. Contractor shall coordinate with Owner, access for normal maintenance requirements.
- C. Contractor shall assume full responsibility for security of all his and his subcontractors' materials and equipment stored on the site.
- D. If directed by the Owner, Contractor shall move stored items which interfere with operations of Owner.
- E. Obtain and pay for use of additional storage or work areas if needed to perform the Work.
- F. The Contractor shall coordinate with the City Police Department and maintain access for local traffic, pedestrians, and emergency vehicles at all times.

1.6 UNDERGROUND UTILITIES

- A. The underground utilities indicated on the drawings are considered approximate

as to their existence, size, and location. In the event that additional utilities are encountered that are not shown on the drawings, it shall be the Contractor's responsibility to locate all existing utilities and to protect same from damage or harm. All utilities interfered with or damaged shall be properly restored, at the expense of the Contractor, to the satisfaction of the Owner. The Contractor shall be responsible for contacting Dig Safe at 1-888-344-7233 and the City of Gloucester for utility mark out prior to commencing work.

PART 2 - PRODUCTS (NOT USED)

PART 3 - EXECUTION (NOT USED)

END OF SECTION 01010

SECTION 01025

MEASUREMENT AND PAYMENT

PART 1 - GENERAL

1.1 SCOPE

- A. Payment for the items specified in the Bid Schedule, shall include compensation for furnishing all labor, tools, equipment, supplies, and manufactured articles, and for all operations, and incidentals appurtenant to the items of work described, to complete the various items of the WORK, all in accordance with the requirements of the Contract Documents, Drawings, Specifications, Addendum, and other Modifications issued by and approved by the Owner and Engineer, including all costs for permits, compliance with the regulations of public agencies having jurisdiction, including Safety and Health Requirements of the Occupational Safety and Health Administration of the U.S. Department of Labor (OSHA). The prices named in the Bid Schedule shall include all Work items described or implied in the Contract Documents, Drawings, Specifications, Addendum, and other Modifications issued by and approved by the Owner and Engineer, and all other Work items necessary to manufacture, install, test, and start-up a complete working project.

- B. Work items to be included in the Bid Schedule prices, not included for separate payment elsewhere include, but are not limited to:

Preconstruction videos and photographs; construction photographs;

Coordination and cooperation with other utilities and contractors working within the work zone during the contract period;

Saw cutting, excavation, handling, hauling, and disposal of materials within trench limits of payment; including pavement, curbing, sidewalk, concrete, cobbles, and surface materials;

Furnishing and installing filter fabric, mulch sock, and silt fence around stockpiles, and along excavation as required; furnishing installing, and maintaining silt sacks in all catch basins; furnishing and installing geotextile and filter fabric for utility construction as directed;

Construction dewatering to control groundwater, wet weather or tidally influenced groundwater, or leakage or exfiltration from sewer pipes and manholes and underdrains; including pumps, piping, dirt bag filters, and sedimentation tanks;

Providing sanitary accommodations; bypass pumps (including up to two 4-inch Dri-Prime Diesel pumps) and welded HDPE bypass piping if required, installation and removal of temporary pipe plugs to isolate sewer, storm, or tidal flow; provide, maintain, and install bypass pumping and temporary service connections for drain and/or sewer;

Excavation, temporary support of excavation, removal of excavation support;

Furnishing and installing crushed stone, pipe bedding materials, filter fabric, gravel backfill, common fill, detectable warning tape as required, and gravel subbase

material in trenches and within limits of payment; including replacement of soils determined by Engineer to be unsuitable for backfill;

Backfill and compaction, compaction testing;

Locating, supporting, bracing, and protecting existing utility pipes, services, conduits, duct banks, traffic light poles, and utility poles, including temporary pole support and removal and replacement of cable guy pole support;

Abandonment of existing utilities, installing mortar plugs in all abandoned pipes and conduits smaller than 8-inches in diameter, removal and disposal of existing, abandoned or relocated utilities;

Supporting or removal and replacement of active or abandoned pipes or utilities in conflict with construction;

Concrete encasement, including external pipe wrap if required, of impacted utilities if water and sewer separation requirements are not met;

Concrete cradles, pipe connections, anchor bolts, and field closures;

Tree pruning, protection, and maintenance;

Providing sanitary facilities throughout project;

Securing staging areas, establishing staging area with vehicular and pedestrian protection, security of staging area and work zone, protecting and maintaining staging area and construction yard, removal and cleaning up of staging area;

Traffic regulation and control, pedestrian and vehicular protection, coordination of police details, obtaining and posting No Parking restrictions;

Cold patch or "temporary" bituminous paving for traffic control, safety, or other use as directed by the Engineer outside the trench limits of payment;

Temporary pavement marking paint;

Snow removal from streets and sidewalks within project limits on all streets that are not fully paved, have castings or steel plates that may hinder municipal snow removal, or have any equipment and or material stored;

Attend City and neighborhood meetings if required;

Transporting trash and recyclables out the work area if municipal pickup is hindered;

Submitting work plans and shop drawings; fulfilling all reporting requirements;

Preparation and submission of monthly and final record drawing information;

Rodent control plan submission, rodent control during construction;

Night work and related equipment including work lights and traffic indicator lights;

The Contractor and Subcontractors shall not take advantage of any apparent error or omission on the Drawings or Specifications. They shall be permitted to make corrections and interpretations as may be deemed necessary for fulfillment of the intent of the Contract Documents at no additional cost to the Owner. The Owner reserves the right to reject any and all bids.

- C. The term furnish means supply and deliver to the Project site, including the actual unloading, unpacking, assembly, erection, placing, installation, anchoring, applying, working to dimension, finishing, curing, protecting, cleaning, and similar operations, unless stated otherwise.

1.2 LUMP SUM ITEMS

- A. Measurement and payment for work performed shall be based on the percent complete for the various lump sum prices on the approved schedule of values.
- B. Payment for the lump sums shall be full compensation for all labor, materials and equipment required to furnish, install, construct, startup and test the work covered under that lump sum item.
- C. Payment shall also fully compensate the Contractor for any other work which is not specified or shown, but which is necessary to complete the work.

1.3 MEASUREMENT FOR PAYMENT

- A. Work completed to date, measured as a percentage of the total Work, shall be submitted by the Contractor and substantiated as required by the Owner.
- B. The Owner will review the submittal for completeness and verification.
 - 1. Include a checklist of completed items; only signed-off items will be considered for payment.
 - 2. Include red-lined drawings indicating degree of completion.
- C. Unit Price Items: Measurement for payment shall be based upon the measured quantity as described in this measurement and payment section.

1.4 BID ITEMS

Measurement and payment for each Bid Item in the Bid Form shall be as set forth below:

Item No.1 – Mobilization/Demobilization

A. Measurement

Measurement for payment shall be based on a lump sum basis, and will be limited to 50% of the lump sum amount of this item until the work is complete and the contractor has completely demobilized including restoration and cleanup of staging areas. The initial payment of 50% mobilization costs shall be payable when the Contractor is operational on site. Operational shall mean the substantial commencement of work on site, not prior to commencement. The lump sum price bid for mobilization shall not exceed 5 percent of the total contract price.

B. Payment

Payment for Item No.1 – Mobilization/Demobilization will be at the lump sum price bid for this item in the proposal. Under the lump sum price bid for this item, the Contractor shall move his equipment to the site and prepare to begin construction. It shall also include payment for demobilization of equipment at the completion of the Project. Mobilization costs include all costs of initiating the Contract, exclusive of the cost of materials. Mobilization includes securing and establishing a staging area for materials and equipment, including erosion and sedimentation controls, setting up sanitary facilities, submitting required shop drawing and work plan submittals, distributing contact numbers for Contractor's staff to Owner and Engineer, preparing and submitting all work plans and submittals, performing a pre-construction video for the entire project area identifying all surface features including sidewalks, roads, curb lines, structures, signs, signals, driveway aprons, and all other surface features within the right-of-way, and transporting all necessary trucks and construction equipment to the site necessary to begin construction.

Item No. 2 – Rock Excavation (Minimum)

A. Measurement

Measurement for payment will be based on the actual cubic yards of rock excavated, removed, and disposed of from within the Trench Payment Limits as indicated in the Drawings and as measured by the Owner or Engineer. Rock encountered during excavation that measures less than one (1) cubic yard, rock that can be removed without use of rock hammer or blasting, or rock encountered outside the trench payment limits, will not be paid under this item and will not justify any additional payment.

B. Payment

Payment for Item No. 2 - Rock Excavation (Minimum) shall be based on the stated unit price for this item in the proposal. Under the Unit Price for this item, the Contractor shall furnish all labor, materials, tools, equipment, and incidentals required to excavate, remove, and dispose of rock from trenches and excavated areas. The work includes all items included in this Section's Paragraph 1.1B, above, as well as drilling, hammering, blasting if allowed by owner, rock disposal, pre-blast surveys and coordination with Fire Department, and all related work, and all incidental work not included for payment elsewhere.

Item No. 2A – Rock Excavation (Additional)

A. Measurement

Measurement for payment will be the quantity measured under Item No. 2. Rock encountered during excavation that measures less than one (1) cubic yard, or rock encountered outside the trench payment limits, will not be paid under this item and will not justify any additional payment.

B. Payment

Payment for Item No. 2A - Rock Excavation (Additional) shall be based on the unit price bid for this item in the proposal. Under the Unit Price for this item, the Contractor shall include additional costs for performing rock excavation and disposal should he decide that the minimum unit price in Item No. 2 is insufficient compensation.

Item No. 3 – Exploratory Excavation

A. Measurement

Measurement for payment will be based on the actual cubic yards of material displaced during exploratory excavation and backfilled as directed and as measured by the Engineer

based on dimensions of open excavation. Exploratory excavations that are not backfilled and compacted prior to beginning any work in the excavation that can be measured for payment elsewhere (except for Bid Items 11-15) will not be measured for payment.

B. Payment

Payment for Item No. 3 – Exploratory Excavation will be based on the unit price bid for this item in the proposal. Under the Unit Price for this item, the Contractor shall furnish all labor, materials, tools, equipment, and incidentals required to complete exploratory excavations as necessary to locate, measure, or observe pipe, structures, utilities, other possible obstructions, and as directed. The work includes all items included in this Section's Paragraph 1.1B, above, as well as saw-cutting, temporary support of excavation, excavation; cutting and removal of section of existing sewer service laterals or sewer/drain main pipe within excavation, coordination with pipeline cleaning and CCTV inspection crews to gain access to the pipe for inspection, snaking existing service laterals to edge of public way and confirm length with field measurements to enable Engineer to determine if cleaning and CCTV inspection is required and if services should be connected to the sewer or drain main pipe; coordination and scheduling with Engineer to allow cut sewer service laterals to be observed safely from the construction trench to enable Engineer to determine if cleaning and CCTV inspection is required, reconnecting removed section of active service laterals or sewer/drain pipe with Fernco Couplings, replacing with PVC pipe if required, installing mortar plugs in inactive service laterals, placing backfill, compaction, furnishing and placing gravel base under paved area; repair of any utility lines and services broken during construction; and all work incidental thereto and all work not specifically included for payment under other items. Pipeline cleaning and CCTV inspection will be measured for payment under Bid Items 11-15.

Item No. 4 – Earth Excavation and Refill Below Normal Depth

A. Measurement

Measurement for payment will be based on the actual cubic yards of unsuitable material excavated, legally disposed, and replaced with suitable gravel below normal depth to as directed by the Engineer and as measured by the Engineer. Earth excavation and refill below normal depth without prior authorization from the Engineer will not be measured for payment.

B. Payment

Payment for Item No. 4 – Earth Excavation and Refill Below Normal Depth will be based on the unit price bid for this item in the proposal. Under the Unit Price for this item, the Contractor shall furnish all labor, materials, tools, equipment, and incidentals required to excavate and refill such materials as necessary beneath the normal depth to replace unsuitable soil materials as directed by the Engineer. The work includes all items included in this Section's Paragraph 1.1B, above, as well as temporary support of excavation, excavation, furnishing and installing gravel backfill or gravel base under paved area; repair of any utility lines and services broken during construction; and all work incidental thereto and all work not specifically included for payment under other items.

Item No. 5 – Furnish and Install New (6 to 8)-inch PVC Sewer or Drain Pipe or Service, including drop connection, All Depths

A. Measurement

Measurement for payment will be based on the actual linear feet of new (6-8)-inch diameter PVC sewer or drain pipe installed, complete as measured by the Engineer along the centerline of the pipe, through the fittings (including the (6-8)-inch (tee or wye) fittings in Item No. 8), between the inside face to inside face of structures or between the points of connection with existing pipes, spot repairs will be measured at a minimum length of 4-feet. Piping installed to construct internal manhole drop connections will be measured by the same manner.

B. Payment

Payment for Item No. 5 – Furnish and Install New (6 to 8)-inch PVC Sewer or Drain Pipe or Service, including drop connection, All Depths will be based on the unit price bid for this item in the proposal. Under the Unit Price for this item, the Contractor shall furnish all labor, materials, tools, equipment, and incidentals required to install new (6 to 8)-inch diameter PVC sewer or drain pipe complete as indicated on the Drawings and as specified or as directed by the Engineer. The work includes all items included in this Section's Paragraph 1.1B, above, as well as saw-cutting and excavation to locate existing pipe or structure where new pipe connection will be made; field verification of internal and external diameter of pipe or structure, removal and legal disposal of existing pipe and fittings, hand cleaning of debris from existing pipe at point of connection with replacement pipe, installing mortar plugs in cut or abandoned pipes smaller than 8-inch inside diameter; installation of new (6-8)-inch PVC pipe, fittings, couplings, and concrete field closures as required; installation of internal drop pipe fittings, anchors, and fasteners; cutting existing sewer or drain service laterals at trench limits of payment or edge of main line construction trench; snaking sewer or drain service laterals to edge of public way and confirm length with field measurement to enable Engineer to determine if cleaning and CCTV inspection is required and if services should be connected to the new pipe; coordination and scheduling with Engineer to allow cut service laterals to be observed safely from the construction trench to enable Engineer to determine if cleaning and CCTV inspection is required; cutting existing structures, cleaning, removal, and disposal of debris from existing structures on either end of proposed pipe and removal of debris with "Vactor", repair and modification of existing structures around point of connection as required; installation of crushed stone bedding, concrete encasement, and all incidental work not specifically included for payment elsewhere. Size and material of existing pipes will vary.

Item No. 6 – Furnish and Install New (10 to 15)-inch PVC Sewer or Drain Pipe or Service, All Depths

A. Measurement

Measurement for payment will be based on the actual linear feet of new (10-15)-inch diameter PVC sewer or drain pipe installed, complete as measured by the Engineer along the centerline of the pipe, through the fittings (including the (10-15)-inch (tee or wye) fittings in Item No. 9), between the inside face to inside face of structures or between the points of connection with existing pipes, spot repairs will be measured at a minimum length of 4-feet.

B. Payment

Payment for Item No. 6 – Furnish and Install New (10 to 15)-inch PVC Sewer or Drain Pipe, All Depths will be based on the unit price bid for this item in the proposal. Under the Unit Price for this item, the Contractor shall furnish all labor, materials, tools, equipment, and incidentals required to install new (10-15)-inch diameter PVC sewer or drain pipe complete as indicated on the Drawings and as specified or as directed by the Engineer. The work includes all items included in this Section's Paragraph 1.1B, above, as well as saw-cutting and excavation to locate existing pipe or structure where new pipe

connection will be made; field verification of internal and external diameter of pipe or structure, removal and legal disposal of existing pipe and fittings, hand cleaning of debris from existing pipe at point of connection with replacement pipe, installing mortar plugs in cut or abandoned pipes smaller than 8-inch inside diameter; installation of new (10-15)-inch PVC pipe, fittings, couplings, and concrete field closures as required; cutting existing sewer or drain service laterals at trench limits of payment or edge of main line construction trench; snaking sewer or drain service laterals to edge of public way and confirm length with field measurement to enable Engineer to determine if cleaning and CCTV inspection is required and if services should be connected to the new pipe; coordination and scheduling with Engineer to allow cut service laterals to be observed safely from the construction trench to enable Engineer to determine if cleaning and CCTV inspection is required; cutting existing structures, cleaning, removal, and disposal of debris from existing structures on either end of proposed pipe and removal of debris with "Vactor", repair and modification of existing structures around point of connection as required; installation of crushed stone bedding, concrete encasement, and all incidental work not specifically included for payment elsewhere. Size and material of existing pipes will vary.

Item No. 7 – Furnish and Install New 18-inch PVC Sewer or Drain Pipe, All Depths

A. Measurement

Measurement for payment will be based on the actual linear feet of new (18)-inch diameter PVC sewer or drain pipe installed, complete as measured by the Engineer along the centerline of the pipe, through the fittings (including the (18)-inch (tee or wye) fittings in Item No. 10), between the inside face to inside face of structures or between the points of connection with existing pipes, spot repairs will be measured at minimum length of 4-feet.

B. Payment

Payment for – Furnish and Install New 18-inch PVC Sewer or Drain Pipe, All Depths will be based on the unit price bid for this item in the proposal. Under the Unit Price for this item, the Contractor shall furnish all labor, materials, tools, equipment, and incidentals required to install new (18)-inch diameter PVC sewer or drain pipe complete as indicated on the Drawings and as specified or as directed by the Engineer. The work includes all items included in this Section's Paragraph 1.1B, above, as well as saw-cutting and excavation to locate existing pipe or structure where new pipe connection will be made; field verification of internal and external diameter of pipe or structure, removal and legal disposal of existing pipe and fittings, hand cleaning of debris from existing pipe at point of connection with replacement pipe, installing mortar plugs in cut or abandoned pipes smaller than 8-inch inside diameter; installation of new (18)-inch PVC pipe, fittings, couplings, and concrete field closures as required; cutting existing sewer or drain service laterals at trench limits of payment or edge of main line construction trench; snaking sewer or drain service laterals to edge of public way and confirm length with field measurement to enable Engineer to determine if cleaning and CCTV inspection is required and if services should be connected to the new pipe; coordination and scheduling with Engineer to allow cut service laterals to be observed safely from the construction trench to enable Engineer to determine if cleaning and CCTV inspection is required; cutting existing structures, cleaning, removal, and disposal of debris from existing structures on either end of proposed pipe and removal of debris with "Vactor", repair and modification of existing structures around point of connection as required; installation of crushed stone bedding, concrete encasement, and all incidental work not specifically included for payment elsewhere. Size and material of existing pipes will vary.

Item No. 8 – Furnish and Install (6-8)-inch Tee Fittings, Connect to Existing (4 to 8)-inch Sewer Service Pipe, All Depths

A. Measurement

Measurement for payment will be based on the number of complete (6-8)-inch PVC (Tee or Wye) fittings installed including new PVC service pipe, fittings, and connections to new or existing sewer service pipe at trench payment limit or edge of main line construction trench, as directed by Engineer and as measured and approved by the Engineer. Installation of (Tee or Wye) fittings and connections to existing sewer service pipe without the direction of the Engineer, or without completion of sewer service pipe snaking (required as part of Bid Item No. 5) and/or CCTV inspection of sewer service pipe (Bid Item No. 11) will not be measured for payment.

B. Payment

Payment for Item No. 8 – Furnish and Install (6-8)-inch Tee Fittings, Connect to Existing (4 to 8)-inch Sewer Service Pipe, All Depths will be based on the unit price bid for this item in the proposal. Under the Unit Price for this item, the Contractor shall furnish all labor, materials, tools, equipment, and incidentals required to connect existing sewer services to the new (6-8)-inch PVC sewer pipe, complete as specified or required by Engineer. The work includes all items included in this Section's Paragraph 1.1B, above, as well as field verification of internal and external diameter of existing sewer service pipe to be connected as directed by the Engineer, providing and installing new PVC Tee or Wye fitting to match size of existing service to be connected, installation of PVC sewer service pipe, fittings, and chimneys between the (tee or wye) fitting and the trench payment limit or edge of main line construction trench; saw-cutting existing sewer service pipe, hand cleaning of debris from existing service pipe, connections between the new PVC service pipe and new or existing service pipe at trench payment limit or edge of main line construction trench, connecting the new PVC service pipe to the new (6-8)-inch PVC (tee or wye) fitting, all fittings and Fernco type couplings, and all incidental work not included for payment elsewhere. Size and material of existing sewer service will vary. Installation of new or replacement sewer service pipe, as directed by Engineer, outside the trench payment limits and outside the main line construction trench will be measured for payment under Bid Item No. 5 providing it is not required to replace pipe damaged during construction.

Item No. 9 – Furnish and Install (10 to 12)-inch Tee Fittings, Connect to Existing (4 to 8)-inch Sewer Service Pipe, All Depths

A. Measurement

Measurement for payment will be based on the number of complete (10-12)-inch PVC (Tee or Wye) fittings installed including new PVC service pipe, fittings, and connections to new or existing sewer service pipe at trench payment limit or edge of main line construction trench, as directed by Engineer and as measured and approved by the Engineer. Installation of (Tee or Wye) fittings and connections to existing sewer service pipe without the direction of the Engineer, or without completion of sewer service pipe snaking (required as part of Bid Item No. 6) and/or CCTV inspection of sewer service pipe (Bid Item No. 11) will not be measured for payment.

B. Payment

Payment for Item No. 9 – Furnish and Install (10 to 12)-inch Tee Fittings, Connect to Existing (4 to 8)-inch Sewer Service Pipe, All Depths will be based on the unit price bid for this item in the proposal. Under the Unit Price for this item, the Contractor shall

furnish all labor, materials, tools, equipment, and incidentals required to connect existing sewer services to the new (10-12)-inch PVC sewer pipe, complete as specified or required by Engineer. The work includes all items included in this Section's Paragraph 1.1B, above, as well as field verification of internal and external diameter of existing sewer service pipe to be connected as directed by the Engineer, providing and installing new PVC Tee or Wye fitting to match size of existing service to be connected, installation of PVC sewer service pipe, fittings, and chimneys between the (tee or wye) fitting and the trench payment limit or edge of main line construction trench; saw-cutting existing sewer service pipe, hand cleaning of debris from existing service pipe, connections between the new PVC service pipe and new or existing service pipe at trench payment limit or edge of main line construction trench, connecting the new PVC service pipe to the new (10-12)-inch PVC (tee or wye) fitting, all fittings and Fernco type couplings, and all incidental work not included for payment elsewhere. Size and material of existing sewer service will vary. Installation of new or replacement sewer service pipe, as directed by Engineer, outside the trench payment limits and outside the main line construction trench will be measured for payment under Bid Item No. 5 providing it is not required to replace pipe damaged during construction.

Item No.10 – Furnish and Install 18-inch Tee Fittings, Connect to Existing (4 to 8)-inch Sewer Service Pipe, All Depths

A. Measurement

Measurement for payment will be based on the number of complete (18)-inch PVC (Tee or Wye) fittings installed including new PVC service pipe, fittings, and connections to new or existing sewer service pipe at trench payment limit or edge of main line construction trench, as directed by Engineer and as measured and approved by the Engineer. Installation of (Tee or Wye) fittings and connections to existing sewer service pipe without the direction of the Engineer, or without completion of sewer service pipe snaking (required as part of Bid Item No. 7) and/or CCTV inspection of sewer service pipe (Bid Item No. 11) will not be measured for payment.

B. Payment

Payment for Item No. 10 – Furnish and Install 18-inch Tee Fittings, Connect to Existing (4 to 8)-inch Sewer Service Pipe, All Depths will be based on the unit price bid for this item in the proposal. Under the Unit Price for this item, the Contractor shall furnish all labor, materials, tools, equipment, and incidentals required to connect existing sewer services to the new (18)-inch PVC sewer pipe, complete as specified or required by Engineer. The work includes all items included in this Section's Paragraph 1.1B, above, as well as field verification of internal and external diameter of existing sewer service pipe to be connected as directed by the Engineer, providing and installing new PVC Tee or Wye fitting to match size of existing service to be connected, installation of PVC sewer service pipe, fittings, and chimneys between the (tee or wye) fitting and the trench payment limit or edge of main line construction trench; saw-cutting existing sewer service pipe, hand cleaning of debris from existing service pipe, connections between the new PVC service pipe and new or existing service pipe at trench payment limit or edge of main line construction trench, connecting the new PVC service pipe to the new (18)-inch PVC (tee or wye) fitting, all fittings and Fernco type couplings, and all incidental work not included for payment elsewhere. Size and material of existing sewer service will vary. Installation of new or replacement sewer service pipe, as directed by Engineer, outside the trench payment limits and outside the main line construction trench will be measured for payment under Bid Item No. 5 providing it is not required to replace pipe damaged during construction.

Item No. 11 – CCTV Inspection of Service Laterals from Trench or Main, All Sizes

A. Measurement

Measurement for payment will be based on the linear feet of pipe CCTV inspected, complete, along the centerline of the pipe, between the cut end of service lateral in construction trench or exploratory excavation (or from the center of the main if camera launched from main) and the termination of CCTV inspection at the edge of public way or building, as directed and approved by the Engineer. Service laterals cleaned and CCTV inspected without the direction of the Engineer will not be measured for payment. Cleaning and CCTV inspection of the main line as necessary to access service lateral for launch camera to be measured for payment under Items 12-15, CCTV inspection of the main line between service laterals will not be measured for payment under Item No. 11.

B. Payment

Payment for Item No. 11 – CCTV Inspection of Service Laterals from Trench or Main, All Sizes shall be based on the Unit Price bid for this item in the proposal. Under the Unit Price for this item, the Contractor shall furnish all labor, materials, tools, equipment, and incidentals required to snake, clean as necessary, and CCTV inspect service laterals between the cut end of service lateral in construction trench or exploratory excavation (or from center of the main if camera launched from main) and the termination of CCTV inspection at edge of public way or building, as indicated on the Drawings and as specified or as directed by the Engineer. The work includes all items included in this Section's Paragraph 1.1B, above, as well as coordination and scheduling with Engineer to allow cut sewer service laterals to be observed safely from the construction trench or excavation to enable Engineer to determine if cleaning and CCTV inspection is required following snaking of the sewer service pipes completed in Bid Item Nos. (5, 6, 7); bypass pumping, flow handling, traffic signage and worksite protection, homeowner notification and coordination, coordination with City of Salem water department for use of hydrants identified by the City for water supply, providing approved backflow device; cleaning pipe as required to permit CCTV inspection, or as directed by the Engineer including three (3) passes with high pressure water jetting equipment; providing tractor driven camera with lateral launch camera and location and depth tracking signal; completing inspection, marking out approximate location and depth of pipe on street with paint based on tracking signal results; producing CCTV logs identifying the location of observations made during CCTV inspections and cross referencing the structure numbers, providing two (2) copies of CCTV inspections on DVDs; removal of all cleaned grit and debris with "Vactor", temporarily storing cleaning debris in appropriate non-leaking container, hauling and legal disposal of the cleaning debris, and all incidental work not specifically included for payment elsewhere.

Item No. 12 – Light Cleaning and CCTV Inspection of (6 to 8)-inch Sewer and Drain Pipe

A. Measurement

Measurement for payment will be based on the linear feet of pipe (approximately 6 to 8 inch inside diameter) cleaned and CCTV inspected complete, along the centerline of the pipe, between the inside face to inside face of structures or the termination of CCTV inspection. Heavy cleaning of pipes as required will be measured separately for payment under Item No. 14 following prior written approval from the Engineer.

B. Payment

Payment for Item No. 12 – Light Cleaning and CCTV Inspection of (6 to 8)-inch Sewer and Drain Pipe shall be based on the Unit Price bid for this item in the proposal. Under the Unit Price for this item, the Contractor shall furnish all labor, materials, tools, equipment, and incidentals required to clean and CCTV inspect sewer and drain pipes, as indicated on the Drawings and as specified or as directed by the Engineer. The work includes all items included in this Section's Paragraph 1.1B, above, as well as coordination with test pit excavation to gain access to pipe segment, bypass pumping, flow handling, traffic signage and worksite protection, homeowner notification and coordination, coordination with City of Salem water department for use of hydrants identified by the City for water supply, providing approved backflow device; providing tractor driven camera with adequate pan, tilt, zoom, and lighting equipped with location and depth tracking signal; cleaning pipe as required to permit CCTV inspection, joint testing and sealing activity, cured-in-place pipelining, or as directed by the Engineer including three (3) passes with high pressure water jetting equipment; completing inspection, marking out approximate location and depth of pipe on street with paint based on tracking signal results, producing CCTV logs identifying the location of observations made during CCTV inspections and cross referencing the structure numbers, providing two (2) copies of CCTV inspections on DVD or USB; removal of all cleaned grit and debris with "Vactor" including connecting manholes, hauling and legal disposal of the cleaning debris, and all incidental work not specifically included for payment elsewhere.

Item No. 13 – Light Cleaning and CCTV Inspection of (10 to 18)-inch Sewer and Drain Pipe

A. Measurement

Measurement for payment will be based on the linear feet of pipe (approximately 10 to 18 inch inside diameter or non-round pipes with larger dimension greater than 10-inch) cleaned and CCTV inspected complete, along the centerline of the pipe, between the inside face to inside face of structures or the termination of CCTV inspection. Heavy cleaning of pipes as required will be measured separately for payment under Item No. 15 following prior written approval from the Engineer.

B. Payment

Payment for Item No. 13 – Light Cleaning and CCTV Inspection of (10 to 18)-inch Sewer and Drain Pipe shall be based on the Unit Price bid for this item in the proposal. Under the Unit Price for this item, the Contractor shall furnish all labor, materials, tools, equipment, and incidentals required to clean and CCTV inspect sewer and drain pipes, as indicated on the Drawings and as specified or as directed by the Engineer. The work includes all items included in this Section's Paragraph 1.1B, above, as well as coordination with test pit excavation to gain access to pipe segment, bypass pumping, flow handling, traffic signage and worksite protection, homeowner notification and coordination, coordination with City of Salem water department for use of hydrants identified by the City for water supply, providing approved backflow device; providing tractor driven camera with adequate pan, tilt, zoom, and lighting equipped with location and depth tracking signal; cleaning pipe as required to permit CCTV inspection, joint testing and sealing activity, cured-in-place pipelining, or as directed by the Engineer including three (3) passes with high pressure water jetting equipment; completing inspection, marking out approximate location and depth of pipe on street with paint based on tracking signal results, producing CCTV logs identifying the location of observations made during CCTV inspections and cross referencing the structure numbers, providing two (2) copies of CCTV inspections on DVD or USB; removal of all cleaned grit and debris with "Vactor" including connecting manholes, hauling and legal disposal of the cleaning debris, and all incidental work not specifically included for payment elsewhere.

Item No. 14 – Heavy Cleaning of (6 to 8)-inch Sewer and Drain Pipe

A. Measurement

Measurement for payment will be based on the actual linear feet of sewer or drain pipe (approximately 6 to 8 inch inside diameter) heavy cleaned complete as measured by the Engineer along the centerline of the pipe, between the beginning and end of each pipe segment based on the measurements recorded in the light cleaning and CCTV inspection from each direction or between the inside face to inside face of structures or termination of CCTV inspection as measured by the Engineer. Heavy cleaning will only be measured for payment where use of saws to cut protruding services or bucket machines, scrapers, root cutters, and augers are required in addition to three (3) passes with high pressure water jetting equipment and light cleaning in accordance with the Specifications; and where prior written authorization by the Engineer has been received. Heavy cleaning without prior authorization will not be measured for payment.

B. Payment

Payment for Item No. 14 – Heavy Cleaning of (6 to 8)-inch Sewer and Drain Pipe will be based on the unit price bid for this item in the proposal. Under the Unit Price for this item, the Contractor shall furnish all labor, materials, tools, equipment, and incidentals required to heavy clean sewer and drain pipes as indicated on the Drawings or as directed by the Engineer. The work includes all items included in this Section's Paragraph 1.1B, above, as well as well as bypass pumping, flow handling, traffic signage and worksite protection, homeowner notification and coordination, coordination with City of Salem water department for use of hydrants identified by the City for water supply, providing approved backflow device, cutting protruding services which prevented access for light cleaning and CCTV inspection; cleaning pipe as required to permit CCTV inspection, joint testing and sealing activity, cured-in-place pipelining, or as directed by the Engineer; removal of all cleaned grit and debris with "Vactor" including connecting manholes, hauling and legal disposal of cleaning debris, and all incidental work not specifically included for payment elsewhere.

Item No. 15 – Heavy Cleaning of (10 to 18)-inch Sewer and Drain Pipe

A. Measurement

Measurement for payment will be based on the actual linear feet of sewer or drain pipe (approximately 10 to 18-inch inside diameter or non-round pipes with larger dimension greater than 10-inch) heavy cleaned complete as measured by the Engineer along the centerline of the pipe, between the beginning and end of each pipe segment based on the measurements recorded in the light cleaning and CCTV inspection from each direction or between the inside face to inside face of structures or termination of CCTV inspection as measured by the Engineer. Heavy cleaning will only be measured for payment where use of saws to cut protruding services or bucket machines, scrapers, root cutters, and augers are required in addition to three (3) passes with high pressure water jetting equipment and light cleaning in accordance with the Specifications; and where prior written authorization by the Engineer has been received. Heavy cleaning without prior authorization will not be measured for payment.

B. Payment

Payment for Item No. 15 – Heavy Cleaning of (10 to 18)-inch Sewer and Drain Pipe will be based on the unit price bid for this item in the proposal. Under the Unit Price for this item, the Contractor shall furnish all labor, materials, tools, equipment, and incidentals

required to heavy clean sewer and drain pipes as indicated on the Drawings or as directed by the Engineer. The work includes all items included in this Section's Paragraph 1.1B, above, as well as bypass pumping, flow handling, traffic signage and worksite protection, homeowner notification and coordination, coordination with City of Salem water department for use of hydrants identified by the City for water supply, providing approved backflow device, cutting protruding services which prevented access for light cleaning and CCTV inspection; cleaning pipe as required to permit CCTV inspection, joint testing and sealing activity, cured-in-place pipelining, or as directed by the Engineer; removal of all cleaned grit and debris with "Vactor" including connecting manholes, hauling and legal disposal of cleaning debris, and all incidental work not specifically included for payment elsewhere.

Item No. 16 – Furnish and Install Cured-in-Place Pipe Liner in Existing (8 to 10)-inch Sewer or Drain Pipe

A. Measurement

Measurement for payment will be based on the actual linear feet of cured-in-place pipe liner (approximately 8 to 10-inch inside diameter) installed, testing, inspected, and as approved by the Engineer, as measured from the inside face to inside face of structures or the points of termination of the cured-in-place liner.

B. Payment

Payment for Item No. 16 – Furnish and Install Cured-in-Place Pipe Lining in Existing (8-10) -inch Sewer or Drain Pipe will be based on the unit price bid for this item in the proposal. Under the Unit Price for this item, the Contractor shall furnish all labor, materials, tools, equipment, and incidentals required to install a cured-in-place pipe liner in sewer or drain pipes (approximately 8 to 10-inch inside diameter). The work includes all items included in this Section's Paragraph 1.1B, above, as well as bypass pumping, flow handling, traffic signage and worksite protection, homeowner notification and coordination; cutting or grounding down existing services protruding into pipe; field verifying inside dimensions of the existing pipe, cutting or trimming protruding services from inside pipe as required, furnishing and installing tight fitting water proof pipe liner formed of non-woven felt tube impregnated with thermoset resin suitable for use in saltwater conditions; cutting and sealing pipe liner at manhole connections to provide watertight pipe and manhole trough seals, cutting and reopening sewer services from inside the sewer or drain pipe by means of remote controlled cutting device and removing cut pieces, completing follow-up CCTV pipeline inspection after liner is cured and services are cut out, certified testing of installed pipe samples, and all incidental work not specifically included for payment elsewhere. Pipeline cleaning and CCTV inspection before cured-in-place pipe liner installation is included for payment under Bid Item Nos. 12-15, follow-up CCTV inspection is included in Item No. 16.

Item No. 17 – Furnish and Install Cured-in-Place Pipe Liner in Existing (12 to 15)-inch Sewer or Drain Pipe

A. Measurement

Measurement for payment will be based on the actual linear feet of cured-in-place pipe liner (approximately 12 to 15-inch inside diameter) installed, testing, inspected, and as approved by the Engineer, as measured from the inside face to inside face of structures or the points of termination of the cured-in-place liner.

B. Payment

Payment for Item No. 17 – Furnish and Install Cured-in-Place Pipe Lining in Existing (12 to 15)-inch Sewer or Drain Pipe will be based on the unit price bid for this item in the proposal. Under the Unit Price for this item, the Contractor shall furnish all labor, materials, tools, equipment, and incidentals required to install a cured-in-place pipe liner in sewer or drain pipes (approximately 12 to 15-inch inside diameter). The work includes all items included in this Section's Paragraph 1.1B, above, as well as bypass pumping, flow handling, traffic signage and worksite protection, homeowner notification and coordination; cutting or grounding down existing services protruding into pipe; field verifying inside dimensions of the existing pipe, cutting or trimming protruding services from inside pipe as required, furnishing and installing tight fitting water proof pipe liner formed of non-woven felt tube impregnated with thermoset resin suitable for use in saltwater conditions; cutting and sealing pipe liner at manhole connections to provide watertight pipe and manhole trough seals, cutting and reopening sewer services from inside the sewer or drain pipe by means of remote controlled cutting device and removing cut pieces, completing follow-up CCTV pipeline inspection after liner is cured and services are cut out, certified testing of installed pipe samples, and all incidental work not specifically included for payment elsewhere. Pipeline cleaning and CCTV inspection before cured-in-place pipe liner installation is included for payment under Bid Item Nos. 13 or 15, follow-up CCTV inspection is included in Item No. 17.

Item No. 18 – Furnish and Install Cured-in-Place Pipe Liner in Existing 18-inch and Non-Round Sewer or Drain Pipe

A. Measurement

Measurement for payment will be based on the actual linear feet of cured-in-place pipe liner (approximately 18-inch inside diameter or non-round pipe with both diameters greater than 12-inch) installed, testing, inspected, and as approved by the Engineer, as measured from the inside face to inside face of structures or the points of termination of the cured-in-place liner.

B. Payment

Payment for Item No. 18 – Furnish and Install Cured-in-Place Pipe Lining in Existing 18-inch and Non-Round Sewer or Drain Pipe will be based on the unit price bid for this item in the proposal. Under the Unit Price for this item, the Contractor shall furnish all labor, materials, tools, equipment, and incidentals required to install a cured-in-place pipe liner in sewer or drain pipes (approximately 18-inch inside diameter or non-round). The work includes all items included in this Section's Paragraph 1.1B, above, as well as bypass pumping, flow handling, traffic signage and worksite protection, homeowner notification and coordination; cutting or grounding down existing services protruding into pipe; field verifying inside dimensions of the existing pipe, cutting or trimming protruding services from inside pipe as required, furnishing and installing tight fitting water proof pipe liner formed of non-woven felt tube impregnated with thermoset resin suitable for use in saltwater conditions; cutting and sealing pipe liner at manhole connections to provide watertight pipe and manhole trough seals, cutting and reopening sewer services from inside the sewer or drain pipe by means of remote controlled cutting device and removing cut pieces, completing follow-up CCTV pipeline inspection after liner is cured and services are cut out, certified testing of installed pipe samples, and all incidental work not specifically included for payment elsewhere. Pipeline cleaning and CCTV inspection before cured-in-place pipe liner installation is included for payment under Bid Item Nos. 13 or 15, follow-up CCTV inspection is included in Item No. 18.

Item No. 19 – Furnish and Install Cured-in-Place Spot Liner in Existing (6 to 8)-inch Sewer or Drain Pipe (minimum 4-foot length)

A. Measurement

Measurement for payment will be based on the actual linear feet of cured-in-place spot repair liner (approximately (6 to 8)-inch inside diameter) installed, testing, inspected, and as approved by the Engineer, as measured from the inside face to inside face of structures or the points of termination of the cured-in-place spot liner. Each spot repair liner will be measured at a minimum of 4-feet in length.

B. Payment

Payment for Item No. 19 – Furnish and Install Cured-in-Place Spot Liner in Existing (6 to 8)-inch Sewer or Drain Pipe (minimum 4-foot length) will be based on the unit price bid for this item in the proposal. Under the Unit Price for this item, the Contractor shall furnish all labor, materials, tools, equipment, and incidentals required to install a cured-in-place pipe spot liner in sanitary sewer pipes of (approximately (6 to 8)-inch inside diameter). The work includes all items included in this Section's Paragraph 1.1B, above, as well as bypass pumping, flow handling, traffic signage and worksite protection, homeowner notification and coordination; cutting or grounding down existing services protruding into pipe; field verifying inside dimensions of the existing pipe, furnishing and installing tight fitting water proof pipe liner formed of non-woven felt tube impregnated with thermoset resin suitable for use in saltwater conditions; installing the spot liner in target pipe at distances up to 200-feet upstream or downstream of nearest manhole access; cutting and sealing pipe liner at manhole connections to provide watertight pipe and manhole trough seals, cutting and reopening sewer services from inside the sewer or drain pipe by means of remote controlled cutting device and removing cut pieces, completing follow-up CCTV pipeline inspection after liner is cured and services are cut out, certified testing of installed pipe samples, and all incidental work not specifically included for payment elsewhere. Pipeline cleaning and CCTV inspection before cured-in-place pipe liner installation is included for payment under Bid Item Nos. 12 or 14, follow-up CCTV inspection is included in Item No. 19.

Item No. 20 – Furnish and Install Cured-in-Place Spot Repair in Existing 12-inch Sewer or Drain Pipe (minimum 4-foot length)

A. Measurement

Measurement for payment will be based on the actual linear feet of cured-in-place spot repair liner (approximately 12-inch inside diameter) installed, testing, inspected, and as approved by the Engineer, as measured from the inside face to inside face of structures or the points of termination of the cured-in-place spot liner. Each spot repair liner will be measured at a minimum of 4-feet in length.

B. Payment

Payment for Item No. 20 – Furnish and Install Cured-in-Place Spot Repair in Existing 12-inch Sewer or Drain Pipe (minimum 4-foot length) will be based on the unit price bid for this item in the proposal. Under the Unit Price for this item, the Contractor shall furnish all labor, materials, tools, equipment, and incidentals required to install a cured-in-place pipe spot liner in sanitary sewer pipes of (approximately 12-inch inside diameter). The work includes all items included in this Section's Paragraph 1.1B, above, as well as bypass pumping, flow handling, traffic signage and worksite protection, homeowner notification and coordination; cutting or grounding down existing services protruding into pipe; field verifying inside dimensions of the existing pipe, furnishing and installing tight fitting water proof pipe liner formed of non-woven felt tube impregnated with thermoset resin suitable for use in saltwater conditions; installing the spot liner in target pipe at distances up to 200-

feet upstream or downstream of nearest manhole access; cutting and sealing pipe liner at manhole connections to provide watertight pipe and manhole trough seals, cutting and reopening sewer services from inside the sewer or drain pipe by means of remote controlled cutting device and removing cut pieces, completing follow-up CCTV pipeline inspection after liner is cured and services are cut out, certified testing of installed pipe samples, and all incidental work not specifically included for payment elsewhere. Pipeline cleaning and CCTV inspection before cured-in-place pipe liner installation is included for payment under Bid Item Nos. 13 or 15, follow-up CCTV inspection is included in Item No. 20.

Item No. 21 – Furnish and Install Cured-in-Place Spot Repair in Existing 18-inch Sewer or Drain Pipe (minimum 4-foot length)

A. Measurement

Measurement for payment will be based on the actual linear feet of cured-in-place spot repair liner (approximately 18-inch inside diameter) installed, testing, inspected, and as approved by the Engineer, as measured from the inside face to inside face of structures or the points of termination of the cured-in-place spot liner. Each spot repair liner will be measured at a minimum of 4-feet in length.

B. Payment

Payment for Item No. 21 – Furnish and Install Cured-in-Place Spot Repair in Existing 18-inch Sewer or Drain Pipe (minimum 4-foot length) will be based on the unit price bid for this item in the proposal. Under the Unit Price for this item, the Contractor shall furnish all labor, materials, tools, equipment, and incidentals required to install a cured-in-place pipe spot liner in sanitary sewer pipes of (approximately 12-inch inside diameter). The work includes all items included in this Section's Paragraph 1.1B, above, as well as bypass pumping, flow handling, traffic signage and worksite protection, homeowner notification and coordination; cutting or grounding down existing services protruding into pipe; field verifying inside dimensions of the existing pipe, furnishing and installing tight fitting water proof pipe liner formed of non-woven felt tube impregnated with thermoset resin suitable for use in saltwater conditions; installing the spot liner in target pipe at distances up to 200-feet upstream or downstream of nearest manhole access; cutting and sealing pipe liner at manhole connections to provide watertight pipe and manhole trough seals, cutting and reopening sewer services from inside the sewer or drain pipe by means of remote controlled cutting device and removing cut pieces, completing follow-up CCTV pipeline inspection after liner is cured and services are cut out, certified testing of installed pipe samples, and all incidental work not specifically included for payment elsewhere. Pipeline cleaning and CCTV inspection before cured-in-place pipe liner installation is included for payment under Bid Item Nos. 13 or 15, follow-up CCTV inspection is included in Item No. 21.

Item No. 22 – Manhole Rehabilitation, Clean, Grout, Waterproof

A. Measurement

Measurement for payment will be based on the vertical feet of manhole cleaned, repaired, and sealed; as directed and as measured by the Engineer, from the lowest pipe invert (or pay limits of Bid Item No. 24) to the top of sealed area limits identified by the Engineer. The portion of manholes sealed as part of Bid Items No. 24 or 25 will not be measured for payment.

B. Payment

Payment for Item No. 22 – Manhole Rehabilitation, Clean, Grout, Waterproof shall be based on the unit price bid for this item in the proposal. Under the Unit Price bid for this item, the Contractor shall furnish all labor, materials, tools, equipment, and incidentals

required to modify and rehabilitate manholes complete, as indicated on the Drawings and as specified or as directed by the Engineer. The work includes all items included in this Section's Paragraph 1.1B, above, as well as (pre and post) digital construction photographs, bypass flow piping or pumping; chipping and chiseling away loose mortar or defective materials; power washing and cleaning entire manhole with "Vactor" removal and legal disposal of cleanings; drilling and injecting exterior epoxy grout manhole sealant suitable for use in saltwater conditions around voids, visible leaks, and evidence of previous leaks in and around inverts, tables, shelves, pipe connections, and joints in locations as directed by Engineer; cutting and trimming protruding pipe connections and "through pipes" as directed; application of mortar to fill voids and missing material; application of internal and external grout and sealant and waterproofing suitable for use in saltwater conditions to the limits identified by the Engineer; and all incidental work not included for payment elsewhere.

Item No. 23 – Manhole Rehabilitation, Replace Frame and Cover

A. Measurement

Measurement for payment will be based on the number of new castings (complete sets of frames and covers or grates) installed on existing sewer or drain structures as directed by the Engineer, and as measured and approved by the Engineer. A frame and cover/grate set shall be measured as a single casting. Castings provided and installed to replace castings damaged by construction or as part of new or replacement manhole bid items will not be measured for payment. Furnishing and delivering new cast iron frames and covers/grates will be measured for payment under Bid Item No. 26.

B. Payment

Payment for Item No. 23 – Manhole Rehabilitation, Replace Frame and Cover shall be based on the unit price bid for this item in the proposal. Under the Unit Price bid for this item, the Contractor shall remove existing frames and covers and furnish, deliver, store, and protect new manhole or catch basin castings (frames and covers or grates) complete, as indicated or specified or as directed by the Engineer. The work includes all items included in this Section's Paragraph 1.1B, above, as well as cleaning debris from manholes; saw-cutting, removal and stockpiling the existing castings, and/or steel plates covering structures (including those currently buried), delivery of existing castings to Owner if requested, removal and reconstruction of up to 6 vertical inches of existing masonry or concrete structure as directed by Engineer, installing new castings (manholes labeled "sewer" or "drain", or catch basin grates) as directed, and constructing concrete collars around frames to base or binder grade; installation and removal of temporary pavement, installation of permanent pavement if outside of pipe trench payment width, and all incidental work not included for payment elsewhere. Reconstructing structure in addition to 6 vertical inches will be measured for payment under Bid Item No. 25.

Item No. 24 – Manhole Rehabilitation, Build/Rebuild Invert and Bench

A. Measurement

Measurement for payment will be based on the number of existing manholes rehabilitated and sealed, with new or rebuilt inverts and benches, as directed by the Engineer and as measured and approved by the Engineer. Manhole rehabilitation and sealing completed as part of Bid Item No. 22 (without building or rebuilding inverts and benches) will not be measured for payment. Structures constructed/reconstructed as part of Bid Item Nos. 28 will not be measured for payment.

B. Payment

Payment for Item No. 24 – Manhole Rehabilitation, Build/Rebuild Invert and Bench shall be based on the unit price bid for this item in the proposal. Under the Unit Price bid for this item, the Contractor shall furnish all labor, materials, tools, equipment, and incidentals required to modify and rehabilitate manholes complete, as indicated on the Drawings and as specified or as directed by the Engineer. The work includes all items included in this Section's Paragraph 1.1B, above, as well as (pre and post) construction photographs; bypass flow piping or pumping; removal and disposal of existing invert, bench, tables, and shelves; chipping and chiseling away loose mortar or defective materials; power washing and cleaning entire manhole with "Vactor"; drilling and injecting exterior epoxy grout manhole sealant around voids, visible leaks, and evidence of previous leaks in and around inverts, tables, shelves, pipe connections, and joints including entire manhole from the invert to 3' above the new table for brick or block manholes or to the lowest joint for pre-cast manholes; cutting and trimming "through pipes" and other pipe connections as directed; application of mortar to fill voids and missing material, build/rebuild brick and mortar invert, bench, and tables; applying internal and external grout and sealant and waterproofing from the invert to 3-feet above new table; and all incidental work not included for payment elsewhere.

Item No. 25 – Reconstruct Sewer or Drain Structures

A. Measurement

Measurement for payment will be based on the vertical feet of sewer, drain, or water structures reconstructed as measured and approved by the Engineer. Measurements for payment will be rounded up to the nearest 6-inches (0.5 vertical feet) of structures reconstructed as directed. Removal, reconstruction, or modification of sewer or drain structures as required to plug existing pipes as required in Bid Item No. 27 or manhole rehabilitation bid item No. 22 or 24, (including up to 6 vertical inches of structure rehabilitation required in Bid Item No. 23) will not be measured for payment.

B. Payment

Payment for Item No. 25 – Reconstruct Sewer or Drain Structures shall be based on the unit price bid for this item in the proposal. Under the Unit Price bid for this item, the Contractor shall furnish all labor, materials, tools, equipment, and incidentals required to reconstruct sewer or drain structures, as indicated on the Drawings and as specified or as directed by the Engineer. The work includes all items included in this Section's Paragraph 1.1B, above, as well as cleaning debris from structures with Vactor; trimming protruding pipe connections, saw-cutting and disposal of removed portions of sewer, drain, or water structure; removal and stockpiling the existing castings (including those currently buried); removal and reconstruction or construction of portion of existing masonry or concrete structures of various shapes and diameters as directed by Engineer, including reconstructing structures with mortared masonry block and brick courses, precast concrete rings, cones, flat tops; applying full coat of grout waterproofing sealant to the interior of all reconstructed masonry structures; removal and resetting existing castings with bricks and mortar as required and constructing concrete collars around frames to base or binder grade as directed; and all incidental work not included for payment elsewhere. Providing and delivering new or replacement (sewer or drain) manhole or catch basin castings to be set/reset will be measured for payment under Bid No. 26.

Item No. 26 – Furnish and Deliver New Manhole or Catch Basin Castings

A. Measurement

Measurement for payment will be based on the number of manhole or catch basin castings (complete sets of frames and covers or grates) provided and delivered to the job site or Owner, as directed and as measured and approved by the Engineer. A frame and cover/grate set shall be measured as a single casting. A frame and double grate set for double catch basin will be measured as two castings. Castings provided and installed to replace castings damaged by construction will not be measured for payment.

B. Payment

Payment for Item No. 29 – Furnish and Deliver New Manhole or Catch Basin Castings shall be based on the unit price bid for this item in the proposal. Under the Unit Price bid for this item, the Contractor shall provide and deliver H20 rated cast iron “Sewer” or “Drain” or “Water” manhole frames and covers or catch basin frames and grates with bituminous coating complete, as indicated on the Drawings and as specified or as directed by the Engineer. The work includes all items included in this Section’s Paragraph 1.1.B, above, as well as delivery and storage of frames and covers/grates and double catch basin grates as indicated, and re-delivery to the Owner or site of proposed installation, and all incidental work not included for payment elsewhere.

Item No. 27 – Furnish and Install Brick and Mortar Plugs in Pipes

A. Measurement

Measurement for payment will be based on the number of brick and mortar plugs (8-inches in diameter or greater) installed in pipes as directed by Engineer, and as measured and approved by the Engineer.

B. Payment

Payment for Item No. 27 – Furnish and Install Brick and Mortar Plugs in Pipes will be based on the unit price bid for this item in the proposal. Under the Unit Price for this item, the Contractor shall furnish all labor, materials, tools, equipment, and incidentals required to furnish and install brick and mortar plugs in pipes, as indicated on the Drawings and as specified or as directed by the Engineer. The work includes all items included in this Section’s Paragraph 1.1B, above, as well as saw cutting and excavation to locate and expose pipe if required, field verification of internal and external existing pipe diameter; cutting existing pipe to be plugged if required, removal and legal disposal or removed pipe section, installing brick and mortar plugs to completely seal pipe at least 12-inches into pipe, fill voids in structure wall around plugged pipe if required, and all incidental work not specifically included for payment elsewhere.

Item No. 28 – 2-inch Temporary Bituminous Concrete Pavement

A. Measurement

Measurement for payment will be based on the actual square yards of 2-inch minimum compacted thickness bituminous concrete binder course placed within the trench payment limits, as directed and measured by the Engineer as directed. Temporary pavement placed outside the trench payment limits and temporary pavement placed without the direction of the Engineer will not be measured for payment.

B. Payment

Payment for Item No. 28 – 2-inch Temporary Bituminous Concrete Pavement will be based on the Unit Price bid for this item in the proposal. Under the Unit Price for this item, the Contractor shall furnish all labor, materials, tools, equipment, and incidentals required to furnish and install 2-inch minimum compacted thickness of temporary

bituminous concrete binder course within the trench payment limits, curb to curb, or behind curb line within the project area as directed by the Engineer. The work includes all items included in this Section's Paragraph 1.1.B, above, as well as saw cutting pavement to create smooth edges and remove all pavement damaged by construction, removal and disposal of cut-back pavement and soil to required depth, restoring and re-grading the existing gravel base course, compaction, raising and resetting existing castings and boxes to grade, power sweeping adjacent road way and edges of pavement, power sweeping; installation of 2-inch minimum compacted thickness of temporary bituminous concrete binder course with paving machine or by hand as directed by the Engineer covering all exposed areas each week, replace all existing pavement markings with temporary marking paint, and all incidental work not specifically included for payment under other items.

Item No. 29 – 4-inch Permanent Bituminous Concrete Pavement in Trenches

A. Measurement

Measurement for payment will be based on the actual square yards of 4-inch minimum compacted thickness permanent bituminous concrete binder course placed within the trench payment limits or as directed and measured by the Engineer. Pavement placed outside the trench limits of payment will not be measured for payment.

B. Payment

Payment for Item No. 29 – 4-inch Permanent Bituminous Concrete Pavement in Trenches will be based on the Unit Price bid for this item in the proposal. Under the Unit Price for this item, the Contractor shall furnish all labor, materials, tools, equipment, and incidentals required to furnish and install 4-inch minimum compacted thickness of permanent bituminous concrete binder course (or binder and surface course as directed) within the trench payment limits or as directed by the Engineer. The work includes all items included in this Section's Paragraph 1.1.B, above, as well as saw cutting pavement at the project limits or at 1-foot offset to limits of temporary trench pavement to create smooth edges and removal all pavement damaged by construction; removal and disposal of cut-back pavement and temporary trench pavement and soil to required depth; restoring and re-grading the gravel base course, compaction testing; raising and resetting castings and boxes to grade; constructing exterior concrete collars surrounding masonry and frame to bottom depth of proposed binder; adjusting all valve and service boxes to proposed grades with exterior concrete collars; power sweeping, applying tack coat to saw cut pavement edges; installation of 4-inch minimum compacted thickness of bituminous concrete binder course (or binder and surface course) in two courses; application of emulsion to entire road surface prior to each binder course and to surface joints after paving is completed; replace all existing pavement markings with temporary marking paint, and all incidental work not specifically included for payment under other items.

END OF SECTION 01025

SECTION 01040

PROJECT COORDINATION

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of Contract, including General and Supplementary Conditions and other Division 1 Specification Sections, apply to this section.

1.2 SUMMARY

- A. This section specifies administrative and supervisory requirements necessary for Project coordination including, but not necessarily limited to:
 - 1. Coordination.
 - 2. Administrative and supervisory personnel.
 - 3. General installation provisions.
 - 4. Cleaning and protection.
- B. Progress meetings and preconstruction conferences are included in Section 01200 – PROJECT MEETINGS.
- C. Requirements for the Contractor's Construction Schedule are included in Section 01300 - SUBMITTAL PROCEDURES.

PART 2 - PRODUCTS (NOT USED)

PART 3 - EXECUTION

3.1 GENERAL INSTALLATION PROVISIONS

- A. Inspection of Conditions: Inspect the conditions under which Work is to be performed. Do not proceed until unsatisfactory conditions have been corrected in an acceptable manner, and at no additional cost to the Owner.
- B. Manufacturer's Written Instructions: Comply with manufacturer's written installation instructions and recommendations, to the extent that those instructions and recommendations are more explicit or stringent than requirements contained in the Contract Documents.

- C. Inspect materials or equipment immediately upon delivery and again prior to installation. Reject damaged and defective items, and at no additional cost to the Owner.
- D. Provide attachment and connection devices and methods for securing work. Secure work true to line and level. Allow for expansion and utility movement.
- E. Recheck measurements and dimensions before starting installation or erection.
- F. Install each component during weather conditions and Project status that will ensure the best possible results. Isolate each part of the completed construction from incompatible material to prevent deterioration.
- G. Coordinate temporary enclosures with required inspections and tests, to minimize the necessity of uncovering completed construction for that purpose.

3.2 CLEANING AND PROTECTION

- A. During handling and installation, clean and protect construction in progress and adjoining materials in place. Install protective covering to ensure protection from damage or deterioration.
- B. Clean and maintain completed construction as frequently as necessary through the remainder of the construction period.
- C. Limiting Exposures: Supervise construction activities to ensure that no part of the construction completed or in progress, is subject to harmful, dangerous, damaging, or otherwise deleterious exposure during the construction period. Where applicable, such exposures include, but are not limited to, the following:
 - 1. Excessive static or dynamic loading.
 - 2. Excessive internal or external pressures.
 - 3. Excessively high or low temperatures.
 - 4. Air contamination or pollution.
 - 5. Water or ice.
 - 6. Solvents.
 - 7. Chemicals.
 - 8. Heavy traffic.
 - 9. Misalignment.
 - 10. Unprotected storage.
 - 11. Improper shipping or handling.
 - 12. Theft.
 - 13. Vandalism.

END OF SECTION 01040

SECTION 01045

CUTTING, CORING AND PATCHING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of Contract, including General and Supplementary Conditions and other Division 1 Specification Sections, apply to this section.

1.2 SUMMARY

- A. This section specifies administrative and procedural requirements for cutting, coring, rough and finish, and patching.
- B. Refer to other sections for specific requirements and limitations applicable to cutting and patching individual parts of the Work.
 - 1. Requirements of this section do not apply to mechanical and electrical installations.
- C. Demolition of selected portions of buildings or structures for alterations is specified in Section 02050 – DEMOLITION AND ALTERATION.

1.3 SUBMITTALS

- A. For informational purposes only, submit proposed cutting and patching well in advance of the time cutting and patching will be performed. Include the following information, as applicable:
 - 1. Describe the extent of cutting and patching required and how it is to be performed; indicate why it cannot be avoided.
 - 2. Describe anticipated results in terms of changes to existing construction; include changes to structural elements and operating components.
 - 3. List products to be used and firms or entities that will perform Work.
 - 4. Indicate dates when cutting and patching is to be performed.
 - 5. List utilities that will be disturbed or affected, including those that will be relocated and those that will be temporarily out-of-service. Indicate how long service will be disrupted.
 - 6. Where cutting and patching involves addition of reinforcement to structural elements, submit details to show how reinforcement is integrated with the original structure.
 - 7. Review by the Engineer prior to proceeding with cutting and patching does not waive the Engineer's right to later require complete removal and replacement of a part of the Work found to be unsatisfactory.
 - 8. Refer to Paragraph 1.4 - Quality Assurance and submit the information specified.

1.4 QUALITY ASSURANCE

- A. No structural members shall be cut without the approval of the Engineer. No holes shall be drilled in beams or other structural members without the approval of the Engineer.
- B. Requirements for Structural Work: Do not cut and patch structural elements in a manner that would reduce their load-carrying capacity or load-deflection ratio.
- C. Operational and Safety Limitations: Do not cut and patch operating elements or safety related components that would result in reducing their capacity to perform as intended, or result in increased maintenance, or decreased operational life or safety.

PART 2 - PRODUCTS

2.1 MATERIALS

- A. Provide materials that are identical to existing materials. If identical materials are not available or cannot be used where exposed surfaces are involved, use materials that match existing adjacent surfaces to the fullest extent possible. Use materials whose installed performance will equal or surpass that of existing materials.
- B. Concrete and grout for rough patching shall be as specified in Divisions 3 and 4.

PART 3 - EXECUTION

3.1 INSPECTION

- A. Before cutting existing surfaces, examine surfaces to be cut and patched and conditions under which cutting and patching is to be performed. Take corrective action before proceeding, if unsafe or unsatisfactory conditions are encountered.
 - 1. Before proceeding, meet at the site with parties involved in cutting and patching, including mechanical and electrical trades. Review areas of potential interference and conflict. Coordinate procedures and resolve potential conflicts before proceeding.

3.2 PREPARATION

- A. Temporary Support and Bracing: Provide temporary support and bracing of area to be cut, prior to start of cutting.
- B. Protection: Protect existing construction during cutting and patching to prevent damage. Provide protection from adverse weather conditions for portions of the

Project that might be exposed during cutting and patching operations.

- C. Avoid interference with use of adjoining areas or interruption of free passage to adjoining areas.
- D. Take all precautions to avoid cutting existing pipe, conduit or ductwork serving the building, but scheduled to be removed or relocated until provisions have been made to bypass them.
- E. Check area during sawing operations for partial cracking and provide additional support and bracing to prevent a partial release of cut area during sawing operations.
- F. Provide equipment of adequate size to remove cut panels.

3.3 PERFORMANCE

- A. General: Employ skilled workmen to perform cutting and patching. Proceed with cutting and patching at the earliest feasible time and complete without delay.
 - 1. Cut existing construction to provide for installation of other components or performance of other construction activities and the subsequent fitting and patching required to restore surfaces to their original condition.
 - 2. All cutting and coring shall be performed in such a manner as to limit the extent of patching.
- B. Cutting: Cut existing construction using methods least likely to damage elements to be retained or adjoining construction. Where possible review proposed procedures with the original installer; comply with the original installer's recommendations.
 - 1. In general, where cutting is required use hand or small power tools designed for sawing or grinding, not hammering and chopping. Cut holes and slots neatly to size required with minimum disturbance of adjacent surfaces. Temporarily cover openings when not in use.
 - 2. To avoid marring existing finished surfaces, cut or drill from the exposed or finished side into concealed surfaces.
 - 3. Cut through concrete and masonry using a cutting machine such as a carborundum saw or diamond core drill.
 - 4. Comply with requirements of applicable sections of Division 2 where cutting and patching requires excavating and backfilling.
 - 5. By-pass utility services such as pipe or conduit, before cutting, where services are shown or required to be removed, relocated or abandoned. Cut-off pipe or conduit in walls or partitions to be removed. Cap, valve or plug and seal the remaining portion of pipe or conduit to prevent entrance of moisture or other foreign matter after by-passing and cutting.
 - 6. Provide full control of slurry generated by sawing operations on both sides of wall.

7. When cutting a reinforced concrete wall, the cutting shall be done so as not to damage bond between the concrete and reinforcing steel left in structure. Cut shall be made so that steel neither protrudes nor is recessed from face of the cut.

C. Coring

1. All holes cut through concrete and masonry walls, slabs or arches, structures, or pipes shall be core drilled unless otherwise approved.
2. If holes are cored through floor slabs they shall be drilled from below.
3. Rough patching shall be such as to bring the cut or cored area flush with existing construction unless otherwise shown. Finish patching shall match existing surfaces as approved.
4. Coring shall be performed with an approved non-impact rotary tool with diamond core drills. Size of holes shall be suitable for pipe, conduit, sleeve, equipment or mechanical seals to be installed.
5. All equipment shall conform to OSHA standards and specifications pertaining to plugs, noise and fume pollution, wiring and maintenance.
6. Provide protection for existing equipment, utilities and critical areas against water or other damage caused by drilling operation.
7. Slurry or tailings resulting from coring operations shall be vacuumed or otherwise removed from the area following drilling.

3.4 CLEANING

- A. Thoroughly clean areas and spaces where cutting and patching is performed or used as access. Remove completely paint, mortar, oils, putty and items of similar nature. Thoroughly clean piping, conduit and similar features before painting or other finishing is applied. Restore damaged pipe covering to its original condition.

END OF SECTION 01045

SECTION 01050

FIELD ENGINEERING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this section.

1.2 SUMMARY

- A. This section includes the following:
 - 1. Examination of site and conditions of construction.
 - 2. Establishment of lines, grades, and easements.
 - 3. Connections to existing facilities.
 - 4. Restoration and protection of public and private property.
- B. Related section includes the following:
 - 1. Section 02524 – CURBS, WALKS, AND DRIVEWAYS

1.3 SUBMITTALS

- A. Shop Drawings: Submit the following in accordance with Section 01300 - SUBMITTAL PROCEDURES:
 - 1. As-Built Drawings: The Contractor shall be responsible for maintaining two sets of redline "as-built locations and dimensions of work". The As-Built Drawings shall be submitted to the Owner at substantial completion of the project.
 - 2. Contractor shall insure that all subcontractors maintain and prepare As-Built drawings for their respective areas of work. Contractor shall review all subcontractor As-Built information to insure accuracy and completeness. Subcontractor's As-Built information shall be incorporated into the drawings described in Paragraph 1.3, A.1.
 - 3. As-Built drawings shall be professionally prepared. All buried utility lines and structures shall be located by a minimum of two (2) swing-ties. Ties shall be taken from permanent structure or landmark.

4. The Contractor shall submit copies of field records and record drawings each month with project invoices. Field data shall be updated each month as applicable. Failure to submit or maintain As-Built drawings shall be cause for rejection or reduction of Partial Payment requests. Payment reduction shall be as determined by the Engineer, without penalty to the Owner.

1.4 PROJECT/SITE CONDITIONS:

A. Environmental Requirements:

1. Unfavorable Construction Conditions:

- a. During unfavorable weather, wet ground, or other unsuitable construction conditions, confine operations to work which will not be affected adversely by such conditions.
- b. No portion of Work shall be constructed under conditions which adversely affect quality or efficiency thereof, unless special means or precautions are taken to perform Work in manner acceptable to the Engineer.

B. Field Measurements:

1. Lines and Grades:

- a. All Work shall be done to lines, grades, and elevations indicated on drawings or specified herein.
- b. Basic vertical control points have been established or designated by the Engineer. Contractor shall be responsible for maintaining or subsequently replacing these controls to the satisfaction of the Engineer if these controls are disturbed. The Contractor shall be responsible for verifying all vertical control information that is used.
 - (1) Points shall be used as datum for work.
 - (2) Contractor shall be responsible for transferring all lines and grades from basic survey control points.
- c. Contractor to perform all additional survey, layout, and measurement work.

- (1) The Contractor shall provide survey work by a firm having successfully completed at least two projects of similar size and complexity within the last five years, and who shall employ experienced personnel and provide adequate supervision to satisfaction of the Engineer at all times when operations are in progress.
 - (2) Surveyor shall be a registered land surveyor in the location of the project.
 - d. Keep the Engineer informed, in writing, two weeks in advance, of times and places at which work is to be performed, so that horizontal and vertical control points may be established and any checking deemed necessary by the Engineer may be performed.
 - e. Remove and reconstruct Work which is improperly located as determined by the Engineer and at no additional cost to the Owner.
2. Easements and Rights-of-Way:
- a. Easements and rights-of-way for utilities, if required, will be provided by the Owner.
 - b. Confine construction operations within limits indicated on drawings and/or within limits of easements or public ways.
 - c. Place construction tools, equipment, excavated materials, and pipeline materials and supplies, so as to cause least possible damage to property and interference with traffic.

PART 2 - PRODUCTS

2.1 MATERIALS

- A. Use new materials in restoration of existing facilities except where soil materials and plants may be reused, as appropriate.

PART 3 - EXECUTION

3.1 EXAMINATION

- A. Examination of Site and Verification of Conditions:
 1. Before starting operations, examine site to become acquainted with conditions to be encountered.
 2. Verify exact locations of sewers, water mains, gas mains, above or below ground electrical wires, other utilities, conduits and structures which may interfere with work.

3. Perform all test pit excavations prior to any pipelaying operations. No pipe trenching will be allowed within 150 feet of a designated test pit until the test pit has been excavated. Contractor shall also perform test pit excavations in locations where he feels information is required to perform the work.

3.2 APPLICATION

A. Restoration and Protection of Public and Private Property:

1. Protect, shore, brace, support, and maintain all underground pipes, conduits, drains, and other underground construction uncovered or otherwise affected by construction operations.
2. Restore all public and private property including pavement, surfacing, curbs, walks, utility poles, guy wires, fences, and other surface structures affected by construction operations, together with all sod and landscaping to their original condition or better, whether within or outside easements.

3.4 CONTRACT CLOSEOUT

A. Provide in accordance with Section 01700 – CONTRACT CLOSEOUT.

END OF SECTION 01050

SECTION 01060

PERMITS AND REGULATORY REQUIREMENTS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of Contract, including General and Supplementary Conditions and other Division 1 Specification Sections, apply to this section.

1.2 RELATED SECTIONS

- A. Section 00700 – GENERAL CONDITIONS.

1.3 REGULATORY AGENCIES

- A. Contractors shall comply with all laws, rules, regulations, and ordinances promulgated by any authority having jurisdiction over the Work.
- B. The contractor shall ensure that all other necessary permits from regulatory agencies and/or inspectional authorities having jurisdiction including but not limited to electrical, plumbing, blasting, road opening, buildings, pressure vessels etc. are obtained and paid for by the Contractor or its subcontractor(s) as appropriate and or required by the State Building code at no additional cost to the Owner. If the Work or portions of the Work are not covered by the State Building Code, Contractor shall obtain a written determination from the Division of Inspection that no permit is required. Within five days of receipt of the permit or the determination that no permit is required, Contractor shall provide a copy of said permit or determination to the Engineer.
- C. Contractor to provide notification and documentation to MassDEP about asbestos cement pipe work and removal.

1.4 PERMITS OBTAINED BY THE CONTRACTOR

- A. The Contractor or its subcontractor shall be responsible for obtaining and paying for at no additional cost to the Owner, all permits, licenses, fees, certifications or approvals required for the work of this contract, not specifically listed in Section 00800 – SUPPLEMENTARY CONDITIONS. Subcontractors shall be responsible for obtaining and paying for permits applicable to their particular trades. The Contractor's responsibility includes but is not limited to building, electrical and other permits required for his equipment, work force, and of particular operations (such as transportation and storage of explosives, fuel, chemical or material storage and air emission) and the like in the performance of the work or facility construction (such as cross-connection/backflow preventers, above or below ground tanks and piping installation and/or removal and

chemical handling). Proper equipment shall be installed, tested and maintained in accordance with local, state and federal requirements.

- D. The Contractor shall be responsible for obtaining and paying for, at no additional cost to the Owner include, but not limited to, the following (as necessary):

- 1. Local Road Opening Permit

- C. The Contractor shall also be responsible for scheduling and coordinating inspections and receipt of local or state permits/approvals/certifications for any tanks, piping and associated appurtenances which are constructed, installed, tested or removed as part of this Contract. Receipt of approvals for storage and use of test chemicals/gasses will be the responsibility of the Contractor.
- D. Construction Safety: Comply with the requirements of Article 6 of Section 00700 – GENERAL CONDITIONS.
- E. Comply with all the requirements of the Massachusetts Department of Environmental Protection, including, but not limited to DEP Backflow Prevention Permits.

1.5 PERMITS OBTAINED BY THE OWNER

- A. The Contractor or its subcontractor shall be responsible for obtaining and paying for at no additional cost to the Owner, all permits, licenses, fees, certifications approvals required for the work of this contract, not specifically listed in Section 00800 – SUPPLEMENTARY CONDITIONS. Subcontractors shall be responsible for obtaining and paying for permits applicable to their particular trades. The Contractor's responsibility includes but is not limited to building, electrical and other permits required for his equipment, work force, and of particular operations (such as transportation and storage of explosives, fuel, chemical or material storage and air emission) and the like in the performance of the work or facility construction (such as cross-connection/backflow preventers, above or below ground tanks and piping installation and/or removal and chemical handling). Proper equipment shall be installed, tested and maintained in accordance with local, state and federal requirements.

- B. The Contractor shall be responsible for obtaining and paying for, at no additional cost to the Owner include, but not limited to, the following (as necessary):

- 1. Local Road Opening Permit

- C. The Contractor shall also be responsible for scheduling and coordinating inspections and receipt of local or state permits/approvals/certifications for any tanks, piping and associated appurtenances which are constructed, installed, tested or removed as part of this Contract. Receipt of approvals for storage and use of test chemicals/gasses will be the responsibility of the Contractor.

D. Construction Safety: Comply with the requirements of Article 6 of Section 00700 – GENERAL CONDITIONS.

E. Comply with all the requirements of the Massachusetts Department of Environmental Protection, including, but not limited to DEP Backflow Prevention Permits.

PART 2- PRODUCTS (NOT USED)

PART 3 - EXECUTION (NOT USED)

END OF SECTION 01060

SECTION 01063

MISCELLANEOUS REQUIREMENTS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 1 Specification Sections, apply to this section.

1.2 PRECONSTRUCTION VIDEOS AND PHOTOGRAPHS

- A. The contractor shall take video and photographic survey of entire project area prior to the beginning of construction.

1.3 SUMMARY

- A. The Contractor shall conform to all miscellaneous requirements as herein specified.

1.4 TRAFFIC CONTROL

- A. For control of moderate traffic, the Contractor shall provide an adequate number of traffic control devices employed at his own expense.
- B. Whenever and wherever traffic is sufficiently congested, public safety is endangered, or as required by authorities having jurisdiction, coordinate and arrange uniformed police officers to direct traffic and to keep traffic off the area affected by construction operations. Such officers shall be in addition to the traffic control requirements specified in other provisions of the contract.
- C. Contractor shall be responsible for obtaining No Parking signs from the City and posting them 48 hours in advance of construction.

1.5 INTERFERENCE WITH EXISTING WORKS

- A. The Contractor shall at all times conduct his operations so as to interfere as little as possible with existing works. The Contractor shall develop a program, in cooperation with the Engineer and interested officials, which shall provide for the construction and putting into service of the new works in the most orderly manner possible. This program shall be adhered to except as deviations there from are expressly permitted. All work of connecting with, cutting into, and reconstructing existing pipes or structures shall be planned to interfere with the operation of the existing facilities for the shortest possible time when the demands on the facilities best permit such interference, even though it may be necessary to work outside of normal working hours to meet these requirements. Before starting work which will interfere with the operation of existing facilities, the Contractor shall do all possible preparatory work and shall see that all tools, materials, and equipment are made ready and at hand.

The Contractor shall make such minor modifications in the work relating to existing structures as may be necessary, without additional compensation.

- B. The Contractor shall be aware this project will be completed simultaneously with other construction projects, therefore; contractor will be required to provide weekly updates to project schedule and timelines, attend weekly project meetings, and coordinate construction scheduling and activities to allow access to work zones and job sites for all contractors.
- C. The Contractor shall have no claim for additional compensation by reason of delay or inconvenience in adapting his operations to meet the above requirements.

1.6 MAINTAINING FLOWS

- A. The Contractor shall plan and coordinate project to minimize service interruption to all residences, businesses and fire hydrants.
- B. The Contractor shall at his own expense, provide, maintain, and operate all temporary facilities such as dams, pumping equipment, conduits, and all other labor and equipment necessary to intercept the sewage flow before it reaches the points where it would interfere with his work, carry it past his work, and return it to the existing sewer below his work.
- C. The Contractor shall at his own cost, provide for the flow of sewers, drains and water courses interrupted during the progress of the work, and shall immediately cart away and remove all offensive matter. The entire procedure of maintaining existing flow shall be fully discussed with the Engineer well in advance of the interruption of any flow.

1.7 HYDRAULIC UPLIFT OF STRUCTURES

- A. The Contractor shall be responsible for the protection of all structures against hydraulic uplift until such structures have been accepted finally by the Owner.

1.8 BURIED UTILITY WARNING AND IDENTIFICATION TAPE

- A. Provide detectable aluminum foil plastic backed tape or detectable magnetic plastic tape manufactured specifically for warning and identification of buried piping. Tape shall be detectable by an electronic detection instrument. Provide tape in rolls, 3 inches minimum width, color coded for the utility involved with warning and identification imprinted in bold black letters continuously and repeatedly over entire tape length. Warning and identification shall be CAUTION BURIED WATER PIPING BELOW or similar. Use permanent code and letter coloring unaffected by moisture and other substances contained in trench backfill material. Bury tape with the printed side up at a depth of 12 inches below the top surface of earth or the top surface of the sub grade under pavements.

1.9 PROTECTION AGAINST ELECTROLYSIS

- A. Where dissimilar metals are used in conjunction with each other, suitable insulation shall be provided between adjoining surfaces so as to eliminate direct

contact and any resultant electrolysis. The insulation shall be bituminous impregnated felt, heavy bituminous coatings, nonmetallic separators or washers, or other acceptable materials.

1.10 WATERTIGHTNESS

- A. All structures, pipes, and equipment which are to contain water shall be watertight under all operating conditions for which they are intended. The Contractor shall furnish all labor, materials and equipment and do all work required by the Engineer to make all such parts of the work watertight, or to replace them if in the opinion of the Engineer any leakage is excessive. All such parts of the work filled with water for testing water tightness shall be left filled as ordered by the Engineer.

1.11 LAYOUT OF WORK

- A. The Contractor shall establish an initial "Construction Base Line" as indicated on the Drawings. Said base line shall be staked at 50 foot stations. The Engineer shall also provide bench mark information on the Drawings or separately in writing. The Contractor shall do all layout of the work from said base line and bench marks.
- B. The Contractor shall employ, at his own expense, a Registered Land Surveyor, approved by the Engineer and cause him to establish permanent bench marks during the entire progress of the work, to which easy access may be made to determine and insure all lines and grades and to verify same from time to time. The Contractor shall keep on the job a level and transit and allow the Owner's Representative and the Engineer unrestricted use of same at the work site. Such check shall not be considered as approval of the Contractor's work.
- C. The Contractor shall maintain the construction base line stakes at all times. Should stakes or marks be destroyed during the course of the work, by the Contractor or by others, the Contractor shall, at his own expense, provide the services of a Registered Land Surveyor, acceptable to the Engineer, to reestablish such stakes and marks.

1.12 CARE OF WATERCOURSES

- A. The Contractor shall maintain the flow in all watercourses, whether open channels or in pipes, in all sewers and other pipes interfered with in the line of work and convey the flow to a suitable point of discharge so as not to flow upon the work or create a nuisance. In the discharge of water removed from the excavations by pumping or by gravity similar precautions shall be observed. Fire hydrants on or adjacent to the work shall be kept operational and accessible to fire-fighting equipment at all times.

PART 2 - PRODUCTS (NOT USED)

PART 3 - EXECUTION (NOT USED)

END OF SECTION 01063

SECTION 01080

ABBREVIATIONS AND DEFINITIONS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS:

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 1 Specification Sections, apply to this section.

1.2 RELATED SECTIONS:

- A. Section 01090 – REFERENCE STANDARDS.

1.3 ABBREVIATIONS:

- A. Where any of the following abbreviations are used in the Contract Documents, they shall have the meaning set forth opposite each. Abbreviations for trade associations and standards organizations are listed in Section 01090 – REFERENCE STANDARDS.

AASHTO American Association of State Highway and Transportation Officials

ACI American Concrete Institute

AISC American Institute of Steel Construction

ANSI American National Standards Institute

ASCE American Society of Civil Engineers

ASTM American Society for Testing and Materials

AWWA American Water Works Association

Fed. Spec. Federal Specifications issued by the Federal Supply Service of the General Services Administration, Washington, D.C.

125-lb. ANSI American National Standard Institute for Cast-iron 250-lb. ANS
or Pipe Flanges and Flanged Fittings, Designation B16.1, for the
250 lb. ANSI Appropriate class

AWG American or Brown and Sharpe Wire Gage

NPT National Pipe Thread

OS&Y Outside screw and yoke

Stl. WG	U. S. Steel Wire, Washburn and Moen, American Steel and Wire or Roebbling Gage
USS Gage	United States Standard Gage
WOG	Water, Oil, Gas
WSP	Working steam pressure
AASHTO	American Association of State Highway and Transportation Officials
ACI	American Concrete Institute
AFBMA	Anti-Friction Bearing Manufacturers Association
AGA	American Gas Association
AGMA	American Gear Manufacturers Association
IEEE	Institute of Electrical and Electronics Engineers, Inc.
AISC	American Institute of Steel Construction
AMCA	Air Moving and Conditioning Association
ANSI	American National Standards Institute
API	American Petroleum Institute
ASCE	American Society of Civil Engineers
ASHRAE	American Society of Heating, Refrigerating and Air Conditioning Engineers
ASME	American Society of Mechanical Engineers
ASTM	American Society for Testing and Materials
AWPA	American Wood-Preservers' Association
AWWA	American Water Works Association
CS	Commercial Standard
IBR	Institute of Boiler and Radiator Manufacturers
IPS	Iron Pipe Size
JIC	Joint Industry Conference Standards

NBS	National Bureau of Standards
NEC	National Electrical Code; latest edition
NEMA	National Electrical Manufacturers Association
NFPA	National Fire Protection Association
SMACNA	Sheet Metal and Air Conditioning Contractors National Association, Inc.
Fed. Spec.	Federal Specifications issued by the Federal Supply Service of the General Services Administration, Washington, D.C.
125-lb. ANSI or 250-lb. ANSI	American National Standard Institute for Cast-Iron Pipe Flanges and Flanged Fittings, Designation B16.1, for the appropriate class
AWG	American or Brown and Sharpe Wire Gage
NPT	National Pipe Thread
OS&Y	Outside screw and yoke
STL. WG	U. S. Steel Wire, Washburn and Moen, American Steel and Wire or Roebling Gage
UL	Underwriters' Laboratories
USS Gage	United States Standard Gage
WOG	Water, Oil, Gas
WSP	Working steam pressure

1.4 DEFINITIONS:

- A. Wherever the words defined in this section or pronouns used in their stead occur in the Contract Documents, they shall have the meanings herein given.
- B. General: Basic Contract definitions are included in the Conditions of the Contract.
- C. Indicated: The term indicated refers to graphic representations, notes, or schedules on the Drawings, or other Paragraphs or Schedules in the Specifications, and similar requirements in the Contract Documents. Terms such as shown, noted, scheduled, and specified are used to help the reader locate the reference. There is no limitation on location.
- D. Directed: Terms such as directed, requested, authorized, selected, approved,

required, and permitted mean directed by the Engineer, requested by the Engineer, and similar phrases.

- E. Approve: The term approved, when used in conjunction, with the Engineer's action on the Contractor's submittals, applications, and requests, is limited to the Engineer's duties and responsibilities as stated in the Conditions of the Contract.
- F. Regulation: The term regulations includes laws, ordinances, statutes, and lawful orders issued by authorities having jurisdiction, as well as rules, conventions, and agreements within the construction industry that control performance of the Work.
- G. Furnish: The term furnish means supply and deliver to the Project site, ready for unloading, unpacking, assembly, installation, and similar operations.
- H. Install: The term install describes operations at the Project site including the actual unloading, unpacking, assembly, erection, placing, anchoring, applying, working to dimension, finishing, curing, protecting, cleaning, and similar operations.
- I. Provide: The term provide means to furnish and install, complete and ready for the intended use.
 - 1. The term experienced, when used with the term Installer means having a minimum of five previous projects similar in size and scope to this Project, being familiar with the special requirements indicated, and having complied with requirements of the authority having jurisdiction.
 - 2. Trades: Using terms such as carpentry is not intended to imply that certain construction activities must be performed by accredited or unionized individuals of a corresponding generic name, such as carpenter. It also does not imply that requirements specified apply exclusively to tradespersons of the corresponding generic name.
- J. Project Site is the space available to the Contractor for performing construction activities, either exclusively or in conjunction, with others performing other work as part of the Project. The extent of the Project Site is shown on the Drawings and may or may not be identical with the description of the land on which the Project is to be built.
- K. Testing Agencies: A testing agency is an independent entity engaged to perform specific inspections or tests, either at the Project Site or elsewhere, and to report on and, if required, to interpret results of those inspections or tests.
- L. Elevation: The figures given on the Drawings or in the other Contract Documents after the word "elevation" or abbreviation of it shall mean the distance in feet above the datum adopted by the Engineer.
- M. Rock: The word "rock," wherever used as the name of an excavated material or material to be excavated, shall mean only boulders and pieces of concrete or

masonry exceeding 1 cu. yd. in volume, or solid ledge rock which, in the opinion of the Engineer, requires, for its removal, drilling and blasting, wedging, sledging, barring, or breaking up with a power-operated tool. No soft or disintegrated rock which can be removed with a hand pick or power-operated excavator or shovel, no loose, shaken, or previously blasted rock or broken stone in rock fillings or elsewhere, and no rock exterior to the maximum limits of measurement allowed, which may fall into the excavation, will be measured or allowed as "rock."

- N. Earth: The word "earth", wherever used as the name of an excavated material or material to be excavated, shall mean all kinds of material other than rock as above defined.

PART 2 - PRODUCTS (NOT USED)

PART 3 - EXECUTION (NOT USED)

END OF SECTION 01080

SECTION 01090

REFERENCE STANDARDS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 1 Specification Sections, apply to this section.

1.2 QUALITY ASSURANCE:

- A. Should specified reference standards conflict with the Contract Documents, refer to paragraph 3.3 of the General Conditions.

1.3 INDUSTRY STANDARDS (SCHEDULE OF REFERENCES):

- A. Copies of Standards: Each entity engaged in construction on the Project is required to be familiar with industry standards applicable to its construction activity. Copies of applicable standards are not attached to the Contract Documents.
 - 1. Where copies of standards are needed to perform a required construction activity, the Contractor shall obtain copies directly from the publication source.
- B. Abbreviations and Names: Trade association names and titles of general standards are frequently abbreviated. The following acronyms or abbreviations, as referenced in Contract Documents, are defined to mean the associated names. Names and addresses are subject to change and are believed, but not assured, to be accurate and up to date as of the date of Contract Documents.

AA Aluminum Association
 818 Connecticut Avenue, N.W.
 Washington, DC 20006

AABC Associated Air Balance Council
 1000 Vermont Avenue, N.W.
 Washington, DC 20005

AASHTO American Association of State Highway and Transportation Officials
 444 North Capitol Street, N.W.
 Washington, DC 20001

ACI American Concrete Institute
 Box 19150
 Reford Station
 Detroit, MI 48219

ADC	Air Diffusion Council 230 North Michigan Avenue Chicago, IL 60601
AFBMA	Antifriction Bearing Manufacturers Association 1101 Connecticut Avenue, N.W., Suite 700 Washington, DC 20036
AGA	American Gas Association
AGC	Associated General Contractors of America 1957 E Street, N.W. Washington, DC 20006
AI	Asphalt Institute Asphalt Institute Building College Park, MD 20740
AIA	American Institute of Architects 1735 New York Avenue, N.W. Washington, DC 20006
AISC	American Institute of Steel Construction Eighth Floor 400 North Michigan Avenue Chicago, IL 60611
AISI	American Iron and Steel Institute 1000 16th Street, N.W. Washington, DC 20036
AITC	American Institute of Timber Construction 333 W. Hampden Avenue Englewood, CO 80110
AMCA	Air Movement and Control Association 30 West University Drive Arlington Heights, IL 60004
ANSI	American National Standards Institute 1430 Broadway New York, NY 10018
APA	American Plywood Association Box 11700 Tacoma, WA 98411

API	American Petroleum Institute 1220 L. Street, N.W. Washington, DC 2005
ARI	Air-Conditioning and Refrigeration Institute 1501 Wilson Boulevard Arlington, VA 22209
ASCE	American Society of Civil Engineers 345 E. 47th Street New York, NY 10017
ASHRAE	American Society of Heating, Refrigeration and Air Conditioning Engineers 1791 Tullie Circle, N.E. Atlanta, GA 30329
ASME	American Society of Mechanical Engineers 345 East 47th Street New York, NY 10017
ASPA	American Sod Producers Association 4415 West Harrison Street Hillside, IL 60162
ASTM	American Society for Testing and Materials 1916 Race Street Philadelphia, PA 19103
AWI	Architectural Woodwork Institute 2310 South Walter Reed Drive Arlington, VA 22206
AWPA	American Wood-Preservers' Association 7735 Old Georgetown Road Bethesda, MD 20014
AWS	American Welding Society 550 LeJeune Road, N.W. Miami, FL 33135
AWWA	American Water Works Association 6666 West Quincy Avenue Denver, CO 80235
BIA	Brick Institute of America 11490 Commerce Park Drive Reston, VA 22091

CDA	Copper Development Association 57th Floor, Chrysler Building 405 Lexington Avenue New York, NY 10174
CFR	Code of Federal Regulations
CLFMI	Chain Link Fence Manufacturers Institute 1101 Connecticut Avenue, N.W. Washington, DC 20036
CRSI	Concrete Reinforcing Steel Institute 933 Plum Grove Road Schaumburg, IL 60195
DHI	Door and Hardware Institute 7711 Old Springhouse Road McLean, VA 22101
EJCDC	Engineers' Joint Contract Documents Committee American Consulting Engineers Council 1015 15th Street, N.W. Washington, DC 20005
EJMA	Expansion Joint Manufacturers Association 25 North Broadway Tarrytown, NY 10591
FGMA	Flat Glass Marketing Association 3310 Harrison White Lakes Professional Building Topeka, KS 66611
FM	Factory Mutual System 1151 Boston-Providence Turnpike P.O. Box 688 Norwood, MA 02062
FS	Federal Specification General Services Administration Specifications and Consumer Information Distribution Section (WRSIS) Washington Navy Yard, Building 197 Washington, DC 20407
GA	Gypsum Association 1603 Orrington Avenue Evanston, IL 60201

JIC	Joint Industrial Council c/o National Machine Tool Builders Association 79-1 Westpark Drive McLean, VA 22102
IBR	Institute of Boiler and Radiator Manufacturers a/k/a Hydronics Institute P.O. Box 218 35 Russo Place Berkeley Heights, NJ 07922
ICBO	International Conference of Building Officials 5360 S. Workman Mill Road Whittier, CA 90601
IEEE	Institute of Electrical and Electronic Engineers 345 East 47th Street New York, NY 10017
IMIAC	International Masonry Industry All-Weather Council International Masonry Institute 815 15th Street, N.W. Washington, DC 20005
MBMA	Metal Buildings Manufacturer's Association 1230 Keith Building Cleveland, OH 44115
MHD	Massachusetts Highway Department
MIL	Military Specifications Naval Publications and Forms Center 5801 Tabor Avenue Philadelphia, PA 19120
ML/SFA	Metal Lath/Steel Framing Association 221 North LaSalle Street Chicago, IL 60601
MSS	Manufacturers Standardization Society of the Valve and Fitting Industry 127 Park Street, NE Vienna, VA 22180
NAAMM	National Association of Architectural Metal Manufacturers 221 North LaSalle Street Chicago, IL 60601

NAPA	National Asphalt Pavement Association 6811 Kenilworth Avenue Calvert Building, Suite 620 Riverdale, MD 20737
NCMA	National Concrete Masonry Association P.O. Box 781 Hendron, VA 22070
NEBB	National Environmental Balancing Bureau 8224 Old Courthouse Road Vienna, VA 22180
NEC	National Electric Code
NEMA	National Electrical Manufacturers' Association 2101 'L' Street, N.W. Washington, DC 20037
NFPA	National Fire Protection Association Battery March Park Quincy, MA 02269
NFPA	National Forest Products Association 1619 Massachusetts Avenue, N.W. Washington, Dc 20036
NSWMA	National Solid Wastes Management Association 1730 Rhode Island Avenue, N.W. Washington, DC 20036
NTMA	National Woodwork Manufacturers Association 205 W. Touhy Avenue Park Ridge, IL 60068
OSHA	Occupational Safety Hazard Administration
PCA	Portland Cement Association 5420 Old Orchard Road Skokie, IL 60077
PCI	Prestressed Concrete Institute 201 North Wells Street Chicago, IL 60606
PS	Product Standard U.S. Department of Commerce Washington, DC 20203

RIS	Redwood Inspection Service One Lombard Street San Francisco, CA 94111
RCSHSB	Red Cedar Shingle and Handsplit Shake Bureau 515 116th Avenue Bellevue, WA 98004
SDI	Steel Deck Institute P.O. Box 9506 Canton, OH 44711
SDI	Steel Door Institute 712 Lakewood Center North 14600 Detroit Avenue Cleveland, OH 44107
SIGMA	Sealed Insulating Glass Manufacturers Association 111 East Wacker Drive Chicago, IL 60601
WSC	Water Systems Council 600 S. Federal Street, Suite 400 Chicago, IL 60605

PART 2 - PRODUCTS (NOT USED)

PART 3 - EXECUTION (NOT USED)

END OF SECTION 01090

SECTION 01105

RODENT CONTROL

PART 1 - GENERAL

1.1 SUMMARY

- A. This section specifies rodent control and general pest control requirements within project areas, and bordering areas as designated by the Engineer. This work is to be performed prior to demolition, excavation, and site preparation and throughout the Contract, so that rodents and other pests do not disperse from or infest the project area.
- B. The Contractor shall develop and implement an Integrated Pest Management (IPM) approach. As part of that approach, the Contractor shall maintain a cooperative dialogue with appropriate agencies and management/representatives of neighboring properties.
- C. The Contractor shall perform the rodent control tasks described in this Scope of Work and also respond to other pest control needs when directed by the Engineer.

1.2 RELATED WORK

- A. DIVISION 1 – GENERAL REQUIREMENTS

1.3 SUBMITTALS

- A. Submit to the Engineer copies of pesticide applicator certifications and licenses within two weeks of notice to proceed.
- B. After performing the survey described in Paragraph 3.2 below and before initiating baiting, submit to the Engineer a written description of proposed pest control procedures, indicating materials, quantities, methods, and time schedule. For all pesticides to be used, submit a copy of the pesticide manufacturer's EPA-approved pesticide label with application directions.
- C. Submit to the Engineer documentation of pest control activities and results and follows:
 - 1. Weekly - Submit data sheets with locations of sites treated, amounts and types of pesticide used, number and types of traps set, survey and inspection results, sanitation conditions, complaint calls investigated, and any problem that occurred.

2. Monthly - Submit a written summary that includes determinable results of the IPM program and recommendations.
3. Quarterly - Submit a map that shows bait stations, manholes, and catch basins where rodent baits are being maintained.

1.4 QUALIFICATIONS

- A. The Contractor shall perform this work at all times in accordance with the following minimum standards and as acceptable to the Engineer.
 1. The Contractor and key personnel shall have experience with commercial and residential accounts and construction projects; have experience and technical training in vertebrate pest management and integrated pest management; have experience with various rodent control techniques, equipment, and strategies; have training and experience with insect control; and have knowledge of and experience with techniques to reduce non-target hazards.
 2. The supervisor shall be licensed and certified by the Massachusetts Pesticide Bureau and certified in General Pest Control (category 41) and Vertebrate Pest Control (category 44). The supervisor shall have specific training and experience in vertebrate pest management, commercial rodent control, general pest control, and integrated pest management.
 3. Applicators shall be licensed by the Massachusetts Pesticide Bureau and certified in General Pest Control (category 41). Applicators shall have specific training and experience in commercial rodent control and integrated pest management.

1.5 COORDINATION

- A. Perform this Work in cooperation with the other Work performed under the Contract.
- B. Initiate the work on or before field mobilization begins for the Contract and with adequate timing to achieve control before environmental disruptions. Provide a maintenance program until Contract is completed and all equipment and materials are removed.
- C. Perform the Work according to the preliminary schedule described in this section and as accepted or revised by the Engineer. Estimated durations and start dates may be changed by the Engineer to suit changes in construction schedules and field conditions. The Work could potentially require performance any day of the week and any hour of the day or night, regardless of weather.

- D. Perform this work in such a manner that toxicant or other control tools do not pose a hazard to persons, domestic animals, or non-target wildlife.

1.6 PERMITS

- A. Obtain and maintain in coordination with the Contractor appropriate permit(s) from city or state agencies for pest control activities associated with this Work.
- B. Obtain and maintain in coordination with the Contractor all right of entry permits required for the performance of this Work. This includes all utilities and private properties to which entrance is required.

PART 2 - PRODUCTS

2.1 PRODUCTS

- A. Furnish and use only pesticide formulations registered by the U.S. Environmental Protection Agency (EPA) and the Massachusetts Department of Food and Agriculture, where appropriate according to label directions and as acceptable to the Engineer.
- B. Furnish and use devices and supplies (e.g., traps and bait stations) to facilitate the management and effectiveness of the pest control program, where appropriate and as acceptable to the Engineer.

PART 3 - EXECUTION

3.1 MEETINGS

- A. Before proceeding with the Work, all pest control personnel shall attend a Work Shop held by the Contractor and Engineer to discuss planned pest control methods and coordination.
- B. The supervisor shall meet with the Contractor and Engineer weekly to discuss pest control activities.

3.2 SURVEY

- A. Prior to baiting, survey the proposed construction area and accessible or observable bordering areas and record signs of rodent activity and sanitation conditions. Closely inspect all embankments, edge areas, and properties within and abutting the construction area. Maintain survey records in the manner described in Paragraph 3.7 below.
- B. Thoroughly inspect construction area and accessible or observable bordering areas and any nearby areas designated by the Engineer, for rodent activity and sanitation

deficiencies weekly throughout the duration of this Contract and in accordance with the work schedule. Maintain inspection records in the manner described in Paragraph 3.7 below.

- C. Plan the control program and allocate resources based on survey and inspection data and as acceptable to the Engineer.

3.3 APPLICATION FOR RODENT CONTROL

- A. Apply rodenticide in strict accordance with EPA-approved label directions and the Rules and Regulations of the Massachusetts Department of Food and Agriculture. Maintain records of all bait placements in the manner described in Paragraph 3.7 below.

- B. Where appropriate, especially for surface placements of rodent baits, use properly secured and tamper-resistant bait stations consistent with EPA regulation. Individually number and properly identify all bait stations.

- C. Surface Applications

- 1. Initial Surface Baiting

Rid the construction area of all detectable rodents before construction begins, or as acceptable to the Engineer. Bait all observable rodent burrows. Install and secure bait stations at regular and appropriate intervals and locations, and document rodent activity (burrows, droppings, bait consumed, dead rodents). Replenish bait and shift bait stations as necessary to ensure complete control of rodent populations. Bait edge and accessible bordering areas as necessary to ensure that rodents will not be dispersed by construction activities and that rodents will not infest work areas.

- 2. Maintenance Surface Baiting

Establish a maintenance baiting program prior to mobilization by the Contractor, including construction areas and accessible bordering areas, as acceptable to the Engineer. Check bait placements weekly. Use survey and baiting data to determine the most effective distribution of baiting locations and bait quantities. Shift and distribute bait and bait stations as appropriate to ensure continued control.

- D. Subsurface Applications

- 1. General

For situations involving underground construction/demolition, utility

relocation, or utility construction, and for other situations when determined necessary by the Engineer, initiate subsurface baiting and rid underground environments of all detectable rodents before construction begins. Assign an identifying number to each manhole and catch basin where bait is placed so that locations of bait placements can be identified and rodent activity (droppings, bait consumed, dead rats) can be documented. Conduct bait applications during off-peak traffic hours unless otherwise directed by the Engineer. Access manholes according to the requirements of appropriate agencies and utility companies. Coordinate the Work with appropriate municipal agencies and utility companies.

2. Initial Subsurface Baiting

Apply appropriate baits to control rodent populations in manholes and catch basins. This will involve suspending and securing bait using noncorrosive wire (e.g., 24 gauge plastic coated). Place bait in all accessible manholes and catch basins within the construction work area. In addition, bait an appropriate set of manholes and catch basins in the blocks bordering the work area and as acceptable to the Engineer. Identify all baited manholes and catch basins with a standardized paint mark on the street and a numbered tag to be attached to the suspending wire. Approximately seven days after completion of the first baiting, check all manhole and catch basin baits and record estimates on the amount of bait consumed. Replenish or increase the amount of bait applied according to the amount consumed or as acceptable to the Engineer. Repeat this process again approximately fourteen days later and until there is little or no bait consumed. Check manholes and catch basins weekly when they repeatedly have 100 percent of the bait consumed.

3. Maintenance Subsurface Baiting

Prior to mobilization by the Contractor, establish a maintenance baiting program appropriate for the rodent infestation patterns identified during initial subsurface baiting. This program shall ensure continued control and shall be performed in a manner acceptable to the Engineer. Maintain bait in manholes and catch basins that have rodent activity and those that had activity during initial baitings. Check each bait according to rodent activity levels. This could range from weekly to approximately every three months, depending upon the recent history of bait consumption. Use utility maps and baiting data to determine the most effective distribution of baiting locations and bait quantities. Shift and distribute baiting locations as necessary to ensure adequate interception points for controlling immigrating rodents.

E. Cleanup

1. Remove visible rodent carcasses and dispose of them daily consistent with the pesticide label directions and applicable codes, laws, and regulations.
2. Upon completion of any pest control operations at the site, remove remaining bait and dispose of it according to the pesticide label and applicable codes, laws, and regulations. Also remove all wires used for subsurface baiting and any bait stations or traps.

3.4 SANITATION

- A. Prior to construction and throughout the duration of this Contract, identify and document harborage and food sources available to rodents on the construction site and in observable bordering areas. This includes any littering or improper or insufficient use of trash receptacles in construction areas. It also includes any bordering areas with sanitation conditions or structural deficiencies that violate City or State sanitation codes.
- B. Maintain records of sanitation conditions in the manner described in Paragraph 3.7 below.

3.5 COMPLAINT CALLS

- A. During construction, respond to pest-related complaints from the "adjacent" neighborhood (i.e. within 200 feet of the project limits) within 12 hours when directed by the Engineer. Inspect the particular premises and adjacent areas for sanitation and structural deficiencies and also signs of historic and recent pest activity. Provide sanitation and structural maintenance information to the property owner or manager. Use pesticides or traps as necessary and appropriate to resolve the complaint when there is a relationship between the pest infestation and construction activities, or when directed by the Engineer.
- B. Maintain records of all complaints investigated, including location, contact person, inspection results, and actions taken. Document the relatedness of the pest infestation to construction activities.

3.6 GENERAL PEST CONTROL

- A. When directed by the Engineer, the Contractor shall determine appropriate methods for any pest control task not specifically identified above and shall submit them in writing to the Engineer for approval in advance. Such pest control tasks would relate to unanticipated pest control needs within construction areas or adjacent areas. This could include control of insects or vertebrates other than rats and mice.
- B. Maintain records of general pest control activities and results in the manner

described in Paragraph 3.7 below.

3.7 RECORD KEEPING

- A. Use standardized data sheets acceptable to the Engineer to maintain accurate records of date, placement, type, and amount of pesticides or other control tools (e.g., traps) applied. Similarly, maintain records of surveys, inspections, changes in pest activity, sanitation conditions, and complaint calls. Submit data in a format acceptable to the Engineer and as required under Paragraph 1.3 (C) above.

END OF SECTION 01105

SECTION 01108

HEALTH AND SAFETY PROCEDURES

PART 1 - GENERAL

1.1 SUMMARY

- A. Prepare a Health and Safety Plan (HASP) that meets all applicable state and federal health and safety regulations, including, but not limited to, those listed below. The Contractor shall be solely responsible for developing a HASP suitable for the Contractor's use and all work done by their subcontractors. The Owner, Engineer and/or their representative is not responsible for establishing or enforcing the health and safety requirements of the Contractor, and that nothing herein shall relieve the Contractor from its exclusive responsibility for the health and safety of its employees, and/or its representatives, and/or subcontractors.
- B. The Contractor shall be responsible for being aware of all potential hazards at the site, including asbestos cement pipe, and reviewing existing information which provides evidence of contamination within the limit of the work.
- C. The Contractor shall also be required to defend, indemnify, and hold the City of Salem, MA, and the Engineer harmless against any and all claims, liabilities, fines, or penalties arising out of actual or alleged failure of the Contractor and/or its agents, employees, or subcontractors to comply with any health or safety regulation, rule, ordinance, legislation, and/or health and safety plan.
- D. All work required in the Specifications regarding development and implementation of a HASP shall be in accordance with State hazardous waste site regulations (310 CMR 40.0018) and OSHA requirements (29 CFR 1910 and 1926). The HASP shall be submitted to the Engineer prior to site mobilization. Work shall not proceed at the site until the Engineer and the City of Salem has received a copy of the Contractor's Health and Safety Plan meeting all the requirements specified herein.
- E. The Contractor is responsible for establishing, implementing and maintaining of ambient air and dust monitoring programs and all other environmental monitoring programs. All such programs shall be operated by the Contractor whenever there are soils handling construction activities occurring at the site.
- F. The Contractor shall be responsible for providing all materials, equipment, and labor associated with applying dust control suppressants, including equipment that shall be required during all soil handling activities, in the event that fugitive dust or excessive odors are encountered.
- G. The Contractor is responsible to implement appropriate health and safety provisions to remove and dispose of asbestos cement in accordance with MassDEP regulation, requirement, and guidance documents.

1.2 DUST CONTROL

- A. During excavation of soil and fill material, dust shall be controlled to limit potential spread of contaminants and potential exposure of contaminants to workers and the public. The dust control measures implemented at the site shall be performed in accordance with Section 01560 – TEMPORARY ENVIRONMENTAL CONTROLS.

1.3 AIR MONITORING

- A. Air monitoring shall involve direct reading instruments capable of providing real-time indications of air contaminants to protect on-site personnel and the local population. The Contractor's Site Health and Safety Officer and Superintendent shall be responsible for assuring that monitoring is conducted in an approved manner, that air monitoring/sampling are conducted at a frequency sufficient to ensure accurate assessments of site conditions, and that work practices, engineering controls, and/or personal protective equipment are proper for the conditions.
- B. At a minimum, detectors for organic contaminants shall be utilized to monitor on-site and off-site breathing zones and possible sources of potentially hazardous material (e.g., excavations, regrading, etc.). All personnel shall be made aware of the potential hazards and be informed of air monitoring information. Particular attention to air quality shall be made in the work area during earthwork activities to ensure that contaminants do not escape to the atmosphere and affect off-site population, on-site control, working conditions, and personnel protection measures.
- B. The Contractor shall keep accurate documentation of all air monitoring, which shall be made available to the Owner and Engineer for review at all times.

PART 2 - PRODUCTS

2.1 HEALTH AND SAFETY PLAN AND CERTIFICATIONS

- A. The Contractor shall, at least two weeks prior to the mobilization on the site, submit six (6) copies of its site-specific Health and Safety Plan to the Engineer. The site-specific Health and Safety Plan shall address the specific work activities to be conducted during the course of this contract and shall include, but not be limited to, the following:
 - 1. All anticipated hazards associated with the Contractor's activities (including the activities of subcontractors) based on the levels of contamination and information presented in previous studies.
 - 2. Provisions for continually updating the Plan in accordance with any new applicable state and federal regulations or any additional information regarding conditions at the site.
 - 3. The following information in accordance with the minimum standards set forth in 29 CFR 1910.120, 29 CFR 1910.1000, and 29 CFR 1926 and 310 CMR 40.0018:
 - 1) Identification of Contractor's Site Safety Officer.
 - 2) Identification of Contractor's Designated Field Personnel.

- 3) Type of Medical Surveillance Program.
 - 4) Identification of Hazard and Risks Associated with the Contractor's work.
 - 5) Contractor's Standard Operating Procedures including Personnel Training and Field Orientation; Personal Hygiene Requirements & Guidelines; Field Monitoring of Site Contaminants; Respiratory Protection Training & Requirements; Levels of Protection and Selection of Equipment Procedures; Zone Delineation of the Project Site; Site Security and Entry Control Procedures; Contingency and Emergency Procedures; and Listing of Emergency Contacts.
 - 6) List of all hazardous materials that the Contractor will have on site; the location of the Material Safety Data Sheets for each material listed and the plan for notifying all on site personnel, including but not limited to, the Engineer and/or their representatives, of the presence of hazardous materials on site. If there are no hazardous materials to be brought on site, the Contractor shall provide a written statement to the Engineer and/or their representative prior to initiating work activities certifying that the Contractor will not transport, store, or use hazardous materials on-site.
4. A certification that states the following:
- 1) The Contractor hereby certifies that the Contractor and its employees who are engaged in work on or near the project meet the requirements of 29 CFR 1910.120, and the provisions of the American National Standards Institute Standard Z88.2 for training, medical surveillance, and respirator protection.
 - 2) The employees have received health and safety training for working in environments with known and unknown hazards;
5. The Contractor shall provide records of Health and Safety monitoring results, including PID and dust readings, and any revisions that may have been made to the plan. These records are to be provided at the weekly project progress meetings. If there are no such records for the preceding week, the Contractor shall provide a statement indicating the absence of such readings and provide a technical justification for foregoing the specified air monitoring.

PART 3 - EXECUTION

3.1 HEALTH AND SAFETY PLAN CONTENTS, MAINTENANCE, AND IMPLEMENTATION

- A. The Contractor shall keep a copy of the HASP on site during all operations and shall conduct daily health and safety meetings. Failure to keep a copy of the HASP on site, or any other breach of the Contractor's Plan, shall be cause for stopping work at the cost of the Contractor. Delays caused by the Contractor's failure to comply with the health and safety regulations, or any health and safety plan, shall not entitle the Contractor to recover any additional costs or time lost. The Contractor shall not be allowed to resume activities until corrective measures are implemented.
- B. Medical surveillance records, OSHA 40-hour training forms, accident forms, and all other documentation requirements of the Contractor's safety and health program for personnel working

on the site shall be up-to-date and kept on file at the site. The Contractor shall provide documentation of employee status upon request of the Engineer.

- C. The Contractor shall make available Level C personal protective equipment and clothing, not including respirators, to the Engineer and/or their representative for use during site inspections by the Engineer and/or their representative, up to a maximum of three (3) complete sets per day. These shall be supplied and maintained at no cost to the Owner and shall be returned to the Contractor upon completion of the work (except for expendable disposal protective clothing). The Contractor shall provide a repository for collection of disposed health and safety materials. Collection and disposal of contaminated expendable supplies shall be the Contractor's responsibility.
- D. The level of dermal and respiratory protection shall be determined based upon continuous air monitoring to be performed by the Contractor. The Engineer may conduct duplicate air monitoring for quality control purposes. As air monitoring indicates the levels of contaminants in the air, the personal protective equipment shall be determined based upon established standards and the standards set forth in the Contractor's Health and Safety Plan. Regardless, modified Level D protection for all on-site personnel is the minimum project requirement.
- E. The Contractor shall be aware of site-specific requirements, such as site security during non-working hours, limited work space, and minimizing the effects of soil excavation, in preparing its health and safety program.

3.2 ROUTINE SAFETY MEETINGS

- A. The Contractor shall keep a copy of the HASP on site during all operations, and shall conduct routine health and safety meetings to ensure that all work is being performed in accordance with OSHA regulations, the Contractor's HASP, and prior to initiating a new task, following an incident or following any changes to the HASP necessitated by site conditions. Failure to conduct routine safety meetings may be cause for stopping work at the cost of the Contractor.

END OF SECTION 01108

SECTION 01110

ENVIRONMENTAL PROTECTION PROCEDURES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 1 Specification Sections, apply to this section.

1.2 SCOPE OF WORK:

- A. The work covered by this section consists of furnishing all labor materials and equipment and performing all work required for the prevention of environmental pollution in conformance with applicable laws and regulations, during and as the result of construction operations under this Contract. For the purpose of this Specification, environmental pollution is defined as the presence of chemical, physical, or biological elements or agents which adversely affect human health or welfare; unfavorably alter ecological balances of importance to human life; affect other species of importance to man; or degrade the utility of the environment for aesthetic and/or recreational purposes.
- B. The control of environmental pollution requires consideration of air, water, and land, and involves management of noise and solid waste, as well as other pollutants.
- C. Schedule and conduct all work in a manner that will minimize the erosion of soils in the area of the work. Provide erosion control measures such as diversion channels, sedimentation or filtration systems, berms, staked hay bales, seeding, mulching, or other special surface treatments as are required to prevent silting and muddying of streams, rivers, impoundments, lakes, etc. All erosion control measures shall be in place in an area prior to any construction activity in that area.

Specific requirements for erosion and sedimentation controls are specified in Section 01568 – EROSION CONTROL, SEDIMENTATION AND CONTAMINATION OF CONSTRUCTION MATERIALS.

- D. These Specifications are intended to ensure that construction is achieved with a minimum of disturbance to the existing ecological balance between a water resource and its surroundings. These are general guidelines. It is the Contractor's responsibility to determine the specific construction techniques to meet these guidelines.

- E. All phases of sedimentation and erosion control shall comply with and be subject to the approval of the Massachusetts Department of Environmental Protection and local Conservation Commission.
- F. Schedule and conduct all work in a manner that will minimize the level of noise escaping the site, especially at night and on weekends.

1.3 APPLICABLE REGULATIONS:

- A. Comply with all applicable Federal, State, and local laws and regulations concerning environmental pollution control and abatement.

1.4 NOTIFICATIONS:

- A. The Engineer will notify the Contractor in writing of any observed non-compliance with the foregoing provisions or of any environmentally objectionable acts and corrective action to be taken. State or local agencies responsible for verification of certain aspects of the environmental protection requirements shall notify the Contractor in writing, through the Engineer, of any non-compliance with State or local requirements. The Contractor shall, after receipt of such notice from the Engineer or from the regulatory agency through the Engineer, immediately take corrective action. Such notice, when delivered to the Contractor or his authorized representative at the site of the work, shall be deemed sufficient for the purpose. If the Contractor fails or refuses to comply promptly, the Owner may issue an order stopping all or part of the work until satisfactory corrective action has been taken. No part of the time lost due to any such stop orders shall be made the subject of a claim for extension of time or for excess costs or damages by the Contractor unless it is later determined that the Contractor was in compliance.

1.5 IMPLEMENTATION:

- A. Prior to commencement of the work, meet with the Engineer to develop mutual understandings relative to compliance with this provision and administration of the environmental pollution control program.
- B. Remove temporary environmental control features, when approved by the Engineer, and incorporate permanent control features into the project at the earliest practicable time.

PART 2 - PRODUCTS (NOT USED)

PART 3 - EXECUTION

3.1 PROTECTION OF LAND RESOURCES:

- A. Land resources within the project boundaries and outside the limits of permanent work shall be restored to a condition, after completion of construction that will

appear to be natural and not detract from the appearance of the project. Confine all construction activities to areas shown on the Drawings.

- B. Outside of areas requiring earthwork for the construction of the new facilities, the Contractor shall not deface, injure, or destroy trees or shrubs, nor remove or cut them without prior approval. No ropes, cables, or guys shall be fastened to or attached to any existing nearby trees for anchorage unless specifically authorized by the Engineer. Where such special emergency use is permitted, first wrap the trunk with a sufficient thickness of burlap or rags over which softwood cleats shall be tied before any rope, cable, or wire is placed. The Contractor shall in any event be responsible for any damage resulting from such use.
- C. Where trees may possibly be defaced, bruised, injured, or otherwise damaged by the Contractor's equipment, dumping or other operations, protect such trees by placing boards, planks, or poles around them. Monuments and markers shall be protected similarly before beginning operations near them.
- D. Any trees or other landscape feature scarred or damaged by the Contractor's equipment or operations shall be restored as nearly as possible to its original condition. The Engineer will decide what method of restoration shall be used and whether damaged trees shall be treated and healed or removed and disposed of.

All scars made on trees by equipment, construction operations, or by the removal of limbs larger than 1-in. in diameter shall be coated as soon as possible with an approved tree wound dressing. All trimming or pruning shall be performed in an approved manner by experienced workmen with saws or pruning shears. Tree trimming with axes will not be permitted.

Trees that are to remain, either within or outside established clearing limits, that are subsequently damaged by the Contractor and are beyond saving in the opinion of the Engineer, shall be immediately removed and replaced.

- E. The locations of the Contractor's storage, and other construction building, required temporarily in the performance of the work, shall be cleared portions of the job site or areas to be cleared as shown on the Drawings and shall require written approval of the Engineer and shall not be within wetlands or floodplains. The preservation of the landscape shall be an imperative consideration in the selection of all sites and in the construction of buildings. Drawings showing storage facilities shall be submitted for approval of the Engineer.
- F. Remove all signs of temporary construction facilities such as haul roads, work areas, structures, foundations of temporary structures, stockpiles of excess of waste materials, or any other vestiges of construction as directed by the Engineer. It is anticipated that excavation, filling, and plowing of roadways will be required to restore the area to near natural conditions which will permit the

growth of vegetation thereon. The disturbed areas shall be prepared and seeded as described in Section 01568, or as approved by the Engineer.

- G. All debris and excess material will be disposed of outside wetland or floodplain areas in an environmentally sound manner.
- H. At a minimum, the Contractor shall maintain on-site absorbent pads, booms and absorbent materials sufficient to address a release of fuel oil, hydraulic oil or any other hazardous materials that the Contractor intends to use or store on site, including fuel oil and hydraulic oil that is used within earth moving equipment. The quantity of spill containment materials maintained on site shall be sufficient to respond to a catastrophic release from the vessel containing the greatest quantity of oil or hazardous material on-site. The Spill and Discharge Plan shall indicate the location and quantity of the materials to be staged on site and the basis for the quantities (i.e. indicate the vessel which will be on site containing the greatest volume of oil or hazardous materials). No fuel or oil tanks or drums may be temporarily staged on site unless they are stored within a secondary containment system. Fuel deliveries must be performed in a designated which has either secondary containment or upon an impervious surface with absorbent berms located around the point of fuel delivery. The Spill and Discharge Plan shall indicate the location of the fueling area and the nature of secondary containment which the Contractor intends on utilizing.

3.2 PROTECTION OF AIR QUALITY:

- A. Burning. The use of burning at the project site for the disposal of refuse and debris will not be permitted.
- B. Dust Control. The Contractor will be required to maintain all excavations, embankments, stockpiles, access roads, plant sites, waste areas, borrow areas, and all other work areas within or without the project boundaries free from dust which could cause the standards for air pollution to be exceeded, and which would cause a hazard or nuisance to others.
- C. An approved method of stabilization consisting of sprinkling or other similar methods will be permitted to control dust. The use of chlorides may be permitted with approval from the Engineer.
- D. Sprinkling, to be approved, must be repeated at such intervals as to keep all parts of the disturbed area at least damp at all times, and the Contractor must have sufficient competent equipment on the job to accomplish this if sprinkling is used. Dust control shall be performed as the work proceeds and whenever a dust nuisance or hazard occurs, as determined by the Engineer.

3.3 MAINTENANCE OF POLLUTION CONTROL FACILITIES DURING CONSTRUCTION:

- A. During the life of this Contract, maintain all facilities constructed for pollution control as long as the operations controlling the particular pollutant are being carried out or until the material concerned has become controlled to the extent that pollution is no longer being created, spread or exacerbated.

3.4 NOISE CONTROL:

- A. The Contractor shall make every effort to minimize noises caused by his operations. Equipment shall be equipped with silencers or mufflers designed to operate with the least possible noise in compliance with State and Federal (OSHA) regulations and local ordinances.

3.5 DUST CONTROL

- A. Nuisance dust levels may be encountered during excavation, backfilling or regarding activities. Dust levels shall be reduced by pre-wetting the surface soils and by establishing and maintaining clean access roads. At a minimum, the Contractor shall provide clean water, free from salt, oil, and other deleterious materials.
- B. Areas to be excavated shall be lightly sprayed with water before excavation. Additional water spray may be utilized only when any indication of excessive dust is observed. The Contractor shall minimize the use of water within the limits of excavation.
- C. Access roads shall be sprayed with water on a regular basis to minimize the generation of dust.
- D. All containers temporarily storing waste material shall be covered at all times except as necessary to place waste material into the container. The Contractor shall inspect the covers daily to ensure the covers are in place and effectively eliminating the generation of dust and make appropriate notes in the site log.
- E. All stockpiles of soil and loose granular construction materials shall be covered at the end of the day with a polyethylene sheeting, a minimum of 6-mil-thick, so as to eliminate the generation of dust. The Contractor is responsible for inspecting the covers daily to ensure the covers are in place and effectively eliminating the generation of dust. Water shall not be used on stockpiles to reduce the generation of dust.

3.6 CONTAMINATED LIQUIDS

- A. The Contractor shall collect and properly dispose of contaminated liquids and other liquids generated or encountered on site during construction.

3.7 BACKFILLING AND COMPACTION

- A. Excavated areas shall be backfilled with appropriate backfill material (including excavated material suitable for reuse and, when necessary, imported off-site material). Any off-site backfill used in excavated areas shall be in accordance with these specifications, and which has been tested and certified as free of contaminants as specified in 02210 – EARTH EXCAVATION, BACKFILL, FILL AND GRADING. In order to minimize the volume of imported clean fill used on the site the Contractor shall use on-site soil/fill to the maximum extent possible which has been determined suitable for reuse by sieve analysis or visual inspection as approved by the Engineer.

END OF SECTION 01110

SECTION 01200

PROJECT MEETINGS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 1 Specification Sections, apply to this section.

1.2 PRECONSTRUCTION CONFERENCE

- A. A preconstruction conference will be held between the Contractor, the Engineer, the Owner, and applicable agency representatives to review the Contractor's proposed methods of complying with the requirements of the Contract Documents.
- B. Contractor will be notified of the time, date and place where the preconstruction conference will be held.

1.3 PROGRESS MEETINGS WITH ENGINEER

- A. In addition to other regular project meetings for other purposes (as indicated elsewhere in the Contract Documents), hold general progress meetings four times each month with times coordinated with preparation of payment requests. Meeting dates shall be established by the Engineer. Require every entity then involved in the planning, coordination or performance of work to be properly represented at each meeting. Include (when applicable) consultants, separate contractors (if any), principal subcontractors, suppliers/manufacturers/fabricators, governing authorities, insurers, special supervisory personnel and others with an interest or expertise in the progress of the work. Review each entity's present and future needs including interface requirements, time, sequence, deliveries, access, site utilization, temporary facilities and services, hours of work, hazards and risks, housekeeping, submittals, change orders, and documentation of information for payment requests. Discuss whether each element of current work is ahead of schedule. Determine how behind-time work will be expedited, and secure commitments from the entities involved in doing so. Discuss whether schedule revisions are required to ensure that current work and subsequent work will be completed within the Contract Time. Review everything of significance which could affect the progress of the work.

PART 2 - PRODUCTS (NOT USED)

PART 3 - EXECUTION (NOT USED)

END OF SECTION 01200

SECTION 01210

GENERAL REQUIREMENTS FOR UTILITY WORK

PART 1 - GENERAL

1.1 DESCRIPTION

- A. This Section specifies general requirements for construction, protection, support, maintenance, and restoration for underground and overhead utilities affected by construction of the Project. The Work includes new construction, reconstruction, relocation, and abandonment.
- B. The utility works and services that may be affected include, but are not limited to:
 - 1. Storm drain, sanitary sewer
 - 2. Water distribution
 - 3. Gas distribution
 - 4. Electric power and street lighting
 - 5. Telephone
 - 6. Cable Television
 - 7. Signal communication
- C. This Section shall be used in conjunction with the specific underground utility work sections that apply to the Contract.

1.2 WORK BY UTILITY COMPANIES

- A. Certain parts of the utility work shall be performed, where shown or specified, by the utility company.
- B. Contact the utility companies in advance of construction to allow sufficient time for the utility companies to accomplish the work they are required to perform. Provide the utility company at least thirty (30) days advance notice of scheduled date for commencement of work by the utility company.
- C. Work performed by utility company as part of the Work of this Contract, and other work performed by utility company solely for the Contractor's convenience, shall be at no additional cost to the Owner.

1.3 DEFINITIONS

- A. Abandoned means that use has been discontinued by the utility company.
- B. To be abandoned means that use will be discontinued as part of the Work of this Contract.

- C. Maintenance means providing continuous and satisfactory service during construction.
- D. Maintain complete-in-place means to protect, support, and otherwise maintain the existing condition and function of a facility during construction.
- E. Restoration means replacement of a facility or portions of a facility that have been removed or made inoperative by the Contractor in the performance of the Work.
- F. Utility Company means the company, agency, owner, or operator of the facility concerned.
- G. Temporary Facility means a facility provided, in lieu of an existing or new facility, to ensure continuity of service. When a temporary facility is not shown on the Contract Drawings, but is provided for the convenience of the Contractor, it shall be constructed at no additional cost to the Owner.

1.4 SUBMITTALS

- A. Shop Drawings: Submit the following in accordance with Section 01300 - SUBMITTALS
 - 1. Submit working drawings and, if applicable, shop drawings showing the details, procedures, and scheduling for performance of the utility work. Show actual verified field locations of existing utility facilities that are affected by the Work of this Contract; interferences which these facilities present to the new work; location of settlement markers; method proposed to proceed with the construction; and, if applicable, method of testing and procedure for restoration.
 - 2. Submit to the Engineer specifications and drawings describing the method to be used to temporarily support existing utilities during construction. Include working drawings that indicate proposed materials and details.
 - 3. Submit to the Engineer materials data required by specification. Also submit certifications that the products to be incorporated in the Work are in conformance with utility company requirements.
 - 4. Submit to the Engineer for review a detailed excavation procedure for subsurface utilities. At a minimum, the procedure shall include:
 - a. Equipment to be used for anticipated subsurface utility investigation and excavation.
 - b. Personnel to be used and designated utility coordinator.
 - c. Duration and schedule of investigation and excavation.

- d. Techniques proposed to isolate and protect existing utilities.
 - e. Method for the Contractor to provide utility information derived from subsurface investigation to field personnel doing excavation.
 - f. A disciplinary plan that delineates all steps to be taken as a result of a utility disruption, including possible removal of Contractor's individuals from the site.
- B. Submit an emergency action plan outlining procedures to be followed by the Contractor in case of unplanned utility interruptions or unplanned damage to utilities in service. Obtain concurrence from each affected utility company.
 - 1. List Contractor's personnel assigned responsible charge for emergency action on site for each shift, and those on call.
 - 2. List phone notification numbers for each utility company, fire, and police departments, and other relevant agencies.
 - 3. Include copies of utility plans showing the valve or switch locations to isolate each line.
- C. Transmit to the Engineer the as-built utility location survey data as specified in Article 3.11 of this Section.

1.5 APPROVAL BY UTILITY COMPANIES

- A. All personnel performing work on utility facilities shall be fully qualified and able to meet the standards of the affected utility company. If the Contractor does not have the required utility experience, Contractor shall retain a specialist firm acceptable to the affected utility company to perform the Work.
- B. Prior acceptance of temporary support methods for each affected utility facility shall be obtained by the Contractor from each utility company concerned.
- C. Prior permission for disrupting a utility shall be obtained by the Contractor from each utility company concerned.
- D. Prior approval for disrupting fire signal lines, high pressure fire water mains and hydrants, and fire service lines shall be obtained from the City of Salem Fire Department.

1.6 NOTIFICATION

- A. Notify the appropriate utility companies and the Engineer at least seven (7) days prior to starting any work involving or adjacent to surface, subsurface, or overhead utility facilities. If cut-off or connection is expected, notify the appropriate gas company Engineering Department four (4) weeks prior to cut-off or connection to gas main.
- B. Immediately notify the Gas Company Engineering Department if surface or subsurface settlement or movement in excess of the design amount is observed, regardless of the proximity to an existing gas facility.

1.7 STANDARD SPECIFICATIONS OF UTILITY OWNERS

- A. Specifications and construction methods from each utility owner apply to individual utility specification sections.
- B. It is the Contractor's responsibility to ensure that, unless otherwise specified, the standards for materials and construction methods required by the utility owner are met.

PART 2 - MATERIALS

2.1 GENERAL

- A. Materials for temporary and permanent work shall be of the type, grade, and class specified by reference to utility company standards.
- B. Materials salvaged during construction that are indicated to be reused are subject to inspection and acceptance by the respective utility companies and the Engineer. Salvaged material not reused or claimed by the utility company shall become the property of the Contractor and must be disposed by the Contractor.

PART 3 - EXECUTION

3.1 GENERAL CONSTRUCTION REQUIREMENTS

- A. Unless otherwise noted, conform to the construction standards, specifications, and standard practices of the affected utility companies. Coordinate with each utility company the work to be done by the Contractor and the work to be done by utility company. Ensure continuity of all existing utility services to all users, except when the utility company determines that temporary interruption is acceptable.
- B. Unless otherwise indicated, maintain all utility facilities complete in place. Provide temporary support of utilities during construction only by methods acceptable to the utility company concerned.

- C. Provide and maintain all temporary facilities required to provide interim utility service when a utility facility is to be relocated and when a utility facility to be replaced is abandoned prior to replacement.
- D. Where an existing utility facility is encountered that is not indicated, or that is determined to be a different utility service than that indicated, promptly notify the Engineer, who will assist in determining the owner of the facility and the disposition of the facility.
- E. All water, sanitary, and storm services must be maintained throughout the project through the use of temporary pumps and piping. Unless otherwise noted, no service interruptions will be permitted.
- F. No water service interruptions will be permitted unless the Contractor provides the Salem Water Department 72 hour (3 day) notice excluding weekend days.

3.2 UNSAFE AND UNSUITABLE UTILITY STRUCTURES

- A. If, upon exposure, the condition of a facility to be maintained complete-in-place is found to be unsafe by the Engineer and the utility company for support or for maintenance of service, replace or reconstruct the facility as authorized by the Engineer, under the provisions for Changes in the Work.

3.3 ABANDONED FACILITIES

- A. Demolish and remove abandoned utility facilities located within areas of the Work of this Contract. Abandoned facilities that do not interfere with the Work of this Contract may remain.
- B. Do not undertake demolition or removal until written permission for such Work has been obtained from the utility company.
- C. When abandoned facilities are to be left in place, plug or cap the ends of conduits and pipes, and fill with concrete fill unless otherwise indicated. Remove abandoned utility manholes, junction boxes, and similar structures to a minimum depth of 4 feet below finish grade, and puncture or break the bottom slabs of manholes and similar structure to allow drainage. Backfill and compact excavations resulting from removal of utility facilities as required to restore original grade.

3.4 SETTLEMENT OR MOVEMENT

- A. In case of settlement or other movement that causes or could cause damage, take immediate remedial measures to correct the conditions and repair the damage.

3.5 ACCESS

- A. At all times permit free and clear access to the affected facilities by personnel of the utility companies.
- B. Throughout the construction period, maintain access to all utility vaults and structures.

3.6 SERVICE CONNECTIONS

- A. Work required for maintaining, supporting, relocating, restoring, and constructing all service connections is included as part of the Work of this Contract, even though some existing service connections, for which record information is not available, may not be shown on the Contract Drawings.

3.7 REPAIR AND RESTORATION

- A. Repair all damage to utilities caused by Work of this Contract. Clean all utility structures of dirt caused by Work of this Contract. Immediately notify the Engineer and the utility company of damage to utilities.
- B. Replacement of pavements, walks, and curbs is not part of the Work of a utilities Section, except when damage beyond the extent of the utility work zone is caused by utility Work.

3.8 EXCAVATION AND BACKFILL

- A. Perform excavation and backfill in accordance with Section 02210 – EARTH EXCAVATION, BACKFILL, FILL, AND GRADING. Perform excavation support, groundwater control, and erosion and sedimentation control in connection with utility work in accordance with Section 02210 – EARTH EXCAVATION, BACKFILL, FILL, AND GRADING.

3.9 CLEANING UP

- A. In accordance with Section 02498 – RESTORATION OF DISTURBED AREAS, the Contractor shall, upon completion of the Work, remove all temporary construction facilities, equipment, debris, and unused materials, and put the project area and adjacent affected areas in a neat and clean condition.

3.10 AS-BUILT UTILITY LOCATION SURVEY

- A. For each new or relocated utility installed perform an as-built location survey prior to backfilling the excavation.
- B. Where existing street curb lines will remain as they are, provide as-built utility locations by measurement from the edge of street curb.

- C. Where final curb lines are not available at the time of utility installation, provide as-built utility locations by coordinates.
- D. For each utility, make the necessary calculations, prepare a separate sketch, certify the field notes and sketch, and transmit them to the Engineer as utility is completed.

END OF SECTION 01210

SECTION 01300

SUBMITTAL PROCEDURES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 1 Specification Sections, apply to this section.

1.2 SUMMARY

- A. This section specifies the general methods and requirements of submissions applicable to the following work-related submittals.
 - 1. Shop Drawings
 - 2. Product Data
 - 3. Samples
 - 4. Mock Ups
 - 5. Operation and Maintenance Manuals
 - 6. Construction or Submittal Schedules
 - 7. Or equal submittals
 - 8. Schedule of Values
 - 9. Technical Memos
- B. Detailed submittal requirements will be specified in the technical specifications section.

1.3 SHOP DRAWINGS, PRODUCT DATA, SAMPLES

- A. Shop Drawings:
 - 1. Shop drawings, as defined in the General Conditions, and as specified in individual work sections include, but are not necessarily limited to: custom-prepared data such as fabrication and erection/installation (working) drawings of concrete reinforcement, structural details and piping layout, schedule information, setting diagrams, actual shop work manufacturing instructions, custom templates, special wiring diagrams, coordination drawings, individual system or equipment inspection and test reports including performance curves and certifications as applicable to the works.
 - 2. All shop and working drawings shall be prepared on standard size, 24-in. by 36-in. sheets, except those which are made by changing existing standard shop or working drawings.

3. All shop drawings shall be submitted using a transmittal form approved by the Engineer. Submittal form shall include identification of transmittal number and specification section number.
4. All shop drawings submitted by subcontractors for review shall be sent directly to the Contractor for approval. The Contractor shall be responsible for their submission at the proper time so as to prevent delays in delivery of materials.
5. The Contractor shall check all subcontractor's shop drawings regarding measurements, size of members, materials, and details to satisfy himself that they conform to the intent of the Drawings and Specifications. Shop drawings found to be inaccurate or otherwise in error shall be returned to the subcontractors for correction before submission thereof.
6. All details on shop drawings submitted for approval shall show clearly the relation of the various parts of the main members and lines of the structure, and where correct fabrication of the work depends upon field measurements; such measurements shall be made and noted on the drawings before being submitted for approval.

B. Product Data:

1. Product data as specified in individual sections, include, but are not necessarily limited to, standard prepared data for manufactured products (sometimes referred to as catalog data), such as the manufacturer's product specification and printed installation instructions, availability of colors and patterns, manufacturer's printed statements of compliances including certificates of compliance and applicability, roughing-in diagrams and templates, catalog cuts, product photographs, standard wiring diagrams, printed performance curves and operational-range diagrams, production or quality control inspection and test reports and certifications and recommended spare-parts listing, and printed product warranties, as applicable to the Work.

C. Samples:

1. Samples specified in individual sections, include, but are not necessarily limited to, physical examples of the work such as sections of manufactured or fabricated work, small cuts or containers of materials, complete units of repetitively-used products, color/texture/pattern swatches and range sets, specimens for coordination of visual effect, graphic symbols, and units of work to be used by the Engineer or Owner for independent inspection and testing, as applicable to the Work.

1.4 CONTRACTOR'S RESPONSIBILITIES

- A. The Contractor shall review shop drawings, product data and samples, including those by subcontractors, prior to submission to determine and verify the following:
 - 1. Field measurements
 - 2. Field construction criteria
 - 3. Catalog numbers and similar data
 - 4. Conformance with the Specifications
- B. Each shop drawing, sample, and product data submitted by the Contractor shall have affixed to it the following Certification Statement including the Contractor's Company name and signed by the Contractor: "Certification Statement: by this submittal, I hereby represent that I have determined and verified all field measurements, field construction criteria, materials, dimensions, catalog numbers and similar data, and I have checked and coordinated each item with other applicable approved shop drawings and all Contract requirements." Shop drawings and product data sheets 11-in. X 17-in. and smaller shall be bound together in an orderly fashion and bear the above Certification Statement on the cover sheet. The cover sheet shall fully describe the packaged data and include a listing of all items within the package. Provide to the Engineer a copy of each submittal transmittal form for shop drawings, product data and samples at the time of submittal of said drawings, product data and samples to the Engineer.
 - 1. Submittals received "WITHOUT" Certification Statement shall not be reviewed.
- C. If a shop drawing shows any deviation from the requirements of the Contract Documents, the Contractor shall make specific mention of the deviations in the Transmittal Form furnished by the Engineer and provide a description of the deviations in a letter attached to the submittal.
 - 1. Submittals received "WITHOUT" description of the deviations in a letter attached to the submittal shall not be reviewed.
- D. The review and approval of shop drawings, samples or product data by the Engineer shall not relieve the Contractor from his responsibility with regard to the fulfillment of the terms of the Contract. All risks of error and omission are assumed by the Contractor and the Engineer will not have responsibility.
- E. No portion of the work requiring a shop drawing, work plan, technical memo, sample, or product data shall be started nor shall any materials be fabricated or installed prior to the approval or qualified approval of such item. Fabrication performed, materials purchased or on-site construction accomplished which does not conform to approved shop drawings and data shall be at the Contractor's risk. The Owner will not be liable for any expense or delay due to corrections or remedies required to accomplish conformity.

- F. Project work, materials, fabrication, and installation shall conform with approved shop drawings, applicable samples, and product data.
- G. Manufacturer's printed installation instructions, a part of product data submitted to the Engineer will not be reviewed and are for informational purposes only.

1.5 "OR EQUAL"

- A. Should the Contractor seek approval of a product other than the brand or brands named in these specifications, it shall furnish written evidence that such product conforms in all respects to the specified requirements, and that it has been used successfully elsewhere under similar conditions. Where the specified requirements involve conformance to recognized codes or standards the Contractor shall furnish evidence of such conformance in the form of test or inspection reports, prepared by a recognized agency, and bearing an authorized signature.
- B. Manufacturers' standard data and catalog cut sheets will not be considered sufficient in themselves, and the Engineer will not be responsible for seeking further data from the manufacturer, or for otherwise researching the product. Failure to provide complete data will be cause for rejection of the product.
- C. The Contractor shall be responsible for all additional costs including license fees, foundation, piping and electrical work necessary to accommodate the proposed "or equal" equipment. Items which result in a cost reduction shall be presented and a change order reflecting the cost savings will be prepared and the contract price modified.

1.6 SUBMISSION REQUIREMENTS

- A. Make submittals promptly in accordance with approved schedule, and in such sequence as to cause no delay in the Work or in the work of any other contractor.
- B. All complete submittals shall be submitted sufficiently in advance of construction requirements to provide no less than fifteen (15) days, excluding Saturdays, Sundays and legal holidays for review from the time received at the Engineer's reviewing office. For submittals of major equipment, that require more than fifteen (15) days to review, due to its complexity and amount of detail and also requiring review by more than one engineering discipline, a letter will be sent by the Project Manager or his/her designee to the Contractor informing him/her of the circumstances and the date it is expected the submittal will be returned to the Contractor.
- C. Number of submittals required:
 - 1. Shop Drawings: Unless otherwise stated in the respective Specifications Sections, submit six (6) copies.

2. Product Data: Unless otherwise stated in the respective Specifications submit six (6) copies.
3. Samples: Submit the number stated in the respective Specification Sections.
4. Schedule of Values: Submit six (6) copies.

D. Submittals shall contain:

1. The date of submission and the dates of any previous submissions.
2. The Project title and number.
3. Contractor identification.
4. The names of:
 - a. Contractor
 - b. Supplier
 - c. Manufacturer
5. Identification of the product, with the specification section number, page and paragraph(s).
6. Field dimensions, clearly identified as such.
7. Relation to adjacent or critical features of the Work or materials.
8. Applicable standards, such as ASTM or Federal Specification numbers.
9. Identification of deviations from Contract Documents.
10. Identification of revisions on re-submittals.
11. An 8-in. x 3-in. blank space for Contractor and Engineer stamps.

- E. Each shipment of drawings shall be accompanied by a transmittal form furnished by the Engineer giving a list of the drawing numbers and the names mentioned above.

1.7 CONTRACTORS COST BREAKDOWN

- A. The Contractor shall submit a Schedule of values in accordance with the requirements to Section 01370 – SCHEDULE OF VALUES.

1.8 CONTRACTOR WORK PLANS and TECHNICAL MEMOS

- A. The Contractor shall submit a work plan for each significant phase of mainline and on-lot construction associated with the work including, but not limited to, the following:
 - i. Staging Area Protection, Equipment, Materials
 - ii. Traffic Management, Safety, Signage
 - iii. Pavement Cutting and Removal
 - iv. Tree Protection
 - v. Trench Dewatering, Erosion and Sedimentation
 - vi. Bypass Pumping and Piping for Sewer and Drain
 - vii. Support of Excavation
 - viii. Sewer and Drain Replacement and Installation
 - ix. Manhole Rehabilitation and Waterproofing
 - x. Cured-in-Place Pipe Liner and Spot Liner Installation
 - xi. Backfill, Compaction, Testing
 - xii. Pipeline and Manhole Cleaning, Inspection, Rehabilitation
 - xiii. Management, Storage, Disposal of Pipeline and Manhole Cleanings, Grit, Debris
 - xiv. Coordination with Work by Other Utilities
- B. The Contractor shall not enter onto private property without giving the Engineer at least ten (10) days advance notice in writing. The Contractor shall notify the Engineer and the owner of the property 10 days in advance before any excavation is performed on private property.
- C. The work plans shall include, but may not be limited to, the following information to accurately describe the proposed work:
 - i. Scope of work
 - ii. Schedule of work
 - iii. Proposed Manpower
 - iv. Proposed Equipment
 - v. Back-up Equipment
 - vi. Staging Area
 - vii. Soil Management
 - viii. Dewatering Requirements
 - ix. Maintenance of Vehicular Traffic
 - x. Maintenance of Pedestrian Traffic
 - xi. Maintenance of Homeowner Access
 - xii. Maintenance of Emergency Vehicular Traffic
 - xiii. Notification of Residents/Businesses
 - xiv. Erosion and Sedimentation Controls
- D. The work plans shall be submitted to the Owner for review at a minimum of ten (10) working days prior to starting a particular phase of construction. The work shall not proceed without the Owners authorization.

1.9 REVIEW OF SHOP DRAWINGS, PRODUCT DATA, WORKING DRAWINGS AND SAMPLES

A. The Engineer's review is for general conformance with the design concept and contract drawings. Markings or comments shall not be construed as relieving the Contractor from compliance with the contract plans and specifications or from departures therefrom. The Contractor remains responsible for details and accuracy, for coordinating the work with all other associated work and trades, for selecting fabrication processes, for techniques of assembly, and for performing work in a safe manner.

B. The review of shop drawings, data, and samples will be general. They shall not be construed:

1. as permitting any departure from the Contract requirements;
2. as relieving the Contractor of responsibility for any errors, including details, dimensions, and materials;
3. as approving departures from details furnished by the Engineer, except as otherwise provided herein.

C. If the shop drawings, data or samples as submitted describe variations and show a departure from the Contract requirements which the Engineer finds to be in the interest of the Owner and to be so minor as not to involve a change in Contract Price or time for performance, the Engineer may return the reviewed drawings without noting an exception.

D. Two (maximum) copies of shop drawings or product data will be returned to the Contractor. Samples will not be returned.

E. Submittals will be returned to the Contractor under one of the action codes indicated and defined on the transmittal form furnished by the Engineer.

F. Re-submittals will be handled in the same manner as first submittals. On re-submittals the Contractor shall direct specific attention, in writing, on the letter of transmittal and on resubmitted shop drawings by use of revision triangles or other similar methods, to revisions other than the corrections requested by the Engineer, on previous submissions. Any such revisions which are not clearly identified shall be made at the risk of the Contractor. The Contractor shall make corrections to any work done because of this type revision that is not in accordance to the Contract Documents as may be required by the Engineer.

G. Partial submittals may not be reviewed. The Engineer will be the only judge as to the completeness of a submittal. Submittals not complete will be returned to the Contractor, and will be considered "Rejected" until resubmitted. The Engineer may at his option provide a list or mark the submittal directing the Contractor to the areas that are incomplete.

H. If the Contractor considers any correction indicated on the shop drawings to constitute a change to the Contract Documents, the Contractor shall give written notice thereof to the Engineer at least seven working days prior to release for manufacture.

I. When the shop drawings have been completed to the satisfaction of the Engineer, the Contractor shall carry out the construction in accordance therewith and

shall make no further changes therein except upon written instructions from the Engineer.

1.10 GENERAL PROCEDURES FOR SUBMITTALS

- A. Coordination of Submittal Times: Prepare and transmit each submittal sufficiently in advance of performing the related work or other applicable activities, or within the time specified in the individual work sections, of the Specifications, so that the installation will not be delayed by processing times including disapproval re-submittal (if required), coordination with other submittals, inspection, testing (off-site and on-site), purchasing, fabrication, delivery and similar sequenced activities. No extension of time will be authorized because of the Contractor's failure to transmit submittals sufficiently in advance of the Work.

2.0 CERTIFICATION FORMS

- A. If specifically specified in other sections of these Specifications, the Contractor shall submit the applicable certification form for each item required, and in the form attached to this section, completely filled in and stamped.

2.1 CERTIFICATES OF COMPLIANCE

- A. Certificates of Compliance specified in the specifications shall include and mean certificates, manufacturer's certificates, certifications, certified copies, letters of certification and certificate of materials.
- B. The Contractor shall be responsible for providing Certificates of Compliance requested and specified in the technical specifications. Certificates are required for demonstrating proof of compliance with specification requirements and shall be executed in 6 copies unless otherwise specified. Each certificate shall be signed by an official authorized to certify on behalf of the manufacturing company and shall contain the name and address of the Supplier, the project name and location, and the quantity and date or dates of shipment or delivery to which the certificates apply. Copies of laboratory test reports submitted with certificates shall contain the name and address of the testing laboratory and the date or dates of the tests to which the report applies. Certification shall not be construed as relieving the Supplier from furnishing satisfactory material, if after tests are performed on selected samples, the material is found not to meet the specific requirements.

PART 2 - PRODUCTS (NOT USED)

PART 3 - EXECUTION (NOT USED)

CERTIFICATE OF DESIGN

The undersigned hereby certifies that he/she is a Professional Engineer registered in the state of Massachusetts and that he/she has been employed by (Name of Contractor) _____ to design _____ in accordance with Specifications Section _____ for the SEWER REHABILITATION PROJECT. The

undersigned further certifies that he/she has performed similar designs previously and has performed the design of the _____; that said design is in conformance with all applicable local, state, and federal codes, rules, and regulations and professional practice standards; that his/her signature and Professional Engineer (P.E.) Stamp have been affixed to all calculations and drawings used in, and resulting from, the design; and that the use of that stamp signifies the responsibility of the undersigned for that design.

The undersigned hereby certifies that he/she has Professional Liability Insurance or will be covered by an Employer Policy with limits of \$1,000,000.00 and a Certificate of Insurance is attached.

The undersigned hereby agrees to make all original design drawings and calculations available to the City of Salem or Owner's representative with seven (7) days following written request therefore by the Owner.

P.E. Name

Contractor's Name

Signature

Signature

Title

Title

Address

Address

END OF SECTION 01300

SECTION 01310

CONSTRUCTION PROGRESS SCHEDULES

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 1 Specification Sections, apply to this section.

1.2 SUMMARY

- A. CONTRACTOR shall prepare and submit to ENGINEER for review within 14 days after Notice to Proceed, a construction progress schedule.
- B. Normal working hours shall be 7:00 A.M. to 4:00 P.M. Monday through Friday excluding legal holidays. Excessive noise and neighbor complaints could necessitate a reduction in work hours allowed. The contractor shall work in consideration of their noise, their neighborhood impact, and be responsive to noise complaints. The contractor shall be permitted to work evening hours and/or weekends upon a written request to the Engineer and Owner a minimum of 48 hours in advance and written approval from the Owner is required.
- C. Night work may be established by CONTRACTOR as regular procedure with written permission of OWNER. Such permission, however, may be revoked at any time by OWNER if CONTRACTOR fails to maintain adequate equipment and supervision for proper prosecution and control of work at night.

1.3 FORM OF SCHEDULES

- A. Prepare schedules in form of a horizontal bar chart.
 - 1. Provide separate horizontal bar for each trade or operation.
 - 2. Horizontal time Scale: Identify first work date of each week.
 - 3. Scale and spacing to allow space for notations and future revisions.
- B. Format of Listings: Chronological order of start of each item of work.
- C. Identification of Listings: By major specification section numbers.

1.4 CONTENT OF SCHEDULES

A. Construction Progress Schedule:

1. Show complete sequence of construction by activity.
2. Show dates for beginning and completion of each major element of construction and installation dates for major terms of equipment. Elements shall include, but not limited to, the following:
 - a. Work plan submitted to Engineer
 - b. Shop drawing receipt from supplier/manufacturer submitted to ENGINEER, review and return to supplier/manufacture
 - c. Material and equipment order, manufacturer and delivery
 - d. Demolition and saw cutting
 - e. Construction of various facilities (water, sewer, drain)
 - f. Performance and Leakage Testing
 - g. Sewer and drain installation
 - h. Connection to existing sewers and drains
 - i. Subcontractor's items of work
 - j. Allowance for inclement weather
 - k. Temporary and Final Paving
 - l. Final cleanup
3. Show projected percentage of completion for each item as of first day of each month.

1.5 SCHEDULE REVISIONS

- A. Every 7 days CONTRACTOR shall revise construction schedule to reflect changes in progress of work.
- B. Indicate progress of each activity at date of submittal.
- C. Show changes occurring since previous submittal of schedule.
 1. Major changes in scope.
 2. Activities modified since previous submittal.
 3. Revised projects of progress and completion.
 4. Other identifiable changes.
- D. Provide a narrative report as needed to define.
 1. Problem areas, anticipated delays, and impact on schedule.

2. Corrective action recommended and its effect.
3. Effect of changes on schedules of other CONTRACTORS.

1.6 SUBMITTAL REQUIREMENTS

- A. For initial submittal of construction schedule and subsequent revisions thereof, furnish six (6) copies of schedule to ENGINEER.

PART 2 - PRODUCTS (NOT USED)

PART 3 - EXECUTION (NOT USED)

END OF SECTION 01310

SECTION 01400

QUALITY ASSURANCE

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this section.

1.2 SUMMARY

- A. This section covers Quality Assurance and Quality Control requirements for this contract.
- B. The Contractor is responsible for controlling the quality of work, including work of its subcontractors, and suppliers and for assuring the quality specified in the Technical Specifications is achieved.
- C. Refer to the Article 6 - Contractor's Responsibilities, paragraphs 6.01 6.02, 6.03, of the GENERAL CONDITIONS.

1.3 TESTING LABORATORY SERVICES

- A. All tests, which require the services of a laboratory to determine compliance with the Contract Documents, shall be performed by an independent commercial testing laboratory acceptable to the Engineer. The laboratory shall be staffed with experienced technicians, properly equipped, and fully qualified to perform the tests in accordance with the specified standards.
- B. Preliminary Testing Services: Unless otherwise specified, the Contractor shall be responsible for all testing laboratory services in connection with concrete and masonry materials and mix designs, structural steel inspections, the design of asphalt mixtures, gradation and compaction tests for structural and embankment fills, backfill materials, and all other tests and engineering data required for the Engineer's review of materials and equipment proposed to be used in the Work. The Contractor shall obtain the Engineer's acceptance of the testing laboratory before having services performed, and shall pay all costs for services.
- C. Quality Control Testing Services: Perform all quality control tests in the field or in the laboratory on concrete, masonry, structural steel, asphalt mixtures, moisture-density (Proctor) and gradation tests on structural and embankment fills, and backfill materials, in-place field density tests on structural and embankment fills, and other materials and equipment, during and after their incorporation in the Work. Field sampling and testing shall be performed in the general manner indicated in the specifications, with minimum interference with

construction operations. The time and location of field sampling and testing shall be approved by the Engineer, and may require such additional sampling and testing as necessary to determine that materials and equipment conform with data previously furnished by Contractor and with the Contract Documents.

- D. Arrangements for delivery of samples and test specimens to the testing laboratory will be made by the Contractor. The laboratory tests shall be performed within a reasonable time consistent with the specified standards. Furnish a written report of each test to the Engineer.
- E. Contractor shall furnish all sample materials and cooperate in the sampling and field testing activities, interrupting the Work when necessary. When sampling or testing activities are performed in the field, the Contractor shall furnish personnel and facilities to assist in the activities.
- F. The Contractor shall not retain any testing laboratory against which the Owner or the Engineer have reasonable objection, and if at any time during the construction process the services become unacceptable to the Owner, or the Engineer, either the Owner or the Engineer may direct in writing that such services be terminated. The request must be supported with evidence of improper testing or unreasonable delay. If the Engineer determines that sufficient cause exists, the Contractor shall terminate the services and engage a different testing laboratory.
- G. Transmittal of Test Reports: Written reports of testing and engineering data furnished by the Contractor for the Engineer's review of materials and equipment proposed to be used in the Work shall be submitted as specified for Shop Drawings.
- H. The testing laboratory shall furnish four copies of a written report of each test performed by laboratory personnel in the field or laboratory to the Contractor. Distribution shall be two copies of each test report to the Engineer's Representative, one copy to the Owner, and one copy for the Contractor within three days after each test is completed.

1.4 QUALITY ASSURANCE AND QUALITY CONTROL

- A. Copies of applicable referenced standards are not included in the Contract Documents. Where copies of standards are needed by the Contractor for superintendence and quality control of the work, the Contractor shall obtain a copy or copies directly from the publication source and maintain at the jobsite, available to the Contractor's personnel, subcontractors, and Engineer.
- B. Quality of Materials: Unless otherwise specified, all materials and equipment furnished for permanent installation in the Work shall conform to applicable standards and specifications and shall be new, unused, and free from defects and imperfections, when installed or otherwise incorporated in the Work. Material and equipment shall not be used by the Contractor for any purpose other than that intended or specified unless such use is authorized by the Engineer.

- C. Where so specified, products or workmanship shall also conform to the additional performance requirements included within the Contract Documents to establish a higher or more stringent standard or quality than that required by the referenced standard.

1.5 OFFSITE INSPECTION

- A. When the specifications require inspection of materials or equipment during the production, manufacturing, or fabricating process, or before shipment, such services shall be performed by an independent testing laboratory, or inspection organization acceptable to Engineer in conjunction with or by the Engineer.
- B. The Contractor shall give appropriate written notice to the Engineer not less than 30 days before offsite inspection services are required, and shall provide for the producer, manufacturer, or fabricator to furnish safe access and proper facilities and to cooperate with inspecting personnel in the performance of their duties.
- C. The inspection organization shall submit a written report to the Contractor who shall provide copies to the Engineer.

1.6 MATERIALS AND EQUIPMENT

- A. The Contractor shall maintain control over procurement sources to ensure that materials and equipment conform to specified requirements in the Contract Documents.
- B. The Contractor shall comply with manufacturer's printed instructions regarding all facets of materials and/or equipment movement, storage, installation, testing, startup, and operation. Should circumstances occur where the contract documents are more stringent than the manufacturer's printed instructions, the Contractor shall comply with the specifications. In cases where the manufacturer's printed instructions are more stringent than the contract documents, the Contractor shall advise the Engineer of the disparity and conform to the manufacturer's printed instructions. In either case, the Contractor is to apply the more stringent specification or recommendation, unless approved otherwise by the Engineer.

1.7 SHOP AND FIELD TESTING

- A. The Contractor is also responsible for providing the shop and field testing specified in the technical specification sections.
- B. The Contractor and its Subcontractor shall perform inspections, tests, and other services as required by the Contract Documents.
- C. Contractor shall provide twenty one days notice to the Engineer so that the Engineer may witness Contractor and/or Subcontractors off site and on site tests. The Engineer's witnessing of tests does not relieve the Contractor and/or

Subcontractors of their obligation to comply with the requirements of the Contract Documents.

1.8 MANUFACTURER'S FIELD SERVICES

- A. When specified in the technical specifications sections, the Contractor shall arrange for and provide technical representation from manufacturer's of respective equipment, items or components. The manufacturer's representative shall be a factory trained service engineer/technician with the type and length of experience specified in the technical specifications.
- B. Services Furnished Under This Contract: An experienced, competent, and authorized factory trained service engineer/technician representative of the manufacturer of each item of equipment for which field services are indicated in the specifications shall visit the site of the Work and inspect, operate, test, check, adjust if necessary, and approve the equipment installation. In each case, the manufacturer's service representative shall be present when the equipment is placed in operation. The manufacturer's service representative shall revisit the jobsite as often as necessary until all problems are corrected and the equipment installation and operation are satisfactory to the Engineer.

1.9 CERTIFICATION FORMS AND CERTIFICATES

- A. The Contractor shall be responsible for submitting the certification forms and certificates in conformance with the requirements specified in Section 01300 - SUBMITTALS.

PART 2 - PRODUCTS (NOT USED)

PART 3 – EXECUTION

3.1 QUALITY ASSURANCE AND QUALITY CONTROL

- A. Quality assurance and quality control is the responsibility of the Contractor, and the Contractor shall maintain control over construction and installation processes to assure compliance with specified requirements.
- B. Certifications for personnel, procedures, and equipment associated with special processes (e.g., welding, cable splicing, instrument calibration, surveying) shall be maintained in the Contractor's field office, available for inspection by the Engineer. Copies will be made available to the Engineer upon request.
- C. Means and methods of construction and installation processes are the responsibility of the Contractor, and at no time is it the intent of the Engineer or Owner to supercede or void that responsibility.

END OF SECTION 01400

SECTION 01500

TEMPORARY FACILITIES AND CONTROLS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 1 Specification Sections, apply to this section.

1.2 PLANT AND HOURS OF CONSTRUCTION

- A. Furnish plant and equipment which will be efficient, appropriate, and large enough to secure a satisfactory quality of work and a rate of progress which will insure the completion of the work within the Contract Time. If at any time such plant appears to the Engineer to be inefficient, inappropriate, or insufficient for securing the quality of work required or for producing the rate of progress aforesaid, he may order the Contractor to increase the efficiency, change the character, or increase the plant equipment, and the Contractor shall conform to such order. Failure of the Engineer to give such order shall in no way relieve the Contractor of his obligations to secure the quality of the work and rate of progress required.
- B. Work in streets, roadways and areas adjacent to them shall cease at noon on days before legal holidays and at noon on Fridays prior to Monday holidays.
- C. Normal working hours shall be 7:00 A.M. to 4:00 P.M. Monday through Friday excluding legal holidays. Excessive noise and neighbor complaints could necessitate a reduction in work hours allowed at the water plant and reservoirs. The contractor shall work in consideration of their noise, their neighborhood impact, and be responsive to noise complaints. The contractor shall be permitted to work evening hours and/or weekends upon a written request to the Engineer & Owner a minimum of 48 hours in advance and written approval from the Owner is required.

1.3 OCCUPYING PRIVATE LAND

- A. The Contractor shall not (except after written consent from the proper parties) enter or occupy with men, tools, materials, or equipment any land outside the rights of way or property of the Owner. A copy of the written consent shall be given to the Engineer, prior to entering or occupying private property.

1.4 PIPE LOCATIONS

- A. Exterior pipelines will be located substantially as indicated on the Drawings, but the right is reserved to the Owner, acting through the Engineer, to make such

modifications in location as may be found desirable to avoid interference with existing structures or for other reasons. Where fittings, etc., are noted on the Drawings, such notation is for the Contractor's convenience and does not relieve him from laying and jointing different or additional items where required.

1.5 DIMENSION OF EXISTING STRUCTURES

- A. Where the dimensions and locations of existing structures are of importance in the installation or connection of any part of the Work, the Contractor shall verify such dimensions and locations in the field before the fabrication of any material or equipment which is dependent on the correctness of such information.

1.6 OPEN EXCAVATIONS

- A. All open excavations shall be adequately safeguarded by providing temporary barricades, fencing, caution signs, lights, and other means to prevent accidents to persons and damage to property. The Contractor shall, at his own expense, provide suitable and safe bridges and other crossings for accommodating travel by pedestrians and workmen. Bridges provided for access during construction shall be removed when no longer required. The length or size of excavation will be controlled by the particular surrounding conditions, but shall always be confined to the limits prescribed by the Engineer. If the excavation becomes a hazard, or if it excessively restricts traffic at any point, the Engineer may require special construction procedures such as limiting the length of the open trench, prohibiting stacking excavated material in the street, and requiring that the trench shall not remain open overnight.
- B. The Contractor shall take precautions to prevent injury to the public due to open trenches. All trenches, excavated material, equipment, or other obstacles which could be dangerous to the public shall be well lighted at night.
- C. Costs incurred for public safety personnel to address unsafe conditions shall be the responsibility of the Contractor.

1.7 TEST PITS

- A. Exploratory Excavations or Test pits (for the purpose of determining subsurface conditions, for locating underground utilities or structures, or for determining the layout of proposed pipeline or structures) shall be excavated in advance of construction and backfilled by the Contractor at locations in areas where the Contractor deems it necessary to obtain subsurface information. Test pits shall be backfilled immediately after their purpose has been satisfied and the surface restored and maintained in a manner satisfactory to the Engineer.

1.8 INTERFERENCE WITH AND PROTECTION OF STREETS

- A. Contractor shall not close or obstruct any portion of a street, road, or private way without obtaining permits therefore from the proper authorities. If any street,

road or private way shall be rendered unsafe by the Contractor's operations, he shall make such repairs or provide such temporary ways or guards as shall be acceptable to the proper authorities.

- B. Streets, roads, private ways, and walks not closed shall be maintained passable and safe by the Contractor, who shall assume and have full responsibility for the adequacy and safety of provisions made therefore
- C. The Contractor shall, at least 24 hours in advance, notify the Police, Fire and School Departments in writing, with a copy to the Engineer, if the closure of a street or road is necessary. He shall cooperate with the Police Department in the establishment of alternate routes and shall provide adequate detour signs, plainly marked and well lighted, in order to minimize confusion.

1.9 CARE AND PROTECTION OF PROPERTY

- A. The Contractor shall be responsible for the preservation of all public and private property, and shall use every precaution necessary to prevent damage thereto. If any direct or indirect damage is done to public or private property by or on account of any act, omission, neglect, or misconduct in the execution of the work on the part of the Contractor, such property shall be restored by the Contractor, at his expense, to a condition similar or equal to that existing before the damage was done, or he shall make good the damage in other manner acceptable to the Engineer.
- B. Along the location of this work, all fences, walks, bushes, trees, shrubbery, and other physical features shall be protected and restored in a thoroughly workman like manner.

1.10 PROTECTION AND RELOCATION OF EXISTING STRUCTURES AND UTILITIES

- A. The Contractor shall assume full responsibility for the protection of all buildings, structures, and utilities, public or private, including poles, signs, services to buildings, utilities in the street, gas pipes, water pipes, hydrants, sewers, drains, and electric and telephone cables, whether or not they are shown on the Drawings. The Contractor shall carefully support and protect all such structures and utilities from injury of any kind. Any damage resulting from the Contractor's operations shall be repaired by him at his expense.
- B. Assistance will be given the Contractor in determining the location of existing services. The Contractor, however, shall bear full responsibility for obtaining all locations of underground structures and utilities (including existing water services, drain lines, and sewers). Services to buildings shall be maintained, and all costs or charges resulting from damage thereto shall be paid by the Contractor.

- C. Protection and temporary removal and replacement of existing utilities and structures as described in this section shall be a part of the work under the Contract and all costs in connection therewith shall be included in the Total Price Bid in the Bid Form.
- D. If, in the opinion of the Engineer, permanent relocation of a utility owned by the City of Salem is required, he may direct the Contractor, in writing, to perform the work. Work so ordered will be paid at the Contract unit prices, if applicable, or as extra work under Article 11 of the Supplementary Conditions. If relocation of a privately owned utility is required, the City of Salem will notify the Utility to perform the work as expeditiously as possible. The Contractor shall fully cooperate with the City of Salem and Utility, and shall have no claim for delay due to such relocation. The Contractor shall notify all utility companies in writing at least 72 hours (excluding Saturdays, Sundays, and Legal holidays) before excavating in any public way. Contractor shall also notify (Massachusetts Dig Safe, telephone number 1-800-322-4844) at least 72 hours prior to start of work.
- E. The Contractor shall coordinate the removal and replacement of traffic loops and signals, if required for the performance of the work, at no additional cost to the Owner.

1.11 INSPECTION OF WORK AWAY FROM THE SITE

- A. If work to be done away from the construction site is to be inspected on behalf of the Owner during its fabrication, manufacture, or testing, or before shipment, the Contractor shall give notice to the Engineer of the place and time where such fabrication, manufacture, testing, or shipping is to be done. Such notice shall be in writing and delivered to the Engineer in ample time so that the necessary arrangements for the inspection can be made.

1.12 COOPERATION WITHIN THIS CONTRACT

- A. All firms or persons authorized to perform any work under this Contract shall cooperate with General Contractor and his Subcontractors or trades, and shall assist in incorporating the work of other trades where necessary or required.
- B. Cutting and patching, drilling and fitting shall be carried out where required by the trade or subcontractor having jurisdiction, unless otherwise indicated herein or directed by the Engineer.

1.13 CLEANUP AND DISPOSAL OF EXCESS MATERIAL

- A. During the course of the work, the Contractor shall keep the site of his operations in as clean and as neat a condition as is possible. He shall dispose of all residue resulting from the construction work and, at the conclusion of the work, he shall remove and haul away any surplus excavation, broken pavement, lumber, equipment, temporary structures, and any other refuse remaining from

the construction operations, and shall leave the entire site of the work in a neat and orderly condition.

- B. In order to prevent environmental pollution arising from the construction activities related to the performance of this Contract, the Contractor and his subcontractors shall comply with all applicable Federal, State, and local laws, and regulations concerning waste material disposal, as well as the specific requirements stated in this section and elsewhere in the Specifications.
- C. The Contractor is advised that the disposal of excess excavated material in wetlands, stream corridors, and plains is strictly prohibited even if the permission of the property owner is obtained. Any violation of this restriction by the Contractor or any person employed by him, will be brought to the immediate attention of the responsible regulatory agencies, with a request that appropriate action be taken against the offending parties. Therefore, the Contractor will be required to remove the fill at his own expense and restore the area impacted.

1.14 PROTECTION OF CONSTRUCTION AND EQUIPMENT

- A. All newly constructed work shall be carefully protected from injury in any way. No wheeling or walking or placing of heavy loads on it shall be allowed and all portions injured shall be reconstructed by the Contractor at its own expense.
- B. All structures shall be protected in a manner approved by the Engineer. Should any of the floors or other parts of the structures become heaved, cracked, or otherwise damaged, all such damaged portions of the work shall be completely repaired and made good by the Contractor at his own expense and to the satisfaction of the Engineer.
- C. If, in the final inspection of the work, any defects, faults or omissions are found, the Contractor shall cause the same to be repaired or removed and replaced by proper materials and workmanship without extra compensation for the materials and labor required. Further, the Contractor shall be fully responsible for the satisfactory maintenance and repair of the construction and other work undertaken herein for at least the guarantee period described in the Contract Documents.
- D. The Contractor shall take all necessary precautions to prevent damage to any structure due to water pressure during and after construction and until such structure is accepted and taken over by the Owner.

1.15 INSTALLATION OF EQUIPMENT

- A. Special care shall be taken to ensure proper alignment for all equipment. Equipment shall be carefully aligned by qualified installers. The anchor bolts shall be set in place and the nuts tightened against the shims. After the alignments have been approved by the Engineer, the equipment shall be secured in place. The alignment of equipment shall be further checked after securing, and after

confirmation of all alignments, the equipment shall be firmly grouted in place as applicable. The Contractor shall be responsible for the exact alignment of equipment with associated piping, and under no circumstances, will "pipe springing" be allowed.

- B. All wedges, shims, filling pieces, keys, packing, red or white lead grout, or other materials necessary to properly align, level and secure apparatus in place shall be furnished by the Contractor. All parts intended to be plumb or level must be proven exactly so. Any grinding necessary to bring parts to proper bearing after erection shall be done at the expense of the Contractor.

1.16 TEMPORARY UTILITIES

- A. Temporary Light and Power: The Contractor shall at his own expense, provide his own temporary light and power as required for the prosecution and completion of work.
- B. Temporary Telephone: The Contractor shall at his own expense, provide his own temporary telephone as required for the prosecution and completion of work.
- C. Temporary Water: Water for drinking purposes and other usage will be provided by the Contractor at his own expense.
- D. Sanitary Provisions: The Contractor shall provide and maintain sanitary accommodations for the use of his employees and the Engineer, as may be necessary to comply with the requirements and regulations of the local and state departments of health.

1.17 WATER SUPPLY

- A. The Contractor shall make arrangements and pay for all water necessary for completion of construction operations under this contract.

1.18 ACCESS TO THE WORK

- A. The Contractor shall provide sufficient and proper facilities at all times for inspection of all work under this project in preparation or in progress, by the Owner, the agents and employees of the Owner, by authorized representatives of the State of Massachusetts and the Federal Government and by the Engineers.
- B. The Contractor shall furnish the Engineer or his authorized representative and other personnel mentioned above with such facilities and assistance as are necessary to ascertain performance of the work in accordance with the plans and specifications.

1.19 DUST CONTROL

- A. During the progress of the work, the Contractor shall conduct his operations and maintain the area of his activities, including sweeping and sprinkling of water as necessary, so as to minimize the creation and dispersion of dust. If the Engineer decides that it is necessary to use calcium chloride, and it is allowed by local authorities, for more effective dust control, the Contractor shall furnish and apply the material as directed.
- B. Contractor shall not apply the material without approval of the Engineer.
- C. Calcium chloride shall be commercial grade, furnished in 100 lb, 5-ply bags, stored under weatherproof cover and stacked alternately for ventilation. Application for dust control shall be at the rate of about 1/2 pound per square yard, unless otherwise directed by the Engineer.

1.20 POLLUTION CONTROL

- A. The Contractor shall conduct clean-up and disposal operations, as necessary, to comply with state and local ordinances and anti-pollution laws.
- B. Outdoor burning of rubbish and waste material on the site will not be permitted.
- C. Disposal of volatile fluid wastes (such as mineral spirits, oil, gasoline, or paint thinner) in storm or sanitary sewer systems or into streams or waterways is not permitted.

1.21 PRECAUTIONS DURING ADVERSE WEATHER

- A. During adverse weather and against the possibility thereof, the Contractor shall take all necessary precautions so that the Work may be properly done and satisfactory in all respects. When required, protection shall be provided by use of tarpaulins, wood and building-paper shelters, or other suitable means.
- B. During cold weather, materials shall be preheated, if required, and the materials and adjacent structure into which they are to be incorporated shall be made and kept sufficiently warm so that a proper bond will take place and a proper curing, aging, or drying will result. Protected spaces shall be artificially heated by suitable means, which will result in a moist or a dry atmosphere according to the particular requirements of the work being protected. Ingredients for concrete and mortar shall be sufficiently heated so that the mixture will be warm throughout when used.

1.22 PROJECT SIGN

1.23 TEMPORARY STOCKPILING/STAGING AREA

- A. A staging area will not be provided by the Owner. Contractor shall identify a location for a staging area and stockpile area, secure permission from the property owner in writing, and receive permission from the City before mobilizing to project area.

PART 2 - PRODUCTS (NOT USED)

PART 3 - EXECUTION (NOT USED)

END OF SECTION 01500

SECTION 01505

MOBILIZATION

PART 1 - GENERAL

1.1 DESCRIPTION

- A. This section includes mobilization consisting of obtaining all permits; moving all plant and equipment onto the site required for the first month's operations; furnishing and erecting plants, temporary buildings, and project and other construction facilities; erecting project signs and traffic management signs; implementing security features and requirements; all as required for the proper performance and completion of the Work. Mobilization shall further include the following principal items:

1. Installing temporary construction power, wiring, and lighting facilities.
2. Developing construction water supply.
3. Providing field office trailers for the CONTRACTOR and the ENGINEER as required, complete with all specified furnishings, office equipment, communications facilities, fax machines, computers, and utility services.
4. Providing on-site sanitary facilities and construction trailer.
5. Arranging for and erection of Contractor's work and storage yard(s), including temporary sewer cleaning debris storage area.
6. Provide written permission from property owners for use of Contractor's proposed staging (stockpile area(s)).
7. Having all OSHA required notices and establishment of safety programs.
8. Having the Contractor's superintendent at the job site full time.
9. Submitting initial submittals, including work plans and detailed project Schedule.
10. Furnish and install project sign(s).

PART 2 - PRODUCTS (NOT USED)

PART 3 - EXECUTION (NOT USED)

END OF SECTION 01505

SECTION 01560

TEMPORARY ENVIRONMENTAL CONTROLS

PART 1 - GENERAL

1.1 DESCRIPTION

- A. This section includes temporary environmental controls necessary for the project including dust abatement, rubbish control, sanitation, chemicals, and cultural resources.

1.2 EXPLOSIVES AND BLASTING

- A. The use of explosives on the Work will not be permitted.

1.3 DUST ABATEMENT AND CONTROL

- A. The Contractor shall prevent its operation from producing dust in amounts damaging to property, cultivated vegetation, or domestic animals, or causing a nuisance to persons living in or occupying buildings in the vicinity. The Contractor shall be responsible for any damage resulting from dust originating from its operations. The dust abatement measures shall be continued until the Contractor is relieved of further responsibility for the Work. Dust abatement measures shall include but not be limited to spraying water, applying calcium chloride, or placing temporary pavement on and around trenches and at work sites.
- B. During excavation of soil/fill material dust shall be controlled to limit potential spread of contaminants and potential exposure of contaminants to workers and the public.
- C. Ambient dust levels at the site shall be monitored by the Contractor prior to construction. During construction, real-time dust monitoring shall be conducted during any soil/fill handling activities. The monitoring shall consist of total dust testing using MIE, Inc. Miniram PDM-3 Dust Monitors, or like instruments. The total dust criteria at the site shall conform to the requirements of the HASP. Should fugitive dust quantities exceed 20 percent of the ambient level, the Contractor shall perform additional measures to reduce the total dust concentrations.
- D. Nuisance dust levels may be encountered during regrading activities and excavation. Dust levels shall be reduced by pre-wetting the surface soils and by establishing and maintaining clean access roads. The Contractor's Dust, Vapor, and Odor Control Plan shall describe the procedures and materials to minimize dust.

- E. At a minimum, the Contractor shall provide clean water, free from salt, oil, and other deleterious materials.
- F. Areas of exposed earth to be excavated shall be lightly sprayed with water before excavation. Additional water spray may be utilized only when any indication of excessive dust is observed. The Contractor shall minimize the use of water within the limits of excavation.
- G. Access roads shall be sprayed with water on a regular basis to minimize the generation of dust.

1.4 RUBBISH CONTROL

- A. During the progress of the Work, the Contractor shall keep the Site and other areas used by it in a neat and clean condition and free from any accumulation of rubbish. The Contractor shall dispose of all rubbish and waste materials of any nature occurring at the Site and shall establish regular intervals of collection and disposal of such materials and waste. The Contractor shall also keep its haul roads free from dirt, rubbish, and unnecessary obstructions resulting from its operations. Disposal of all rubbish and surplus materials shall be off the Site in accordance with local codes and ordinances governing locations and methods of disposal, and in conformance with all applicable safety laws, and to the particular requirements of Part 1926 of the OSHA Safety and Health Standards for Construction.
- B. In the event that the Contractor's work zone restricts municipal trash or recycling collection or makes it difficult for residents to bring trash or recycling to the street, the Contractor shall collect all trash and recycling within the work zone and transport it outside the work zone for municipal collection. Return trash and recycling receptacles back to respective properties.

1.5 SANITATION

- A. Toilet Facilities: Fixed or portable chemical toilets shall be provided wherever needed for the use of employees. Toilets at construction job sites shall conform to the requirements of Part 1926 of the OSHA Standards for Construction.
- B. Sanitary and Other Organic Wastes: The Contractor shall establish a regular daily collection of all sanitary and organic wastes. All wastes and refuse from sanitary facilities provided by the Contractor or organic material wastes from any other source related to the Contractor's operations shall be disposed of away from the Site in a manner satisfactory to the Work and in accordance with all laws and regulations pertaining thereto.

1.6 CHEMICALS

- A. All chemicals used during project construction or furnished for project operation, whether defoliant, soil sterilant, herbicide, pesticide, disinfectant, polymer, reactant

or of other classification, shall show approval of either the U.S. Environmental Protection Agency or the U.S. Department of Agriculture. Use of all such chemicals and disposal of residues shall be in strict accordance with the printed instructions of the manufacturer.

1.7 CULTURAL RESOURCES

- A. The Contractor's attention is directed to the National Historic Preservation Act of 1966 (16 U.S.C. 470) and 36 CFR 800 which provides for the preservation of potential historical architectural, archaeological, or cultural resources (hereinafter called "cultural resources").
- B. The Contractor shall conform to the applicable requirements of the National Historic Preservation Act of 1966 as it relates to the preservation of cultural resources.
- C. In the event potential cultural resources are discovered during subsurface excavations at the site of construction, the following procedures shall be instituted:
 - 1. The Engineer will issue a Field Order directing the Contractor to cease all construction operations at the location of such potential cultural resources find.
 - 2. Such Field Order shall be effective until such time as a qualified archaeologist can be called to assess the value of these potential cultural resources and make recommendations to the State Historic Preservation Office.
- D. If the archaeologist determines that the potential find is a bona fide cultural resource, at the direction of the State Historic Preservation Office, the Contractor shall suspend work at the location of the find under the provisions for changes contained in Articles 10, 11, and 12 of the General Conditions.

1.8 NOISE CONTROL

- A. The Contractor shall comply with the City of Salem Noise Ordinance.

PART 2 – PRODUCTS (Not Used)

PART 3 – EXECUTION (Not Used)

END OF SECTION 01560

SECTION 01568

EROSION CONTROL, SEDIMENTATION AND CONTAINMENT OF CONSTRUCTION MATERIALS

PART 1 – GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 1 Specification Sections, apply to this section.

1.2 SUMMARY

- A. Provide all work and take all measures to control soil erosion resulting from construction operations, prevent flow of sediment from construction site, and contain construction materials (including excavation and backfill) within protected working area as to prevent damage to any stream or wetlands.

1.3 SUBMITTALS

- A. Shop Drawings: Submit the following in accordance with Section 01300 - SUBMITTAL PROCEDURES:
 - 1. Two weeks prior to the start of the work, submit to Engineer, for review, a plan with detailed sketches showing the proposed methods to be used for controlling erosion during construction which include use of a sedimentation tank, silt sacks, and erosion and sedimentation barrier.
 - 2. Submit to the Engineer manufacturer's data sheets for filter fabric, silt socks, silt sacks, mulch, salt hay, and sedimentation tank.

1.4 QUALITY ASSURANCE

- A. Use acceptable procedures, including use of water diversion structures, diversion ditches, settling basins, and sediment traps.
- B. Operations restricted to areas of work indicated on drawings and area which must be entered for construction of temporary or permanent facilities.
- C. If construction materials are washed away during construction, remove materials from fouled areas.
- D. Stabilize diversion outlets by means acceptable to Engineer.

- E. Engineer has authority to limit surface area of erodible earth material exposed by clearing and grubbing, excavation, borrow and fill operations and to direct immediate permanent or temporary pollution control measures to prevent contamination of any stream or wetlands, including construction of temporary berms, dikes, dams, sediment basins, sediment traps, slope drains, and use of temporary mulches, mats, or other control devices or methods as necessary to control erosion.

PART 2 – PRODUCTS

2.1 BALES

- A. Hay or straw or other suitable material acceptable to Engineer.
 - 1. Twine for bale bales shall be biodegradable.
 - 2. Hay bales shall be salt marsh hay as approved by the City of Salem Conservation Commission.

2.2 WOOD STAKES

- A. 2 in. by 2 in. by 3 ft.

2.3 FILTER FABRIC

- A. Provide silt fence conforming to the requirements specified in Section 02273.

2.4 SILT SOCK

- A. Silt sock or mulch sock shall be 12”-18” and manufactured by Silt Soxx or equal.

2.5 MULCH

- A. Mulch and/or compost materials used to fill silt sock shall be approved by the [City of Salem] Conservation Agent.

2.6 SILT SACKS

- A. Provide woven poly propylene fabric bags to prevent sedimentation from entering existing catch basins. Bags shall be manufactured by ACF Environmental or equal.

2.6 STRAW WATTLES

- A. Straw wattles shall consist of certified seed free agricultural straw inside and flexible and durable tubular netting with knotted ends. Wattles shall be 12-inches in diameter and staked to the ground every 3-4 feet.

- B. Straw wattles shall overlap horizontally at least one-foot every prevent bypass. Tubular black polypropylene shall be photodegradable.

PART 3 – EXECUTION

3.1 GENERAL

- A. Do not discharge chemicals, fuels, lubricants, bitumen, raw sewage and other harmful waste into or alongside any body of water or into natural or man-made channels.
- B. Contractor shall be responsible for all the requirements of the City of Salem Conservation Commission Letter Permit or Order of Conditions, if applicable.

3.2 INSTALLATION

- A. Install sedimentation barriers in all locations as directed, surrounding base of all deposits of stored excavated material outside of disturbed area, and where directed by the Engineer.
- B. Install sedimentation barriers immediately after site is cleared and before trench excavation. Locate sedimentation barriers, surrounding stored material, approximately 6 ft. from material.
- C. Hold bales in place with two 2 in. by 2 in. by 3 ft. stakes so that each bale is butted tightly against ad-joining bale thereby precluding short-circuiting of erosion check.
- D. Construct mulch sock berms or diversions to intercept and divert runoff water from critical areas.
- E. Protect catch basins from sedimentation by installing silt sacs, hay bales around the basin or siltation fabric under grating casting.
- F. Discharge silt-laden water from excavations into sedimentation tank and then onto filter fabric mat, sedimentation basin, and/or baled hay or straw sediment traps to ensure that only sediment-free water is returned to watercourses.
- G. Do not place excavated soil material adjacent to water-course in manner that will cause it to wash away by high water or runoff.
- H. Prevent damage to vegetation by excessive watering or silt accumulation in the discharge area. Prevent damage to vegetation adjacent to or outside of construction area limits.

- I. Prevent indiscriminate, arbitrary, or capricious operation of equipment in streams, wetlands or surface waters. Do not dump spoiled material into any streams, wetlands, surface waters or unspecified locations.
- J. Do not pump silt-laden water from trenches or excavations into surface waters, streams, wetlands, or natural or man-made channels leading thereto.
- K. Do not dispose of trees, brush, debris, paints, chemicals, asphalt products, concrete curing compounds, fuels, lubricants, insecticides, wash water from concrete trucks or hydroseeders, or any other pollutant in streams, wet-lands, surface waters, or natural or man-made channels leading thereto, or unspecified locations.
- L. Do not alter flow line of any stream unless indicated or specified.
- M. Clean and dispose of debris from sedimentation tanks, basins, and barriers on a weekly basis.
- N. Upon completion of work and upon approval of Conservation Commission and Engineer, remove and dispose of sedimentation barriers.

3.3 SEDIMENTATION AND EROSION CONTROL:

- A. The Contractor shall plan and execute all operations, particularly those associated with excavation and backfilling, in such a manner as to prohibit excavated and exposed fill or other foreign material to be washed or otherwise carried into streets, drains or waterways. The water quality of waterways, or storm drains shall not be degraded due to construction operations.
- B. It is the intent of these Specifications to prevent the unnecessary occurrence of sedimentation or siltation of storm drains and watercourses. In the event that sedimentation or siltation prevention measures used by the Contractor prove to be inadequate the Contractor shall be required to adjust his/her operations to the extent necessary to prevent any such sedimentation or siltation from occurring. Any damage or degradation caused by inadequate controls must be restored by the Contractor at no additional cost to the Owner.
- C. Provide positive means of erosion control such as mulch sock barrier around construction to carry off surface water. Erosion control measures such as sedimentation basins, hay bale or mulch sock check dams, and other equivalent techniques shall be used as appropriate. Offsite surface water shall be diverted around the site to a downstream channel ahead of siltation barriers. Flow of surface water into excavated areas shall be prevented.
- D. The Contractor shall keep drains, streams and other water crossings clear of mud, silt, debris, or other objectionable materials resulting from construction operations.

- E. The Contractor shall use temporary pavement geotextile and mulching to protect areas exposed during construction. He/she shall minimize the amount of bare earth exposed at any one time during construction, and he/she shall also minimize the length of time bare earth is exposed.
- F. Baled hay and filter materials shall be placed to form temporary water stops, dams, diversions, dikes, berms, and for other uses connected with water pollution control. As directed by the Owner and/or their representative, bales may be disposed by the Contractor as best suits field conditions and requirements.
- G. On sloping terrain, hay bales may be used to trap sediment until vegetation has become established. The details of their placement shall be incorporated into the Erosion and Sedimentation Control Plan, as approved by the Owner or Engineer.
- H. Sediment-laden water that is being pumped from the trenches or excavations shall not be pumped directly into storm drains or water courses. Sedimentation tanks used in conjunction with hay bale or mulch sock sedimentation basins or other means acceptable to the Owner or Engineer shall be used for this purpose.
- I. All excavated waste materials and collected solid waste, shall be handled in accordance with the Contractor-prepared, Owner or Engineer -accepted, Waste Management Plan.
- J. The Contractor shall include the cost of sedimentation and erosion control work in his total bid price.

3.4 PROTECTION OF STREAMS WETLANDS, AND SURFACE WATER:

- A. Care shall be taken to prevent or reduce to a minimum any damage to any stream, drainage ditch, storm drain or sewer from pollution by debris, sediment, or other material, or from the manipulation of equipment and/or materials in or near such streams. Water that has been used for washing or processing, or that contains oils or sediments that will reduce the quality of the water in the stream, shall not be directly returned to the stream. Such water will be diverted through a sedimentation tank and sedimentation basin or filter before being directed into the streams.
- B. The Contractor shall not discharge water from dewatering operations directly into any live or intermittent stream, channel, wetlands, surface water, or any storm sewer within express written authority or permit from the governing agency. Water from dewatering operations shall be treated by filtration, sedimentation tanks and settling basins, or other approved method to reduce the amount of sediment contained in the water to allowable levels.
- C. All preventative measures shall be taken to avoid spillage of petroleum products and other pollutants. In the event of any spillage, prompt remedial action shall be taken in accordance with the Massachusetts Department of Environmental

Protection regulations. The Contractor shall be responsible for returning the site to pre-existing conditions at no additional cost to the Owner.

END OF SECTION 01568

SECTION 01600

CONTROL OF MATERIALS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 1 Specification Sections, apply to this section.

1.2 APPROVAL OF MATERIALS

- A. Unless otherwise specified, only new materials and equipment shall be incorporated in the work. All materials and equipment furnished by the Contractor shall be subject to the inspection and approval of the Engineer. No material shall be delivered to the work without prior approval of the Engineer.
- B. As specified in Section 01300, the Contractor shall submit to the Engineer, data relating to materials and equipment he proposes to furnish for the work. Such data shall be in sufficient detail to enable the Engineer to identify the particular product and to form an opinion as to its conformity to the specifications.
- C. Facilities and labor for handling and inspection of all materials and equipment shall be furnished by the Contractor. If the Engineer requires, either prior to beginning or during the progress of the work, the Contractor shall submit additional samples or materials for such special tests as may be necessary to demonstrate that they conform to the specifications. Such samples shall be furnished, stored, packed, and shipped as directed at the Contractor's expense. Except as otherwise noted, the Owner will make arrangements for and pay for the tests.
- D. Any delay of approval resulting from the Contractor's failure to submit samples or data promptly shall not be used as a basis of a claim against the Owner or the Engineer.
- E. In order to demonstrate the proficiency of workmen or to facilitate the choice among several textures, types, finishes, and surfaces, the Contractor shall provide such samples of workmanship or finish as may be required.
- F. The materials and equipment used on the work shall correspond to the approved samples or other data.

PART 2 - PRODUCTS (NOT USED)

PAGE 3 - EXECUTION (NOT USED)

END OF SECTION 01600

SECTION 01610

DELIVERY, STORAGE AND HANDLING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 1 Specification Sections, apply to this section.

1.2 SUMMARY

- A. This section specifies the general requirements for the delivery, handling, storage and protection for all items required in the construction of the work. Specific requirements, if any, are specified with the related item.

1.3 TRANSPORTATION AND DELIVERY

- A. Transport and handle items in accordance with manufacturer's printed instructions.
- B. Schedule delivery to reduce long term on-site storage prior to installation and/or operation. Under no circumstances shall equipment be delivered to the site more than one month prior to installation without written authorization from the Engineer.
- C. Coordinate delivery with installation to ensure minimum holding time for items that are hazardous, flammable, easily damaged or sensitive to deterioration.
- D. Deliver products to the site in manufacturer's original sealed containers or other packing systems, complete with instructions for handling, storing, unpacking, protecting and installing.
- E. All items delivered to the site shall be unloaded and placed in a manner which will not hamper the Contractor's normal construction operation or those of subcontractors and other contractors and will not interfere with the flow of necessary traffic.
- F. Provide equipment and personnel to unload all items delivered to the site.
- G. Promptly inspect shipment to assure that products comply with requirements, quantities are correct, and items are undamaged. For items furnished by others (i.e. Owner, other Contractors), perform inspection in the presence of the Engineer. Notify Engineer verbally, and in writing, of any problems.

1.4 STORAGE AND PROTECTION

- A. Store and protect products in accordance with the manufacturer's printed instructions, with seals and labels intact and legible. Storage instruction shall be studied by the Contractor and reviewed with the Engineer by him. Instructions shall be carefully followed and a written record of this kept by the Contractor. Arrange storage to permit access for inspection.

- B. Store loose granular materials on solid flat surface in a well-drained area. Prevent mixing with foreign matter.
- C. Cement and lime shall be stored under a roof and off the ground and shall be kept completely dry at all times. All structural, miscellaneous and reinforcing steel shall be stored off the ground or otherwise to prevent accumulation of dirt or grease, and in a position to prevent accumulations of standing water and to minimize rusting. Beams shall be stored with the webs vertical. Precast concrete shall be handled and stored in a manner to prevent accumulations of dirt, standing water, staining, chipping or cracking. Brick, block and similar masonry products shall be handled and stored in manner to reduce breakage, cracking and spalling to a minimum.
- D. All mechanical and electrical equipment and instruments subject to corrosive damage by the atmosphere (even though covered by canvas) shall be stored in a weathertight building to prevent injury. The building may be a temporary structure on the site or elsewhere, but it must be satisfactory to the Engineer. Building shall be provided with ventilation to prevent condensation. Maintain temperature and humidity within range required by manufacturer.
 - 1. All equipment shall be stored fully lubricated with oil, grease and other lubricants unless otherwise instructed by the manufacturer.
 - 2. Moving parts shall be rotated a minimum of once weekly to insure proper lubrication and to avoid metal-to-metal "welding". Upon installation of the equipment, the Contractor shall start the equipment, at least half load, once weekly for an adequate period of time to ensure that the equipment does not deteriorate from lack of use.
 - 3. Lubricants shall be changed upon completion of installation and as frequently as required thereafter during the period between installation and acceptance. New lubricants shall be put into the equipment at the time of acceptance.
 - 4. Prior to acceptance of the equipment, the Contractor shall have the manufacturer inspect the equipment and certify that its condition has not been detrimentally affected by the long storage period. Such certifications by the manufacturer shall be deemed to mean that the equipment is judged by the manufacturer to be in a condition equal to that of equipment that has been shipped, installed, tested and accepted in a minimum time period. As such, the manufacturer will guaranty the equipment equally in both instances. If such a certification is not given, the equipment shall be judged to be defective. It shall be removed and replaced at the Contractor's expense.

PART 2 - PRODUCTS (NOT USED)

PART 3 - EXECUTION (NOT USED)

END OF SECTION 01610

SECTION 01700

CONTRACT CLOSEOUT

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 1 Specification Sections, apply to this section.

1.2 SUMMARY

- A. This section specifies administrative and procedural requirements for project closeout, including but not limited to:
 - 1. Closeout procedures.
 - 2. Final cleaning.
 - 3. Adjusting.

1.3 RELATED WORK

- A. Warranties and Bonds are included in Section 01740.

1.4 CLOSEOUT PROCEDURES

- A. Submit written certification that Contract Documents have been reviewed, Work has been inspected, and that Work is complete in accordance with Contract Documents and ready for Engineer's inspection.
- B. Provide submittals to Engineer that are required by governing or other authorities.
- C. Submit final Application for Payment identifying total adjusted Contract Sum, previous payment, and sum remaining due.
- D. Submit all warranties.
- E. Submit written notice that all subcontractors and suppliers have been paid in full.
- F. Submit written notice showing the disposition of all insurance filings and claims.
- G. Copy of "Statement of Compliance" filed with the Division of Labor and Workforce Development, as required under the State Wage Rate Provisions.

1.5 FINAL CLEANING

- A. Complete the following cleaning operations before requesting inspection for Certification of Substantial Completion.
 - 1. Remove labels that are not permanent labels.
 - 2. Clean exposed exterior and interior hard-surfaced finishes to a dust-free condition, free of stains, films and similar foreign substances. Restore reflective surfaces to their original reflective condition. Leave concrete floors broom clean.
 - 3. Contractor shall have the installing Subcontractor shall wipe surface of mechanical and electrical equipment. Remove excess lubrication and other substances. Clean plumbing fixtures to a sanitary condition. Clean light fixtures and lamps.
 - 4. Clean the site, including landscape development areas, of rubbish, litter and other foreign substances. Sweep paved areas broom clean; remove stains, spills and other foreign deposits. Rake grounds that are neither paved nor planted, to a smooth even-textured surface.

1.6 ADJUSTING

- A. Adjust operating products and equipment to ensure smooth and unhindered operation.

PART 2 - PRODUCTS (NOT USED)

PART 3 - EXECUTION (NOT USED)

END OF SECTION 01700

SECTION 01710

CLEANING UP

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 1 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. During its progress, the work and the adjacent areas affected thereby shall be cleaned up and all rubbish, surplus materials, and unneeded construction equipment shall be removed and all damage repaired so that the public and property owners will be inconvenienced as little as possible.
- B. Where material or debris has washed or flowed into or been placed in existing watercourses, ditches, gutters, drains, pipes structures, work done under this contract, or elsewhere during the course of the Contractor's operations, such material or debris shall be entirely removed and satisfactorily disposed of during the progress of the work, and the ditches, channels, drains, pipes, structures, and work, etc., shall, upon completion of the work, be left in a clean and neat condition.
- C. On or before the completion of the work, the Contractor shall, unless otherwise especially directed or permitted in writing, tear down and remove all temporary buildings and structures built by him; shall remove all temporary works, tools, and machinery or other construction equipment furnished by him; shall remove, acceptably disinfect, and cover all organic matter and material containing organic matter in, under, and around privies, houses, and other buildings used by him; shall remove all rubbish from any grounds which he has occupied; and shall leave the roads and all parts of the premises and adjacent property affected by his operations in a neat and satisfactory condition.
- D. The Contractor shall thoroughly clean all materials and equipment installed by him and his sub-contractors, and on completion of the work shall deliver it undamaged and in fresh and new-appearing condition. All mechanical equipment shall be left fully charged with lubricant and ready for operation.
- E. The Contractor shall restore or replace, when and as directed, any public or private property damaged by his work, equipment, or employees, to a condition at least equal to that existing immediately prior to the beginning of operations. To this end the Contractor shall do as required all necessary highway or driveway, walk, and landscaping work. Suitable materials, equipment, and methods shall be used for such restoration. The restoration of existing property or structures shall be done as promptly as practicable as work progresses and shall not be left until the end of the contract period.

END OF SECTION 01710

SECTION 01740

WARRANTIES AND BONDS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 1 Specification Sections, apply to this Section.

1.2 SUMMARY

- A. This Section specifies general administrative and procedural requirements for warranties and bonds required by the Contract Documents, including manufacturer's standard warranties on products and special warranties.

1.3 RELATED WORK

- A. Refer to General Conditions of the Contract for the general requirements relating to warranties and bonds.
- B. General closeout requirements are included in Section 01700 Project Closeout.
- C. Specific requirements for warranties for the Work and products and installations that are specified to be warranted are included in the individual Sections of Division 2 through 16.
- D. Certifications and other commitments and agreements for continuing services to Owner are specified elsewhere in the Contract Documents.

1.4 SUBMITTALS

- A. Submit written warranties to the Owner prior to the date fixed by the Engineer for Substantial Completion. If the Certificate of Substantial Completion designates a commencement data for warranties other than the date of Substantial Completion for the Work, or a designated portion of the Work, submit written warranties upon request of the Owner.
- B. When a designated portion of the Work is completed and occupied or used by the Owner, by separate agreement with the Contractor during the construction period, submit properly executed warranties to the Owner within fifteen days of completion of that designated portion of the Work.
- C. When a special warranty is required to be executed by the Contractor, or the Contractor and a subcontractor, supplier or manufacturer, prepare a written document that contains appropriate terms and identification, ready for execution by the required parties. Submit a draft to the Engineer for approval prior to final execution.

- D. Refer to individual Sections of Divisions 2 through 16 for specific content requirements, and particular requirements for submittal of special warranties.
- E. At Final Completion, compile two copies of each required warranty and bond properly executed by the Contractor, or by the Contractor, subcontractor, supplier, or manufacturer. Organize the warranty documents into an orderly sequence based on the table of contents of the Project Manual.
- F. Bind warranties and bonds in heavy-duty, commercial quality, durable 3-ring vinyl covered loose-leaf binders, thickness as necessary to accommodate contents, and sized to receive 8-1/2-in. by 11-in. paper.
- G. Table of Contents: Neatly typed, in the sequence of the Table of Contents of the Project Manual, with each item identified with the number and title of the specification Section in which specified, and the name of the product or work item.
- H. Provide heavy paper dividers with celluloid covered tabs for each separate warranty. Mark the tab to identify the product or installation. Provide a typed description of the product or installation, including the name of the product, and the name, address and telephone number of the installer, supplier, and manufacturer.
- I. Identify each binder on the front and the spine with the typed or printed title "WARRANTIES AND BONDS," the Project title or name, and the name, address, and telephone numbers of the Contractor and equipment supplier.
- J. When operating and maintenance manuals are required for warranted construction, provide additional copies of each required warranty, as necessary, for inclusion in each required manual.

1.5 WARRANTY REQUIREMENT

- A. Related Damages and Losses: When correcting warranted Work that has failed, remove and replace other Work that has been damaged as a result of such failure or that must be removed and replaced to provide access for correction of warranted Work.
- B. Reinstatement of Warranty: When Work covered by a warranty has failed and been corrected by replacement or rebuilding, reinstate the warranty by written endorsement. The reinstated warranty shall be equal to the original warranty with an equitable adjustment for depreciation.
- C. Replacement Cost: Upon determination that Work covered by a warranty has failed, replace or rebuild the Work to an acceptable condition complying with requirements of Contract Documents. The Contractor is responsible for the cost of replacing or rebuilding defective Work regardless of whether the Owner has benefited from use of the Work through a portion of its anticipated useful service life.
- D. Owner's Recourse: Written warranties made to the Owner are in addition to implied warranties, and shall not limit the duties, obligations, rights and remedies otherwise

available under the law, nor shall warranty periods be interpreted as limitations on time in which the Owner can enforce such other duties, obligations, rights or remedies.

- E. Rejection of Warranties: The Owner reserves the right to reject warranties and to limit selections to products with warranties not in conflict with requirements of the Contract Documents.
- F. The Owner reserves the right to refuse to accept Work for the Project where a special warranty, certification, or similar commitment is required on such Work or part of the Work, until evidence is presented that entities required to countersign such commitments are willing to do so.
- G. Disclaimers and Limitations: Manufacturer's disclaimers and limitations on product warranties do not relieve the Contractor of the warranty on the Work that incorporates the products, nor does it relieve suppliers, manufacturers, and subcontractors required to countersign special warranties with the Contractor.

1.6 DEFINITION

- A. Standard Product Warranties are pre-printed written warranties published by individual manufacturers for particular products and are specifically endorsed by the manufacturer to the Owner.
- B. Special Warranties are written warranties required by or incorporated in the Contract Documents, either to extend time limits provided by standard warranties or to provide greater rights for the Owner.

PART 2 - PRODUCTS - (NOT USED)

PART 3 - EXECUTION - (NOT USED)

END OF SECTION 01740

SECTION 01850

TRAFFIC MANAGEMENT

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this section.

1.2 SUMMARY

- A. This section includes the following:
 - 1. Pedestrian and vehicular traffic and other safety control devices, requirements and management for the protection of the traveling public and working personnel during construction and related operations, as approved by the Owner.
 - 2. The design, application, and installation of all devices required by this section shall conform to the requirements of the Manual on Uniform Traffic Control Devices (MUTCD) and Part VI Latest Edition, published by the U. S. DOT, latest edition, American Disabilities Act (ADA), and the Commonwealth of Massachusetts, Highway Department (MHD), Standard Specifications for Highways and Bridges, Section 850, except as modified herein.
 - 3. Traffic control during construction and maintenance operations includes installing and maintaining temporary pedestrian and construction facilities, furnishing, installing, inspecting, resetting, and removing channelization devices necessary to maintain pedestrian and vehicular traffic during construction and fencing of excavations as required.
 - 4. "Approved by the Owner" throughout this Section shall mean the approval of the City of Salem.

1.3 SUBMITTALS

- A. Shop Drawings: Submit the following in accordance with Section 01300 – SUBMITTAL PROCEDURES:
 - 1. Traffic Management Plan: Where designs for pedestrian and traffic control devices are not indicated on the Contract Drawings, the Contractor shall submit to the Owner for approval, a traffic management plan, complete with details of the proposed methods, including materials.

2. Shop Drawings

- a. Submit complete shop drawings for staged construction, and temporary pedestrian and construction facilities and sidewalks, as needed, certified by a Professional Engineer registered in the Commonwealth of Massachusetts.
- b. Show on the shop drawings all materials, including traffic control devices, signs and methods of installation.
- c. Include with the shop drawings alignment tapers, lane widths, police detail locations, temporary pavement markings, barriers and traffic control device spacing.

3. Safety Signing for Construction Operations. Where not indicated on the Contract Drawings, the Contractor shall submit temporary pedestrian and construction facilities plan and sign placement and sign size sketches showing the proposed sign setups he intends to use to provide the necessary traffic control and protection during the progress of the work, plus the sign and legend size and layout. These sketches shall be submitted to the Owner for review and approval before work begins.

4. The Contractor shall submit to the Owner the information required by this section a minimum of 14 working days prior to the start of construction and prior to the start of construction at any new location throughout the duration of work under this contract.

5. Before starting any work under this Contract, the Contractor shall prepare, and submit to the Engineer for approval, a plan that indicates the traffic routing proposed by the Contractor during the various stages and time periods of the work, and the temporary pedestrian and construction facilities, temporary barricades, signs, drums, and other traffic control devices to be employed during each stage and time period of the work, to maintain traffic and access to abutting properties. Particular care shall be taken to establish and maintain methods and procedures that will not create unnecessary or unusual hazards to public safety. Traffic control devices required only during working hour operations shall be removed at the end of each working day.

1.4 QUALITY ASSURANCE

- A. Provide in accordance with Section 01400.

1.5 DELIVERY, STORAGE AND HANDLING

- A. Provide in accordance with Section 01600 and 01610 and as specified.
- B. No material shall be stored within the work area or on adjacent roadways or residential streets except which is needed to complete the work for that day.

1.6 SYSTEM DESCRIPTION

- A. Materials required for the work of this Section need not be new, but must be in first-class condition and acceptable to the Owner. Any materials that in the judgment of the Owner are unsatisfactory in appearance or performance shall be removed and immediately replaced by acceptable units.
- B. Signs, portable barricades, and drums shall have "Type III High Intensity Encapsulated Lens Reflective Sheeting" in accordance with Section M9.30.0 of the 1995 MHD Standard Specifications for Highways and Bridges and MUTCD requirements.
- C. Safety Signing for Construction Operations shall be fabricated in accordance with the provisions of subsection M9.30.0, Type III or IV High Intensity, of the MHD Standard Specifications for Highways and Bridges, where these colors are specified.
- D. Portable Type III Barricades shall conform with Standard Plate No. 406.2.0 of the MHD Construction and Traffic Standard Details (Metric Edition). Reflectorized sheeting to conform to Section M9.30.0 Type III or IV, of the MHD Standard Specifications for Highways and Bridges.
- E. Pre-cast concrete median barrier shall conform with Standard Plate No. 401.15.0 of the MHD Construction and Traffic Standard Details.
- F. Traffic Drums shall conform to Standard Plate No. TR.7.1 of the MHD Construction and Traffic Standard Detail and provided in the type and quantity required by the standards specified herein.
- G. Temporary pavement markings and devices shall be used as required by MUTCD and ADA standards for traffic control and pedestrian safety.
- H. The Contractor shall provide necessary access for fire apparatus and other emergency vehicles through the work zones to abutting properties at all times.
- I. At the end of each working period, trenches in areas of public travel shall be covered with steel plates; each edge of the plates shall be either beveled or protected by a bituminous concrete ramp at a slope of two feet horizontally to 1-inch vertically. Any temporary patching material may be used to construct the ramps. The cost of necessary patching materials, and their maintenance and removal, will be considered incidental to the work being performed with no separate payment.
- J. Sweeping and cleaning of surfaces beyond the limits of the project required to clean up material caused by spillage or vehicular tracking during the various phases of the work shall be considered as incidental to the work being performed under the Contract and there will be no additional compensation. Sweeping and cleaning shall be done daily.

1.7 UTILITIES

- A. The Contractor shall be responsible for the coordination of his/her work with all utility work being performed by utility owners in relation to this project or projects adjacent to this project. The Contractor shall phase all work in a manner that will provide positive and safe through movement of traffic passing the construction site.

1.8 TEMPORARY LIGHTING

- A. The Contractor shall provide all the temporary lighting to properly illuminate the work area and approaches in the event of nighttime work.

1.9 EXCAVATIONS

- A. Open excavations adjacent to the traveled way or shoulders shall not remain open through non-work hours unless adequately steel plated for the passage of heavy vehicles and specifically authorized by the Engineer.

1.10 PERMITS

- A. The Contractor shall be responsible for obtaining all permits to perform the work.

1.11 ACCESS TO PROPERTIES

- A. At least one serviceable driveway access to all residences and businesses within the project shall be maintained at all times.

1.12 HAULING

- A. The Contractor is advised that all roads and bridges within or adjacent to the project shall be subject to legal loads and vehicles.
- B. The Contractor is advised that no agreements have been made by the City of Salem or the MHD with surrounding cities or towns to relieve the Contractor of liability for damage to local roads and bridges caused by the Contractor's operation. The Contractor shall contact appropriate officials of the surrounding cities or towns concerning hauling over Salem roads and bridges.

1.13 TRAFFIC CONTROL STANDARDS AND SPECIFICATIONS

- A. The following standards and specifications are to be considered to be part of the Traffic Control Plan:
 - 1. Section 850 of the Standard Specifications.
 - 2. Manual on Uniform Traffic Control Devices, current edition including all revisions, amendments and addenda.

1.14 BARRICADES, WARNING SIGNS AND OTHER PROTECTIVE DEVICES

- A. Install, inspect, remove and rest all temporary construction elements in accordance with an approved construction staging sequence and traffic management plan.
- B. Regulatory and warning devices shall be subject to removal, replacement, and repositioning as often as necessary, and as directed by the Owner.
- C. Maintenance of Construction and Regulatory Signing
 - 1. Safety signing for construction operations shall consist of furnishing, positioning, repositioning, inspecting, maintaining, and removing regulatory, warning, and guide signs and temporary bus stop signs and taxi stop signs and their supports as approved by the City of Salem.
 - 2. Replace all signs which are damaged or are missing from their location without additional compensation.
 - 3. Maintain all signs in a satisfactory manner including the removal of dirt or road film that cause a reduction in sign reflective efficiency.
- D. Portable Barricades
 - 1. Furnish, install, relocate, remove, re-install, and maintain portable barricades in accordance with MHD and MUTCD requirements or as directed by the Owner.
 - 2. Barricades shall be maintained in good and serviceable condition throughout the duration of the Contract.
 - 3. Temporary pedestrian and construction facilities shall be kept clean and freshly painted as required.
- E. Signs, Covered
 - 1. Cover any existing regulatory and warning signs as necessary and as directed by the Owner.
 - 2. Use a cover approved by the Owner, which shall be securely fastened to the existing sign and shall completely cover the legend of the existing sign. The cover shall remain in place as long as necessary at which time it shall be promptly removed.
 - 3. Signs shall be covered without causing any damage to the existing sign.
- F. Traffic Signals
 - 1. Traffic signals shall remain operable at all times throughout the duration of the contract unless approved otherwise by the Owner.

2. It shall be the Contractor's responsibility to maintain the traffic signal system in good working order. The Contractor, at his expense, shall repair any damage to the traffic signal system resulting from the Contractor's work. Any alterations made to traffic signals needed to perform the work in this Contract shall be done by a Contractor certified to work on traffic signal installations and will be subject to the approval of the signal owner.

G. Temporary Pre-cast Concrete Median Barrier

1. Temporary pre-cast concrete median barrier shall be furnished and installed, once relocated, as shown on the traffic management plans and where required by the Engineer to protect work zones and excavations, which cannot be completed and backfilled within a daily work period. Barriers shall be removed when no longer required.
2. Temporary pre-cast barrier for use for temporary pedestrian and construction facilities shall have three (3) shelves cast in the barrier to receive a post for panel and fence installations.

I. Temporary Safety Fencing

1. Temporary orange plastic safety fencing, 4 feet high, shall be erected at work zones abutting pedestrian travel paths and at work zones hazardous to pedestrians, as determined and required by the Engineer.

1.15 TRAFFIC OFFICERS SERVICE

- A. Uniformed officers shall be utilized to maintain safe traffic flow throughout the construction period.
- B. Forty-eight hours of advance notice of starting work shall be given to the City of Salem Police Department. Contractor is required to use as many police details as needed to ensure the safety of pedestrians and traffic at all times. Additional police details shall be provided at the Owner's request.

1.16 PEDESTRIAN TRAFFIC

- A. Sidewalks shall be maintained at all times through the construction period. Temporary sidewalks, pedestrian detours and pedestrian and construction facilities shall be constructed as needed to maintain pedestrian traffic and business access, as shown on the plans or as ordered.
- B. Pedestrian access will be provided to abutting land uses such as residences and businesses at all times, as approved by the Owner and in accordance with MUTCD and ADA requirements.
- C. Unobstructed walkways of 6 feet minimum width, unless otherwise approved by the Owner, will be provided at all times.

- D. Temporary pedestrian walkways shall be separated from roadway and constructed areas by barricades as approved by the Owner.

1.17 TRAFFIC CONTROL REQUIREMENTS

- A. The Contractor shall meet the following conditions, unless otherwise specifically approved by the Engineer:
1. All work shall be prosecuted with proper regard for the convenience of the public and in a manner to permit unimpeded traffic flow whenever possible. The interruption of traffic will not be permitted unless specifically allowed by the Engineer and in accordance with the requirements of the Owner and in conformance with MUTCD requirements.
 2. The Contractor shall be responsible for coordination with the Owner's departments affected by the project.
 3. Traffic control devices and signs shall be removed, demounted or properly covered for those periods of the day not in use.
 4. The City of Salem DPW shall be notified of any re-routing of traffic 72 hours in advance. Approval must be obtained from the Owner prior to any rerouting of traffic (except emergencies). Coordination with other Salem agencies or departments will be by the DPW.
 5. The Contractor shall coordinate the work with the schedules of delivery trucks to the adjacent stores and property owners so as not to impede their access.
 6. No operations shall be conducted, including the loading or unloading of vehicles, on or near the traveled lanes or road shoulders without first erecting warning signs and channelizing devices as directed. These precautions shall be maintained at all times while work is in progress.
 7. Construction signs and channelizing devices shall be used to separate traffic from the work areas and for traffic control. Placement, other than as shown in the plans or the MUTCD, will require prior approval.
 8. Temporary signs and channelizing devices shall not be set up until there is adequate visibility or appropriate construction lighting. The Contractor shall schedule his work so that temporary signs and channelizing devices are removed and traffic is returned to its normal pattern before the end of the work period.
 9. Work requiring overnight lane closures shall not begin until all materials required for the completion of each night's work are delivered or available to the project site, unless otherwise approved by the Engineer.

10. Accesses to residences and businesses shall be maintained at all times.
11. Work operations shall not be performed on the roadway in such a manner that traffic is obstructed or endangered simultaneously from both sides of the roadway.
12. The Contractor shall keep all roadway areas open to traffic as clear as possible at all times. Materials shall not be stored on any roadway area or within 10 ft. of the traveled way. Material shall be delivered to the installation areas as they are needed to provide a continuous installation. Location of storage areas shall be subject to approval.
13. The Contractor shall remove all equipment and construction vehicles from the traveled way and shoulders open to traffic during non-work hours. Vehicles shall be parked no closer than 10 feet from the traveled way in pre-approved areas unless specifically permitted.
14. The Contractor shall furnish 60" x 30" approved signs reading "CONSTRUCTION VEHICLE - DO NOT FOLLOW" to be used on trucks hauling to the project, when such signs are deemed necessary by the Engineer. The color, type of sheeting and size of lettering shall conform to that of the permanent construction signs.
15. Each driver of any vehicle used on this contract shall be furnished written instructions concerning the manner of operation for that vehicle. Specifically, these instructions shall warn against stopping on the traveled portions of the roadway, against passing other vehicles, and against traveling in close proximity to other vehicles. A copy of these instructions shall be given to the Engineer.
16. Temporary signs and channelizing devices shall not be set up in inclement weather.

PART 2 - PRODUCTS (Not Used)

PART 3 - EXECUTION (Not used)

END OF SECTION 01850

SECTION 02010

SUBSURFACE INVESTIGATION

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this section.

1.2 SUMMARY

- A. The Contractor acknowledges that he/she has satisfied himself as to the nature and location of the Work; the general and local conditions, particularly those bearing upon transportation, disposal, handling, and storage of materials; availability of labor, water, electric power, and roads; uncertainties of weather; groundwater table or similar physical conditions at the site; the characterization and conformation of subsurface materials to be encountered; the character of equipment and facilities needed prior to and during the prosecution of the Work; and all other matters that can in any way affect the work or the cost thereof under this Contract. Any failure by the Contractor to acquaint himself with all available information concerning these conditions will not relieve him/her from responsibility for estimating properly the difficulty or cost of successfully performing the Work.
- B. The Contractor's attention is directed to Article 4 of Section 00700 - GENERAL CONDITIONS pertaining to Subsurface and Physical Condition.

1.3 SUBSURFACE DATA

- A. Subsurface Investigations have not been completed by the Engineer or Owner as part of the design of this project but have been completed by others in some project areas as part of other projects in the area and are attached to these Contract Documents for reference.
- B. The Contractor acknowledges that he/she assumes all risk contingent upon the nature of the subsurface conditions to be actually encountered by him/her in performing the work covered by the Contract, even though such actual conditions may result in the Contractor performing more or less work than he/she originally anticipated.
- C. The Contractor shall be aware that borings have not been provided and the existing soil conditions and groundwater level are not known in most areas. Contractor shall assume that construction dewatering due to groundwater, rock and ledge removal, and removal and disposal of unsuitable soils will be required during construction.

- D. The Contractor shall be aware that this project is in close proximity to the ocean and filled areas, and unsuitable soils area assumed to exist, and groundwater levels are assumed to be high and highly variable.
- E. Re-use of excavated soils on- or off-site is subject to local, state and federal regulations. Excess, displaced soil shall be re-used or disposed off site at no additional cost to the Owner.
- F. The Contractor shall be responsible for soil and fill transport and disposal.

PART 2 – PRODUCTS (Not Used)

PART 3 – EXECUTION (Not Used)

END OF SECTION 02010

SECTION 02050

DEMOLITION, ALTERATION, ABANDONMENT

PART 1 – GENERAL

1.1 SUMMARY

- A. This section includes the following:
 - 1. Demolish and alter existing pipe and structures as indicated on drawings, as specified, and as directed by Engineer.
 - 2. Remove designated pipes, structures, valves, fittings, and appurtenances.
 - 3. Remove, salvage, or otherwise dispose of minor site improvements as specified in Section 02100 – SITE PREPARATION.

1.2 RELATED WORK

- A. DIVISION 1 – GENERAL REQUIREMENTS
- B. Section 02100 – SITE PREPARATION
- C. Section 02210 – EARTH EXCAVATION, BACKFILL, FILL AND GRADING
- D. Section 03315 – GROUT

1.3 SUBMITTALS

- A. Shop Drawings: Submit the following in accordance with Section 01300 –SUBMITTALS:
 - 1. Submit to Engineer for review, a demolition plan describing proposed sequence, methods, and equipment for demolition and disposal of each structure.

1.4 QUALITY ASSURANCE

- A. Provide in accordance with GENERAL SPECIFICATIONS and as specified.
- B. Demolish and remove existing construction, utilities, equipment, and appurtenances without damaging integrity of existing structures, equipment, and appurtenances that are to remain.
- C. Store equipment to be salvaged for relocation where directed by Engineer, and if necessary, protect from damage during work.
- D. Repair or remove items that are damaged. Repair and install damaged items at no additional compensation and to condition at least equal to that which existed prior to start of work.

- E. Exercise all precautions for fire prevention. Make acceptable fire extinguishers available at all times in areas where demolition work by burning torches is being done. Do not burn demolition debris on or near site.
- F. Protect persons and property throughout progress of work. Proceed in such manner as to minimize spread of dust and flying particles and to provide safe working conditions for personnel.
- G. Obtain permission from Engineer before abandoning or removing any existing pipes, structures, materials, equipment and appurtenances. Provide Engineer with 5 working day notification prior to abandoning/removing.
- H. Make arrangements with and perform work required by utility companies and municipal departments for discontinuance or interruption of utility services due to demolition work.

1.5 REGULATORY REQUIREMENTS

- A. Conform to applicable codes and requirements for demolition of structure, safety of adjacent structure, dust control, service utilities, and discovered hazards.
- B. Dispose or recycle all demolition debris in accordance with all applicable regulations.

PART 2 - PRODUCTS (NOT USED)

PART 3 – EXECUTION

3.1 PREPARATION

- A. Provide, erect, and maintain temporary barriers and security devices.
- B. Notify Engineer of procedures which may affect property, or potential noise, utility outage, or disruption. Coordinate with Engineer as needed.
- C. Erect and maintain weatherproof airtight closures for exterior openings.
- D. Erect and maintain temporary partitions to prevent spread of dust, odors and noise to permit continued Engineer occupancy.
- E. Protect existing items, which are not indicated to be removed.
- F. Arrange with, pay for all required fees, and perform work required by utility companies and municipal departments for discontinuance or interruptions of utility services due to demolition work.

3.2 DEMOLITION REQUIREMENTS

- A. Conduct demolition in accordance with approved plan, so as to minimize interference with adjacent building areas.

- B. Under no circumstances shall explosives be used.
- C. Conduct operations with minimum interference to public or private accesses.
- D. Maintain protected access and egress at all times. Do not close or obstruct roadways without permits.
- E. Cease operations immediately if adjacent structure appears to be in danger. Notify Engineer.

3.3 SELECTIVE DEMOLITION

- A. Demolish and remove components in an orderly and careful manner.
- B. Protect existing supporting structural members and equipment.
- C. Confine apparatus, storage of materials, demolition work, new construction, and operations of workmen to areas that will not interfere with continued use and operation of entire facility. Provide and maintain lights, barriers, and temporary passageways for free and safe access.
- D. Wet down work during demolition operations to prevent dust from arising. Provide maximum practicable protection from inclement weather for materials, equipment, and personnel located in partially dismantled structures. Provide shoring or bracing where necessary to prevent settlement or displacement of existing or new structures. Do not overload floors. Complete demolition work on upper levels before disturbing supporting members on lower levels.
- E. Cap or plug with brick and mortar, as indicated, pipes and other conduits abandoned due to demolition.
- F. Upon removal of equipment, cut anchor bolts flush with concrete pads, manhole structure walls or floor.

3.4 ABANDONMENT

- A. Disposal of all materials shall be performed in compliance with applicable local, state, and federal codes and requirements. Provide labor, equipment, and materials to perform work as specified and indicated.
- B. The Contractor shall flush all pipe and structures to be removed or abandoned to remove solids and objectionable material prior to commencing demolition, modification, or abandonment.
- C. When existing pipe is removed, the Contractor shall plug all resulting abandoned connections whether or not shown. Where removed piping is exposed, the remaining piping shall be blind-flanged, fitted with a removable cap or plug, or bulk headed. Where existing piping, to include catch basin laterals, is to be abandoned, the Contractor shall cut back the abandoned pipe for a distance of 5 feet (1.524 meters) from any connecting structures to remain. Pipes to be abandoned in structures to be abandoned may be capped, plugged or bulk headed from inside the structure. All holes at the existing structures shall be repaired. Abandoned pipe smaller than 10 in. diameter shall be capped or plugged at both ends prior to backfill. Abandoned pipe 10 in. diameter and larger shall be filled with Controlled Density Fill (CDF) prior to being capped,

plugged, or bullheaded and backfilling unless otherwise noted. Each pipe reach to be abandoned with CDF shall be filled with CDF from the up-gradient end of the pipe reach wherever possible. The CDF shall completely fill each pipe reach and flow out the other end. The Contractor can aid the flow of the CDF in the pipe by providing a temporary structure at the access point to build up head or by pumping the CDF or by providing vibration in the pipe reach or access point. Requirements for Controlled Density Fill are described in Section 02210 – EARTH EXCAVATION, BACKFILL, FILL AND GRADING.

- D. Where existing drainage structures such as catch basins, drain manholes, sewer manholes, and combined sewer manholes are to be abandoned in place, the Contractor shall remove the frames, grates, and covers and cut the structures down a minimum of 2 feet below final grade or remove the entire structure including based as directed. The Contractor shall put a minimum of four (4), 2-inch diameter drainage holes in the invert of each structure and then backfill the structure with flowable fill or sand as specified and as approved by the Engineer. Backfill around the structure shall be in accordance with Section 02210 – EARTH EXCAVATION, BACKFILL, FILL AND GRADING.
- E. Permanent plugs shall be constructed of Class B concrete, brick or other material approved by the engineer.
- F. Fill excavations with solid fill resulting from earth removal operations and/or with select borrow material in accordance with Section 02210 – EARTH EXCAVATION, BACKFILL, FILL AND GRADING and the Contract Drawings. Final grade to be restored in kind unless otherwise noted.
- G. Exercise precautions for fire prevention. Make fire extinguishers approved for Class A, B and C fires available at all times in areas where performing demolition or abandonment work with burning torches. Do not burn demolition debris on site.

3.5 SALVAGE

- A. Materials, equipment, and appurtenances removed, that are not designated for relocation, or future use by Engineer shall become property of Contractor. Haul from site and dispose of at no additional compensation.
- B. Remove, store and protect the following materials and equipment until such time as the Engineer reviews them and requests relocation for future use. If upon review the Engineer declines to salvage the following material, the Contractor shall dispose of the items legally and at no additional cost to the Owner.
 - 1. Existing gates, frames, covers, valves, piping, and appurtenances in existing manholes, catch basins and tide gate structures..
- C. All salvaged items shall be relocated to a location identified by the Engineer.

3.6 CLEAN UP

- A. Remove demolished materials from site as work progresses.

- B. Leave areas of work in clean condition.
- C. Upon completion of demolition, the contractor is required to implement his approved sampling plan, outlined in the paint debris collection plan, on all collected paint debris.
- D. All cobbles to be kept, as practical, and delivered to City of Salem.

3.7 REPAIR OF DAMAGE

- A. Any damage to existing facilities to remain, as caused by the Contractor's operations shall be repaired at no additional cost to the Engineer. Damaged items shall be repaired or replaced with new materials as required to restore damaged items or surfaces to a condition equal to and matching that existing prior to damage or start of work of this Contract.
- B. Promptly repair damage to adjacent construction caused by selective demolition operations.
- C. Patching: Comply with Section 01045 – CUTTING, CORING, AND PATCHING.
- D. Repairs: Where repairs to existing surfaces are required, patch to produce surfaces suitable for new materials.
- E. Where feasible, test and inspect patched areas after completion to demonstrate integrity of installation.

3.8 CONTRACT CLOSEOUT

- A. Provide in accordance with Section 01700 – CONTRACT CLOSEOUT

END OF SECTION 02050

SECTION 02100
SITE PREPARATION

PART 1 - GENERAL

1.1 SUMMARY

- A. This section includes the following:
 - 1. Provide labor, material, tools and equipment to prepare site as indicated and specified.
 - 2. Protection of existing trees and vegetation outside the limit of work and specifically designated trees and vegetation within the limit of work.
 - 3. Removal trees, stumps and other vegetation.
 - 4. Topsoil stripping.
 - 5. Clearing and grubbing.

1.2 RELATED WORK

- A. DIVISION 1 – GENERAL REQUIREMENTS
- B. Section 02210 – EARTH EXCAVATION, BACKFILL, FILL, AND GRADING

1.3 SUBMITTALS – (Not Used)

PART 2 - PRODUCTS

PART 3 - EXECUTION

3.1 EXISTING TREES AND VEGETATION

- A. Avoid cutting or injuring trees and vegetation outside easement or property line and outside areas to be cleared as indicated, without Engineer's permission. Protect existing trees from damage.
- B. Contractor shall be responsible for damages outside these lines.

3.2 EXISTING STRUCTURES AND PROPERTY

- A. Remove and reset at completion of project existing signs, posts, catch basin frames and grates, manhole frames and covers, and granite curbing within construction path unless directed otherwise.

- B. Store at a site designated the Engineer and items in reusable condition as determined by the Engineer.
- C. For work in loamed areas, strip loam to one side to avoid mixing with excavation materials. Do not take loam from site.

3.3 CLEARING

- A. Cut or remove trees, brush, and other vegetable matter such as snags, bark and refuse, from areas to be cleared as shown on plans within proposed tree line limits and as directed by the Engineer. Clear ground to width of permanent easement unless otherwise directed.
- B. Cut trees, stumps, and stubs to be cleared, except where clearing done by machinery, as close to ground surface as practicable, but no more than 6 in. above ground surface for small trees and 12 in. for larger trees.
- C. Bury elm bark, at least 1 ft. deep, or burn in incinerators off site with anti-pollution controls and fire prevention controls, to prevent spread of Dutch Elm disease as required by applicable laws.

3.4 CLEARING IN WOODED AREAS

- A. Chip and spread wood cleared at locations and cover as directed by the Engineer. Do NOT PERMIT use of elm wood and elm bark as wood chips.

3.5 GRUBBING, STRIPPING, DISPOSAL

- A. Remove stumps and roots larger than 3 in. in diameter to a depth of 12 in., and roots larger than 1/2 in. in diameter to a depth of 6 in. Measure depths to cut from existing ground surface or proposed finished grade, whichever is lower.
- B. Strip stumps, roots, foreign matter, topsoil, loam and unsuitable earth from ground surface. Utilize topsoil and loam insofar as possible for finished surfacing. Do not take loam from site.
- C. Promptly dispose off site material from clearing and grubbing not reused or stockpiled. In doing so, observe all applicable laws, ordinances, rules and regulations. Do not consider work completed until final cleaning, unless otherwise directed.

3.6 STOCKPILES

- A. Stockpiles shall be neatly trimmed and graded to provide drainage from surfaces and to prevent depressions where water may become impounded. All construction operations shall be performed so as not to cause mixing of objectionable materials with the topsoil, and stockpiles shall be protected and shall not be disturbed except for subsequent operations for replacing topsoil. The location of stockpiles shall be approved by the Engineer.

3.7 EXCESS TOPSOIL

- A. Topsoil which has been stripped and stockpiled, but is not needed after the completion of all final topsoiling and grassing shall be stockpiled on site in a location to be approved by the Engineer and shall remain the property of the Owner.

3.8 CONTRACT CLOSEOUT

- A. Provide in accordance with Section 01700 – CONTRACT CLOSEOUT.

END OF SECTION 02100

SECTION 02210

EARTH EXCAVATION, BACKFILL, FILL AND GRADING

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and other Division 1 Specification Sections, apply to this section.

1.2 SUMMARY

- A. This Section includes excavations of normal depth in earth and rock for trenches and structures; backfilling such excavations to the extent required; filling; dewatering, blasting, rough grading; constructing embankments; miscellaneous earth excavation and rock excavation; the removal, hauling and stockpiling of suitable excavated material for subsequent use in the work; all rehandling, hauling and placing of stockpiled materials for use in refilling, filling, backfilling, grading and such other operations; the removal and satisfactory disposal off the site of unsuitable material; and appurtenant work, complete, in accordance with the Drawings and Specifications, and as directed.
- B. All excavated materials not utilized for backfill or fill including all surplus or excess excavated materials, boulders, and pavement materials from the required excavations shall be removed and legally disposed off the project site in disposal areas furnished by the Contractor at no additional expense to the Owner.

1.3 SUBMITTALS

- A. General: Shop Drawings, submit the following in accordance with Section 01300 – SUBMITTAL PROCEDURES.
- B. Backfill Materials: Submit a grain size analysis and curve performed in accordance with ASTM D422 for each proposed source of backfill for review by the Engineer. The grain size analysis shall indicate that the backfill material conforms to the gradation requirements specified.
- C. Submit a moisture-density curve indicating the maximum dry density and optimum moisture content as determined by ASTM D1557 for each proposed source of backfill for review of the Engineer.
- D. Blasting Design: NOT APPLICABLE
- E. Blasting Reports: NOT APPLICABLE
- F. Filter fabric: Submit the manufacturer's information on the filter fabric to the Engineer for review in accordance with Section 02273 – GEOTEXTILE FABRIC.

- G. Submit the qualifications of the independent geotechnical testing laboratory performing soil testing and inspection services during earthwork operations. The geotechnical testing laboratory must demonstrate to the Engineer's satisfaction, based on evaluation of laboratory submitted criteria conforming to ASTM D3740, that it has the experience and capability to conduct required field and laboratory geotechnical testing. In addition, the laboratory shall be supervised by a Registered Professional Engineer in the State of Massachusetts.
- H. Backfill Materials: Submit a 20 lb. sample, grain size analysis and curve performed in accordance with ASTM D422 and compaction test results (ASTM D1557 Procedure C) for each proposed source of backfill for review by the Engineer at least one week prior to use of the material. The grain size analysis shall indicate that the backfill material conforms to the gradation requirements specified.
- I. In addition, a certification statement and analytical results shall accompany each physical sample of material to be imported as crushed stone, bedding sand, gravel sub-base, or structural backfill. At a minimum the certification shall state the point of origin and that the material is free of contaminants. The certification shall include representative sample analysis from each point of origin of backfill to be used on the site.
- J. Submit additional samples every 1000 cubic yards or anytime consistency of material changes in the opinion of the Engineer and submit associated chemical laboratory data on the imported materials throughout the course of the Work, if requested by the Engineer, to evaluate the consistency of the source or process, at no additional cost to the Owner.
- K. Excavation and Excavation Support Plan: For informational purposes only, and if requested by the Engineer, the Contractor shall submit the following prior to the start of the work, in accordance with Section 01300 – SUBMITTALS.
1. Submit within a minimum of four (4) weeks prior to construction, the qualifications of the Contractor's excavation support specialist. The excavation support specialist shall have completed at least five (5) successful excavation support projects of equal size and complexity and with equal systems within the last five (5) years.
 2. Submit a detailed temporary excavation support plan stamped and signed by a Registered Professional Engineer at least two weeks prior to start of the construction. Do not submit design calculations. The review will be only for the information of the Owner and third parties for an overall understanding of the project relating to access, maintenance of existing facilities and proper utilization of the site. The Contractor shall remain responsible for the adequacy and safety of the means, methods and sequencing of construction. The plan shall include the following items as a minimum.
 - a. Proposed temporary excavation support system(s), bracing details, location, layout, depths, extent of different types of support relative to maintaining all existing building foundations adjacent to trench excavations, features, buildings, structures to be constructed, and methods and sequence of

installation and removal.

- b. Certificate of Design: NOT APPLICABLE
 - c. Requirements of dewatering during the construction.
 - d. Minimum lateral distance from the edge of the excavation support system for use of vehicles, construction equipment, and stockpiled construction and excavated materials.
 - e. List of equipment used for installing the excavation support systems.
- 3. Submit a Construction Contingency Plan specifying the methods and procedures to maintain temporary excavation support system stability if the allowable movement of the adjacent ground and adjacent structures is exceeded.
 - 4. Controlled Density Fill (CDF) Mix Design or Concrete Flowable Fill:
 - a. Prior to beginning the work the Contractor shall submit for review, flowable fill mix designs which shall show the proportions and graduations of all materials for each class and type of flowable fill specified herein.

L. Dewatering Plan: Contractor shall submit the following prior to the start of the work, in accordance with Section 01300 – SUBMITTALS.

- 1. Submit within a minimum of four (4) weeks prior to execution of any dewatering, the qualifications of the Contractor's dewatering specialist. The dewatering specialist shall have completed at least five (5) successful dewatering projects of equal size and complexity and with equal systems within the last five (5) years.
- 2. Submit a detailed dewatering plan at least (2) weeks prior to start of any dewatering operation. Do not submit design calculations, but submit working drawings for review by the Engineer. The review will be only for the information of the Owner and third parties for an overall understanding of the project relating to access, maintenance of existing facilities and proper utilization of the site. The Contractor shall remain responsible for the adequacy and safety of the means, methods and sequencing of construction. The plan shall include the following items as a minimum.
 - a. The proposed type of dewatering plan and details stamped and signed by a Registered Professional Engineer.
 - b. Certificate of Design: NOT APPLICABLE
 - c. A list and description of equipment including, but not limited to, pumps, prime movers, and standby equipment, as well as the arrangement and

location of system components.

- d. Detailed description of dewatering, maintenance, and system removal procedures.
 - e. Erosion/sedimentation control measures, and methods of disposal of pumped water.
 - f. Types and sizes of sedimentation basins and filters.
 - g. List of all applicable laws, regulations, rules and codes to which dewatering design conforms.
3. Submit a modified dewatering plan within 24 hours, if open pumping from sumps and ditches results in boils, loss of fines or softening of the ground.

1.4 EXCAVATION CLASSIFICATIONS

- A. Earth Excavation or "Excavation" consists of removal of materials encountered to the subgrade elevations indicated and subsequent reuse or disposal of the materials removed. All excavation is classified as earth excavation unless it otherwise meets the classifications provided below for unauthorized excavation, additional excavation, or rock excavation.
- B. Unauthorized Excavation consists of removal of materials beyond indicated subgrade elevations or horizontal dimensions without specific direction of the Engineer. Unauthorized excavation, as well as remedial work directed by the Engineer, shall be at Contractor's expense.
 - 1. Under footings, foundations bases, concrete slabs, retaining walls or other structures, fill unauthorized excavations to the proper elevations with lean concrete. Elsewhere, backfill and compact unauthorized excavations as specified for excavations of the same class, unless otherwise directed by the Engineer.
- C. Additional Excavation:
 - 1. When excavation has reached required subgrade elevations, notify the Engineer who will review subgrade conditions.
 - 2. If unsuitable bearing materials are encountered at required subgrade elevations, carry excavations deeper and replace excavated material as directed by the Engineer.
 - 3. Removal of unsuitable material and its replacement as directed will be paid on the basis of contract conditions relative to changes in work or as provided for under the unit rates for this classification.

D. Rock Excavation:

1. Rock excavation in trenches and pits includes removal and disposal of materials and obstructions encountered which cannot be excavated with a 1.0 cubic yard (heaped) capacity, 42-inch wide bucket on track-mounted power excavator equivalent to Caterpillar Model 215, rated at not less than 90HP flywheel power and 30,000 lb. drawbar pull. Trenches in excess of 10 feet 0-inches in width and pits in excess of 30 feet 0-inches in either length or width are classified as open excavation.
2. Rock excavation in open excavations includes removal and disposal of materials and obstructions encountered which cannot be dislodged and excavated with modern track-mounted heavy-duty excavating equipment without drilling, blasting or ripping. Rock excavation equipment is defined as Caterpillar Model No. 973 or No. 977K, or equivalent track-mounted loader, rated at not less than 170HP flywheel power and developing 40,000 lb. break-out force (measured in accordance with SAE J732C).
3. Determination of rock excavation classification will be made by the Engineer. Typical of materials classified as rock are boulders 1.0 cu. yd. or more in volume, solid rock, rock in ledges, and rock-hard cementitious aggregate deposits. Intermittent drilling, blasting or ripping performed to increase production and not necessary to permit excavation of material encountered will be classified as earth excavation. Do not perform rock excavation work until material to be excavated has been cross-sectioned and classified by Engineer. If the area to be excavated is preblasted prior to the excavation of overburden soils, the Engineer shall be notified at least two days in advance to allow observation of the preblast drilling by the Engineer in order to classify the excavation. Visual observation of the completed excavation may be made by the Engineer to modify the excavation classifications. Removal of rock excavation prior to classification by the Engineer shall be considered as earth excavation unless accepted by the Engineer in writing. Such excavation will be paid on the basis of contract unit rates for this classification.

1.5 EXCAVATION

- A. The Contractor shall perform all excavations of every description and of whatever substances encountered, in a manner as required to allow for placing of temporary earth support, forms, installation of pipe and other work, and to permit access to the Engineer for the purpose of observing the work. Bottoms of trenches and excavations shall be protected from frost and shall be firm, dry and in an acceptable condition to receive the work; work shall not be placed on frozen surfaces nor shall work be placed on wet or unstable surfaces.
- B. All excavations made in open cut will be controlled by the conditions existing at the various locations and shall always be confined to the limits as designated by the Engineer. In no case shall earth be excavated or disturbed by machinery so near to the finished subgrade for structures and pipelines as to result in the disturbance of the earth below the subgrade. The final excavation to subgrade should be accomplished with a smooth faced

bucket or by hand if directed by the Engineer.

- C. Stockpiles are to be segregated based on geotechnical properties, visual, olfactory, and field screening results. Similar material shall be stockpiled together. Each stockpile must be clearly separable from adjacent stockpiles.

1.6 TEMPORARY EARTH SUPPORT

- A. The Contractor shall design, furnish, place and maintain such temporary excavation support systems as required to maintain lateral support and to prevent danger to persons or damage to pavements, facilities, utilities, or structures, and to prevent injurious caving or erosion or the loss of ground, and to maintain pedestrian and vehicular traffic as directed and required.
- B. Common types of excavation support systems include, but not limited to singular or multiple stages comprised of cantilevered or internally braced soldier piles and lagging, steel sheet-pile wall, timber sheet-pile wall, trench box, or combinations thereof.
- C. Support systems shall be designed for earth pressures, hydrostatic pressure, equipment, temporary stockpiles, construction loads, and other surcharge loads.
- D. In all sheeting, shoring and bracing operations, care shall be taken to prevent injury to persons or damage to structures, roadways, facilities, pipelines, utilities and services. Any injuries to persons shall be the responsibility of the Contractor; and any damage to the work or existing structures occurring as a result of settlement, water or earth pressure, or other causes due to inadequate bracing of other construction operations of the Contractor shall be repaired by the Contractor at no additional cost to the Owner.
- E. The Contractor shall bear the entire cost and responsibility of correcting any failure, damages, subsidence, upheaval or cave-ins as a result of improper installation, maintenance or design of the temporary excavation support systems. The Contractor shall pay for all claims, costs and damages that arise as a result of the work performed at no additional cost to the Owner.
- F. Where sheeting is to be used, it shall be driven ahead of excavation operations to the extent practicable so as to avoid the loss of material from behind the sheeting; where voids occur outside of the sheeting, they shall be filled immediately with selected fill, thoroughly compacted.
- G. Design the embedment depth below bottom of excavation to minimize lateral and vertical earth movements and provide bottom stability. Toe of braced temporary excavation support systems shall not be less than 3 feet [1.5 m] below the bottom of excavation.
- H. Design temporary excavation support systems to withstand an additional 2 feet [60 cm] of excavation below proposed bottom of excavation without redesign except for the addition of lagging and/or bracing.
- I. The Contractor shall leave in place all sheeting and bracing at the locations and within the limits ordered by the Engineer in writing. The Contractor shall cut off the sheeting at

elevations to be determined by the Engineer.

- J. The Contractor shall comply with all federal, state, and local safety regulations and requirements.

1.7 DEWATERING SYSTEM

- A. The Contractor shall design, furnish, install, operate, maintain and remove at his own expense, a temporary dewatering system to ensure that work is performed under dry and stable conditions, free from groundwater and/or surface runoff. The temporary dewatering system shall be implemented so as not to adversely affect construction procedures nor cause excessive disturbance of underlying natural ground. The Contractor shall implement erosion control measures for disposing of discharged water in order to prevent pumped drainage water from causing damage to adjacent property.
- B. Any damage resulting from the failure of the dewatering operations of the Contractor, and any damage resulting from the failure of the Contractor to maintain all the areas of work in a suitable dry condition, shall be repaired by the Contractor, at no additional expense to the Owner. The Contractor's pumping and dewatering shall be carried out in such a manner as to prevent damage to the Contract work and so that no loss of ground will result from these operations. If sub-grade soils are disturbed or become unstable due to dewatering operation or an inadequate dewatering system, notify the Engineer, stabilize the sub-grade, and modify system to perform as specified at no additional cost to the Owner. Precautions shall be taken to protect new work from flooding during storms or from other causes. Pumping shall be continuous where directed by the Engineer to protect the work and/or to maintain satisfactory progress.
- C. Notify the Engineer immediately if any settlement or movement is detected on structures. If the settlement or movement is deemed by the Engineer to be related to the dewatering, take actions to protect the adjacent structures and submit a modified dewatering plan to the Engineer within 24 hours. Implement the modified plan and repair any damage incurred to the adjacent structures at no additional cost to the Owner.
- D. All pipelines or structures not stable against uplift during construction or prior to completion shall be thoroughly braced and protected. Water from the trenches, excavations and drainage operations shall be disposed to avoid public nuisance, injury to public health or the environment, damage to public or private property, or damage to the work completed or in progress. If oil and/or other hazardous materials are encountered after dewatering begins immediately notify the Engineer.
- E. The Contractor shall control the grading in the areas surrounding all excavation so that the surface of the ground shall be properly sloped to prevent water from running into the excavated area. Where required, temporary ditches shall be provided for drainage. Upon completion of the work and when directed, all areas shall be restored by the Contractor in a satisfactory manner and as directed.

1.8 BLASTING

- A. Blasting is not allowed unless it is reviewed and approved by the Owner.

PART 2 – PRODUCTS

2.1 DEWATERING MATERIALS

- A. Provide and store auxiliary dewatering equipment, consisting of pumps and hoses on the site in the event of breakdown, at least on (1) pump for every five (5) used.
- B. Provide and maintain erosion/sedimentation control devices as indicated or specified and in accordance with the dewatering plan.
- C. Provide temporary pipes, hoses, flumes, or channels for the transport of discharge water to the discharge location.

2.2 TEMPORARY EXCAVATION SUPPORT MATERIALS

- A. Provide specific trench box sizes for each pipe and utility excavation with structural capacity of retaining soil types as described in OSHA's 29 CFR Part 1926 subpart P.
- B. Timber lagging Left in Place: Pressured treated per appropriate AWPA standards.
- C. Tamping tools adapted for backfilling voids after removal of the excavation support system.

2.3 TRENCH DAMS

- A. Trench Dam shall be self supporting and provide a watertight seal around the pipe by use of appropriately sized elastomeric PVC flexible coupling. Barriers shall form an impenetrable barrier in the pipe envelope to the flow of water. Baffles constructed of ABS plastic are acceptable. Trench Dams shall be Ripley's Dams of Durham, NH or equal.

2.4 BACKFILL MATERIALS

- A. Clean Fill - Analytical Results. The Contractor shall provide certification that imported fill and/or topsoil material to be used as fill, borrow or subbase is free of contaminants. Certification must indicate the point of origin and include laboratory analytical results as specified and include a statement that the material is free of organic, or any other unsuitable contaminants and that metal concentrations are consistent with background levels. No processed concrete, recycled asphalt, brick, coal ash or wood ash shall be present in any fill material. Evidence of such recycled products in the fill shall be rejected and returned to the supplier at no additional cost to the owner.
- B. Common Fill: Common fill shall be soil containing no stone greater than 2/3 loose lift thickness. The materials shall be free of trash, ice, snow, tree stumps, roots and other organic and deleterious materials. Common fill shall not contain more than 25 percent by

weight of silt and clay. It shall be of such a nature and character that it can be compacted to the specified densities in a reasonable length of time. Topsoil and subsoil shall not be considered common fill.

Common fill shall be used as trench backfill above the crushed stone layer and below the gravel subbase material, and outside limits of structures.

- C. **Structural Fill:** Structural fill shall consist of gravel and sand consisting of hard durable particles, and free from trash, ice and snow, tree stumps, roots and other organic and deleterious or organic matter. Structural fill shall be used as replacement backfill for unsuitable soils below pipes and structures. Structural fill shall conform to the following gradation requirements.

Sieve Size	Percent Finer by Weight
6-inch	100 (1)
3-inch	70-100
1-inch	45-90
No. 4	20-70
No. 10	15-60
No. 40	10-40
No. 200	0-10
<u>(1) Four-inch maximum particle size within 12 inches of slab, footing or pavement grade.</u>	

- D. Crushed Stone: Crushed stone shall consist of durable crushed rock or durable crushed gravel stone, free from ice and snow, sand, clay, loam, or other deleterious or organic material. The crushed stone shall be uniformly blended and shall conform to the following requirements.

	Percent Passing by Weight	
Sieve Size	1-1/2-inch Stone	¾-inch Stone
2-inch	100	
1-1/2-inch	95-100	
1-inch	35-70	100
¾-inch	0-25	90-100
½-inch		10-50
3/8-inch		0-10
No. 4		0-8

Crushed stone (1-1/2-inch) shall be used as the working mat below precast or masonry structures, and ¾-inch shall be used for bedding around PVC pipes.

- E. Gravel Subbase: The top layer of backfill in unpaved sections of roads and where directed by the Engineer shall consist of compacted 6-inch or 12-inch thickness of gravel subbase meeting MHD specification section M1.03.1 as indicated below:

Sieve Size	Percent Passing by Weight
3-inch	100
1-1/2-inch	70-100
3/4-inch	50-85
No. 4	30-60
No. 200	0-10

- F. Control Density Fill (CDF) / Flowable Fill: Controlled density fill shall consist of a cementitious hard excavatable mixture of aggregate, Portland Cement, Fly Ash and air entrained admixtures. The material shall be of the type specified in the Massachusetts Highway Department 1995 Standard Specifications for Highway and Bridges, Type 2E. Controlled density fill shall be used as trench backfill material at locations where compaction equipment is inaccessible as directed by the Engineer.

- G. Reclaimed Gravel Subbase: If allowed for re-use, roadway and existing subbase materials generated from reclamation may be utilized as materials for reclaimed subbase for new road widths and sidewalks and road base repair providing it substantially meets the specifications gravel subbase and as directed by Engineer.

PART 3 - EXECUTION

3.1 DEWATERING

- A. Execution of any earth excavation, installing earth retention systems, and dewatering shall not commence until the related submittals have been reviewed by the Engineer with all Engineer's comments satisfactorily addressed and the geotechnical instrumentation has been installed.
- B. Furnish, install, operate, and maintain dewatering, re-infiltration, treatment and discharge systems as indicated or specified and in accordance with the dewatering plan. No dewatering flows shall be discharged to surface waters either directly or indirectly without appropriate settling, at a minimum, the Contractor shall provide a settling tank with a capacity of 10,000 gallons if re-infiltration is not sufficient, so that if pumping rates exceed discharge rates, sufficient storage capacity is available. Delays due to insufficient storage capacity will be at no additional cost to the Owner. The Contractor is responsible to evaluate available data and determine the necessary storage capacity so as not to impede construction activities.
- C. Carry out dewatering program in such a manner as to prevent undermining or disturbing foundations of existing structures or of work ongoing or previously completed.
- D. Dewatering shall lower the groundwater to at least 12-inches below the bottom of excavation.
- E. Do not excavate until the dewatering system is operational.
- F. Discontinue open pumping from sumps and ditches, if such pumping is resulting in boils, loss of fines, softening of the ground, or instability of the slopes. Modify dewatering plan and submit to the Engineer at no additional cost to the Owner.
- G. Where sub-grade materials are disturbed or become unstable due to dewatering operations, remove and replace the materials at no additional cost to the Owner.
- H. Dewatering Discharges:
 - 1. Water to be infiltrated need not be treated. Contractor shall provide infiltration that complies with relevant local, state and federal regulations including Order of Conditions from local Conservation Commission.

3.2 EXCAVATION SUPPORT SYSTEM

- A. Installation of the temporary excavation support systems shall not commence until the related earth excavation and dewatering submittals have been reviewed by the Engineer with all Engineer's comments satisfactorily addressed.
- B. Install excavation support systems in accordance with the temporary excavation support plan.
- C. Carry out program of temporary excavation support in such a manner as to prevent undermining or disturbing foundations of existing structures of work ongoing or previously completed.
- D. Bottom of the trench box excavation support system shall be above the pipe invert or structure bottom prior to installing the pipe.
- E. Notify utility owners if existing utilities interfere with the temporary excavation support system. Modify the existing utility with the utility owners permission or have the utility owner make the modifications at no additional cost to the Owner.
- F. When indicated or approved by the Engineer, remove the temporary excavation support system without endangering the constructed or adjacent structures, utilities, or property. Immediately backfill all voids left or caused by withdrawal of temporary excavation support systems with bank-run gravel, clean screened gravel or select borrow by tamping with tools specifically adapted for that purpose.

3.3 FILLING AND BACKFILLING

- A. Subgrade Preparation: After the subgrade has been shaped to line, grade, and cross-section, it shall be thoroughly compacted. This operation shall include any required reshaping and wetting to obtain proper compaction. All soft or otherwise unsuitable material shall be removed and replaced with structural fill material from excavation or borrow. The resulting area, and all other low sections, holes, or depressions shall be brought to the required grade with structural fill material and the entire subgrade shaped to line, grade and cross-section and thoroughly compacted.
- B. Backfill Material Selection: Unless otherwise specified or directed, material used for filling and backfilling shall meet the requirements specified under Products (Part 2). In general, the material used for backfilling utility trench excavations and grading roadway and sidewalks shall be material removed from the excavations or reclaimed from existing road base provided that the reuse of these materials result in the required trench compaction and meets the requirements specified for common fill or gravel subbase and as approved by Engineer. In areas where the bottom of the excavation is in fine sand and silt, and is below the groundwater table, the first lift of backfill shall be 12-inches of compacted 3/4-inch crushed stone to provide a working mat and drainage layer.

Spread and place backfill to a maximum loose lift thickness of 6 inches. Maintain backfill material with an uniform moisture content, with no visible wet or dry streaking, between

plus 2 percent and minus 3 percent of optimum moisture content. The final filled soil mass shall be as uniform as possible in lift thickness, moisture content, and effort required to compact soil mass.

C. Trench Backfill and Roadway Grading:

1. The trenches shall be backfilled as soon as practicable with common fill material. All trench backfilling shall be done with special care, in the following manner and as directed by the Engineer.
2. Backfill material for pipe bedding as shown on the drawings shall be deposited in the trench, uniformly on both sides of the pipe, for the entire width of the trench to the depths shown on the drawings. The backfill material shall be placed by hand shovels, in layers not more than 4-inches thick in loose depth, and each layer shall be thoroughly and evenly compacted by tamping on each side of the pipe to provide uniform support around the pipe, free from voids.
3. The balance of backfill shall be spread in layers not exceeding 12-inches in loose depth. Each layer shall be thoroughly compacted by mechanical methods and shall contain no rock, stones or boulders larger than 4-inches in their greatest dimension.
4. All trench backfilling shall be done with special care and must be carefully placed so as not to disturb the work at any time; if necessary, a timber grillage or other suitable method shall be used to break the fall of material. The moisture content of the backfill material shall be such that proper compaction will be obtained. Puddling of backfill with water will not be permitted. Backfill within areas to receive topsoil or pavement construction shall be made to grades required to establish the proper subgrade for the placement of topsoil or pavement base courses.
5. In backfilling trenches, each layer of backfill material shall be moistened and compacted to a density at least 95 percent of its maximum density, and in such a manner as to permit the rolling and compaction of the filled trench or excavation with the adjoining earth to provide the required bearing value, so that paving of the excavated and disturbed areas, where required, can proceed immediately after backfilling is completed.
6. Any trenches or excavations improperly backfilled or where settlement occurs shall be reopened, to the depth required for proper compaction, then refilled and compacted with the surface restored to the required grade and condition, at no additional expense to the Owner.
7. During filling and backfilling operations, pipelines will be checked by the Engineer to determine whether any displacement of the pipe has occurred. If the observation of the pipelines shows poor alignment, displaced pipe or any other defects they shall be remedied in a manner satisfactory to the Engineer at no additional cost to the Owner.

8. The top 6 or 12-inches of backfill in paved roads shall be constructed with 6 or 12-inches of gravel subbase material as directed. The material shall be placed in two 6-inch lifts; each lift proof rolled and compacted with rollers before placing subsequent lifts.
9. In no case shall frozen materials be used for trench backfill.

D. Backfilling against Structures:

1. Backfilling against masonry or concrete shall not be done until permitted by the Engineer. The Contractor shall not place backfill against or on structures until they have attained sufficient strength to support the loads (including construction loads) to which they will be subjected, without distortion, cracking or other damage. As soon as practicable after the structures are structurally adequate and other necessary work has been satisfactorily completed, special leakage tests of the structures shall be made by the Contractor, as required by the Engineer. After the satisfactory completion of leakage tests and the satisfactory completion of any other required work in connection with the structures, the backfilling around the structures shall proceed using suitable and approved excavation material. The best of the backfill material shall be used for backfilling within 2 feet of the structure. Just prior to placing backfill, the areas shall be cleaned of all excess construction material and debris and the bottom of excavations shall be in a thoroughly compacted condition.
2. Symmetrical backfill loading shall be maintained. Special care shall be taken to prevent any wedging action or eccentric loading upon or against the structures. During backfilling operations, care shall be exercised that the equipment used will not overload the structures in passing over and compacting these fills. Except as otherwise specified or directed, backfill shall be placed in layers not more than 12-inches in loose depth and each layer of backfill shall be compacted thoroughly and evenly using approved types of mechanical equipment. Each pass of the equipment shall cover the entire area of each layer of backfill.
3. In compacting and other operations, the Contractor shall conduct his operations in a manner to prevent damage to structures due to passage of heavy equipment over, or adjacent to, structures, and any damage thereto shall be made good by the Contractor at no additional expense to the Owner.

- E. After backfilling trenches, and excavations, and graded areas where pavements are to be constructed, the Contractor shall maintain the surfaces of backfill areas in good condition so as to present a smooth surface at all times level with adjacent surfaces. Any subsequent settling over backfilled areas shall be repaired by the Contractor immediately, in a manner satisfactory to the Engineer, and such maintenance shall be provided by the Contractor for the life of this Contract, at no additional expense to the Owner.
- F. The finished subgrade of the fills and filled excavations upon which topsoil is to be placed, or pavements are to be constructed, shall not be disturbed by traffic of other operations and shall be maintained in a satisfactory condition until the finished courses are placed. The

storage or stockpiling of materials on finished subgrade will not be permitted.

- G. Uniformly smooth grading of all areas to be graded, as indicated and as directed, including excavated and filled sections, embankments and adjacent transition areas, and all areas disturbed as a result of the Contractor's operations, shall be accomplished. The finished surfaces shall be reasonably smooth, compacted and free from surface irregularities.

3.4 COMPACTION

- A. **Compaction Requirements:** The degree of compaction is expressed as a percentage of the maximum dry density at optimum moisture content as determined by ASTM Test D1557, Method C. The compaction requirements are as follows:

Area	ASTM Density Degree of Compaction
Below footings	95%
Below slabs	95%
Pavement base course	95%
Pavement subbase	95%
Sidewalk Gravel Base	95%
General fill below pavement subbase	92%
Trench backfill - below pavements	92%
- below landscaped areas	90%
- below structures	95%
Other areas	90%

- B. **Moisture Control:**

1. Fill that is too wet for proper compaction shall be disced, harrowed, or otherwise dried to a proper moisture content to allow compaction to the required density. If fill cannot be dried within 24 hours of placement, it shall be removed and replaced with drier fill.
2. Fill that is too dry for proper compaction shall receive water uniformly applied over the surface of the loose layer. Sufficient water shall be added to allow compaction to the required density.

- C. **Unfavorable Conditions:**

1. In no case shall fill be placed over material that is frozen. No fill material shall be placed, spread or rolled during unfavorable weather conditions. When work is interrupted by heavy rains, fill operations shall not be resumed until the moisture

content and the density of the previously placed fill are as specified.

2. In freezing weather, a layer of fill shall not be left in an uncompacted state at the close of the day's operations. Prior to terminating work for the day, the final layer of compacted fill shall be rolled with a smooth wheeled roller to eliminate ridges of soil left by compaction equipment.

D. Compaction Control:

1. All methods used to determine and verify the proper compaction of backfill shall be in accordance with AASHTO standards specifications for density of soil and soil-aggregate in-place by nuclear methods (shallow depth) (designation T238-86 method B-direct transmission shall be used to determine in-place density) and moisture content of soil and soil aggregate in place by nuclear methods (shallow depth) (designation T239-91). Any corrective work required as a result of such tests, such as additional compaction, or a decrease in the thickness of layers, shall be performed by the Contractor at no additional expense to the Owner. In-place density tests shall be made at the Contractor's expense by the geotechnical testing laboratory.
2. The Engineer's duties do not include supervision or direction of the actual work by the Contractor, his employees or agents. Neither the presence of the Engineer nor any observation and testing performed by him shall excuse the Contractor from defects discovered in his work at that time or subsequent to the testing.
3. In-place density tests shall be performed as a minimum according to the following or as directed by the Engineer:
 - a. Two tests per list under spread footings and slabs.
 - b. A minimum of every 5 cubic yards of backfill in trenches or around structures.
 - c. A minimum of one test on subgrade and one test on subbase of every 1,000 square yards of roadway or 100 square yards construction.

3.5 FINE GRADING, AREAS where Pavements or Sidewalks are to be Constructed:

- A. Subgrade: Before surface or subbase is spread, the subgrade shall be shaped to a true surface conforming to the Drawings and as directed by the Engineer. All depressions and high spots shall be filled with gravel subbase material or removed and such areas again compacted until the surface is smooth and properly compacted. A tolerance of 1/4-inch above or below the finished subgrade will be allowed provided that this 1/4-inch above or below grade is not maintained for a distance longer than 50 feet and that the required crown or gutter line is maintained in the subgrade. Any portion which is not accessible to a roller shall be thoroughly compacted by other mechanical methods.
- B. Subbase Spread and Application:

1. The contractor shall employ at his own expense a Registered Land Surveyor to establish, maintain and ensure that the grades and thicknesses for road reconstruction are completed to the specified tolerances and design.
2. The contractor shall establish and/or maintain the subbase grade within 1/4 inches plus or minus of the existing or design grades as indicated directly on plans or as indicated for top of paving surfaces less required thickness, or as directed by the Engineer.

END OF SECTION 02210

SECTION 02273

GEOTEXTILE FABRIC

PART 1 - GENERAL

1.1 SUMMARY

- A. Provide geotextile fabric for separation of existing soil from crushed stone.
- B. Provide geotextile fabric for silt fence as indicated or specified.

1.2 RELATED WORK

- A. DIVISION 1 – GENERAL REQUIREMENTS

1.3 SUBMITTALS

- A. Shop Drawings: Submit the following in accordance with Section 01300 – SUBMITTALS.
 - 1. At least two weeks prior to shipment, submit manufacturer's certificate of compliance and physical property data sheet indicating that requirements for materials and manufacture are in conformance as specified.
 - 2. For informational purposes only, submit manufacturer's printed installation instructions.

1.4 QUALITY ASSURANCE

- A. Provide in accordance with GENERAL SPECIFICATIONS and as specified.
- B. General:
 - 1. Producer of geotextile fabric to maintain competent laboratory at point of manufacture to insure quality control in accordance with ASTM testing procedures. Laboratory to maintain records of quality control results.
 - 2. Do not expose geotextile fabric, except the geotextile fabric for silt fence, to ultraviolet radiation (sunlight) for more than 14 days total in period of time following manufacture until geotextile fabric is installed and covered with fill or backfill material.
 - 3. Take all precautions to protect geotextile fabric from damage resulting from any cause. Either repair or replace geotextile fabric to Engineer's satisfaction at no additional cost to the Owner.

1.5 DELIVERY, STORAGE AND HANDLING

- A. Provide in accordance with GENERAL SPECIFICATIONS and as specified.
- B. Provide geotextile fabric in rolls wrapped with protective covering to protect geotextile fabric from mud, dirt, dust, and debris. Label each roll of geotextile fabric with number or symbol to identify production run.
- C. Protect geotextile fabric from sunlight during transportation and storage. Do not leave geotextile fabric exposed to sunlight for more than two weeks during installation operations.

PART 2 - PRODUCTS

2.1 MANUFACTURERS

- A. Provide the following nonwoven geotextile fabric:
 - 1. Trevira 011/200 as manufactured by Hoechst Celanese Corp., Spartanburg, South Carolina.
 - 2. Mirafi 160N as manufactured by Mirafi, Pendergrass, GA.
 - 3. Amoco 4551 as manufactured by Amoco Fabrics and Fibers Co., Atlanta, GA.
 - 4. Or acceptable equivalent product.
- B. Provide the following woven geotextile fabric for silt fence:
 - 1. Amoco 2122 as manufactured by Amoco Fabrics and Fibers Co., Atlanta, GA.
 - 2. Mirafi 100X as manufactured by Mirafi, Pendergrass, GA.
 - 3. Geotex 910SC as manufactured by Synthetic Industry, Chattanooga, TN.
 - 4. Or acceptable equivalent product.

2.2 MATERIAL

- A. Geotextile fabric shall conform to test requirements for minimum average roll value (weakest principle direction) for strength properties of any individual roll tested from manufacturing lot or lots of particular shipment in excess of minimum average roll value (weakest principle direction) as specified hereafter:
- B. Physical Properties of Minimum Average Roll of nonwoven geotextile fabric for placement between natural sand and rip rap and as the separation layer between

the native soil and the crushed stone working mat below drainage structures shall be:

Property	ASTM Test Method	Units	Value
1. Grab Strength	D4632	lbs [N]	150 [670](min.)
2. Grab Elongation	D4632	%	50 (min.)
3. Trapezoidal Tear Strength	D4533	lbs [N]	60 [270](min.)
4. Puncture Strength	D4833	lbs [N]	75 [330](min.)
5. Permittivity	D4491	sec -1	1.3 (min.)
6. Apparent Opening Size	D4751	Sieve Number	70-100
7. Ultraviolet Stability	D4355	Percent	70 (min.)

C. Physical Properties of Minimum Average Roll of the woven geotextile fabric for silt fence shall be:

Property	ASTM Test Method	Units	Value
1. Grab Strength	D4632	lbs [N]	100[450](min.)
2. Permittivity	D4491	sec -1	0.10 (min.)
3. Apparent Opening Size	D4751	Sieve Number	20-30
4. Ultraviolet Stability	D4355	Percent	70 (min.)

PART 3 - EXECUTION

3.1 INSTALLATION

- A. Install geotextile fabric in accordance with manufacturer's printed instructions.
- B. Overlap geotextile fabric 18 inches minimum for unsewn lap joint. Overlap fabric 6 inches at seam for sewn joint.
- C. Do not permit traffic or construction equipment to travel directly on geotextile fabric.
- D. Place geotextile fabric in relatively smooth condition to prevent tearing or puncturing. Lay geotextile fabric loosely but without wrinkles or creases so that placement of the backfill materials will not stretch or tear geotextile fabric. Leave sufficient slack in geotextile fabric around irregularities to allow for readjustments.

- E. Patch all tears in geotextile fabric by placing additional section of geotextile fabric over tear with a minimum of 3 feet overlay.
- F. Install silt fence in accordance with the manufacturer's printed instructions and as indicated.

3.2 CONTRACT CLOSEOUT

- A. Provide in accordance with Section 01700 – CONTRACT CLOSEOUT.

END OF SECTION 02273

SECTION 02498

RESTORATION OF DISTURBED AREAS

PART 1 - GENERAL

1.1 RELATED DOCUMENTS

- A. Drawings and general provisions of the Contract, including General and Supplementary General Conditions and Division 1 Specification Sections, apply to this section.

1.2 SUMMARY

- A. Provide all plant, labor, equipment, appliances and materials, and in performing all operations in connection with restoration to preconstruction conditions of all areas affected by work under this Contract, complete in accordance with the drawings and specifications.

1.3 GENERAL DESCRIPTION

During its progress, the work and the adjacent areas affected thereby shall be cleaned up and all rubbish, surplus materials, and unneeded construction equipment shall be removed and all damage repaired so that the public and property owners will be inconvenienced as little as possible.

Contractor shall make arrangements and notify property owners 72 hours prior to work which will affect their properties and indicate what will be done to restore the area after construction is completed.

Contractor shall notify all utility companies and local, state and federal authorities which will be affected by his work 72 hours prior to beginning work.

The Contractor on or before the completion of the work, except as otherwise expressly directed or permitted in writing by the Owner, shall tear down and remove and legally dispose of all temporary structures built or used; shall remove all rubbish and debris of all kinds from all Contract structures and from any grounds which he shall have occupied within the limits of the project site; shall leave the site of the work in a satisfactorily neat and clean condition; shall remove from the land all abandoned materials and plant; and shall leave the spoil areas and the property which may have been affected by his operations in a neat and satisfactory condition. Also included is the restoration of all private grounds, including lawns, landscaped areas, driveway aprons and walkways damaged or disturbed in connection with the new work not elsewhere specified. Unless otherwise specified, all materials salvaged and not required to be reused shall be the property of the Contractor, and shall be legally disposed of off the site of the work.

The Contractor shall restore or replace, when and as directed, any public or private property damaged by his work, equipment, or employees, to a condition

at least equal to that existing immediately prior to the beginning of operations. To this end the Contractor shall do as required all necessary highway or driveway, walk, and landscaping work. Suitable materials, equipment, and methods shall be used for such restoration. The restoration of existing property or structures shall be done as promptly as practicable as work progresses and shall not be left until the end of the contract period.

Remove and reset or replace all fencing, guardrails, lawns, posts, curbing, signs, roadways, driveways, sidewalks, and other items which interfere with the progress of the work. Shore or guy any utility pole as required by the utility company.

Included in the work under this Section is the restoration, including replacement of damaged and disturbed shrubs and trees, retaining walls, of all grounds and grassed and landscaped areas removed or disturbed or damaged during the construction of the new work, including pipe laterals within private property areas, and storage and field office areas.

Also included in the work under this Section is the furnishing of all labor, materials, and equipment required to remove, store, and reset or replace bumper posts, stone walls of all types, flagstone walks, fences of all types, railings, signs and sign posts, signal posts, and such other miscellaneous objects damaged or disturbed during construction.

Wherever streets, lawns, roadways, driveways or sidewalks within or outside the contract limit lines have been excavated in fulfilling the work required under this Contract, the Contractor shall furnish and install all materials to bring finished surfaces level with the existing adjacent surfaces and returned to its original condition.

If, during the progress of the contract work, any water pipe, sewer, conduit, drain, or other utility (public or private) is damaged as a result of operations under this Contract, the Contractor, as determined by the Engineer, shall repair all such damage and restore work to its original condition, at no additional expense to Owner.

Where material or debris has washed or flowed into or been placed in existing watercourses, ditches, gutters, drains, pipes structures, work done under this contract, or elsewhere during the course of the Contractor's operations, such material or debris shall be entirely removed and satisfactorily disposed of during the progress of the work, and the ditches, channels, drains, pipes, structures, and work, etc., shall, upon completion of the work, be left in a clean and neat condition.

The Contractor shall thoroughly clean all materials and equipment installed by him and his sub-contractors, and on completion of the work shall deliver it undamaged and in fresh and new-appearing condition. All mechanical equipment shall be left fully charged with lubricant and ready for operation.

Restoration work shall be completed to the satisfaction of the Engineer. Work not deemed satisfactory by the Engineer shall be redone by the Contractor at the

Contractor's expense.

1.4 TRENCHES NOT IN PAVED AREAS

- A. Where the trench occurs adjacent to paved streets in shoulders, sidewalks, or in cross-country areas, the Contractor shall thoroughly mechanically compact the backfill and shall maintain the surface as the work progresses. If settlement takes place, the Contractor shall immediately deposit additional fill to restore the level of the ground. In areas adjacent to streets and highways which are not to be loam and seeded, the top 12-inch layer of trench backfill shall consist of compacted dense-blend gravel borrow or sand and gravel as required to match existing conditions. Trench backfill in unpaved roadways shall have the top 12-inch layer of backfill consist of compacted sand and gravel.
- B. If in the opinion of the Engineer, the top 12-inch layer is unsuitable for use as base course, he may order the Contractor to remove this layer and to provide material that meets specifications.

END OF SECTION 02498

SECTION 02500

PAVING AND SURFACING

PART 1 – GENERAL

1.1 SUMMARY

- A. This section specifies following: installation of pavement on all roadway and parking areas; trench pavement; pavement reclamation for subbase; cold planning; fine grading and compacting; and adjustment of castings as indicated and specified.
- B. Pavement and surfacing shall be constructed in courses as shown on the plans and as directed in accordance with these specifications and in close conformity with the lines, grades, compacted thickness and typical cross section shown on the plans.
- C. The Contractor shall take all reasonable measures to assure proper drainage on the final surface of the roadway. Pavement that does not drain properly due to poor workmanship shall not be accepted by the Owner and shall be replaced by the Contractor at no additional cost to the Owner.
- D. Reference is made herein to the Commonwealth of Massachusetts, Department of Public Works, Massachusetts Highway Department, Standard Specifications for Highways and Bridges, latest edition, hereinafter referred to as the “Massachusetts Highway Department”. All references to method of measurement, basis of payment, and payment items in the Standard specifications are hereby deleted. References made to particular sections or paragraphs in the Standard Specifications shall include all related articles mentioned therein.

1.2 RELATED WORK

- A. DIVISION 1 – GENERAL REQUIREMENTS
- B. Section 02210 – EARTH EXCAVATION, BACKFILL, FILL AND GRADING
- D. Section 02590 – BRICK MASONRY

1.3 SUBMITTALS

- A. Submit the following in accordance with the General Conditions of Contract and Section 01300 – SUBMITTALS:
- B. Shop Drawings:
 - 1. Manufacturer product data, specifications and certificates for all materials including but not limited to:
 - a. Bituminous Concrete base, binder and top, including design mix for roadway and parking area pavement.

- b. Gravel Subbase – Submit in accordance with Section 02210 – EARTH EXCAVATION, BACKFILL, FILL AND GRADING
- c. Brick and Mortar – Submit in accordance with Section 02590 – BRICK MASONRY

2. Infrared pavement sealing equipment specifications.

- C. The Contractor shall submit grain size analysis and moisture density curve performed in accordance with ASTM D422 of the reclaimed pavement material to be reused as subbase. The analysis shall be completed in order to compaction test the reclaimed pavement to be used a subbase. The grain size analysis shall indicate that the material conforms to the gradation requirements specified.
 - 1. Submit additional grain size analysis, moisture density curve and certifications for every 1000 cubic yards (every 200 cubic yards for moisture density curves) of material or anytime consistency of material changes in the opinion of the Engineer. Submit associated chemical laboratory data on the imported materials throughout the course of the Work, if requested by the Engineer, to evaluate the consistency of the source or process, at no additional cost to the Owner.
- D. Submit compaction testing results for all pavement layers and subbase.
- E. Submit temperature testing results for all in-place pavement layers, pavement at time of delivery to the site, ambient air and subbase.
- F. Submit Qualifications of the Contractor's Independent Testing Laboratory as specified in Paragraph 1.4.B, three (3) weeks prior to any testing.

1.4 QUALITY CONTROL

- A. The Engineer may require the Contractor to remove at his/her own expense, any defective mix not conforming to the specified job mix formula within the stipulated tolerances. Samples of the actual mixture in use will be taken as many times daily as necessary and the mixtures shall be maintained uniform for the project. The Engineer may suspend further approval for use of the Plant mixtures if the mixtures do not conform to the specified requirements.
- B. Materials shall not be placed when underlying surface is muddy, frozen, or has frost, snow, or water thereon.
- C. The Contractor shall repair or remove and replace unacceptable paving as directed by Engineer, and at no additional cost to the Owner.
- D. Independent Testing Laboratory: The Contractor shall employ an independent testing laboratory to perform the following tests:
 - 1. Particle size, gradation analyses and compaction testing for subbase. in accordance with Section 02210 – EARTH EXCAVATION, BACKFILL, FILL AND GRADING.

2. Particle size, gradation analyses and compaction testing for reclaimed subbase in accordance with the Standard Specifications.
 3. Compaction testing of all in place pavement courses. The density of the bituminous concrete pavement will be determined by using Nuclear Density Gauge Test - Method ASTM D2950.
 4. Temperature testing of all in place pavement courses, temperature testing of pavement at time of delivery, temperature of subbase and temperature of ambient air.
 5. Core samples of installed pavement to verify the thickness meets requirements.
- E. Grade Control:
1. The Contractor shall employ at his own expense a Registered Land Surveyor to establish, maintain and ensure that the grades and thicknesses for road reconstruction is completed to the specified tolerances and design.
 2. The Contractor shall maintain the subbase grade within 0.25 inches plus or minus of the existing or design grades.
- F. Thickness Tolerances: The Contractor shall test in-place bituminous concrete courses for compliance with requirements for thickness. In-place compacted thickness will not be acceptable if exceeding following allowable variation from required thickness:
1. Top Course: 1/4-inch, plus or minus.
 2. Binder Course: 1/4-inch, plus or minus.
 3. Base Course: 1/4-inch, plus or minus
- E. Bituminous Concrete Temperature Requirements: The Contractor shall supply an approved Dial Type Asphalt Thermometer (Range 0° F to 500° F) for each paving machine in operation on the project. The thermometer shall remain the property of the Contractor upon completion of the project.
1. Refer to Section 1.5 below for delivery temperature requirements.
 2. Temperature of bituminous concrete at the time of placement shall be in accordance with the table in Standard Specifications Section 460.61.
- F. Weather and Date Limitations:
1. Apply prime and tack coats when ambient temperature is above 50 deg.F and when temperature has not been below 35 deg.F for 12 hours immediately prior to application. Do not apply when subbase is wet or contains an excess of moisture.
 2. Binder for temporary pavement may be placed when air temperature is above 30 deg.F and rising.

3. Permanent bituminous concrete shall only be installed when atmospheric temperature is above 40 deg.F.
4. The Contractor shall not install permanent pavement between the dates of October 15th and April 15th unless written approval has been obtained from the Engineer.

G. Compaction Testing:

1. All bituminous mixtures shall be compacted to at least 95% of the density achieved on the laboratory testing of the design mix for the project. Density will be checked by the Nuclear Density Gage Method, ASTM D2950. Testing shall be completed by Contractor at no expense to Owner for every 200 square yards of surface area placed.
2. All subbase shall be compacted and testing in accordance with 02210 – EARTH EXCAVATION, BACKFILL, FILL AND GRADING.
3. All reclaimed subbase shall be compacted and tested in with the MHD Standard Specifications Section 403.64.

H. Core Samples: Core Samples to verify in place pavement thickness to be taken as directed; at least one core sample for every 200 square yards of surface area placed.

1.5 DELIVERY, STORAGE AND HANDLING

- A. Batch ticket information shall be submitted to the Engineer upon placement of bituminous concrete.
- B. Transportation and delivery of bituminous concrete shall be in accordance with the MHD Standard Specifications Section 450.
 1. The temperature of the mix upon delivery to the project site shall be in accordance with the table in Section 450

1.6 DEFINITIONS

- A. Temporary Pavement: Temporary pavement shall mean temporary with regards to the duration of the contract. All temporary pavement shall be removed prior to the placement of permanent pavement. Bituminous concrete for temporary pavement shall meet the material requirements for Bituminous Concrete Binder Course as specified below.
- B. Full Depth Road Reconstruction: Full depth road reconstruction shall mean excavation and replacement of all existing pavement courses; including cobble, brick, cement concrete and bituminous concrete; and subbase to depth of subgrade.

1.7 REGULATIONS (Not Used)

1.8 GUARANTEE

- A. The Contractor shall maintain the surfacing for one year from the date of substantial

completion and shall promptly fill with similar material in compliance with the specifications, any depressions and holes that may occur so as to keep the surfacing in a safe and satisfactory condition for traffic.

- B. The Contractor shall infrared seal the joints of all repairs made to the surfacing due to improper installation during the one-year guarantee period at no additional cost to the Owner.

PART 2 – PRODUCTS

2.1 MATERIALS

- A. Gravel Subbase: Shall conform to MHD Standard Specifications M1.03.1.
- B. Bituminous Concrete Binder Course: Shall conform to the MHD Standard Specifications, M3.11.00 through M3.11.09, Class I Bituminous Concrete Pavement, Type I-1 – Binder Coarse.
- C. Bituminous Concrete Top Course: Shall conform to the MHD Standard Specifications, M3.11.00 through M3.11.09, Class I Bituminous Concrete Pavement, Type I-1 – Top Coarse.
- D. Bituminous Concrete Base Course: Shall conform to the MHD Standard Specifications, M3.11.00 through M3.11.09, Class I Bituminous Concrete Pavement, Type I-1 – Base Coarse.
- E. Bituminous Concrete for Sidewalk: Shall conform to the MHD Standard Specifications, M3.11.00 Class I Bituminous Concrete Pavement.
- F. Bituminous Concrete for Driveways: Shall conform to the MHD Standard Specifications, M3.11.00 through M3.11.09, Class I Bituminous Concrete Pavement, Type I-1 – Top Coarse.
- G. Tack coat shall be RS-1 emulsion.
- H. Asphalt emulsion shall conform to Standard Specification MHD Section M3 – M3.03.0 and shall be AC-20 conforming to AASHTO M226.
- I. Bituminous Concrete for Berms and Curbs: Shall conform to the MHD Standard Specifications, M3.11.00 through M3.11.09, Class I Bituminous Concrete Pavement, Type I-1 – Dense Mix.
- J. Hot Poured Rubberized Joint Sealer: Shall conform to the MHD Standard Specifications, M.3.05.0. The sealer shall meet the requirements of Federal Specification Number SS-S-1401.
- K. Reclaimed Pavement Subbase: Shall conform to the MHD Standard Specifications, M.1.11.0. Gradation requirements are included below:

Sieve Designation	Percent Passing
3-inch	100
1½-inch	70 - 100
¾ - inch	50 - 85
No. 4	30 - 60
No. 50	8 - 24
No. 200	0 - 10

- L. Crack sealer: Crack sealer shall be asphalt slurry mixture type SS-1, SS-1h and shall be maintained at a significant fluidity to be able to flow into the hairline cracks

PART 3 – EXECUTION

3.1 SUBGRADE PREPARATION

- A. Bring subgrade to required grade as necessary prior to placing subbase material.
- B. As directed by the Engineer, over-excavate on-site fill material and any unacceptable materials below the subgrade. Utilize excavating equipment equipped with a toothless or smooth edged, excavating bucket to expose the on-site fill material and unacceptable materials to avoid disturbance of the bearing surface.
- C. Backfill the overexcavation with crushed stone and compact as indicated in Section 02210 – EARTH EXCAVATION, BACKFILL, FILL AND GRADING and in accordance with MHD Standard Specifications.
- D. Proof roll the subgrade prior to placing subbase.

3.2 PLACEMENT AND PREPARATION OF SUBBASE

- A. Do not begin placement of subbase and paving work until deficient subgrade areas have been corrected and are ready to receive paving.
- B. Subbase under roadway shall be installed and compacted in accordance with Section 02210 – EARTH EXCAVATION, BACKFILL, FILL AND GRADING.
- C. The subbase and reclaimed subbase shall be fine graded and compacted for road reconstruction and where indicated in accordance with MHD Standard Specification Section 170.61.
- D. The subbase shall be spread in layers not more than 6-inches thick except the last layer of gravel shall be 3-inches thick, compacted measure. All layers shall be compacted to not less than 95 percent of the maximum dry density of the material as determined by ASTM D1557 Method C at optimum moisture content.

3.3 CLASS I BITUMINOUS CONCRETE BASE COURSE

- A. Base course shall be furnished and installed in accordance with MHD Standard Specification Section 420.

3.4 CLASS I BITUMINOUS CONCRETE FOR TEMPORARY PAVEMENT

- A. SPREADING, FINISHING AND COMPACTING

1. Binder course shall be spread to a finished thickness of 2-inches. A smooth even surface shall be produced.
2. Binder course shall be compacted with a vibratory plate compactor or roller to produce a smooth even surface.
3. Binder course placement for temporary paving shall be installed on a weekly basis or as otherwise indicated by the Owner and Engineer. Cold patch for temporary pavement shall not be allowed.
4. Binder course placed as temporary paving shall be maintained until removed prior to final paving.
5. If requested and/or approved by the Engineer, Asphalt Cold Patch for temporary pavement shall be placed and compacted in two lifts to a total thickness of 2-inches.

3.5 CLASS I BITUMINOUS CONCRETE BINDER AND TOP COURSE

A. EXISTING PAVEMENT EDGES AND JOINTS

1. The edges of existing pavement which are to remain shall be saw cut to an even, straight edge. Trench edges shall be cut back one foot from edge of the trench on each side.
2. Air blast clean edges.
3. All joints at the junction of existing pavement (including recently placed mixtures) and binder course shall be sealed with an asphalt emulsion and covered with sand.
4. All joints at the junction of existing pavements (including recently placed mixtures) and the top course pavement shall be sealed with hot rubberized sealer. The use of hot rubberized sealer may be omitted at the Engineers discretion if the temperature of the existing mixture at the joint is above 203°F.
5. Construct joints to have same texture, density and smoothness as other sections of bituminous concrete course.
6. Overlap joints so that there is a least a one foot overlap between each coarse.
7. A keyway shall be provided at the limits of the full depth road reconstruction between the new roadway and the existing roadway as shown on the pavement joint detail.

B. TACK COAT

1. All contact surfaces shall be cleaned of all foreign matter and loose material and shall be dry before the tack coat is placed.

2. Supply tack coat at a rate of 0.05 to 0.10 gallons per square yard over the binder course. Apply material to penetrate and seal, but not flood, surface. Cure and dry as long as necessary to attain penetration and evaporation of volatile.
3. The tack coat truck shall have pneumatic tires of such width and number that the load produced on the surface shall not exceed 12 kg/mm of tire width, and it shall be designed, equipped, and operated so that at an even heated emulsion may be applied uniformly on variable widths of surface at readily controlled rates from 0.05 to 0.30 gallons per square yard as directed by the Engineer.
4. The tack coat shall be applied within a pressure range of 0.17 to 0.52MPa. Distributor equipment shall include a tachometer, pressure gauges, volume-measuring devices, and a thermometer for reading the temperature of tank contents. The distributor shall be self-powered and shall be equipped with a power unit for the pump and full circulation spray bars adjustable laterally and vertically.
5. The contact surfaces of manhole, catch basin and gate box frames and covers and other appurtenant structures in pavement shall be painted thoroughly with tack coat just before mixture is placed against them.

C. SPREADING AND FINISHING

1. Spreading and finishing of bituminous concrete binder and top course shall be completed in accordance with MHD Standard Specification Section 450.
2. The temperature of the bituminous concrete at the time of placement shall be in accordance with the table in MHD Standard Specification Section 450
3. Place pavement in strips not less than 2-feet wide, unless otherwise acceptable to Engineer. After first strip has been placed and rolled, place succeeding strips and extend rolling to overlap previous strips. Complete binder course for a section before placing top course.
4. Hand Spreading: Hand spreading will be permitted only for particular locations in the work which because irregularities, inaccessibility or other unavoidable obstacles do not allow mechanical spreading and finishing.
5. Immediately after placement of the new pavement, all joints between the existing and new pavement shall be sealed with RS-1 and sanded.

D. COMPACTION

1. Compaction of bituminous concrete shall be completed in accordance with MHD Standard Specification Section 480.
2. Begin rolling when mixture will bear roller weight without excessive displacement.
3. Compact mixture with hot hand tampers or vibrating plate compactors in areas inaccessible to rollers.

4. Breakdown Rolling: Accomplish breakdown or initial rolling immediately following rolling of joints and outside edge. Check surface after breakdown rolling, and repair displaced areas by loosening and filling, if required, with hot material.
5. Second Rolling: Follow breakdown rolling as soon as possible, while mixture is hot. Continue second rolling until mixture has been thoroughly compacted.
6. Finish Rolling: Perform finish rolling while mixture is still warm enough for removal of roller marks. Continue rolling until roller marks are eliminated and course has attained maximum density.

E. CUTTING AND PATCHING

1. Remove and replace paving areas mixed with foreign materials and defective areas. Saw cut-out such areas and fill with fresh, hot bituminous concrete. Compact by rolling to match the surrounding surface density and smoothness.
2. All saw cut joints in surface coarse shall be sealed by infrared methods.

F. PROTECTION

1. After final rolling, do not permit vehicular traffic on pavement until it has cooled and hardened. Erect barricades to protect paving from traffic until mixture has cooled enough not to become marked by wheel traffic.

3.6 CRACK SEALING

- A. Prior to sealing a crack all compressible material shall be removed by high-pressure air or routing. If grass or vegetation is present in the crack the Contractor shall inject a liquid herbicide to prevent future growth.
- B. For larger cracks, sealing shall be with modified asphalts (e.g. hot rubberized asphalt sealer).
- C. For small hairline cracks, sealing shall be with the asphalt slurry mixture. The crack sealer shall be squeegeed over the surface and forced in the cracks.
- D. Sealing of all cracks shall be considered to be complete upon review and approval by the Engineer.

3.7 RAISING AND ADJUSTING CASTINGS

- A. Prior to installation of top layer of permanent paving, all existing catch basin castings, manhole castings, and valve boxes shall be raised, if necessary, to the proper grade by the Contractor.
- B. Castings owned by private utilities may be raised by the responsible utility. The Contractor shall be responsible for coordinating this work.
- C. Bituminous concrete courses shall be sawcut a minimum of 12" from outside edge of frame

or for enough room to allow compaction by a vibratory plate compactor.

- D. Adjust casting with masonry work in accordance Section 02590 – BRICK MASONRY to grade. Adjustments shall be a maximum of 12” in height.
- E. The method of adjusting these castings shall be as follows: Cut around catch basin or manhole castings a minimum of 8 inches from casting. Excavate and if required rebuild up to 10 inches of masonry below the bottom of the casting. Backfill with suitable material and compact to bottom of casting conforming to Section 03300. Place high, early strength cement or bituminous concrete collar, as directed by the Engineer, to approximately 1½ inches below the raised casting grade. Masonry work shall conform to Sections 02252 and 02604, Manholes, and Catch Basins respectively.
- F. The method of raising valve boxes shall be as follows: Cut around valve box a minimum of 8 inches from valve box. Excavate as required and raise the valve box. Pour high early strength cement or bituminous concrete collar, as directed, to approximately 1½ inches below the top of the valve box.
- G. Castings which need to be raised or adjusted to complete final top course full-width paving shall be done immediately prior to paving.

3.8 BITUMINOUS CONCRETE EXCAVATION BY COLD PLANER

- A. Keyways: The Contractor shall saw cut the limits of the cold plane excavation at the connection to existing pavement. A 1’ wide by 4” deep key will be cold planed along the limits of the connection to existing pavement.
- B. Equipment: The Cold Planer shall be equipped with an elevating device capable of loading planed material directly into dump trucks while operative. The Cold Planer shall further have all necessary safety devices such as reflectors, headlights, taillights, flashing lights, and back-up signals so as to operate safely in traffic both in the day or at night. The Cold Planer shall be designed and built for planing flexible pavements and possess the ability to plane cement concrete patches when encountered in bituminous pavement. The Cold Planer shall be self-propelled and have the means for planing without tearing or gouging the underlying surface. The Cold Planer shall be adjustable as to crown and depth and shall meet the standards of the Air Quality Act for noise and air pollution.
- C. Variable lacing patterns shall be provided to permit a rough grooved surface as directed. A 2-inch (5cm) cut is required in one (1) pass. The minimum width of pavement planed in each pass shall be 6-feet (1.8m), except in areas to be trimmed and edged.
- E. The milled or planed surface shall conform generally to the existing grade and cross slope. The surface shall not be torn, gouged, shoved, broken or excessively grooved. It shall be free of imperfections in workmanship that prevent resurfacing after this operation. Excess material shall be swept and removed so that the surface is acceptable to traffic.
- F. The Contractor shall install bituminous concrete binder to the depth of the existing pavement at any areas, which as discovered after cold planning have no existing bituminous concrete.

- G. The Contractor shall maintain the cold planed road until the time of overlay by repairing any pot holes or damaged subbase with bituminous concrete binder at no additional cost to the Owner. The edges of existing base subbase shall be saw cut and tax coated.
 - 1. Cold patch for repair shall be used to repair cold planed patches only after the approval of the Engineer and at no additional cost to the Owner. The Contractor shall remove all cold patch installed complete and replace with permanent bituminous concrete binder prior to completing the overlay at no additional cost to the Owner.
- H. The Contractor shall adjust all castings which do not match the existing pavement grade and slope, including coordinating with private utilities to adjust castings not owned by the City.

3.9 RECLAIMED BASE COURSE

- A. Equipment: Pulverization will be by means of a traveling pulvi-miller or equivalent machine capable of ripping through existing asphalt at depths up to 12" with one pass. The machine shall be self-propelled and be equipped with an adjustable grading blade, thus leaving its path generally smooth for traffic equipment. Road planers or cold milling machines, which are designed to mill or shred the existing bituminous concrete pavement rather than to crush or fracture it, are not considered capable of achieving specification gradation. The required and necessary scraping action of the milling shall provide an increase in the percentage of fine aggregate.
- B. Existing bituminous concrete and gravel base must be ripped and mixed so as to form a homogeneous mass of uniformly processed base material, which will bond together when compacted.
- C. The Contractor shall protect all existing casting, curb work and structures. All existing pavement on side streets, driveways and limits of work shall be saw cut and protected from damage.
- D. The pavement area to be reclaimed shall be swept with a power sweeper to remove all sand, dirt, organic matter, and other unsuitable materials.
- E. The Contractor shall reclaim only that area of pavement that can be processed and compacted by the end of the same working day. Reclaimed areas shall be acceptable for vehicular traffic at the end of each working day.
- F. The total thickness of the existing pavement and the uppermost portion of the subbase layer shall be recycled to the depth shown on the plans.
- G. If gradation deficiencies exist the appropriate crushed stone aggregate size shall be blended with recycled material to produce a uniform mixture meeting gradation requirements.
- H. Dense graded crushed stone shall be added for volume purposes if required.

3.10 INFRARED PAVING

- A. Equipment: The infrared heating system shall be capable of heating the existing bituminous concrete for rework up to a depth of 2" without flaming or altering the binding effect of the asphalt.
- B. The heated asphalt shall be removed and new hot mix asphalt shall be added to match the existing grades.
- C. The infrared paving repair shall be compacted in accordance with this section.
- D. Joints shall be sealed with asphalt emulsion

END OF SECTION 02500

SECTION 02590

BRICK AND CONCRETE BLOCK MASONRY

PART 1 - GENERAL

1.1 SUMMARY

- A. The work covered under this Section includes the furnishing of all plant, labor, equipment, appliances and materials, and in performing all operations in connection with providing brick masonry, as directed, for furnishing and installing masonry plugs, extending frames to grade, masonry walls, manhole invert tables and for all other necessary appurtenant work complete and accepted in accordance with the Drawings and Specifications and as directed.

1.2 RELATED WORK

- A. DIVISION 1 – GENERAL REQUIREMENTS

- 1. Refer to this section for brick sidewalk construction.

1.3 SUBMITTALS

- A. Shop Drawings: Submit the following in accordance with Section 01300 – SUBMITTALS.

- 1. Submit manufacturer specification sheets for and shop drawings for all masonry items, mortar and appurtenances.

1.4 QUALITY CONTROL

- A. Adequate precautions shall be taken in freezing weather to protect the masonry from damage by frost.
- B. The Contractor shall not construct brick or block masonry in freezing weather or if the bricks or blocks contain frost, except with the Engineer's written permission and subject to the conditions the Engineer requires.

PART 2 - MATERIALS

- 2.1 Bricks: Bricks shall be clay or shale brick and shall conform in all respects to ASTM C32, latest revision, Grade SS. Brick used for extending manhole frames to grade shall be concrete brick conforming to ASTM C139, latest revision.
- 2.2 Concrete Blocks: Concrete blocks shall conform in all respects to ASTM C139, latest revision.
- 2.4 Cement: Cement shall conform to the standard specifications for Portland cement of ASTM C150, latest revision, Type II, unless otherwise directed. Whenever directed by the Owner,

quick-setting cement (Type III) shall be used for any desired purpose at no additional expense to the Owner.

- 2.5 Sand: Sand for mortar shall be graded uniformly from fine to coarse and when dry shall pass a No. 8 sieve. Sand shall consist of aggregate having clean, hard, durable, strong, uncoated grains and free from injurious amounts of dust, lumps, soft or flaky particles, shale, alkali, organic matter, loam or other deleterious substances. The sand shall be washed clean before loading on delivery trucks. Natural sand which shows a color darker than the standard color when tested in accordance with the Colorimetric Test for Sands as described in ASTM C40, latest revision, will be cause for rejection.
- 2.6 Lime: Lime shall be hydrated lime conforming to ASTM C207, latest revision.
- 2.7 Water: Mixing water for concrete and mortar shall be clean and free from oil, acid, alkali, injurious amounts of vegetable matter and other impurities. Potable water obtained from a municipal supply is preferable.
- 2.8 Mortar: Mortar and mortar plaster shall be composed of one part Type II portland cement, and two parts sand to which a small amount of hydrated lime, not to exceed 10 lbs. to each bag of cement, shall be added. Only a sufficient amount of water shall be added to make a stiff plastic mortar of a consistency and texture satisfactory to the Owner. Retempering of mortar in which the cement has started to set will not be permitted.

PART 3 - EXECUTION:

- 3.1 Brick masonry plugs for pipes and structures shall be 8-inches thick, unless otherwise shown or directed.
- 3.2 Each concrete block shall have a length of no more than 18-inches and a height of no more than 8-inches, unless otherwise shown or directed.
- 3.3 Bricks or concrete blocks that are broken, warped, cracked or of improper size or quality, or otherwise defective shall not be used in the work and shall be removed from the site. Broken or chipped bricks or blocks may be used to shape around irregular openings only if permission is granted by the Engineer.
- 3.4 Use either rectangular block units, or block units curved in shape with the inside and outside surfaces curved to the required radii. For corners use blocks with a return side not less than ½ the length of the normal block.
- 3.5 When using concrete blocks in the cones, or tops of manholes, or other structure, they may have any shape required to form the structure with inside and outside joints not more than 3/8-inches thick. Also, design the block so that only full-length or ½-length units are required to lay any one course.
- 3.6 Bed joints shall be formed of a thick layer of mortar which shall be smoothed or furrowed slightly. Head joints shall be formed by applying to the brick to be laid a full coat of mortar on the entire end, or on the entire sides as the case requires, and then shoving the mortar-covered end or side of the brick tightly against the bricks laid previously; the practice of buttering at the

corners of the brick and then throwing mortar or scrapings into the empty joints will not be permitted. Dry or butt joints will not be permitted. Joints on the inside face of walls shall be tooled slightly concave with an approved jointer when the mortar is thumbprint hard; the mortar shall be compressed with complete contact along the edges so as to seal the surface of the joints.

- 3.7 Do not make joints more than ½-inch thick and use a uniform thickness throughout the structure. Finish all joints properly as the work progresses and on exposed faces strike them neatly using the “weather” joint, except if a plaster coat is required rake the joint.
- 3.8 All beds on which masonry is to be laid shall be cleaned and wetted properly. Thoroughly wet all bricks or blocks and let the surface dry so they shall be damp, but free of any surface water when placed to prevent slipping on the mortar.
- 3.9 Lay the first course of bricks or blocks on a full bed of mortar. Lay all bricks or blocks in courses with full and close mortar joints. Maintain horizontal courses throughout the structure. Adjoining courses shall break joints by ½ the length of the brick or block, if possible. Make at least one course in every 7, for double-wall construction, all headers. If using brick for making closures, make their length not less than the width of a whole brick and, if possible make closures with whole brick as headers.
- 3.10 Apply a plaster coat of mortar to the interior and exterior surfaces of brick, concrete block, or block masonry, in manholes, inlets, and similar sewer or drain structures. Make this plaster coat with the same mortar used in laying the bricks or blocks and make it not less than ½-inch thick. Before applying a plaster coat to a brick or block surface, wet them with water and let the surface dry enough to bond to the plaster coat.
- 3.11 Brick masonry for extending frames to grade shall be constructed to the thickness indicated and shall be to the dimensions of the flange of the cast iron frames at top of manholes.
- 3.12 Brick masonry for manhole invert tables shall be one course constructed to the slope shown on the details or as directed.
- 3.13 Masonry walls shall be constructed to the thickness indicated. Other brick and concrete masonry shall be provided to the details and the dimensions specified, indicated or as directed.
- 3.14 Masonry construction shall be done in a manner to insure watertight construction and all leaks in masonry shall be sealed.
- 3.15 Unless the plans or contract provides otherwise, construct concrete footings, not less than 6-inches thick, and that cover the entire area under all brick or concrete block masonry.
- 3.16 Plaster shall be troweled to a smooth hard finish and no backfill shall be placed until the mortar has thoroughly hardened.
- 3.17 All workmanship shall conform to the best standard practice, and all brick and concrete block masonry shall be laid by skilled workmen.

END OF SECTION 02590

SECTION 02622

POLYVINYL CHLORIDE GRAVITY PIPE

PART 1 - GENERAL

1.1 SUMMARY

- A. This section includes the following:
 - 1. Providing and testing of pipe, pipe fittings and specials, jointing materials, and accessories, of various sizes, classes, joints and types, and appurtenant work, at the locations and to the lines and grades as indicated and/or as directed, complete in place, in accordance with the drawings and specifications.
 - 2. The pipe specified under this section shall include all gravity pipes for new or replacement sewer and drain pipe.

1.2 RELATED WORK

- A. DIVISION 1 – GENERAL REQUIREMENTS
- B. Section 02210 – EARTH EXCAVATION, BACKFILL, FILL AND GRADING
- C. Section 02252 – PRECAST CONCRETE MANHOLES

1.3 SUBMITTALS

- A. Shop Drawings: Submit the following in accordance with Section 01300 – SUBMITTALS:
 - 1. Submit shop drawings or descriptive literature, or both, showing pipe dimensions, joints, joint gaskets, and other details for each size of pipe to be furnished for the project within two weeks of Notice to Proceed. All pipe furnished shall be manufactured only in accordance with the specifications and the drawings.

PART 2 - PRODUCTS

2.1 PIPE FITTINGS AND SPECIALS

- A. The polyvinyl chloride pipe and fittings, including those required for stubs, shall conform to ASTM Standard Specifications for Type PSM PVC Sewer Pipe and Fittings, Designation ASTM D3034, latest revision, for sizes 4"-15". Main line pipe (sizes 8" to 24") shall have pipe diameter to wall thickness ratio SDR-35. Service laterals and service pipe (sizes 6" to 8") shall have pipe diameter to wall thickness ratio of SDR-35. The pipe shall be tested by the flat plate deflection method at a minimum of 45 psi at 5 percent deflection in accordance with ASTM D 2412. Standard laying lengths shall be either 14 feet or 20 feet. Fittings shall be compatible with SDR-26 pipe, SDR-35 pipe, or both pipes as required where service pipes connect to main line.

2.2 JOINTS

- A. Joints for the polyvinyl chloride pipe shall be push-on bell and spigot joints using elastomeric ring gaskets. The gaskets shall be securely fixed into place in the bells so that they cannot be dislodged during joint assembly. The gaskets shall be of a composition and texture which is resistant to common ingredients of sewage and industrial wastes, as well as petroleum products (oil, gasoline, etc.) and groundwater, and which will endure permanently under the conditions of the proposed use. The joints shall conform to ASTM Standard Specifications for Joints for Drain and Sewer Plastic Pipes using Flexible Elastomeric Seals, Designation D3212. Gaskets shall conform to ASTM F477.

2.3 INSPECTION, TESTS, AND ACCEPTANCE

- A. All pipe delivered to the job site shall be accompanied by test reports certifying that the pipe and fittings conform to the above-mentioned ASTM Specifications. In addition, the pipe shall be subject to thorough inspection and tests, as deemed necessary by the Engineer.
- B. All tests shall be made in accordance with the methods prescribed by the above mentioned ASTM Specifications, and the acceptance or rejection shall be based on the test results.
- C. The Contractor shall furnish all labor to assist the Engineer in inspecting the pipe. Pipe will be inspected upon delivery, and such as does not conform to the requirements of this contract shall be rejected and shall immediately be removed from the project site by the Contractor.

PART 3 - EXECUTION

3.1 HANDLING PIPE

- A. All pipe shall be stored at the site until installation in a manner which will keep the pipe at ambient outdoor temperatures. Temporary shading shall be provided as required to meet this requirement. Simply covering the pipe which allows temperature build-up when exposed to direct sunlight will not be permitted.
- B. Care shall be taken to avoid damaging the pipe and fittings.

3.2 INSTALLATION

- A. Each pipe unit shall be inspected before being installed. No single piece of pipe shall be laid unless it is generally straight. The centerline of the pipe shall not deviate from a straight line drawn between the centers of the openings at the ends of the pipe by more than 1/16-inch per foot of length. If a piece of pipe fails to meet this requirement for straightness, it shall be rejected and removed from the site. Any pipe unit or fitting discovered to be defective either before or after installation shall be removed and replaced with a sound unit. Installation shall conform to ASTM D 2321.
- B. No pipe or fitting shall be permanently supported on saddles, blocking, or stones. Crushed stone and sand shall be as specified in Section 02210.
- C. Suitable bell holes shall be provided, so that after placement, only the barrel of the pipe receives bearing pressure from the supporting material. Special care shall be taken to hold the trench width at the crown of the pipe to the maximum width indicated in the Trench Detail on the Contract Drawings.

- D. All pipe and fittings shall be cleared of all debris, dirt, etc., before being installed and shall be kept clean until accepted in the completed work.
- E. Pipe and fittings shall be installed to the lines and grades indicated on the Drawings. Care shall be taken to ensure true alignments and gradients.
- F. Before any joint is made, the previously installed unit shall be checked to assure that a close joint with the adjoining unit has been maintained and that the inverts are matched and conform to the required grade. The pipe shall not be driven down to the required grade by striking it with a shovel handle, timber or other unyielding object.
- G. All joint surfaces shall be cleaned. Immediately before jointing the pipe, the bell or groove shall be lubricated in accordance with the manufacturer 's recommendation. Each pipe unit shall then be carefully pushed into place without damage to pipe or gasket. Suitable devices shall be used to force the pipe units together so that they will fit with minimum open recess inside and outside and have tightly sealed joints. Care shall be taken not to use such force as to wedge apart and split the bell or groove ends.
- H. Joints shall not be "pulled" or "cramped" unless permitted by the Engineer.
- I. Where any two pipe units do not fit each other closely enough to enable them to be properly jointed, they shall be removed and replaced with suitable units and new gaskets.
- J. Details of gasket installation and joint assembly shall follow the directions of the manufacturers of the joint materials and of the pipe, all subject to review by the Engineer. The resulting joints shall be watertight and flexible.
- K. All premolded gasket joint polyvinyl chloride pipe of a particular manufacturer may be rejected if there are more than five unsatisfactory joint assembly operations or "bell breaks" in 100 consecutive joints, even though the pipe and joint conform to the appropriate ASTM Specifications as hereinbefore specified. If the pipe is unsatisfactory, as determined above, the Contractor shall, if required, remove all pipe of that manufacturer of the same shipment from the work and shall furnish pipe from another manufacturer which will conform to all of the requirements of these specifications.
- L. Open ends of pipe and branches shall be closed with polyvinyl chloride stoppers secured in place in an acceptable manner.
- M. After each pipe has been properly bedded, enough bedding material shall be placed between the pipe and the sides of the trench, and thoroughly compacted, to hold the pipe in correct alignment. Bell holes, provided for jointing, shall be filled with bedding material and compacted, and then bedding material shall be placed and compacted to complete the pipe bedding.
- N. The Contractor shall take all precautions to prevent flotation of the pipe in the trench.
- O. At all times pipe installation is not in progress, the open ends of the pipe shall be closed with temporary watertight plugs, or by other acceptable means.

- P. If water is in the trench when work is to be resumed, the plug shall not be removed until suitable provisions have been made to prevent water, earth, or other substances from entering the pipe.
- Q. Pipelines shall not be used as conductors for trench drainage during construction.
- R. During backfilling operations, a brightly colored polyethylene tape manufactured specifically for warning and identification of buried utility lines shall be buried 2 feet below the ground surface along the entire length of the pipe from the pumping station to the point of discharge. Tape shall be provided in rolls, 6-inches minimum width, color coded for intended service with warning and identification imprinted in bold black letters continuously and repeatedly over entire tape length. Warning and identification shall be “CAUTION BURIED SEWAGE PIPE BELOW” or similar wording. Code and letter coloring shall be permanent, unaffected by moisture and other substances contained the trench backfill material.

3.3 ALLOWABLE PIPE DEFLECTION

- A. Pipe provided under this Specification shall be so installed as to not exceed a maximum deflection of 5.0 percent. Such deflection shall be computed by multiplying the amount of deflection (nominal diameter less minimum diameter when measured) by 100 and dividing by the nominal diameter of the pipe.
- B. Upon completion of a section of pipe, including placement and compaction of backfill, the Contractor shall measure the amount of deflection by pulling a specially designed gage assembly through the completed section. The gage assembly shall be in accordance with the recommendations of the pipe manufacturer, and be reviewed by the Engineer. The section of pipe must be placed and backfilled for a minimum of 90 days before the deflection can be measured.
- C. Should the installed pipe fail to meet this requirement, the Contractor shall do all work to correct the problem without additional compensation.

3.4 CLEANING

- A. Care shall be taken to prevent earth, water and other materials from entering the pipeline. As soon as possible after the pipe and manholes are completed, the Contractor shall clean out the pipeline and manholes being careful to prevent soil, water and debris from entering any existing pipe.

3.5 TESTING OF PIPE

- A. If the visual inspection of the completed pipe or any part thereof shows any pipe, manhole or joint which allows infiltration of water in a noticeable stream or jet, the defective work or material shall be replaced or repaired as directed.
- B. After completing installation and backfill of pipe, the Contractor shall, at his expense, conduct a line acceptance test using low pressure air.
- C. Equipment used shall meet the following minimum requirements.

- D. Pneumatic plugs shall have a sealing length equal to or greater than the diameter of the pipe to be inspected.
- E. Pneumatic plugs shall resist internal test pressures without requiring external bracing or blocking.
- F. All air used shall pass through a single control panel.
- G. Three individual hoses shall be used for the following connections.
 - 1. From control panel to pneumatic plugs for inflation.
 - 2. From control panel to sealed line for introducing the low pressure air.
 - 3. From sealed line to control panel for continually monitoring the air pressure rise in the sealed line.
- H. All pneumatic plugs shall be seal tested before being used in the actual test installation. One length of pipe shall be laid on the ground and sealed at both ends with the pneumatic plugs to be checked. Air shall be introduced into the plugs to the manufacturer's recommended inflation pressure. The sealed pipe shall be pressurized to 5 psig. The plugs shall hold against this pressure without bracing and without movement of the plugs out of the pipe.
- I. After a manhole to manhole reach of pipe has been backfilled and cleaned, and the pneumatic plugs are checked by the above procedure, the plugs shall be placed in the line at each manhole and inflated to 25 psig. Low pressure air shall be introduced into this sealed line until the internal air pressure reaches 4 psig greater than the average back pressure of any groundwater that may be over the pipe. At least two minutes shall be allowed for the air pressure to stabilize.
- J. After the stabilization period (3.5 psig minimum pressure in the pipe), the air hose from the control panel to the air supply shall be disconnected. The portion of line being tested shall be termed "Acceptable" if the time required in minutes for the pressure to decrease from 3.5 to 2.5 psig (greater than the average back pressure of any groundwater that may be over the pipe) is not less than the time shown for the given diameter in the following table:

Pipe Diameter	Time
<u>Inches</u>	<u>Minutes</u>
4	2.0
6	3.0
8	4.0
10	5.0
12	6.0

- K. In areas where groundwater is known to exist, the Contractor shall install a 1/2-inch diameter capped pipe nipple, approximately 10-inches long, through the manhole wall adjacent to one of the sewer lines entering the manhole. This shall be done at the time the line is installed. Immediately prior to the performance of the Line Acceptance Test, the groundwater shall be determined by removing the pipe cap, blowing air through the pipe nipple into the ground so as to clear it, and then connecting a clear plastic tube to the nipple. The hose shall be held vertically and a measurement of the height in feet of water over the invert of the pipe shall be taken after the water has stopped rising in this plastic tube. The height in feet shall be divided by 2.3 to establish the pounds of pressure that will be added to all readings. (For example, if the height of water is 11-1/2 feet, then the added pressure will be 5 psig. This increases the 3.5 psig to 8.5 psig, and the 2.5 psig to 7.5 psig. The allowable drop of one pound and the timing remain the same). In no case shall the starting pressure exceed 9.0 psig.

3.6 TEST FAILURE

- A. If the section of pipe fails to pass the leakage and pressure test, or if there is any visible leakage, the Contractor shall locate, uncover and repair or replace the defective pipe fitting or joint and retest all at his own expense. Pipe will be considered passing only when the leakage does not exceed the above standard. Passing the test does not absolve the Contractor from his responsibility if leaks develop later within the period of warranty.

3.7 CONTRACT CLOSEOUT

- A. Provide in accordance with Section 01650 – CONTRACT CLOSEOUT.

END OF SECTION 02622

SECTION 02652

EXTERNAL CHEMICAL SEALING FOR MANHOLES

PART 1 – GENERAL

1.1 SUMMARY

- A. This section governs all work, materials and testing required for the chemical grouting of manhole defects. Manholes or section of manholes with active leaks shall be repaired as indicated in Section 01010 – SUMMARY OF WORK.
- B. The Contractor shall be responsible for furnishing all labor, materials, equipment, and testing required for the completion of chemical grouting of manhole defects in Accordance with the Contract documents.

1.2 RELATED WORK

- A. DIVISION 1 – GENERAL REQUIREMENTS
- B. Section 02763 – INTERIOR MANHOLE REHABILITATION

1.3 SUBMITTALS

- A. Submit the following in accordance with Conditions of Contract and Section 01300 – SUBMITTALS.
 - 1. Manufacturer to provide proof of product liability insurance, material data sheets, and MSDS sheets for all materials used in the grating/sealing process as well as manufacturer installation procedures.
 - 2. Provide case histories of successful use or defend choice of materials to the satisfaction of the Engineer.
 - 3. Submit manufacturer's recommended installation procedures for informational purposes.

1.4 MANUFACTURER'S RECOMMENDATIONS

- A. All materials, additives, mix ratios, and procedures needed for the grouting process shall be in accordance with manufacturer's recommendations. Manufacturer must provide proof of product liability insurance, material data sheets and MSDS sheets.

1.5 MANHOLES

- A. Manholes to be grouted are of brick, precast concrete or concrete block.

PART 2 – PRODUCTS

2.1 GROUTING MATERIALS

- A. Hydro-Active Chemical grout shall be an Acrylate or a Polyurethane based material designed for used in a wet environment. Material must be capable of with standing movement cased by thermal cycle changes and or settling of the structure.

2.2 GROUT MATERIALS

- A. Polyurethane Chemical Grouts
Hydro – Active Seal Foam by De neef or equivalent
- B. Acrylate Chemical Grouts
AV – 100 Acrylamide by Avanti or equivalent
AC – 400 Acylate Chemical Grout by De neef or equivalent

2.3 INJECTION ACCESSORIES

- A. Oakcum Rope
Grout Needles
Flow Valve
Hydraulic Cement
- B. The following properties shall be exhibited by the grout.
 - 1. Documented service of satisfactory performance in similar usage.
 - 2. Controllable reaction times and shrinkage through the use additives supplied by the same manufacturer. The minimum set time shall be established so that adequate grout travel is achieved.
 - 3. Resistance to chemicals; to most organic solvents, mild acids and alkali.
 - 4. The chemical shall be essentially non-toxic in a cured form.
 - 5. The material shall be able to withstand freeze/thaw and moving load conditions

2.4 ADDITIVES

- A. Additives may be utilized for catalyzing the reaction, lowering the freezing temperature of the chemical, and minimizing dehydration of the materials.

2.5 MATERIAL IDENTIFICATION

- A. The Contractor shall completely identify the types of grout, mortar, and sealant used and provide case histories of successful use or defend the choice of grouting materials based on chemical and physical properties, ease of application, and expected performance, to the satisfaction of the Engineer.

2.6 MIXING AND HANDLING

- A. Mixing and handling of chemical grout, which may be toxic under certain conditions shall be in accordance with the recommendations of the manufacturer and in such a manner to minimize hazard to personnel. It is the responsibility of the Contractor to provide appropriate protective measures to ensure that chemicals or gels are handled by authorized personnel in the proper manner. All equipment shall be subjected to the approval of the Engineer. Only personnel thoroughly familiar with the handling of the grouting material and additives shall perform the grouting operations.

PART 3 – EXECUTION

3.1 GENERAL

- A. Manhole grouting shall not be performed until the repair of the manhole frame and grade ring or any other structural manhole repairs are complete.

3.2 PRELIMINARY REPAIRS

- A. The Contractor shall cut and trim all roots within the manhole.
- B. The Contractor shall seal all unsealed lifting holes, unsealed step holes, voids larger than approximately one-half (1/2) inch in thickness. All cracked or deteriorated material shall be removed from the area to be patched and replaced with a waterproof quick setting mortar such as de neefs Dene-Plug or Dene-Plug hot or equivalent with manufacturer's specifications.
- C. The Contractor shall perform the Soakum Oakum Technique by soaking dry oil free oakum with HA Multi Gel and or HA Seal foam NF and forcing the Oakum/Resin plug into opening until it sets.

3.3 TEMPERATURE

- A. Normal grouting operations shall be performed in accordance with Manufacturer's recommendations.

3.4 GROUTING MATERIAL USAGE

- A. Grouting to a manhole may include corbel, wall, pipe seals, manhole joints, well to flattip joint, and or bench/trough. The Engineer will direct areas of the manholes designated to be grouted. If entire manhole is scheduled for grouting, grouting shall include corbel, wall, pipe seals, and bench trough. Pipe seal grouting shall include all pipe seals in the specified manhole and grouting of the specified manhole including the bench/trough to the maximum height of 18 inches from crown.

3.5 DRILLING AND INJECTION

- A. Injection holes shall be drilled through the manhole wall at locations recommended by the manufacturer or as directed by the Engineer.
- B. Grout shall be injected through the holes under pressure with suitable injection packers and or wall spears. Injection pressure shall not cause damage to the manhole structure or surrounding surface. Grout shall be injected through the lowest holes first. The procedure shall be repeated until the manhole is externally sealed with grout.
- C. Grouting from the ground surface shall not be allowed unless interior gases are above average.
- D. Grout travel shall be verified by observation of grout to defects or adjacent injection holes. Provide additional injection holes, if necessary to ensure grout travel.
- E. Injection holes shall be cleaned with a drill and patched with a waterproof quick setting mortar such as Quadrex material or equivalent (Refer to Section 02763 – INTERIOR MANHOLE REHABILITATION).

3.6 TESTING OF REHABILITATED MANHOLES

- A. If exfiltration or vacuum testing is used, usually 10 percent of the sealed manholes, as chosen by the inspector, are tested. Manholes that fail are reworked and retested by the Contractor. If more than 5 percent of the manholes tested fail the initial test, an additional 10 percent of the sealed manholes are tested. This process continues until the testing is satisfactory or until all manholes have been tested. Limitations and considerations include recognizing the exfiltration and vacuum testing by be impractical or cost-prohibitive for all manholes; therefore, the use of either method is subject to the following limitations and considerations.
- B. Complete Sealing: These methods are used only when the entire manhole has been sealed or rehabilitated. The lack of sealing or rehabilitation of some portions of the manhole may prevent passage of either of these tests. Spot repairs and partial sealing or rehabilitation are therefore subject infiltration and visual testing only.
- C. Inlet and Outlet Sewers: Manholes built over a large diameter sewers may be impractical and uneconomical to test using either of these methods due to bypassing requirements, availability of plugs, and high forces that are generated on the plugs. Consideration must be given to these factors when determining the method of acceptance testing to be used.
- D. Structural Conditions: The structural condition of some manholes may be such that testing with these methods is impractical and destructive. The Owner's Representative and Contractor shall therefore deem as structurally sound, prior to testing and using these methods, those manholes that have not been structurally lined.

3.7 CONTRACT CLOSEOUT

- A. Provide in accordance with Section 01700 – CONTRACT CLOSEOUT.

END OF SECTION 02652

SECTION 02760

PIPELINE INTERNAL INSPECTION

PART 1 – GENERAL

1.1 SUMMARY

- A. This Section includes the following:
 - 1. Furnishing all plant, labor, equipment and materials, as well as performing all operations associated with manhole and structure cleaning as indicated on the Drawings in accordance with these Specifications.
 - 2. Performing the work in a sequence that is the least disruptive to vehicular and pedestrian traffic and in a manner that shall protect the public from damage to persons and property.

1.2 RELATED WORK

- A. DIVISION 1 – GENERAL REQUIREMENTS
- B. Section 02761 – BYPASS FLOW HANDLING
- C. Section 02765 – SEWER LINE AND MANHOLE CLEANING

1.3 SUBMITTALS

- A. General: Submit each item in this article according to the conditions of the Contract and Division 1, Section 01300 – SUBMITTALS:
 - 1. Shop drawings and/or manufacturer's descriptive literature indicating materials, equipment and methods to complete pipeline inspection operations.
 - 2. Shop drawings and/or manufacturer's descriptive literature indicating materials, equipment and methods to complete internal inspection operations including lateral launching and camera location/depth signal locator equipment.
 - 3. A representative sample DVD or USB showing the quality of work obtained by the assembly prior to internal inspection and cleaning.
 - 4. Two (2) copies of inspection reports for both pre and post construction internal inspections.
 - 5. Confined Space Entry certifications for all personnel entering pipeline or access structures.

- B. Contractor shall submit complete documentation of qualifications as specified herein.

1.4 QUALITY ASSURANCE

- A. Provide in accordance with GENERAL SPECIFICATIONS and as specified herein.
- B. The Contractor cleaning and internally inspecting the pipeline shall have completed at least three (3) projects of similar size and complexity as this project in the United States within the past three (3) years. Contractor may employ the services of a subcontractor that specializes in this work to fulfill this requirement.
- C. Rejection of any subcontractor and/or manufacturer by the Engineer due to insufficient qualifications shall not be grounds for modifications to the Contract Documents such as change in scope, time of completion or contract amount.
- D. All Contractor's personnel entering pipeline or access structures shall be Confined Space Entry trained per OSHA, Title 29 CFR 1910.46 and shall have a copy of their certification available on site at all times.

1.5 DELIVERY, STORAGE AND HANDLING

- A. Provide in accordance with GENERAL SPECIFICATIONS.

PART 2 - PRODUCTS

2.1 CLOSED-CIRCUIT TELEVISION INSPECTION

- A. Camera and vehicle assembly:
 - 1. Industry standard for internally inspecting pipelines within the range of diameters applicable to this project.
 - 2. Remote-controlled, robotic assembly capable of viewing 360° of pipeline interiors. At areas of interest, camera shall be capable of rotating its lens to obtain a more direct viewing angle.
 - 3. Capable of operation in 100 percent humidity conditions.
 - 4. Capable of being moved through the pipeline in either direction at a slow rate by means of manual cable winches or motorized mechanical equipment of indirect drive type.
 - 5. Capable of slowing down and stopping at areas of interest.
 - 6. Capable of panning, tilting, and zooming
 - 7. Provide high intensity light feature for recording purposes.

8. Capable of measuring the camera's position within the pipeline accurate 0.10 feet.
 9. Capable of recording still digital images of observations of interest.
 10. Capable of launching camera from tractor camera into lateral services from mainline pipe up to 100 feet.
 11. Capable of locating tractor camera and launch camera in mainline and laterals to provide approximate location and depth.
- B. During the internal inspection of pipelines, the Owner and the Engineer shall have the ability to view the pipe interior as it is being inspected on a TV monitor set up in a remote location.
- C. Digital Recordings:
1. Digital recordings must be presented on DVD or USB media and display continuously and simultaneously generated transparent digital information to include the date, time, pipeline section number, corresponding station numbers and direction of camera relative to flow.

Example: Time: 4:14:08 PM
 Date: 5/7/02

 ELM ST.
 MH #2 to MH #3 (Downstream)
 STATION 2+50.7
 2. Digital recording files shall be arranged in "Chapters" by pipe section.
 3. Separate DVDs or USB shall be provided for each day of CCTV inspection.
 4. DVDs shall be labeled to include:

-Date of Inspection
-Street or Location
-Town/City
-Building Number (if known) for service lateral inspections
- D. Advanced technologies:
1. Contractor may utilize an alternative method of internal inspection, such as digital systems, provided the method meets the minimum requirements indicated herein and provided it is acceptable and the Engineer.

PART 3 – EXECUTION

3.1 GENERAL

- A. Contractor shall perform all work in accordance with municipal, state and federal requirements including OSHA.
- B. Contractor shall obtain relevant permits required to perform work prior to the commencement of construction at no additional cost to the Owner.
- C. Contractor shall locate and uncover all manholes and/or access structures required to complete the work in accordance with this Section.
- D. Contractor shall maintain existing flows around the work during cleaning inspection operations in accordance with Section 02761.

3.2 CLOSED CIRCUIT TELEVISION INSPECTION

- A. Contractor shall stop and focus the camera at locations where one or more of the following points of interest are observed:
 - 1. Inflow/Infiltration sources.
 - 2. Construction defects, discolorations, wrinkles, etc.
 - 3. Structural defects including broken pipe, collapsed pipe, cracks or abnormalities.
 - 4. Abnormal joint conditions such as root intrusion, protruding lateral connections, in-line pipe size changes and/or material changes.
 - 5. Mineral deposits, grease, obstructions, etc.
 - 6. Lateral connections; plugged or open.
 - 7. Offset joints or misalignments:
 - 8. Manholes, access structures, etc.
 - 9. Any other locations where the conditions may affect construction operations.
 - 10. Any other location as required by the Engineer.
- B. The Contractor shall provide and maintain access to the system, including inflow control and dewatering within pipelines and associated structures as well as all other work required to perform the internal inspections to the satisfaction of the Engineer.

3.3 INSPECTION REPORTS

- A. At the conclusion of each internal inspection, the Contractor shall provide a summary report highlighting results of the investigations and summarizing conditions and points of interest listed in Paragraph 3.2 and as specified herein including the distance of each

observation from the beginning manhole, and digital photo insets. All documentation shall be cross-referenced by stationing to enable the reviewer to identify a particular location.

3.4 ACCEPTANCE

- A. Acceptance of the pipeline cleaning shall be made upon the successful completion of the television inspection. If, in the opinion of the Engineer, cleaning has not been completed in accordance with these Specifications, the Contractor shall be required to re-clean and re-inspect the pipe until the cleaning is shown to be satisfactory, at no additional cost to the Owner. The Engineer may require the Contractor to pull a double squeegee (with each squeegee the same diameter as the pipe) through each manhole section as evidence of adequate cleaning.
- B. Internal inspection operations, both pre and post construction shall be considered for acceptance upon receipt by the Engineer of the following:
 - 1. Two (2) copies of the internal inspection reports
 - 2. Two (2) copies of DVD or USB recordings showing pipelines and associated structures inspections.

3.5 CONTRACT CLOSEOUT

- A. Provide in accordance with Section 01700 – CONTRACT CLOSEOUT.

END OF SECTION 02760

SECTION 02761

BYPASS FLOW HANDLING

PART 1 – GENERAL

1.1 SUMMARY

- A. This Section includes the following:
 - 1. Furnishing all plant, labor, equipment and materials, as well as performing all operations associated with handling bypass flows from the existing sewer and drain system around the work as required and/or indicated on the Drawings in accordance with these Specifications.
 - 2. Maintaining flow from main pipelines without interruption of service, and maintaining flow in lateral connections with minimal interruption of service.
 - 3. Performing the work in a sequence that is the least disruptive to vehicular and pedestrian traffic and in a manner that shall protect the public from damage to persons and property.
- B. Contractor shall design the bypass flow handling system.

1.2 RELATED DOCUMENTS

- A. DIVISION 1 – GENERAL REQUIREMENTS
- B. Section 02760 – PIPELINE CLEANING AND INTERNAL INSPECTION

1.3 SUBMITTALS

- A. Submit the following in accordance with Section 01300 – SUBMITTALS:
 - a. Location, configuration and cross-country routing of bypass flow handling pipes.
 - b. Staging area(s) for pumps and other equipment.
 - c. Upstream flow collection location and/or bulkheads.
 - d. Downstream discharge location.
 - e. Method of protecting structures that accept discharge flows.
 - f. Locations of individual bypass flow handling systems.
 - g. Sample notification of property owner service shutdown.
 - h. Traffic management plan.
 - i. Roadway crossing details including hose ramps or trench details.
 - j. Noise pollution abatement plan.

3. List of 24-hour emergency telephone numbers at which the Contractor may be reached.
- B. Contractor shall submit a Certificate of Design (refer to Section 01300 – SUBMITTALS) for the bypass flow handling system and shall be responsible for the design of the following system components:
1. Pumps.
 2. Generators and power sources.
 3. Suction and discharge piping, including fused HDPE as required.
 4. Temporary pipe supports and anchoring.
 5. Pipe plugging and bulkheads.
 6. Noise control equipment.
 7. Calculation of average and maximum daily flows to be handled based on the pipe size, pipe material, and slopes confirmed in the field by the Contractor for each pipe segment to be bypassed.
 8. Calculations of static lift, friction losses, flow velocity and flow rate of the proposed bypass pumping system to confirm the calculated flows can be handled by the proposed system.
 9. Systems testing and start-up.
 10. Maintenance of system for off-construction hours.
 11. Contingency plan and equipment for system failures.
- C. Contractor shall submit complete documentation of qualifications as specified herein.

1.4 QUALITY ASSURANCE

- A. Provide in accordance with Section GENERAL SPECIFICATIONS and as specified.
- B. The Contractor designing and installing the bypass flow handling system shall have completed at least five (5) projects of similar size and complexity as this project in the United States within the past three (3) years. Contractor may employ the services of a subcontractor that specializes in this work to fulfill this requirement.
- C. Rejection of any subcontractor and/or manufacturer by the Engineer due to insufficient qualifications shall not be grounds for modifications to the Contract Documents such as change in scope, time of completion or contract amount.

1.5 DELIVERY, STORAGE AND HANDLING

- A. Provide in accordance with GENERAL SPECIFICATIONS.

PART 2 - PRODUCTS

2.1 EQUIPMENT

- A. The bypass flow handling equipment shall be of sufficient size and material to convey existing flows from one access structure to at least the next access structure immediately downstream of the work without overflow, spillage or discharge to the surrounding environment.
- B. Contractor shall be fully equipped to operate and respond to any repair or replacement of the system (24 hours per day and 7 days per week) while the bypass flow handling system is in use.
- C. Contractor shall incorporate noise reduction equipment to minimize impact on the surrounding environment. Such measures shall include insulated enclosures, hospital grade silencers or mufflers, equipment modifications and/or special equipment to limit noise to eighty (80) dBA at seven (7) feet or sixty (60) dBA at the nearest residence or business.

PART 3 – EXECUTION

3.1 PREPARATIONS

- A. Contractor shall perform all work in accordance with municipal, state and federal requirements.
- B. Contractor shall obtain relevant permits required to perform work prior to the commencement of construction at no additional cost to the Owner.
- C. Prior to the commencement of construction, Contractor shall perform all possible preparatory work. The Contractor shall, at all times, conduct operations to interfere as little as possible with existing flows.
- D. Contractor shall verify flow conditions in the existing system prior to the commencement of construction. The Contractor shall have no claim for additional compensation by reason of delay or inconvenience in adapting its operations to the need for maintaining existing flows.
- E. Twice, prior to start-up of bypass flow handling system, Contractor shall notify, in writing, each property owner whose service shall be temporarily shut down within seven (7) days prior to the shut down and twenty-four (24) hours prior to the shut down. Contractor shall prepare notifications in accordance with Engineer's requirements.

3.2 GENERAL

- A. Contractor shall design the layout and routing of the bypass flow handling system to minimize disturbance to public and private land and to maintain access for pedestrians and traffic.

- B. The Contractor shall maintain traffic throughout the duration of bypass flow handling in accordance with the requirements of the “Manual on Uniform Traffic Control Devices”, latest edition.
- C. If excavation is required across roadways, all work shall be performed in accordance with municipal and/or state requirements.
- D. Contractor shall furnish, install, maintain and operate all temporary facilities such as dams, pumping equipment, conduits and all other labor and equipment necessary to intercept the flow before it reaches points where it would interfere with the work.
- E. Contractor may utilize pipelines in an existing parallel system as an alternative to installing a full bypass flow handling system pending approval by the Engineer. Contractor shall submit a Certificate of Design prior to utilizing the parallel system and shall restore the parallel system to pre-construction conditions upon completion of construction.
- F. Contractor shall design, furnish and install individual bypass flow handling systems for flowing lateral connections or high occupancy buildings.
- G. Upon completion of construction, the Contractor shall remove plugging and/or bulkheads in a manner that permits the existing flows to slowly return to pre-construction conditions and prevent surcharging, flooding or causing any other disturbances downstream.

3.3 CONTRACT CLOSEOUT

- A. Provide in accordance with Section 01700 – CONTRACT CLOSEOUT.

END OF SECTION 02761

SECTION 02765

SEWER LINE AND MANHOLE CLEANING

PART 1 - GENERAL

1.1 SUMMARY

- A. This Section includes the following:
 - 1. Furnishing all plant, labor, equipment and materials, as well as performing all operations associated with pipeline cleaning within the pipelines indicated on the Drawings in accordance with these Specifications.
 - 2. Furnishing all plant, labor, equipment and materials, as well as performing all operations associated with manhole and structure cleaning as indicated on the Drawings in accordance with these Specifications.
 - 3. Performing the work in a sequence that is the least disruptive to vehicular and pedestrian traffic and in a manner that shall protect the public from damage to persons and property.

1.2 RELATED WORK

- A. DIVISION 1 – GENERAL REQUIREMENTS
- B. Section 02760 – PIPELINE INTERNAL INSPECTION
- C. Section 02761 – BYPASS FLOW HANDLING.

1.3 SUBMITTALS

- A. General: Submit each item in this article according to the conditions of the Contract and Division 1, Section 01300 – SUBMITTALS.
 - 1. Shop drawings and/or manufacturer's descriptive literature indicating materials, equipment and methods to complete pipeline cleaning operations.
 - 2. Shop drawings and/or manufacturer's descriptive literature indicating materials, equipment and methods to complete internal inspection operations to complete manhole and structure cleaning operations.
 - 3. Confined Space Entry certifications for all personnel entering pipeline or access structures.
- B. Contractor shall submit complete documentation of qualifications as specified herein.

1.4 QUALITY ASSURANCE

- A. Provide in accordance with GENERAL SPECIFICATIONS and as specified herein.

- B. The Contractor cleaning and internally inspecting the pipeline shall have completed at least three (3) projects of similar size and complexity as this project in the United States within the past three (3) years. Contractor may employ the services of a subcontractor that specializes in this work to fulfill this requirement.
- C. Rejection of any subcontractor and/or manufacturer by the Engineer due to insufficient qualifications shall not be grounds for modifications to the Contract Documents such as change in scope, time of completion or contract amount.
- D. All Contractor's personnel entering pipeline or access structures shall be Confined Space Entry trained per OSHA, Title 29 CFR 1910.46 and shall have a copy of their certification available on site at all times.

1.5 DELIVERY, STORAGE AND HANDLING

- A. Provide in accordance with GENERAL SPECIFICATIONS.

PART 2 - PRODUCTS

2.1 CLEANING

- A. Contractor shall use mechanical, hydraulically-propelled, and/or high-velocity cleaning equipment, which does not exert internal pressures great enough to damage the pipelines and associated structures. Selection of the cleaning equipment shall be based on the condition of the pipeline at the time work is scheduled to commence.
- B. Equipment shall include, at a minimum, the following:
 - 1. Motorized equipment complete with belt booster clutch, overload clutch or other means or devices that shall prevent damage to the pipeline and associated structures. Direct drive shall not be permitted.
 - 2. Standard mechanical equipment including a combination of rodding machines, boring machines, bucket machines, hydraulic balls, B-liners, cones, ferrets or similar equipment. Direct drive shall not be permitted.
 - 3. High pressure, hydraulically-propelled equipment and chemical compounds as approved by the Engineer.
 - 4. Mechanical cutting devices suitable for the removal of roots, gaskets, protruding lateral connections, etc.
 - 5. Footage metering devices for location of all equipment, devices and points of reference on measuring target that is known at all times at the ground level.

C. Hydraulic Sewer Cleaning Equipment

- 1. The equipment used shall be of a movable dam type and be constructed so that a portion of the dam may be collapsed at any time during the cleaning operation to protect against flooding of the sewer. The movable dam shall be the same diameter as

the pipe being cleaned and shall provide flexible scraper around the outer periphery to ensure total removal of grease. If sewer cleaning balls or other such equipment which cannot be collapsed instantly are used, special precautions against flooding of the sewers and public or private property shall be taken.

D. High Velocity Jet (Hydro-cleaning) Equipment

1. All high velocity sewer cleaning equipment shall be constructed for ease and safety of operation. The equipment shall have a selection of two or more velocity nozzles. The nozzles shall be capable of producing a scouring action from 15 to 45 degrees in all size lines to be cleaned. Equipment shall also include a high velocity gun for washing and scouring manhole walls and floor. The gun shall be capable of producing flows from a fine spray to a long distance solid stream. The equipment shall carry its own water tank, auxiliary engines, pumps and hydraulically driven hose reel. All controls shall be located so the equipment can be operated above ground.

E. Mechanical Cleaning Equipment

1. Bucket machines shall be in pairs and with sufficient powers to perform the work in an efficient manner. Machines shall be belt operated or have an overload device. Machines with direct drive which could cause damage to the pipe shall not be acceptable.
2. Power rodding machines shall be either sectional or continuous type capable of holding a minimum of 750-ft of rod. The rod shall be specifically treated steel. To ensure safe operation, the machine shall have a fully enclosed body and an automatic safety release clutch or relief valve.

PART 3 – EXECUTION

3.1 GENERAL

- A. Sewer line walls shall be cleaned adequately to provide for a camera used in internal inspection to discern structural defects, misalignment and infiltration/inflow sources. Cleaning shall be performed immediately prior to internal inspection to preclude the buildup of debris from infiltration/inflow sources and discharges from upstream pipeline sections.
- B. Contractor shall perform all work in accordance with municipal, state and federal requirements including OSHA.
- C. Contractor shall obtain relevant permits required to perform work prior to the commencement of construction at no additional cost to the Owner.
- D. Contractor shall locate and uncover all manholes and/or access structures required to complete the work in accordance with this Section.
- E. Contractor shall maintain existing flows around the work during cleaning inspection operations in accordance with Section 02761.

3.2 PREPARATION

- A. Selection of cleaning equipment shall be based on the conditions of the manhole and sewer lines at the time the work commences.
 - 1. Light cleaning (small amounts of debris existing within the sewer line): Use balls, scooters, high pressure water jetting (maximum of three passes) equipment, brushes and swabs.
 - 2. Heavy cleaning (large deposits of debris or heavy root growth existing within the sewer line): Use bucket machines, scrapers and augers. Cleaning which requires more than three passes with hydraulic cleaning equipment to achieve acceptable results shall be considered heavy cleaning.
- B. Written authorization shall be requested and obtained prior to conducting any heavy cleaning. Authorization shall be required for each individual sewer reach. Heavy cleaning without prior authorization will not be paid for.

3.3 PERFORMANCE

- A. Contractor shall clean the pipeline and manholes to facilitate inspection, testing, and rehabilitation.
- B. Contractor shall protect the pipeline and manholes from damage that could be inflicted by use of cleaning equipment. Any damage inflicted, regardless of technique, shall be repaired by the Contractor to the satisfaction of the Owner, at no additional cost to the Owner.
- C. Each designated sewer manhole section shall be cleaned using hydraulically propelled, high velocity jet, or mechanically powered equipment. The equipment selected for cleaning shall be capable of removing dirt, grease, rocks, sand and other deleterious materials and obstructions from the sewer lines and manholes. If cleaning of an entire section cannot be successfully performed from one manhole, the equipment shall be set up on the other manhole and cleaning again attempted. If successful cleaning cannot be performed from the second manhole, or the equipment fails to traverse the entire length between manholes, it will be assumed that major blockage exists and the cleaning effort shall be abandoned. Blockages, if any, shall be reported to the Engineer immediately.
- D. During all sewer cleaning operations, satisfactory precautions shall be taken to protect the sewer lines from damage that might be inflicted by the improper use of cleaning equipment. Whenever hydraulically propelled cleaning tools which depend upon water pressure to provide their cleaning force or any tools which retard the flow of water in the sewer line are used, precautions shall be taken to ensure that the water pressure created does not cause any damage or flooding to public or private property being served by the manhole section involved. The flow of sewage in the sewer lines shall be used to provide necessary pressures for hydraulic cleaning devices whenever possible. When additional quantities of water from fire hydrants are necessary to avoid delay in normal working procedures, the water shall be conserved and not used unnecessarily. No fire hydrant shall be obstructed so as to prevent its use in case of a fire in the area served by the hydrant, nor shall a hydrant be used for the purpose described unless a vacuum break is provided.

- E. Roots shall be removed in the designated sections where root intrusion is a problem. Special precautions should be exercised during the cleaning operation to assure virtually complete removal of visible roots from the joint area. Procedures may include the use of mechanical devices such as rodding machines, expanding root cutters, and porcupines; hydraulic procedures such as high pressure jet cleaners; or chemical root treatment.
- F. To aid in the removal of roots, pipeline and manhole sections which have root intrusion may be treated with an approved label herbicide. the application of the herbicide to the roots shall be done in strict accordance with the manufacturer's recommendations and product specifications in such a manner to preclude any damage to the surrounding vegetation. Vegetation damage for whatever reason shall be replaced with identical vegetation. All safety precautions recommended by the manufacturer shall be strictly adhered to concerning handling and application of the herbicide.
- G. All sludge, dirt, sand, rocks, grease, and other solid or semi-solid materials that may cause an obstruction or impede the inspection and/or construction shall be removed and disposed off site during cleaning operations in watertight containers in conformance with all applicable federal, state and municipal laws and regulations, at no additional cost to the Owner. All materials that will not cause an obstruction or impede the inspection and/or construction shall be flushed downstream, but not be allowed to enter surface water bodies.
- H. If during cleaning operations an obstruction is encountered, the Contractor shall prosecute cleaning operations from both the upstream and downstream directions. Should the obstruction prevent the pipeline from being cleaned, the Engineer shall be notified immediately. If, in the opinion of the Engineer, a point repair is required to facilitate cleaning, Contractor shall perform the repair and clean through said repair upon its completion. No additional compensation shall be paid to the Contractor for any portion of the pipe which requires re-cleaning after successful completion of the repair.
- I. All debris, residue and other materials resulting from cleaning operations shall be removed from the site no less often than at the end of each workday and shall be disposed of in an approved manner. Under no circumstances will the accumulation of debris, residue, etc, on the site beyond the stated time be permitted, unless prior written authorization is given for storage in totally enclosed containers.
- J. Contractor shall re-clean the pipeline, if in the opinion of the Engineer, materials have washed into the pipeline after acceptance of the cleaning and prior to construction at no additional cost to the Owner.

3.4 FIELD TESTING

- A. Acceptance of sewer line cleaning shall be contingent on satisfactory completion of the television inspection. If, in the opinion of the Engineer, the television inspection shows the cleaning to be unsatisfactory and/or not been completed in accordance with the Specifications, the sewer line shall be re-cleaned and re-inspected until the cleaning is shown to be satisfactory at no additional cost to the Owner. In areas where television inspection is not performed, a double squeegee (with each squeegee the same diameter as the sewer) shall be pulled cleanly through each section between manholes as evidence of satisfactory cleaning.

- B. If internal sealing is to follow the television inspection, particular attention shall be given to the adequacy of the cleaning to ensure that proper seating of the sealing packer can be achieved.
- C. Refer to Section 02760 – PIPELINE INTERNAL INSPECTION for Internal Inspection Acceptance Requirements

3.5 CONTRACT CLOSEOUT

- A. Provide in accordance with Section 01700 – CONTRACT CLOSEOUT.

END OF SECTION 02765

SECTION 02769

CURED-IN-PLACE PIPE LINER

PART 1 – GENERAL

1.1 SUMMARY

- A. Furnish all labor, materials, equipment and incidentals required and install and test cured-in-place pipe (CIPP) lining and appurtenances complete as shown on the Drawings and as specified herein.

1.2 RELATED WORK

- A. DIVISION 1 – GENERAL REQUIREMENTS
- B. Section 02765 - SEWER LINE AND MANHOLE CLEANING.
- C. Section 02760 - PIPELINE INTERNAL INSPECTION.
- D. Section 02761 – BYPASS FLOW HANDLING

1.3 SUBMITTALS

- A. Submit, in accordance with Section 01300 - SUBMITTALS:
 - 1. Shop drawings and schedules of all CIPP liner and appurtenances required. Design data and specification data sheets listing all parameters used in the liner design and thickness calculations based on ASTM F1216 and D2412 for fully deteriorated pipe. All CIPP liner design calculations shall be sealed and signed by a registered professional designer.
 - 2. Detailed procedure for installing the liner.
 - 3. The name of the liner manufacturer and the location of the facility where the liner was manufactured
 - 4. Certified test reports from the manufacturer that the liner for this Contract was manufactured and tested in accordance with the ASTM Standards specified herein.
- B. Provide manufacturer's certifications that the proposed liner and resin are suitable for installation in pipelines where saltwater infiltration is present.

1.4 REFERENCE STANDARDS

- A. American Society of Testing Materials (ASTM)
 - 1. ASTM D790 – Standard Test Method for Flexural Properties of Un-reinforced and Reinforced Plastics and Electrical Insulating Materials.
 - 2. ASTM D2412 – Standard Test Method for Determination of External Loading Characteristics of Plastic Pipe by Parallel-Plate Loading.

3. ASTM D1216 – Standard Practice for Rehabilitation of Existing Pipelines and Conduits by the Inversion and Curing of a Resin-Impregnated Tube.
- B. Where reference is made to one of the above standards, the revision in effect at the time of the bid opening shall apply.

1.5 QUALITY ASSURANCE

- A. The Contractor performing the lining work shall be fully qualified, experienced and equipped to complete this work expeditiously and in a satisfactory manner. Submit the following information for review and approval at the time of bid submittal:
 1. The number of years of experience in performing pipe lining projects.
 2. The name of the lining manufacturer and supplier for this work and previous work listed below. The contractor shall be an approved installer as certified and/or licensed by the liner manufacturer.
 3. A list of municipal clients that the Contractor has performed this type of work for without defects or performance problems.
 - a. The list shall contain names and telephone numbers of persons to be called to verify previous satisfactory performance.
 - b. A full description of the actual work performed.
 - c. The list of municipal clients and description of projects shall include the approximate liner footage (lf) of lining work completed. Provide a sufficient number of references to total 50,000 lf or more of lining work completed to date.
- B. The Contractor shall also be capable of providing crews as needed to complete the work without undue delay and shall begin work within (7) days from authorized notice to proceed.
- C. The Engineer shall approve or disapprove the Contractor and/or manufacturer based on the submitted information and a follow up interview.
- D. The CIPP liner shall be provided by a single manufacturer. The supplier shall be responsible for the provision of all test requirements specified herein as applicable. In addition, all liner to be installed under this Contract may be inspected at the plant for compliance with this Section by an independent testing laboratory provided by the Owner, at his own expense. The Contractor shall require the manufacturer's cooperation in these inspections.
- E. Inspection of the liner may also be made by the Engineer or other representative of the Owner after delivery. The liner shall be subject to rejection at any time on account of failure to meet any of the requirements specified, even though sample liner may have been accepted as satisfactory at the place of manufacture. Liner rejected after delivery shall be marked for identification and shall be removed from the job site at once.

1.6 SYSTEM DESCRIPTION

1.7 DELIVERY, STORAGE AND HANDLING

- A. Care shall be taken in shipping, handling and storage to avoid damaging the liner. Extra care shall be taken during cold weather construction. Any liner damaged in shipment shall be replaced as directed by the Engineer.
- B. Any liner showing a split or tear, or which has recieved a blow that may have caused damage, even though damage may not be visible, shall be marked as rejected and removed at once from the job site.
- C. The liner shall be maintained at a proper temperature in refrigerated facilities to prevent premature curing at all times prior to installation. The liner shall be protected from UV light prior to installation. Any liner showing evidence of premature curing will be rejected for use and will be removed from site immediately.

1.8 PROJECT/SITE REQUIREMENTS

1.9 MAINTENANCE

1.10 GUARANTEE

- A. All lining work shall be fully guaranteed by the Contractor and manufactured for a period of (1) year from the date of Substantial Completion. During this period, all serious defects discovered by the Owner shall be removed and replaced in a satisfactory manner at no additional cost to the owner. The Owner may conduct an independent television inspection, at his own expense, of the lining work prior to the completion of the (1) year guarantee period.

PART 2 – PRODUCTS

2.1 MATERIALS

- A. The liner shall be by Insituform; InLiner (or equal).
- B. The liner shall be composed of tubing material consisting of one or more layers of flexible non-woven polyester with or without additives such as woven fiberglass or other fibers. The felt tubing shall be impregnated with a thermosetting polyester resin and catalyst, vinyl ester and catalyst or epoxy resin and hardener. the liner material and resin shall be completely compatible. The outside layer of the tube shall be coated with an impermeable material compatible with the resin and fabric.
- C. The liner shall be capable of fitting into irregularly shaped pipe sections and through bends and dips within the pipeline.
- D. The liner shall be able to cure in the presence of water at a temperature of 180 degrees F or less.
- E. When inverted and cured the liner shall form a continuous, tight fitting, hard, impermeable liner which is chemically resistant to chemicals found in domestic sewage.

- F. The liner shall be chemically resistant to trace amounts of gasoline and other oil products commonly found in municipal sewerage and soils adjacent to the sewer pipe to be lined.
- G. The liner shall be fabricated to a size that when reformed will tightly fill the sewer being rehabilitated. Allowance of longitudinal and circumferential expansion shall be taken into account when sizing and installing the liner. All dimensions shall be field verified by the Contractor prior to delivery of the liner. Field measurements shall be used to ensure maximum closure between the new liner and the existing sewer pipe.
- H. The application of resin to the felt tubing (wet-out) shall be conducted under factory conditions and the materials shall be fully protected against UV light, excessive heat and contamination at all times.
- I. The length of the liner shall be the length deemed necessary by the Contractor to effectively carry out the insertion of the liner and sealing of the liner at the outlet and inlet manholes. The required length of the liner shall be verified in the field by the Contractor prior to fabrication.
- J. The liner shall be designed, fabricated and installed for the actual conditions encountered for this application and shall comply with the following minimum conditions:
 - 1. Temperature: 40 to 150 degrees F
 - 2. Maximum long term deflection: 5 percent
 - 3. The liner shall be designed to support all loads produced by backfill (120lbs/sq ft), traffic (H-20) and hydrostatic loading from groundwater elevation at grade.
 - 4. The liner shall be watertight
- K. The cured liner shall have the following minimum structural properties

<u>Property</u>	<u>Test Method</u>	<u>Minimum Standard</u>
Flexural Strength	ASTM D790	4,500
Flexural Modulus	ASTM D790	250,000

PART 3 – EXECUTION

3.1 INSTALLATION

- A. Clean each length of pipe to be lined and dispose of any resulting material as specified in Section 02765 – SEWER LINE AND MANHOLE CLEANING.
- B. Conduct a videotaped color television inspection of each length of pipe to be lined in accordance with Section – 02760 PIPELINE INTERNAL INSPECTION.
- C. All service connections protruding into the sewer line to be lined shall be cut or ground down so as to be flushed with the pipe to be lined prior to liner installation.
- D. The Contractor shall provide bypass pumping of sewage flows in accordance with Section 02761 – BYPASS FLOW HANDLING.

- E. Notify all property owners who discharge sewage directly into the sewer to be lined that their sewage service will be discontinued while the liner is being installed. Notify each affected property owner at least (72) hours in advance of commencement of the work, giving the date, start time and time when service will be completely restored. (Also provide a telephone number which property owners can call for information during the work).
- F. Furnish and install the liner in the full length of sewer as shown on the Drawings. The installation of the liner shall be in complete accordance with the applicable provisions herein and the manufacturer's installation requirements.
- G. For each length of liner installed, remove specimens of at least 24-in length for testing of flexural properties. The specimens shall be cut from a section of installed and reformed liner at an intermediate point or the termination point of the installation. Contractor shall retain independent laboratory testing company and provide evidence of successful test to meet minimum structural properties.
- H. All cutting and sealing of the liner at manhole connections shall provide watertight pipe and manhole trough seals.
- I. Reopen all of the existing active service connections in each length of sewer following reformation and cooling of the liner. The service connections shall be reopened from inside the sewer by means of a television camera controlled cutting device appropriate for the liner material and the rehabilitated sewer pipe. All of the liner penetrations or openings shall be watertight.
- J. Following installation of the liner and reopening of the service connections, conduct a final videotaped color television inspection of the completed work. Copies of these tapes and the videotapes made prior to the liner installation shall be submitted to the Engineer of approval and shall be retained by the Owner.

3.2 FIELD TESTING AND ACCEPTANCE

- A. Field acceptance of the liner shall be based on the Engineer's evaluation of the installation including TV videotapes and a review of certified test data for the installed pipe samples.
- B. Groundwater infiltration of the liner shall be zero.
- C. All service connections shall be open, clear, and watertight.
- D. There shall be no evidence of splits, cracks, breaks, lifts, kinks, delaminations, or crazing in the liner.
- E. If any defective liner is discovered after it has been installed, it shall be removed and replaced with either a sound liner or a new pipe at no additional cost to the owner.

END OF SECTION 02769

SECTION 02770

CURED-IN-PLACE SPOT REPAIR

PART 1 – GENERAL

1.1 SCOPE OF WORK

- A. Furnish all materials, labor and equipment and perform all incidental work necessary to install and test cured-in-place spot repairs (CIPSR) as shown on the Drawings and as listed in (Section 01010).

1.2 RELATED WORK

- A. DIVISION 1 – GENERAL REQUIREMENTS
- B. Section 02765 – SEWER LINE AND MANHOLE CLEANING.
- C. Section 02760 – PIPELINE INTERNAL INSPECTION.
- D. Section 02761 – BYPASS FLOW HANDLING
- E. Section 02769 – CURED-IN-PLACE PIPE LINER

1.3 SUBMITTALS

- A. Submit, in accordance with Section 01300, and within 15 days of the Effective Date of the Agreement, the name of CIPSR supplier and a list of materials to be furnished.
- B. Provide two submittals of certified test reports to confirm that CIPSR materials have been manufactured and tested in accordance with ASTM Standards specified herein.
 - 1. Within 15 days of the Effective Date of the Agreement, submit test reports for the materials to be used for this work. Test results shall be the manufacturer's standards for acceptance of field fabricated and installed CIPSR.
 - 2. Prior to the installation of any CIPSR, make test specimens for the materials to be utilized for this work. Make sufficient number of specimens for conducting the referenced testing. Specimens shall be cut from the resin-impregnated patch prior to insertion into the pipe.
- C. Provide manufacturer's certification that the proposed liner and resin are suitable for installation in pipelines where salt water infiltration is present.

1.4 REFERENCE STANDARDS

- A. American Society for Testing and Materials (ASTM)
 - 1. ASTM D543 – Standard Practices for Evaluating the Resistance of Plastics to Chemical Reagents
 - 2. ASTM D638 – Standard Test Method for Tensile Properties of Plastics.
 - 3. ASTM D790 – Standard Test Methods for Flexural Properties of

Unreinforced and Reinforced Plastics and Electrical Insulating materials.

4. ASTM D2412 – Standard Test Method for Determining of External Loading Characteristics of Plastic Pipe by Parallel-Plate Loading.
5. ASTM D2990 – Standard Test Methods for Tensile, Compressive, and Flexural Creep and Creep-Rupture of Plastics.

- B. Where referenced is made to one of the above standards, the revision in effect at the time of bid opening shall apply.

1.5 QUALITY ASSURANCE

- A. The Contractor or subcontractor to furnish and install CIPSRs shall be fully qualified, experienced and equipped to complete the work in a timely and satisfactory manner. Submit the following information to the Engineer for review and approval before CIPSR work is performed.
1. The number of years of experience in performing this type of specialized work.
 2. Name of the CIPSR manufacturer and supplier for this work and previous work performed. The Contractor shall be certified by the manufacturer to install the CIPSR patches.
 3. A list of all municipal installations performed over the past 5 years along with the contract name, telephone number, and brief description of work performed.
 4. The Owner reserves the right to disapprove the use of the CIPSR Contractor based on the submitted qualifications.
- B. All CIP spot repairs, regardless of pipe size or length, shall be furnished, fabricated and installed by a single manufacturer.
- C. As directed by the Engineer, replace all CIPSRs that utilize materials or methods of installation other than that approved. Remove and replace the CIPSR section that affected pipe with new pipe at no cost to the Owner.

1.6 GUARANTEE

- A. All CIP spot repairs shall be guaranteed by the Contractor for a period of 5 years from the date of acceptance. During this period, all defects in the CIPSRs shall be repaired in a manner satisfactory to the Engineer or the affected pipe shall be removed and replaced with a new pipe at no additional cost to the Owner.

PART 2 – PRODUCTS

2.1 FIBERGLASS/POLYESTER FELT REPAIR MATERIAL

- A. The CIPSR shall be resin impregnated fiberglass/polyester felt sleeve which is wrapped around an inflatable packer and positioned in the sewer to be rehabilitated and cured in place by circulating hot water to cure the resin. Ambient curing shall not be allowed.
- B. The CIPSR sleeve shall be fabricated from a minimum of two layers of fiberglass with a single layer of polyester felt sandwiched between the fiberglass layers. The material shall be sewn together with multiple polyester threads using zigzag stitching spaced evenly over the full width of the material. The three layer composite reinforcement material shall have a minimum mass of 40.6 oz/sq yd with a thickness not less than 0.24-in. Fiberglass alone shall not be acceptable.
- C. The fiberglass shall be woven roving having a minimum weight of 24 oz/sq yd and shall be made of "E" glass coated with a sizing compatible with the resin being used.
- D. The polyester felt shall be needle punched and have a minimum weight of 16.5 oz/sq yd.
- E. The resin shall be a two-part epoxy type liquid thermosetting resin suitable for the intended use as well as the proposed curing method. The diluted epoxy resin shall contain at least 60 percent of bisphenol A, 10 to 20 percent of bisphenol F with the remainder of the mixture being a diluent. Epoxy resin shall be D.E.R. (R) 353 by the Dow Chemical Company; ME 948 by Micon or equal.
- F. The epoxy resin shall be brought on site in a resin manufacturer's original containers. Each container shall be clearly labeled as the contents and product data. The resin shall be stored, mixed and applied in accordance with the manufacturer's recommendations.
- G. The CIPSR shall provide a service life of 25 years and shall have, as a minimum, the initial and long term properties listed below.

<u>MECHANICAL PROPERTY</u>	<u>INITIAL</u>	<u>LONG TERM</u>
Flexural Strength	8,000 psi	_____
Flexural Modulus of Elasticity	280,000 psi	140,000 psi
Tensile Strength	5,000 psi	_____
Tensile Modulus of Elasticity	280,000 psi	140,000 psi

- H. When cured, the CIPSR shall form a continuous, tight-fitting, hard, impermeable liner which is chemically resistant to any chemical normally found in domestic sewage. The CIPSR shall have a suitable membrane coating for protection of the interior surface and to provide a uniform, smooth flow surface. No membranes or plastic coating shall be allowed between the repair patch and the pipe wall.
- I. The fiberglass/polyester felt sleeve shall be fabricated to size that will tightly fit the sewer being rehabilitated after being installed and cured. The transition from the patch to the existing pipe must be smoothly tapered.
- J. The CIPSR shall be by Avanti International of Webster, TX or equal.
- K. The thickness of the cured liner shall be as recommended by the manufacturer, but shall not exceed 1/4-in when cured unless authorized in writing by the Engineer.

- L. Spot repairs shall have a minimum length of 3-ft and shall not exceed 30-ft in length. CIPSR lengths shall extend a minimum of 1-ft beyond the pipe defects at each end of the repaired section. Length of each required repair shall be verified in the field prior to installation.
- M. CIP spot repairs shall not begin or end at a service connection or pipe joint.
- N. All cured-in-place spot repairs shall be one piece. Separately fabricated or installed CIPSRs utilizing overlapped or “budded” ends shall not be acceptable.

PART 3 – EXECUTION

3.1 INSTALLATION

- A. Clean each length of pipe to be lined and disposed of any resulting material as specified in Section 02765.
- B. All obstructions in the sewer which may impede the insertion of the liner shall be removed by the contractor.
- C. Conduct a television inspection of each length of pipe after it is cleaned as specified in Section 02760. Document the location of all active service connections and verify the lengths of repairs as identified in (Section 01010). A copy of these video tapes shall be submitted to the Engineer and provided to the Owner.
- D. Notify all property owners who discharge sewage directly to the sewer being repaired that their service will be discontinued while the CIPSR is being inserted, cured and active service connections reopened. Notify individual property owners at least 48 hours in advance, giving the date, start time and estimated completion time for the work being conducted.
- E. Furnish bypass pumping of sewage flows where rehabilitation work is being performed. Bypass pumping shall be conducted in conformance with the requirements of Section 02761.
- F. The CIPSR materials shall be measured, cut and impregnated with epoxy resin in the field to the measurements determined from the videotape inspections. The installation and curing of the CIPSRs shall be in complete accordance with the manufacturers’ specifications and a representative of the manufacturer shall be present during the first day of installation.
- G. The installed spot repair shall be cured by circulating hot water through the resin impregnated patch. Ambient curing shall not be allowed.
- H. The inflatable element and hydrostatic pressure used during the installation process shall be sufficient to tightly hold the CIPSR to the existing pipe wall, producing dimples at all service connections and squeezing surplus resin into any cracks in the pipe. This pressure shall be great enough to overcome or prevent infiltration from entering the existing pipeline during the curing process.

- I. The Contractor shall ensure that the shroud covering the packer is completely removed from the repaired pipe.
- J. Where CIPSRs connect to existing manholes, the repair shall create a watertight seal at the pipe connection and into the trough. All cut edges of the cured liner shall be thoroughly sealed with the same resin as was used in the CIPSR materials.
- K. Reopen all of the existing active service connections on each length of sewer following patching. The active service connections shall be reopened from inside the sewer by means of cutting device controlled by a closed-circuit television camera. All cut out material shall be flushed out of the sewer.
- L. Each active service connection shall be cut completely open and shall have smooth edges with no protruding material capable of hindering flow or catching and holding solids contained in the flow stream.
- M. Following installation of the spot repairs and reopening the active service connections, conduct a second videotape inspection of the completed work. This tape, along with the tape made in Paragraph 3.1B above shall become the property of the owner.

3.2 FIELD TESTING AND ACCEPTANCE

- A. Field acceptance of all CIP spot repairs shall be based on the Engineer's evaluation of the installation and curing data along with review of the TV videotapes and manhole inspections.
- B. Groundwater infiltration of CIPSR shall be zero.
- C. All active service connections shall be open and clear.
- D. There shall be no dry spots, voids, lifts, delaminations or any other type defect in the CIPSR.
- E. Defective CIPSRs shall be removed and replaced with new CIPSRs. If the replacement CIPSR is not satisfactory to the Engineer, then remove the entire section of pipe being rehabilitated and replace it with new PVC pipe at no additional cost to the Owner.

END OF SECTION 02770

SECTION 03315

GROUT

PART 1 - GENERAL

1.1 SUMMARY

- A. Furnish all materials for grout in accordance with the provisions of this Section and shall form, mix, place, cure, repair, finish, and do all other work as required to produce finished grout, in accordance with the requirements of the Contract Documents.
- B. The following types of grout shall be covered in this Section:
 - 1. Non-Shrink Grout: This type of grout is to be used wherever grout is shown in the Contract Documents, unless another type is specifically referenced.
 - 2. Cement Grout
 - 3. Epoxy Grout
 - 4. Topping Grout

1.2 RELATED WORK

- A. Division 1 – GENERAL REQUIREMENTS

1.3 SUBMITTALS

- A. Shop Drawings: Submit the following in accordance with Section 01300 – SUBMITTALS:
 - 1. Submit certified test results verifying the compressive strength, shrinkage, and expansion requirements specified herein; and manufacturer's literature containing instructions and recommendations on the mixing, handling, placement and appropriate uses for each type of non-shrink and epoxy grout used in the work.

1.4 QUALITY ASSURANCE

- A. Field Tests:
 - 1. Cement Grout and Topping Grout
 - a. Compressive strength of cement grout and topping grout shall be tested in accordance with the requirements of ASTM C 109. The frequency of tests shall conform to the requirements of Section 03300.
 - 2. Prepackaged Grout

- a. Compression test specimens shall be taken during construction from the first placement of each type of grout, and for each different batch number of each type of grout thereafter. The specimens will be made by the Engineer or its representative.
 - b. Compression tests and fabrication of specimens for non-shrink grout shall be performed as specified in ASTM C 109. A set of three specimens shall be made for testing at 24 hour, 28 days, and each additional time period as appropriate.
 - c. Compression tests and fabrication of specimens for epoxy grout shall be performed as specified in ASTM C 579, Method B. A set of three specimens shall be made for testing at 24 hours, and each earlier time period as appropriate.
3. All grout, already placed, which fails to meet the requirements of these specifications, is subject to removal and replacement at the cost of the Contractor.
4. The cost of all laboratory and field tests on grout shall be borne by the Contractor, and the Contractor shall assist the Engineer in obtaining specimens for testing. The Contractor shall supply all materials necessary for fabricating the test specimens.

PART 2 - PRODUCTS

2.1 CEMENT GROUT

- A. Cement Grout: Cement grout shall be composed of one part cement, three parts sand, and the minimum amount of water necessary to obtain the desired consistency. Where needed to match the color of adjacent concrete, white Portland cement shall be blended with regular cement as needed. The minimum compressive strength at 28 days shall be 4000 psi.

2.2 PREPACKAGED GROUTS

- A. Non-Shrink Grout:
 1. Non-shrink grout shall be a prepackaged, inorganic, non-gas-liberating, non-metallic, cement-based grout requiring only the addition of water. Manufacturer's instructions shall be printed on each bag or other container in which the materials are packaged. The specific formulation for each class of non-shrink grout specified herein shall be that recommended by the manufacturer for the particular application.
 2. Class A non-shrink grouts shall have a minimum 28 day compressive strength of 5000 psi; shall have no shrinkage (0.0 percent) and a maximum 4.0 percent expansion in the plastic state when tested in accordance with ASTM C-827; and shall have no shrinkage (0.0 percent) and a maximum of 0.2 percent expansion in the hardened state when tested in accordance with CRD C 621.

3. Class B non-shrink grouts shall have a minimum 28 day compressive strength of 5000 psi and shall meet the requirements of CRD C 621.
4. Application:
 - a. Class A non-shrink grout shall be used for the repair of all holes and defects in concrete members which are water bearing or in contact with soil or other fill material, grouting under all equipment base plates, and at all locations where grout is specified in the contract documents; except, for those applications for Class B non-shrink grout and epoxy grout specified herein. Class A non-shrink grout may be used in place of Class B non-shrink grout for all applications.
 - b. Class B non-shrink grout shall be used for the repair of all holes and defects in concrete members which are not water-bearing and not in contact with soil or other fill material, grouting under all base plates for structural steel members, and grouting railing posts in place.

B. Epoxy Grout:

1. Epoxy grout shall be a pourable, non-shrink, 100 percent solids system. The epoxy grout system shall have three components: resin, hardener, and specially blended aggregate, all pre-measured and prepackaged. The resin component shall not contain any non-reactive diluents. Resins containing butyl glycidyl ether (BGE) or other highly volatile and hazardous reactive diluents are not acceptable. Variation of component ratios is not permitted unless specifically recommended by the manufacturer. Manufacturer's instructions shall be printed on each container in which the materials are packaged. Epoxy grout shall be Burk Epoxy Anchoring Grout by The Burke Company, Sikadur 32 Hi-Mod by Sika Corporation, Richmond, VA, Sikadur 32, Hi-Mod Gel by Sika Corporation, Richmond, VA, or equal.
2. The chemical formulation of the epoxy grout shall be that recommended by the manufacturer for the particular application.
3. The mixed epoxy grout system shall have a minimum working life of 45 minutes at 75 degrees F.
4. The epoxy grout shall develop a compressive strength of 5000 psi in 24 hours and 10,000 psi in seven days when tested in accordance with ASTM C 579, Method B. There shall be no shrinkage (0.0 percent) and a maximum 4.0 percent expansion when tested in accordance with ASTM C 827.
5. The epoxy grout shall exhibit a minimum effective bearing area of 95 percent. This shall be determined by a test consisting of filling a 2-inch diameter by 4-inch high metal cylinder mold covered with a glass plate coated with a release agent. A weight shall be placed on the glass plate. At 24 hours after casting, the weight and plate shall be removed and the area in plan of all voids measured. The surface of the grout shall be probed with a sharp instrument to locate all voids.

6. The peak exotherm of a 2-inch diameter by 4-inch high cylinder shall not exceed 95 degrees F when tested with 75 degree F material at laboratory temperature. The epoxy grout shall exhibit a maximum thermal coefficient of 30×10^{-6} inches/inch/degree F when tested according to ASTM C 531 or ASTM D 696.
7. Application: Epoxy grout shall be used to embed all anchor bolts and reinforcing steel required to be set in grout, and for all other applications required in the Contract Documents.

2.3 TOPPING GROUT

- A. Grout for topping of slabs shall be composed of cement, fine aggregate, coarse aggregate, water, and admixtures proportioned and mixed as specified herein. All materials and procedures specified for normal concrete in Section 03300 shall apply except as noted otherwise herein.
- B. Topping grout shall contain a minimum of 564 pound of cement per cubic yard with a maximum water cement ratio of 0.45.
- C. Coarse aggregate shall be graded as follows:

US Standard Sieve Size	Percent By Weight Passing
1/2"	100
3/8"	90-100
No. 4	20-55
No. 8	5-30
No. 16	0-10
No. 30	0

- D. Final mix design shall be as determined by trial mix design under supervision of the approved testing laboratory.
- E. Strength: Minimum compressive strength of topping grout at the end of 28 days shall be 3000 psi.

2.4 CURING MATERIALS

- A. Curing materials shall be as specified in Section 03300, for cement grout and as recommended by the manufacturer of prepackaged grouts.

2.5 CONSISTENCY

- A. The consistency of grouts shall be that necessary to completely fill the space to be grouted for the particular application.
- B. The slump for topping grout shall be adjusted to match placement and finishing conditions but shall not exceed 4 inches.

2.6 MEASUREMENT OF INGREDIENTS

- A. Measurements for cement grout shall be made accurately by volume using containers. Shovel measurement shall not be allowed.
- B. Prepackaged grouts shall have ingredients measured by means recommended by the manufacturer.

PART 3 - EXECUTION

3.1 GENERAL

- A. All surface preparation, curing, and protection of cement grout shall be as specified in Section 03300. The finish of the grout surface shall match that of the adjacent concrete.
- B. The manufacturer of Class A non-shrink grout and epoxy grout shall provide on-site technical assistance upon request.
- C. Base concrete or masonry must have attained its design strength before grout is placed, unless authorized by the Engineer.

3.2 GROUTING PROCEDURES

- A. Prepackage Grouts: All mixing, surface preparation, handling, placing, consolidation, curing, and other means of execution for prepackaged grouts shall be done according to the instructions and recommendations of the manufacturer.
- B. Base Plate Grouting:
 - 1. For base plates, the original concrete shall be blocked out or finished off a sufficient distance below the plate to provide for a one-inch thickness of grout or a thickness as shown on the drawings.
 - 2. After the base plate has been set in position at the proper elevation by steel wedges or double nuts on the anchor bolts, the space between the bottom of the plate and the original pour of concrete shall be filled with non-shrink-type grout. The mixture shall be of a trowelable consistency and tamped or rodded solidly into the space between the plate and the base concrete. A backing board or stop shall be provided at the back side of the space to be filled with grout. Where this method of placement is not practical or where required by the Owner, alternate grouting methods shall be submitted for acceptance by the Engineer.

C. Topping Grout:

1. All mechanical, electrical, and finish work shall be completed prior to placement of topping. The base slab shall be given a roughened textured surface by sandblasting or hydroblasting exposing the aggregates to ensure bonding to the base slab.
2. The minimum thickness of grout topping shall be one inch. Where the finished surface of concrete fill is to form an intersecting angle of less than 45 degrees with the concrete surface it is to be placed against, a key shall be formed in the concrete surface at the intersection point. The key shall be a minimum of 3-1/2-inches wide by 1-1/2-inches deep.
3. The base slab shall be thoroughly cleaned and wetted prior to placing topping. No topping concrete shall be placed until the slab is completely free from standing pools or ponds of water. A thin coat of neat Type II cement grout shall be broomed into the surface of the slab just before topping of fill placement. The topping shall be compacted by rolling or tamping, brought to established grade, and floated..
4. Topping grout placed on sloping slabs shall proceed uniformly from the bottom of the slab to the top, for the full width of the placement.
5. The surface shall be tested with a straight edge to detect high and low spots which shall be immediately eliminated. When the topping has hardened sufficiently, it shall be steel troweled to a smooth surface free from pinholes and other imperfections. An approved type of mechanical trowel may be used as an assist in this operation, but the last pass over the surface shall be by hand-troweling. During finishing, no water, dry cement or mixture of dry cement and sand shall be applied to the surface.

3.3 CONSOLIDATION

- A. Grout shall be placed in such a manner, for the consistency necessary for each application, so as to assure that the space to be grouted is completely filled.

END OF SECTION 03315

ATTACHMENTS

D-1 Manhole Details

Table of all Defects to be Repaired

Maps, CCTV Photos, and Logs

Locus Map: Sewer Rehabilitation Project Locations

Map 1: Highland Avenue and Essex Street

Map 2: Crescent Drive

Map 3: Liberty Street

Map 4: Oakview Avenue

Map 5: Churchill Street

Map 6: Sable and Circle Hill Road

Map 7: Wheatland Street


Map 8: Cleveland and Buchanan Road

Map 9: Nichols and Butler Street

Map 10: Pope Street Easement

Map 11: Washington Street

Map 12: Buena Vista Avenue (Cross Country
Sewer)




NOTES:

1. INNER EDGE OF BRICK TABLE TO BE AT ELEVATION OF CROWN OF TOP OF PIPE. TABLE TO SLOPE AT 1" PER 1' TO INSIDE OF MANHOLE BASE.
2. TYPICAL SANITARY MANHOLE TO BE 4 FOOT DIAMETER.

TYPICAL MANHOLE DETAIL

NOT TO SCALE



NOTE:

DROP MANHOLES SHALL BE USED WHEN ENTRANCE PIPE INVERTS ARE 2' OR GREATER THAN MANHOLE INVERT.

INTERIOR DROP MANHOLE

NOT TO SCALE

Client
CITY OF SALEM, MASSACHUSETTS

Project
SEWER REHABILITATION PROJECT

MANHOLE DETAILS

Scale
N.T.S.

Date
8/16/2017

Job
Name

Designed by
WMR

Drawn by
DJW

Checked by
WMR

Approved by
WMR

No. Description Date

REVISIONS



New England Civil
Engineering Corp.

SALEM, MASSACHUSETTS

Sheet

D-1

Table of All Defects to be Repaired

Defect ID #	Map	Street	Repair Type	Description	Sewer/ Drain	Pipe Segment	Pipe Size	Pipe Material	Approximate Defect Length or Depth to Invert	Bid Item #
6	Map 01	Essex Street	Catchbasin mortar plug	Plug CB connection to sewer	Drain	CB 2660	Unknown	Unknown		27
29	Map 01	Highland Ave	CIPP Liner	multiple fractures	Sewer	815-3858	8	VC	320-feet	12 <i>and</i> 16
46	Map 01	Highland Ave	Rebuild Invert and Bench (includes 3-feet waterproofing)	Invert in poor condition	Sewer	SMH 932	8	PVC	Invert depth 6.5-feet	24
47	Map 01	Highland Ave	Rebuild Invert and Bench (includes 3-feet waterproofing)	Invert in poor condition	Sewer	SMH 3899	8	PVC/VC	Invert depth 3-feet	24
51	Map 01	Highland Ave	CIPP Liner	Multiple material changes	Sewer	3858-3899	8	multiple	75-feet	12 <i>and</i> 16
52	Map 01	Highland Ave	CIPP Liner	Multiple fractures in pipe	Sewer	3857-1057	12	VC	26-feet	13 <i>and</i> 17
53	Map 01	Highland Ave	CIPP Liner	Concrete pipe severely eroded	Sewer	1057-1058	12	Concrete	80-feet	13 <i>and</i> 17
54	Map 01	Highland Ave	CIPP Liner	Concrete pipe severely eroded	Sewer	1058-1061	12	Concrete	96-feet	13 <i>and</i> 17
55	Map 01	Highland Ave	CIPP Liner	Concrete pipe severely eroded	Sewer	1061-1062	12	Concrete	201-feet	13 <i>and</i> 17
56	Map 01	May Street	CIPP Liner	Hinged fracture, cracks	Sewer	939-940	12	VC	30-feet	13 <i>and</i> 17
57	Map 01	Highland Ave	Rebuild Invert and Bench (includes 3-feet waterproofing)	Hole in invert of manhole	Sewer	SMH 1059	12	VC	Invert depth 6.5-feet	24
58	Map 01	May Street	Rebuild Invert and Bench (includes 3-feet waterproofing)	Hole in invert of manhole	Sewer	SMH 939	15	VC	Invert depth 10.5-feet	24
59	Map 01	Highland Ave	CIPP Liner	Hole in pipe, cracks and fractures	Drain	1627-6937	12	VC	194-feet	13 <i>and</i> 17
30	Map 02	Crescent Drive	CIPP Spot Liner or Furnish and Install New Pipe Section	12-foot repair, 1-9' heavy cracks from SMH 2465	Sewer	2465-731	8	VC	9-feet	12 <i>and</i> 5 <i>or</i> 19
31	Map 02	Crescent Drive	CIPP Spot Liner or Furnish and Install New Pipe Section	4-foot repair, 40-feet from SMH 2327	Sewer	2327-2329	8	VC	3-feet	12 <i>and</i> 5 <i>or</i> 19
32	Map 02	Crescent Drive	CIPP Spot Liner or Furnish and Install New Pipe Section	4-foot repair, 100-feet from SMH 2327	Sewer	2327-2329	8	VC	3-feet	12 <i>and</i> 5 <i>or</i> 19
33	Map 02	Summit Street	Rebuild Invert and Bench (includes 3-feet waterproofing)	Repair deteriorated invert, install inside drop	Sewer	SMH731	8	VC/CI	Invert depth 12-feet	5 <i>and</i> 24
34	Map 02	Crescent Drive	CIPP Spot Liner or Furnish and Install New Pipe Section	4-foot repair, near SMH 731 no image available	Sewer	2329-731	8	VC	3-feet	12 <i>and</i> 5 <i>or</i> 19

NECE cannot assume liability for any damages caused by any errors or omissions in the data.
Contractor to field verify and measure pipe size and material before bidding and beginning work.
Refer to CCTV Logs for service pipe connection locations.


Table of All Defects to be Repaired

Defect ID #	Map	Street	Repair Type	Description	Sewer/ Drain	Pipe Segment	Pipe Size	Pipe Material	Approximate Defect Length or Depth to Invert	Bid Item #
35	Map 02	Crescent Drive	Rebuild Invert and Bench (includes 3-feet waterproofing)	Seal 3-feet of table and walls	Sewer	SMH799	8	VC	Invert depth 8-feet	24
37	Map 02	Gallows Hill Park	Rebuild Invert and Bench (includes 3-feet waterproofing)	Located in baseball field	Sewer	SMH956	10	VC/PVC	Invert depth 9-feet	24
12	Map 03	Liberty Street	CIPP Liner	Discharges into 48-inch interceptor sewer	Sewer	4064-425	Approx 12x18	Eggshaped Concrete	332-feet	13 <i>and</i> 18
2	Map 04	Oakview Avenue	CIPP Spot Liner or Furnish and Install New Pipe Section	4-foot repair, 58-feet from SMH 3979	Sewer	3153-3979	8	VC	3-feet	12 <i>and</i> (5 <i>and</i> 8) <i>or</i> 19
13	Map 05	Churchhill Easement	CIPP Liner	Heavy roots removed from joints, steep terrain	Sewer	4076-2846	8	VC	38-feet	12 <i>and</i> 16
14	Map 05	Churchhill Street Easement	CIPP Liner	Through easement, roots removed from pipe joints, Chainlink fence at location, 2846 is drop manhole	Sewer	2847-2846	8	VC	18-feet	12 <i>and</i> 16
38	Map 05	Churchill Street Easement	Rebuild Invert and Bench (includes 3-feet waterproofing)	Seal 3-feet of table and walls	Sewer	SMH2846	8	VC	Invert depth 12-feet	24
16	Map 06	Sable Road	CIPP Liner	multiple hinged fractures	Sewer	2211-2212	8	VC	151-feet	12 <i>and</i> 16
17	Map 06	Circle Hill Road	CIPP Spot Liner or Furnish and Install New Pipe Section	4-foot repair, 13-feet from SMH 2217	Sewer	2217-2216	8	VC	3-feet	12 <i>and</i> (5 <i>and</i> 8) <i>or</i> 19
18	Map 06	Circle Hill Road	CIPP Liner	multiple hinged fractures	Sewer	2216-2219	8	VC	106-feet	12 <i>and</i> 16
22	Map 06	Sable Road	CIPP Liner	multiple hinged fractures	Sewer	2208-2209	8	VC	92-feet	12 <i>and</i> 16
23	Map 06	Sable Road	CIPP Liner	multiple hinged fractures	Sewer	2209-2210	8	VC	146-feet	12 <i>and</i> 16
24	Map 06	Sable Road	CIPP Liner	multiple hinged fractures	Sewer	2210-2211	8	VC	147-feet	12 <i>and</i> 16
25	Map 06	Sable Road	CIPP Liner	multiple hinged fractures	Sewer	2222-2223	8	VC	97-feet	12 <i>and</i> 16
26	Map 06	Sable Road	CIPP Liner	multiple hinged fractures	Sewer	2223-2212	8	VC	100-feet	12 <i>and</i> 16
60	Map 06	Circle Hill Road	CIPP Spot Liner or Furnish and Install New Pipe Section	4-foot repair, 29-feet from SMH 2217	Sewer	2217-2216	8	VC	3-feet	12 <i>and</i> (5 <i>and</i> 8) <i>or</i> 19
28	Map 07	Wheatland Street	CIPP Spot Liner or Furnish and Install New Pipe Section	4-foot spot repair, 12-feet from SMH 1937	Sewer	1937-1938	8	VC	3-feet	12 <i>and</i> (5 <i>and</i> 8) <i>or</i> 19
3	Map 08	Cleveland Road	CIPP Spot Liner or Furnish and Install New Pipe Section	4-foot repair, approx 20-feet from SMH 3225	Sewer	3225-3226	8	VC	3-feet	12 <i>and</i> (5 <i>and</i> 8) <i>or</i> 19

NECE cannot assume liability for any damages caused by any errors or omissions in the data.
Contractor to field verify and measure pipe size and material before bidding and beginning work.
Refer to CCTV Logs for service pipe connection locations.

Table of All Defects to be Repaired

Defect ID #	Map	Street	Repair Type	Description	Sewer/ Drain	Pipe Segment	Pipe Size	Pipe Material	Approximate Defect Length or Depth to Invert	Bid Item #
5	Map 08	Cleveland Road	CIPP Spot Liner or Furnish and Install New Pipe Section	4-foot repair, approx 4-feet from SMH 3231	Sewer	3231-3230	8	VC	3-feet	12 and (5 and 8) or 19
39	Map 08	Buchanan Road	CIPP Spot Liner or Furnish and Install New Pipe Section	4-foot repair, Factory service; not in use; open to dirt, 55-feet SMH 3231	Sewer	3231-3232	8	VC	1-foot	12 and (5 and 8) or 19
41	Map 09	Nichols Street	CIPP Spot Liner or Furnish and Install New Pipe Section	4-foot repair, approx 34-feet from SMH 877	Sewer	877-880	6	VC	3-feet	12 and (5 and 8) or 19
42	Map 09	Nichols Street	CIPP Spot Liner or Furnish and Install New Pipe Section	12-foot repair, approx 15-feet from DMH 4935	Drain	4936-4935	12	VC	8-feet	13 and (6 and 9) or 20
43	Map 09	Butler Street	CIPP Spot Liner or Furnish and Install New Pipe Section	16-foot repair, 46-feet from SMH 3071	Sewer	3071-3073	8	VC	14-feet	12 and (5 and 8) or 19
44	Map 09	Butler Street	CIPP Spot Liner or Furnish and Install New Pipe Section	4-foot repair, 96-feet from SMH 3071	Sewer	3071-3073	8	VC	3-feet	12 and (5 and 8) or 19
20	Map 10	Pope Street Easement	CIPP Liner	though easement	Sewer	2484-904	18	VC	186-feet	13 and 18
21	Map 10	Pope Street	CIPP Liner	multiple hinged fractures	Sewer	904-911	12	VC	142-feet	13 and 17
61	Map 11	Washington Street	CIPP Spot Liner	8-foot repair 134-feet from SMH 4047, no digging permitted at this site	Sewer	4047-289	12	VC/CMP	4-feet	13 and 20
62	Map 11	Washington Street	Rebuild Invert and Bench (includes 3-feet waterproofing) Reconstruct Sewer Structure Furnish and Install New Manhole Casting	Manhole is converted catchbasin access is limited.	Sewer	SMH 4047	12	VC	Invert depth 4-feet	22, 23, 24, and 25
45	Map 12	McGrath Park	CIPP Spot Liner	4-foot repair, In soccer field, no digging permitted at this site, 85-feet from SMH 1831	Sewer	1831-1830	18	AC	4-feet	13 and 21
63	Map 12	Buena Vista Easement	Rebuild Invert and Bench (includes 3-feet waterproofing)	In easement	Sewer	SMH 1859	12	CI	Invert depth 12-feet	24
64	Map 12	Buena Vista Easement	Rebuild Invert and Bench (includes 3-feet waterproofing)	In easement	Sewer	SMH 1857	12	CI	Invert depth 12-feet	24
65	Map 12	Buena Vista Easement	Rebuild Invert and Bench (includes 3-feet waterproofing)	In easement	Sewer	SMH 1856	18	AC	10-feet to invert	24



Sewer Rehabilitation Project Locations Salem, MA


Friday, August 18, 2017

0 800 1,600
Feet

• Repair Locations

Maps are for graphical purposes only and do not represent a legal survey. NECE cannot assume liability for any damages caused by any errors or omissions in the data. Contractor to field verify and measure pipe size and material before bidding and beginning work.

MAP 1



Legend

Repair Type

- CIPP Liner (7)
- Brick and Mortar Plug (1)
- Rebuild Invert and Bench (4)

- Drain Manhole
- Catchbasin
- Drain Pipe
- Rehab Planned
- Sewer Manhole
- Sewer Pipe
- Rehab Planned

Services

- Sanitary Service - Active
- Sanitary Service - Unknown if in use
- Sanitary Service - Capped

Sanitary Sewer Repair Project - Highland Avenue and Essex Street Salem, MA

Wednesday, August 16, 2017

0 55 110
Feet

1 inch = 110 feet





Location 29—CIPP Liner 320-feet



Location 51—CIPP Liner 75-feet



Location 52—CIPP Liner 26-feet



Location 53—CIPP Liner 80-feet



Location 54—CIPP Liner 96-feet



Location 55—CIPP Liner 201-feet



Location 56—CIPP Liner 30-feet



Location 46—Rebuild Invert & Bench



Location 59—CIPP Liner (Drain) 194-feet



Location 47—Rebuild Invert & Bench



Location 57—Rebuild Invert & Bench



Location 58—Rebuild Invert & Bench



NEW ENGLAND CIVIL ENGINEERING CORP.

120 WASHINGTON STREET, SUITE 202E, P.O. BOX 3026, SALEM, MA 01970
PH: 978.741.7401 - FAX: 978.741.7402 - WWW.ENGINEERINGCORPORATION.COM

City: 8/19/14 Salem MH Start: 815 MH Finish: 3858
Location: Highland ave Pipe Diameter: 8 Pipe Material: VC
Contractor: Markley Material Change: ☐ Yes ☒ No
NECE Staff Present: WBC Pipe Type: ☐ Stormwater ☒ Sanitary
Weather: Sun Total Pipe Length: 321'
Total Pages/Day: 7 of 19 Total CCTV Length: 321'
Section Number: _____

Additional Information:

pipe seems to be small for flow
Mineral deposits in joints 1/3 - 1/2 - 3/4 heavy grease
grease deposits on crown of pipe, lots of debris in pipe
Camera underwater 240-

	Distance (ft)	Service	Other	Description	Position (o'clock)	Comments
<div>Flow Direction</div> <div><div>Start MH</div><div>815</div><div>↓</div><div>Finish MH</div><div>3858</div></div>	1	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Crack	12-3	
	54	<input checked="" type="checkbox"/>	<input type="checkbox"/>	VC / BT	9	
	84	<input checked="" type="checkbox"/>	<input type="checkbox"/>	manu/capped	11	
	140	<input checked="" type="checkbox"/>	<input type="checkbox"/>	manu	9	gushing appears to be infil as
	169	<input checked="" type="checkbox"/>	<input type="checkbox"/>	manu/capped	9	
	219	<input checked="" type="checkbox"/>	<input type="checkbox"/>	BT / ATU	12	
	220	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Cracks	3	
	225	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Cracks	12	
	229	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Cracks	12-3	
	238	<input type="checkbox"/>	<input checked="" type="checkbox"/>	too much debris		
	266	<input checked="" type="checkbox"/>	<input type="checkbox"/>	man/capped	9	
	275	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Cracks open		1-2 lengths
	290	<input checked="" type="checkbox"/>	<input type="checkbox"/>	manu/VC	9	
	295	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Cracks / infiltration	3/9	
	304	<input type="checkbox"/>	<input checked="" type="checkbox"/>	fractures	3/9	open 1-1 length
315	<input type="checkbox"/>	<input checked="" type="checkbox"/>	gravel exposed / hole	9	possible service	



NEW ENGLAND CIVIL ENGINEERING CORP.

120 WASHINGTON STREET, SUITE 202E, P.O. BOX 3026, SALEM, MA 01970
PH: 978.741.7401 - FAX: 978.741.7402 - WWW.ENGINEERINGCORPORATION.COM

City: 8/19/14 Salem MH Start: 3858 MH Finish: 3899
Location: Highland Ave Pipe Diameter: 8 Pipe Material: pvc/vc/pvc/vc
Contractor: Mackey Material Change: ☒ Yes ☐ No
NECE Staff Present: RNC Pipe Type: ☐ Stormwater ☒ Sanitary
Weather: Sun Total Pipe Length: 76
Total Pages/Day: 8 of 19 Total CCTV Length: 76'
Section Number: _____

Additional Information:

1/2 pipe flow, multiple material change

	Distance (ft)	Service	Other	Description	Position (o'clock)	Comments
<div>Flow Direction</div> <div> <div>Start MH</div> <div>3858</div> <div>↑</div> <div>↓</div> <div>Finish MH</div> <div>3899</div> </div>	22	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Change to vc		
		<input type="checkbox"/>	<input checked="" type="checkbox"/>	open joints		
	34	<input type="checkbox"/>	<input checked="" type="checkbox"/>	lighter cracks		
	57	<input type="checkbox"/>	<input checked="" type="checkbox"/>	roots	12	-open crack dripping
	60	<input type="checkbox"/>	<input checked="" type="checkbox"/>	transition to pvc		
	73	<input type="checkbox"/>	<input checked="" type="checkbox"/>	change to vc		
	76	<input type="checkbox"/>	<input checked="" type="checkbox"/>	MH 3899		
		<input type="checkbox"/>	<input type="checkbox"/>			
		<input type="checkbox"/>	<input type="checkbox"/>			
		<input type="checkbox"/>	<input type="checkbox"/>			
		<input type="checkbox"/>	<input type="checkbox"/>			
		<input type="checkbox"/>	<input type="checkbox"/>			
		<input type="checkbox"/>	<input type="checkbox"/>			
		<input type="checkbox"/>	<input type="checkbox"/>			
		<input type="checkbox"/>	<input type="checkbox"/>			



NEW ENGLAND CIVIL ENGINEERING CORP.

120 WASHINGTON STREET, SUITE 202E, P.O. BOX 3026, SALEM, MA 01970
PH: 978.741.7401 - FAX: 978.741.7402 - WWW.ENGINEERINGCORPORATION.COM

City: 8/19/14 Salem MH Start: 3857 MH Finish: 1057
Location: Highland Ave / Essex St Pipe Diameter: 12 Pipe Material: VC
Contractor: PRC Inc Material Change: ☐ Yes ☒ No
NECE Staff Present: NOC Pipe Type: ☐ Stormwater ☒ Sanitary
Weather: Sun Total Pipe Length: 26'
Total Pages/Day: 14 of 19 Total CCTV Length: 26'
Section Number: _____

Additional Information:

heavy cracks inline,, invert maybe deteriorated in MH 1057

	Distance (ft)	Service	Other	Description	Position (o'clock)	Comments
<div>Flow Direction</div> <div> <div>Start MH</div> <div>3857</div> <div>↑</div> <div>↓</div> <div>Finish MH</div> <div>1057</div> </div>	13-24	<input type="checkbox"/>	<input checked="" type="checkbox"/>	cracks/misalign		13-24
	26	<input type="checkbox"/>	<input type="checkbox"/>	MH 1057		
		<input type="checkbox"/>	<input type="checkbox"/>			
		<input type="checkbox"/>	<input type="checkbox"/>			
		<input type="checkbox"/>	<input type="checkbox"/>			
		<input type="checkbox"/>	<input type="checkbox"/>			
		<input type="checkbox"/>	<input type="checkbox"/>			
		<input type="checkbox"/>	<input type="checkbox"/>			
		<input type="checkbox"/>	<input type="checkbox"/>			
		<input type="checkbox"/>	<input type="checkbox"/>			
		<input type="checkbox"/>	<input type="checkbox"/>			
		<input type="checkbox"/>	<input type="checkbox"/>			
		<input type="checkbox"/>	<input type="checkbox"/>			
		<input type="checkbox"/>	<input type="checkbox"/>			
		<input type="checkbox"/>	<input type="checkbox"/>			



NEW ENGLAND CIVIL ENGINEERING CORP.

120 WASHINGTON STREET, SUITE 202E, P.O. BOX 3026, SALEM, MA 01970
PH: 978.741.7401 - FAX: 978.741.7402 - WWW.ENGINEERINGCORPORATION.COM

City: 8/19/14 Salem MH Start: 1058 MH Finish: 1057
Location: Highland Ave Pipe Diameter: 12 Pipe Material: Concrete
Contractor: Machy Material Change: ☐ Yes ☒ No
NECE Staff Present: WPC Pipe Type: ☐ Stormwater ☒ Sanitary
Weather: Sun Total Pipe Length: 83'
Total Pages/Day: 15 of 19 Total CCTV Length: 83'
Section Number: _____

Additional Information: could not get camera into MH 1057

○	Distance (ft)	Service	Other	Description	Position (o'clock)	Comments
<div style="display: flex; flex-direction: column; align-items: center;"> <div>Start MH</div> <div>1058</div> <div style="margin-top: 100px;"> <div style="writing-mode: vertical-rl; transform: rotate(180deg);">Flow Direction</div> <div style="font-size: 2em;">↓</div> </div> <div>Finish MH</div> <div>1057</div> </div>	62	<input checked="" type="checkbox"/>	<input type="checkbox"/>	vc	9	day may not be in use
	83'	<input type="checkbox"/>	<input checked="" type="checkbox"/>	MH 1057		
		<input type="checkbox"/>	<input type="checkbox"/>			
		<input type="checkbox"/>	<input type="checkbox"/>			
		<input type="checkbox"/>	<input type="checkbox"/>			
		<input type="checkbox"/>	<input type="checkbox"/>			
		<input type="checkbox"/>	<input type="checkbox"/>			
		<input type="checkbox"/>	<input type="checkbox"/>			
		<input type="checkbox"/>	<input type="checkbox"/>			
		<input type="checkbox"/>	<input type="checkbox"/>			
		<input type="checkbox"/>	<input type="checkbox"/>			
		<input type="checkbox"/>	<input type="checkbox"/>			
		<input type="checkbox"/>	<input type="checkbox"/>			
		<input type="checkbox"/>	<input type="checkbox"/>			
		<input type="checkbox"/>	<input type="checkbox"/>			



NEW ENGLAND CIVIL ENGINEERING CORP.

120 WASHINGTON STREET, SUITE 202E, P.O. BOX 3026, SALEM, MA 01970
PH: 978.741.7401 - FAX: 978.741.7402 - WWW.ENGINEERINGCORPORATION.COM

City: 8/19/14 Salim MH Start: 1058 MH Finish: 1061
Location: Highland ave Pipe Diameter: 12 Pipe Material: Concrete
Contractor: Marney Material Change: ☐ Yes ☒ No
NECE Staff Present: NDC Pipe Type: ☐ Stormwater ☒ Sanitary
Weather: Sm Total Pipe Length: 93'
Total Pages/Day: 16 of Total CCTV Length: 93'
Section Number: _____

Additional Information:

appears pipe 15th in / e road

	Distance (ft)	Service	Other	Description	Position (o'clock)	Comments
<div>Flow Direction</div> <div> <div>Start MH</div> <div>1058</div> <div>↑</div> <div>↓</div> <div>Finish MH</div> <div>1061</div> </div>	1-3'	<input type="checkbox"/>	<input checked="" type="checkbox"/>	cracks	12/3/16	
	27	<input type="checkbox"/>	<input checked="" type="checkbox"/>	hole	8	
	93	<input type="checkbox"/>	<input checked="" type="checkbox"/>	MH 1061		
		<input type="checkbox"/>	<input type="checkbox"/>			
		<input type="checkbox"/>	<input type="checkbox"/>			
		<input type="checkbox"/>	<input type="checkbox"/>			
		<input type="checkbox"/>	<input type="checkbox"/>			
		<input type="checkbox"/>	<input type="checkbox"/>			
		<input type="checkbox"/>	<input type="checkbox"/>			
		<input type="checkbox"/>	<input type="checkbox"/>			
		<input type="checkbox"/>	<input type="checkbox"/>			
		<input type="checkbox"/>	<input type="checkbox"/>			
		<input type="checkbox"/>	<input type="checkbox"/>			
		<input type="checkbox"/>	<input type="checkbox"/>			
		<input type="checkbox"/>	<input type="checkbox"/>			



NEW ENGLAND CIVIL ENGINEERING CORP.

120 WASHINGTON STREET, SUITE 202E, P.O. BOX 3026, SALEM, MA 01970
PH: 978.741.7401 - FAX: 978.741.7402 - WWW.ENGINEERINGCORPORATION.COM

City: 8/19/14 Salmon MH Start: 1061 MH Finish: 1062
Location: Essex St/Hightbridge Pipe Diameter: 12 Pipe Material: Concrete
Contractor: Wack Material Change: ☐ Yes ☐ No
NECE Staff Present: WDC Pipe Type: ☐ Stormwater ☒ Sanitary
Weather: _____ Total Pipe Length: 708
Total Pages/Day: 17 of Total CCTV Length: 118 + 88
Section Number: _____

Additional Information:

*pipe seems thin can see thickness through hole in pipe
invert likely deteriorated along entire segment*

	Distance (ft)	Service	Other	Description	Position (o'clock)	Comments
<div>Flow Direction</div> <div>Start MH 1061</div> <div>↓</div> <div>Finish MH 1062</div>	10	<input checked="" type="checkbox"/>	<input type="checkbox"/>	VC / doesn't appear in use	9	
	20	<input type="checkbox"/>	<input checked="" type="checkbox"/>	hole	7	
	71	<input checked="" type="checkbox"/>	<input type="checkbox"/>	VC / doesn't appear in use	9	
	83	<input checked="" type="checkbox"/>	<input type="checkbox"/>	VC / ATU	3	
	118	<input checked="" type="checkbox"/>	<input type="checkbox"/>	VC	9	
	118	<input type="checkbox"/>	<input checked="" type="checkbox"/>	Cracks / ATU	12	protruding into pipe
		<input type="checkbox"/>	<input type="checkbox"/>	Reverse Setup	1062-1061	
	29	<input type="checkbox"/>	<input checked="" type="checkbox"/>	large hole	7	
	37	<input type="checkbox"/>	<input checked="" type="checkbox"/>	invert deteriorated	6	
	75	<input type="checkbox"/>	<input checked="" type="checkbox"/>	hole - large	5	
	88	<input checked="" type="checkbox"/>	<input type="checkbox"/>		3	protruding
	542	<input checked="" type="checkbox"/>	<input type="checkbox"/>	VC / maybe not in use	9	Same as reverse
		<input type="checkbox"/>	<input type="checkbox"/>			
		<input type="checkbox"/>	<input type="checkbox"/>			
		<input type="checkbox"/>	<input type="checkbox"/>			



NEW ENGLAND CIVIL ENGINEERING CORP.

120 WASHINGTON STREET, SUITE 202E, P.O. BOX 3026, SALEM, MA 01970
PH: 978.741.7401 - FAX: 978.741.7402 - WWW.ENGINEERINGCORPORATION.COM

City: 8/19/14 Salem MH Start: 939 MH Finish: 940
Location: May St Pipe Diameter: 12 Pipe Material: VC
Contractor: Marking Material Change: ☐ Yes ☒ No
NECE Staff Present: Loc Pipe Type: ☐ Stormwater ☒ Sanitary
Weather: Sun Total Pipe Length: 28'
Total Pages/Day: 19 of Total CCTV Length: 28'
Section Number: _____

Additional Information:

	Distance (ft)	Service	Other	Description	Position (o'clock)	Comments
<div>Flow Direction</div> <div> <div>Start MH</div> <div>939</div> <div>↑</div> <div>↓</div> <div>Finish MH</div> <div>940</div> </div>	16	<input type="checkbox"/>	<input checked="" type="checkbox"/>	fractures	3/4/6	2 Circum
	14	<input checked="" type="checkbox"/>	<input type="checkbox"/>	manu/capped	12	
	16	<input checked="" type="checkbox"/>	<input type="checkbox"/>	manu/capped	12	
	28	<input type="checkbox"/>	<input checked="" type="checkbox"/>	SMH 940		
		<input type="checkbox"/>	<input type="checkbox"/>			
		<input type="checkbox"/>	<input type="checkbox"/>			
		<input type="checkbox"/>	<input type="checkbox"/>			
		<input type="checkbox"/>	<input type="checkbox"/>			
		<input type="checkbox"/>	<input type="checkbox"/>			
		<input type="checkbox"/>	<input type="checkbox"/>			
		<input type="checkbox"/>	<input type="checkbox"/>			
		<input type="checkbox"/>	<input type="checkbox"/>			
		<input type="checkbox"/>	<input type="checkbox"/>			
		<input type="checkbox"/>	<input type="checkbox"/>			




NEW ENGLAND CIVIL ENGINEERING CORP.

120 WASHINGTON STREET, SUITE 202E, P.O. BOX 3026, SALEM, MA 01970
PH: 978.741.7401 - FAX: 978.741.7402 - WWW.ENGINEERINGCORPORATION.COM

City: Salem MH Start: DM 1627 MH Finish: DM 6937
Location: Nguc Island Auct Jackson Pipe Diameter: 12 Pipe Material: VC
Contractor: Mackey Material Change: ☐ Yes ☒ No
NECE Staff Present: _____ Pipe Type: ☒ Stormwater ☐ Sanitary
Weather: _____ Total Pipe Length: _____
Total Pages/Day: _____ Total CCTV Length: 157'
Section Number: _____

Additional Information: Reverse from previous
end survey at 157'

	Distance (ft)	Service	Other	Description	Position (o'clock)	Comments
<div>Start MH</div> <div>DM 1627</div> <div>DM 4</div> <div>Flow Direction</div> <div>Finish MH</div> <div>DM 6937</div> <div>DM 3</div>	57	<input type="checkbox"/>	<input checked="" type="checkbox"/>	joint		offset joint
	57-74	<input type="checkbox"/>	<input checked="" type="checkbox"/>	cracking	3+9	Moderate cracking
	65	<input type="checkbox"/>	<input checked="" type="checkbox"/>	fracture	3	Small fracture in pipe
	81-102	<input type="checkbox"/>	<input checked="" type="checkbox"/>	joints		offset joints
	135-144	<input type="checkbox"/>	<input checked="" type="checkbox"/>	joints		offset joints
	144-156	<input type="checkbox"/>	<input checked="" type="checkbox"/>	cracking	12-12	heavy cracking
	157	<input type="checkbox"/>	<input checked="" type="checkbox"/>	pipe failure	3	pipe collapsed/missing
		<input type="checkbox"/>	<input type="checkbox"/>			
		<input type="checkbox"/>	<input type="checkbox"/>			
		<input type="checkbox"/>	<input type="checkbox"/>			
		<input type="checkbox"/>	<input type="checkbox"/>			
		<input type="checkbox"/>	<input type="checkbox"/>			
		<input type="checkbox"/>	<input type="checkbox"/>			
		<input type="checkbox"/>	<input type="checkbox"/>			
		<input type="checkbox"/>	<input type="checkbox"/>			






Location 37—Rebuild Invert & Bench



Location 35—Rebuild Invert & Bench



Location 33—Install 8-inch Inside Drop,
Rebuild Invert & Bench



Location 30—(12-foot Repair) CIPP Spot Liner
or Furnish and Install New Pipe Section



Location 31—(4-foot Repair) CIPP Spot Liner
or Furnish and Install New Pipe Section



Location 32—(4-foot Repair) CIPP Spot Liner
or Furnish and Install New Pipe Section

Tabular Report of PSR SMH2327
A
for City of Salem
Setup 12 **Surveyor** Craig Medwid **Certificate #** U-213-17284 **System Owner**

Drainage		Survey Customer			
P/O #		Date	2016/08/04	Time	7:16
City	salem	Further location details			
Start	SMH2327	Rim to invert		Grade to invert	
Finish	SMH2329	Rim to invert		Grade to invert	
Use	Sanitary	Direction	Down	Flow control	
Shape	Circular	Height	8	Width	ins
Material	Vitrified Clay Pipe	Joint length		Ft	
Lining		Year laid		Year rehabilitated	
Purpose		Cat		Weather	
Additional info				Media No	
Location				Year Cleaned	
Project witchcraft heights				Length Surveyed 303.3	
Northing				Pressure	
Coordinate System				GPS Accuracy	


Count	Video	CD	Code	In1	In2	%	JntFr	To	ImRef	Remarks
0.0			ST Start of Survey							
0.0			AMH Manhole							SMH2327
0.0			MWL Water Level			5				
40.7			B Broken				05	10		
66.8			TF Tap Factory	6.000			09			
74.0			TF Tap Factory	6.000			03			
100.7			B Broken				12	06		
146.7			TF Tap Factory	6.000			09			
153.9			TF Tap Factory	6.000			03			
221.5			TF Tap Factory	4.000			09			
227.4			MMC Material change							pvc
228.8			TF Tap Factory	6.000			03			
250.4			MMC Material change							vcp
282.8			MMC Material change							pvc
286.9			TF Tap Factory	6.000			03			
292.3			MMC Material change							vcp
293.6			TF Tap Factory	6.000			09			
303.3			AMH Manhole							SMH2329
303.3			FH End of Survey							

 303.3 Ft **Total Length Surveyed**
Scores

Structural:	Pipe Rating 10	Pipe Ratings Index 5	Peak 5	Mean Pipe 0
O&M:	Pipe Rating 0	Pipe Ratings Index 0	Peak 0	Mean Pipe 0

Maps are for graphical purposes only and do not represent a legal survey. NECE cannot assume liability for any damages caused by any errors or omissions in the data. Contractor to field verify and measure pipe size and material before bidding and beginning work.

MAP 3



Sanitary Sewer Repair Project - Liberty Street Salem, MA

Thursday, August 17, 2017

0 30 60
Feet

1 inch = 60 feet



Tabular Report of PSR SMH UPSTREAM A for Salem

Setup 20	Surveyor ZC	Certificate # U-614-06021733	System Owner
Drainage	Survey Customer		
P/O #	Date 2016/07/20	Time 7:34	Street Liberty St.
City Salem	Further location details		
Up SMH UPSTREAM	Rim to invert	Grade to invert	Rim to grade Ft
Down SMH 425	Rim to invert	Grade to invert	Rim to grade Ft
Use	Direction Up	Flow control	Media No
Shape Egg Shaped	Height 18	Width 12 ins	Preclean N
Material Concrete Pipe (non-reinforced)	Joint length Ft	Total length Ft	Date Cleaned
Lining	Year laid	Year rehabilitated	Length Surveyed 174.5 Ft
Purpose	Cat	Weather	Pressure
Additional info		<div> <div>Structural</div> <div>O & M</div> <div>Constructional</div> </div>	
Location		<div> <div>Miscellaneous</div> <div>Hydraulic</div> </div>	
Project Salem Utilites	Work Order		
Northing	Easting	Elevation	
Coordinate System	GPS Accuracy		

Count	Video	CD	Code	In1	In2	%	JntFr	To	ImRef	Remarks
0.0			ST Start of Survey							
0.0			AMH Manhole							SMH 425
0.0			MWL Water Level			5				
7.5			CL Crack Longitudinal				12			
7.6			MGO General Observation							aggregate exposed
18.0			TB Tap Break-in	6.000			11			
19.7			TB Tap Break-in	6.000			09			
20.9			CM Crack Multiple				10	12		
22.1			CL Crack Longitudinal				02			
23.4			TB Tap Break-in	6.000			01			
25.5			CL Crack Longitudinal				12			
48.1			TB Tap Break-in	6.000			11			
50.4			CL Crack Longitudinal				11			
54.2			TB Tap Break-in	6.000			03			
55.7			TB Tap Break-in	6.000			11			
57.6			TB Tap Break-in	6.000			12			
58.7			CL Crack Longitudinal				12			
62.3			CL Crack Longitudinal				12			
66.2		S01	CL Crack Longitudinal				12			
77.3			TB Tap Break-in	6.000			01			
91.0			CL Crack Longitudinal				12			
105.3			TB Tap Break-in	6.000			12			
111.7			TB Tap Break-in	6.000			11			
112.0			TB Tap Break-in	6.000			01			
118.9			JOM Joint Offset Medium							
126.0		F01	CL Crack Longitudinal				12			
131.8		S02	CL Crack Longitudinal				12			
134.6			CL Crack Longitudinal				09			
136.8			JOM Joint Offset Medium							
140.7		F02	CL Crack Longitudinal				12			
146.3			JOM Joint Offset Medium							

Tabular Report of PSR SMH UPSTREAM A for Salem

Setup 20	Surveyor ZC	Certificate # U-614-06021733	System Owner			
Drainage	Survey Customer					
P/O #	Date 2016/07/20	Time 7:34	Street Liberty St.			
City Salem	Further location details					
Up SMH UPSTREAM	Rim to invert	Grade to invert	Rim to grade Ft			
Down SMH 425	Rim to invert	Grade to invert	Rim to grade Ft			
Use	Direction Up	Flow control	Media No			
Shape Egg Shaped	Height 18	Width 12 ins	Preclean N			
Material Concrete Pipe (non-reinforced)	Joint length Ft	Total length Ft	Date Cleaned			
Lining	Year laid	Year rehabilitated	Length Surveyed 174.5 Ft			
Purpose	Cat	Weather	Pressure			
Additional info		<div> <div>Structural</div> <div>O & M</div> <div>Constructional</div> </div>				
Location		<div> <div>Miscellaneous</div> <div>Hydraulic</div> </div>				
Project Salem Utilites	Work Order					
Northing	Easting	Elevation				
Coordinate System	GPS Accuracy					
Count Video	CD Code	In1	In2	% JntFr	To ImRef	Remarks
149.5	CL Crack Longitudinal				03	
151.0	CL Crack Longitudinal				12	
157.4	TB Tap Break-in	6.000			01	
159.1	HSV Hole Soil Visible				12	
168.9	RPP Repair Patch				12	brick repair at joint
169.8	DAGS Deposits Attached Grease			5	09 03	
174.0	TB Tap Break-in	6.000			11	
174.5	DAGS Deposits Attached Grease			25	12	
174.5	MSA Abandoned Survey					

174.5 Ft Total Length Surveyed

Scores	Structural:	Pipe Rating 59	Pipe Ratings Index 2	Peak 5	Mean Pipe 0.3
	O&M:	Pipe Rating 6	Pipe Ratings Index 0.4	Peak 4	Mean Pipe 0

Tabular Report of PSR SMH UPSTREAM A for Salem

Setup 21	Surveyor ZC	Certificate # U-614-06021733	System Owner
Drainage	Survey Customer		
P/O #	Date 2016/07/21	Time 10:02	Street Liberty St.
City Salem	Further location details		
Up SMH UPSTREAM	Rim to invert	Grade to invert	Rim to grade Ft
Down SMH 425	Rim to invert	Grade to invert	Rim to grade Ft
Use	Direction Down	Flow control	Media No
Shape Egg Shaped	Height 18	Width 12 ins	Preclean N
Material Concrete Pipe (non-reinforced)	Joint length Ft	Total length Ft	Date Cleaned
Lining	Year laid	Year rehabilitated	Length Surveyed 173.0 Ft
Purpose	Cat	Weather	Pressure
Additional info	Reverse set up on sheet:20		<div>Structural</div> <div>O & M</div> <div>Constructional</div>
Location			<div>Miscellaneous</div> <div>Hydraulic</div>
Project Salem Utilites	Work Order		
Northing	Easting	Elevation	
Coordinate System	GPS Accuracy		

Count	Video	CD	Code	In1	In2	%	JntFr	To	ImRef	Remarks
0.0			ST Start of Survey							
0.0			AMH Manhole							SMH UPSTREAM
0.0			MWL Water Level			5				
10.7		S01	CL Crack Longitudinal				12			
13.2			RFJ Roots Fine Joint				J 05			
16.5			BSV Broken Soil Visible				12			
16.8			HSV Hole Soil Visible				05			
22.3			RPP Repair Patch				12			stone rock
32.2			RFJ Roots Fine Joint				J 07			
40.6			TB Tap Break-in	6.000			02			
41.2			TB Tap Break-in	6.000			11			
47.7			RFJ Roots Fine Joint				J 03			
49.6			TB Tap Break-in	6.000			11			
66.1			RMJ Roots Medium Joint			5	J 04			
67.9			BSV Broken Soil Visible				11			
69.7			RFJ Roots Fine Joint				J 08			
78.0			TB Tap Break-in	6.000			02			
79.7			TB Tap Break-in	6.000			11			
93.4			TB Tap Break-in	6.000			11			
110.3			RFJ Roots Fine Joint				J 05			
115.4			TB Tap Break-in	6.000			10			
116.8			JOM Joint Offset Medium							
123.0			RMJ Roots Medium Joint			5	J 05			
124.5		F01	CL Crack Longitudinal				12			
125.9			TB Tap Break-in	6.000			11			
128.0			CL Crack Longitudinal				12			
129.3			RMJ Roots Medium Joint			5	J 03 09			
131.6			CL Crack Longitudinal				12			
132.5			RFJ Roots Fine Joint				J 03			
138.2			FH3 Fracture Longitudinal Hinge, 3				09 03			
139.0			RFJ Roots Fine Joint				J 10			

Tabular Report of PSR SMH UPSTREAM A for Salem

Setup 21	Surveyor ZC	Certificate # U-614-06021733	System Owner
Drainage	Survey Customer		
P/O #	Date 2016/07/21	Time 10:02	Street Liberty St.
City Salem	Further location details		
Up SMH UPSTREAM	Rim to invert	Grade to invert	Rim to grade Ft
Down SMH 425	Rim to invert	Grade to invert	Rim to grade Ft
Use	Direction Down	Flow control	Media No
Shape Egg Shaped	Height 18	Width 12 ins	Preclean N
Material Concrete Pipe (non-reinforced)	Joint length Ft	Total length Ft	Date Cleaned
Lining	Year laid	Year rehabilitated	Length Surveyed 173.0 Ft
Purpose	Cat	Weather	Pressure
Additional info	Reverse set up on sheet:20		<div>Structural</div> <div>O & M</div> <div>Constructional</div>
Location			Miscellaneous Hydraulic
Project Salem Utilites	Work Order		
Northing	Easting	Elevation	
Coordinate System	GPS Accuracy		

Count	Video	CD	Code	In1	In2	%	JntFr	To	ImRef	Remarks
140.7			TB Tap Break-in	6.000			11			
147.4			DAGS Deposits Attached Grease			5	09	03		
149.9			TB Tap Break-in	6.000			10			
149.9			TB Tap Break-in	6.000			11			
154.4			RPP Repair Patch				11			brick patch
155.9			TB Tap Break-in	6.000			02			
161.7			CL Crack Longitudinal				12			
164.7			CL Crack Longitudinal				12			
170.2			HSV Hole Soil Visible				12			
173.0			TB Tap Break-in	6.000			10			
173.0			MSA Abandoned Survey							

173.0 Ft Total Length Surveyed


Scores	Structural:	Pipe Rating 80	Pipe Ratings Index 2.3	Peak 7	Mean Pipe 0.5
	O&M:	Pipe Rating 18	Pipe Ratings Index 0.8	Peak 3	Mean Pipe 0.1

Maps are for graphical purposes only and do not represent a legal survey. NECE cannot assume liability for any damages caused by any errors or omissions in the data. Contractor to field verify and measure pipe size and material before bidding and beginning work.

MAP 4



Defect 2
(4-foot Repair) CIPP Spot Liner or
Furnish and Install New Pipe Section



Sanitary Sewer Repair Project - Oakview Avenue **Salem, MA** **Thursday, August 17, 2017**





NEW ENGLAND CIVIL ENGINEERING CORP.

120 WASHINGTON STREET, SUITE 202E, P.O. BOX 3026, SALEM, MA 01970
PH: 978.741.7401 - FAX: 978.741.7402 - WWW.ENGINEERINGCORPORATION.COM

CCTV Inspection Record


Date:	6/12/12	Section Number:	
Street:	Oakview	From MH:	3153
City:	Salem	To MH:	3979
Contractor:	MACKEY	Pipe Size:	8
NECE Staff Present:	Rebecca Dupont-Coutu	Pipe Material:	VC
Weather:	SUNNY	Material Change:	<input type="checkbox"/> YES <input checked="" type="checkbox"/> NO
Total Pages/Day:	1	Pipe Type:	<input checked="" type="checkbox"/> Sanitary <input type="checkbox"/> Stormwater
Total CCTV Length:	146'	Total Pipe Length:	146'

Additional Information: Heavy roots filled pipe at 78' and 81'. There was a piece of the pipe in the invert of MH 3979 when Mackey began cleaning. City may have damaged pipe when trying to relieve sewer back up previous week.

Flow	Distance (ft)	Service	Other	Description	Position (o'clock)	Notes
<div style="display: flex; align-items: center;"> <div style="margin-right: 10px;"> </div> <div> <p>Start MH # 3153</p> </div> </div>	40	<input checked="" type="checkbox"/>	<input type="checkbox"/>	MANUFACTURED	9	Capped
	42	<input checked="" type="checkbox"/>	<input type="checkbox"/>	MANUFACTURED	3	Capped
	45	<input checked="" type="checkbox"/>	<input type="checkbox"/>	BREAK IN	3	Appears in use
	50	<input type="checkbox"/>	<input checked="" type="checkbox"/>	ROOTS	3	Light
	64	<input checked="" type="checkbox"/>	<input type="checkbox"/>	BREAK IN	9	Roots
	67	<input type="checkbox"/>	<input checked="" type="checkbox"/>	ROOTS		
	78	<input type="checkbox"/>	<input checked="" type="checkbox"/>	ROOTS		
	78	<input type="checkbox"/>	<input checked="" type="checkbox"/>	SM CRACKS	6	
	80	<input type="checkbox"/>	<input checked="" type="checkbox"/>	LG HOLE	6	
		<input type="checkbox"/>	<input type="checkbox"/>	SURVEY ABANDONED		Cannot get by hole in invert
		<input type="checkbox"/>	<input type="checkbox"/>	OTHER		Reverse Set up 3979-3153
	11	<input checked="" type="checkbox"/>	<input type="checkbox"/>	CAPPED	9	Roots
	14	<input checked="" type="checkbox"/>	<input type="checkbox"/>	BREAK IN	9	
	22	<input checked="" type="checkbox"/>	<input type="checkbox"/>	BREAK IN	9	Appears in use, Roots
	30	<input checked="" type="checkbox"/>	<input type="checkbox"/>	MANUFACTURED	9	Capped
<div style="display: flex; align-items: center;"> <div style="margin-right: 10px;"> </div> <div> <p>End MH # 3979</p> </div> </div>	56	<input type="checkbox"/>	<input checked="" type="checkbox"/>	INVERT DAMAGED		Other side of Reverse Set Up
		<input type="checkbox"/>	<input type="checkbox"/>	SURVEY COMPLETE		
		<input type="checkbox"/>	<input type="checkbox"/>			

Maps are for graphical purposes only and do not represent a legal survey. NECE cannot assume liability for any damages caused by any errors or omissions in the data. Contractor to field verify and measure pipe size and material before bidding and beginning work.

MAP 5



Legend

Repair Type

- | | | |
|----------------------------|---------------------------|---------------|
| CIPP Liner (2) | Sanitary Service - Active | Drain Manhole |
| Rebuild Invert & Bench (1) | Sewer Manhole | Catchbasin |
| | Sewer Pipe (6) | Drain Pipe |
| | Rehab Planned (2) | |

Sanitary Sewer Repair Project - Churchill Sewer Easement Salem, MA

Wednesday, August 16, 2017

0 15 30
Feet

1 inch = 30 feet



Tabular Report of PSR SMH 2847 A for NECE

Setup 15	Surveyor ZC	Certificate # U-614-06021733	System Owner
Drainage	Survey Customer		
P/O #	Date 2016/12/22	Time 13:39	Street Dunlap st.
City Salem	Further location details		
Up SMH 2847	Rim to invert	Grade to invert	Rim to grade Ft
Down SMH 2846	Rim to invert	Grade to invert	Rim to grade Ft
Use	Direction Down	Flow control	Media No
Shape Circular	Height 8 Width	ins Preclean J	Date Cleaned 2016/12/21
Material Vitrified Clay Pipe	Joint length Ft	Total length Ft	Length Surveyed 23.0 Ft
Lining	Year laid	Year rehabilitated	Weather
Purpose	Cat		Pressure
Additional info	Reverse set up on sheet:11		<div>Structural</div> <div>O & M</div> <div>Constructional</div>
Location			<div>Miscellaneous</div> <div>Hydraulic</div>
Project Salem Utilities	Work Order		
Northing	Easting	Elevation	
Coordinate System	GPS Accuracy		

Count	Video	CD	Code	In1	In2	%	JntFr	To	ImRef	Remarks
0.0			ST Start of Survey							
0.0			AMH Manhole							SMH 2847
0.0			MWL Water Level			5				
9.3			TF Tap Factory	6.000			03			
10.4			RMJ Roots Medium Joint			35	J 09			
11.4			TB Tap Break-in	6.000			09			
12.3			RMJ Roots Medium Joint			25	J 03			
23.0			MSA Abandoned Survey							roots

23.0 Ft Total Length Surveyed

Scores	Structural:	Pipe Rating 0	Pipe Ratings Index 0	Peak 0	Mean Pipe 0
	O&M:	Pipe Rating 6	Pipe Ratings Index 2	Peak 3	Mean Pipe 0.3

Tabular Report of PSR SMH 2846 A for NECE

Setup 14	Surveyor ZC	Certificate # U-614-06021733	System Owner
Drainage	Survey Customer		
P/O #	Date 2016/12/22	Time 12:51	Street Dunlap st.
City Salem	Further location details		
Up SMH 2846	Rim to invert	Grade to invert	Rim to grade Ft
Down SMH 2839	Rim to invert	Grade to invert	Rim to grade Ft
Use	Direction Up	Flow control	Media No
Shape Circular	Height 8 Width	ins Preclean J	Date Cleaned 2016/12/21
Material Vitrified Clay Pipe	Joint length Ft	Total length Ft	Length Surveyed 126.2 Ft
Lining	Year laid	Year rehabilitated	Weather
Purpose	Cat	Pressure	
Additional info	Reverse set up on sheet:11		<div>Structural</div> <div>O & M</div> <div>Constructional</div>
Location			<div>Miscellaneous</div> <div>Hydraulic</div>
Project Salem Utilities	Work Order		
Northing	Easting	Elevation	
Coordinate System	GPS Accuracy		

Count	Video	CD	Code	In1	In2	%	JntFr	To	ImRef	Remarks
0.0			ST Start of Survey							
0.0			AMH Manhole							SMH 2839
0.0			MWL Water Level			10				
6.7			CM Crack Multiple					09 12		
23.1			RFJ Roots Fine Joint				J 07			
33.0			JOM Joint Offset Medium							
33.2			RFJ Roots Fine Joint				J 06			
39.3			CL Crack Longitudinal					08		
67.6			RFJ Roots Fine Joint				J 09			
67.6			CL Crack Longitudinal					11		
69.5			CL Crack Longitudinal					09		
69.8			CL Crack Longitudinal					03		
71.4			RMJ Roots Medium Joint			25	J 03			
73.4			CL Crack Longitudinal					10		
73.4			CM Crack Multiple					09 03		
75.5			RMJ Roots Medium Joint			5	J 03			
77.5			RMJ Roots Medium Joint			5	J 09			
81.7			RMJ Roots Medium Joint			5	J 09			
91.4			RMJ Roots Medium Joint			5	J 09			
93.6			RMJ Roots Medium Joint			5	J 03			
95.8			RMJ Roots Medium Joint			5	J 09			
104.0			CM Crack Multiple					10 02		
104.0			RFJ Roots Fine Joint				J 03			
107.6			RMJ Roots Medium Joint			10	J 09			
113.8			RMJ Roots Medium Joint			5	J 04			
116.3			CM Crack Multiple					06 12		
124.0			RFJ Roots Fine Joint				J 03			
125.2			RBB Roots Ball Barrel			70	09			
126.2			MSA Abandoned Survey							

126.2 Ft Total Length Surveyed

Tabular Report of PSR SMH 2846 A for NECE

Setup 16	Surveyor ZC	Certificate # U-614-06021733	System Owner
Drainage	Survey Customer		
P/O #	Date 2016/12/22	Time 14:05	Street Dunlap st.
City Salem	Further location details		
Up SMH 2846	Rim to invert	Grade to invert	Rim to grade Ft
Down SMH 2839	Rim to invert	Grade to invert	Rim to grade Ft
Use	Direction Up	Flow control	Media No
Shape Circular	Height 8 Width	ins Preclean J	Date Cleaned 2016/12/21
Material Vitrified Clay Pipe	Joint length Ft	Total length 136.8 Ft	Length Surveyed 136.8 Ft
Lining	Year laid	Year rehabilitated	Weather
Purpose	Cat	Pressure	
Additional info	Reverse set up on sheet:11		<div>Structural</div> <div>O & M</div> <div>Constructional</div>
Location			<div>Miscellaneous</div> <div>Hydraulic</div>
Project Salem Utilities	Work Order		
Northing	Easting	Elevation	
Coordinate System	GPS Accuracy		

Count	Video	CD	Code	In1	In2	%	JntFr	To	ImRef	Remarks
0.0			ST Start of Survey							
0.0			AMH Manhole							SMH 2839
0.0			MWL Water Level			10				
69.4			CL Crack Longitudinal				03			
71.1			RFJ Roots Fine Joint				J 03			
73.1			CM Crack Multiple				09 12			
75.1			RFJ Roots Fine Joint				J 03			
77.3			RFJ Roots Fine Joint				J 09			
91.3			RFJ Roots Fine Joint				J 09			
93.3			RFJ Roots Fine Joint				J 02			
107.5			RFJ Roots Fine Joint				J 09			
123.6			RFJ Roots Fine Joint				J 02			
125.5			RFJ Roots Fine Joint				J 09			
129.3			RFJ Roots Fine Joint				J 02			
133.9			RFJ Roots Fine Joint				J 12			
136.8			AMH Manhole							SMH 2846
136.8			FH End of Survey							

136.8 Ft Total Length Surveyed

Scores	Structural:	Pipe Rating 5	Pipe Ratings Index 2.5	Peak 3	Mean Pipe 0
	O&M:	Pipe Rating 10	Pipe Ratings Index 1	Peak 1	Mean Pipe 0.1

Tabular Report of PSR SMH 2846A A for City of Salem

Setup 91 Surveyor CM Certificate # U-614-06021733 System Owner


Drainage	Survey Customer				
P/O #	Date	2017/03/06	Time	15:59	Street Dunlap St.
City salem	Further location details				
Start SMH 2839	Rim to invert	Grade to invert	Rim to grade	Ft	
Finish SMH 2846A	Rim to invert	Grade to invert	Rim to grade	Ft	
Use	Direction Up	Flow control	Media No		
Shape Circular	Height 8	Width ins	Preclean J	Year Cleaned 2017/03/06	
Material Vitrified Clay Pipe	Joint length	Ft	Total length 135.6	Ft	Length Surveyed 135.6
Lining	Year laid	Year rehabilitated	Weather		
Purpose	Cat	Pressure			
Additional info Reverse set up on sheet:85			<div>Structural</div> <div>O&M</div> <div>Constructional</div>		
Location			<div>Miscellaneous</div> <div>Hydraulic</div>		
Project Salem Utilities			Work Order		
Northing		Easting	Elevation		
Coordinate System		GPS Accuracy			

Count	Video	CD	Code	In1	In2	%	JntFr	To	ImRef	Remarks
0.0			ST Start of Survey							
0.0			AMH Manhole							SMH 2839
0.0			MWL Water Level			5				
69.5			CL Crack Longitudinal				03			
72.7			CM Crack Multiple				09 10			
76.9			RFJ Roots Fine Joint				J 09			
93.2			RFJ Roots Fine Joint				J 02			
107.4			RFJ Roots Fine Joint				J 09			
121.7			CL Crack Longitudinal				12			
125.3			RMJ Roots Medium Joint			5	J 09			
129.2			RMJ Roots Medium Joint			5	J 01			
133.2			CL Crack Longitudinal				03			
133.6			HSV Hole Soil Visible				12			
135.6			AMH Manhole							SMH 2846A
135.6			FH End of Survey							

135.6 Ft Total Length Surveyed

Scores

Structural:	Pipe Rating 14	Pipe Ratings Index 2.8	Peak 5	Mean Pipe 0.1
O&M:	Pipe Rating 9	Pipe Ratings Index 1.8	Peak 3	Mean Pipe 0.1




Sanitary Sewer Repair Project - Sable and Circle Hill Road Salem, MA

Thursday, August 17, 2017

0 50 100
Feet


1 inch = 100 feet



Location 17—(4-foot Repair) CIPP Spot Liner or Furnish and Install New Pipe Section



Location 18—CIPP liner (106-feet)



Location 60—(4-foot Repair) CIPP Spot Liner or Furnish and Install New Pipe Section

Tabular Report of PSR SMH2208

A for City of Salem

Setup 5 Surveyor Craig Medwid Certificate # U-213-17284 System Owner

Drainage		Survey Customer				
P/O #	Date	2016/08/03	Time	11:58	Street	sable rd
City	Salem	Further location details				
Start	SMH2208	Rim to invert	Grade to invert	Rim to grade	Ft	
Finish	SMH2209	Rim to invert	Grade to invert	Rim to grade	Ft	
Use	Sanitary	Direction	Down	Flow control	Media No	
Shape	Circular	Height	8	Width	ins	Preclean J
Material	Vitrified Clay Pipe	Joint length	Ft	Total length	88.7	Ft
Lining		Year laid		Year rehabilitated		Weather
Purpose		Cat				Pressure
Additional info				<div> <div>Structural</div> <div>O&M</div> <div>Constructional</div> </div>		
Location				<div> <div>Miscellaneous</div> <div>Hydraulic</div> </div>		
Project				witchcraft heights		
Northing				Easting		
Coordinate System				GPS Accuracy		

Count	Video	CD	Code	In1	In2	%	JntFr	To	ImRef	Remarks
0.0			ST Start of Survey							
0.0			AMH Manhole							SMH2208
0.0			MWL Water Level			5				
6.8			TF Tap Factory	6.000			03			broken
28.0			B Broken				12	12		
29.0			TF Tap Factory	6.000			03			
50.2			B Broken				11	01		
70.3			MMC Material change							pvc
82.3			TF Tap Factory	6.000			09			
88.7			AMH Manhole							SMH2209
88.7			FH End of Survey							

88.7 Ft Total Length Surveyed

Scores

Structural:	Pipe Rating 10	Pipe Ratings Index 5	Peak 5	Mean Pipe 0.1
O&M:	Pipe Rating 0	Pipe Ratings Index 0	Peak 0	Mean Pipe 0

Tabular Report of PSR SMH2209

A

for City of Salem

Setup 6

Surveyor

Craig Medwid

Certificate #

U-213-17284

System Owner

Drainage		Survey Customer			
P/O #	Date	2016/08/03	Time	12:06	Street
City	Salem	Further location details			
Start	SMH2209	Rim to invert	Grade to invert	Rim to grade	Ft
Finish	SMH2210	Rim to invert	Grade to invert	Rim to grade	Ft
Use	Sanitary	Direction	Down	Flow control	Media No
Shape	Circular	Height	8	Width	ins
Material	Vitrified Clay Pipe	Joint length	Ft	Total length	Ft
Lining		Year laid		Year rehabilitated	Weather
Purpose		Cat			Pressure
Additional info				Structural	O&M
Location				Miscellaneous	Hydraulic
Project				Witchcraft heights	Work Order
Northing				Easting	Elevation
Coordinate System				GPS Accuracy	

Count	Video	CD	Code	In1	In2	%	JntFr	To	ImRef	Remarks
0.0			ST Start of Survey							
0.0			AMH Manhole							SMH2209
0.0			MWL Water Level			5				
9.7			TB Tap Break-in	6.000				03		
10.3			HSV Hole Soil Visible					05 07		
20.0			B Broken					12 12		
20.0			FC Fracture Circumferential					12 12		
30.0			B Broken					12 12		
35.0			B Broken					12 12		
36.0			TF Tap Factory	6.000				09		
39.0			FM Fracture Multiple					12 12		
51.0			XP Collapse Pipe Sewer			50				
52.0			MSA Abandoned Survey							COLLAPSE *

52.0 Ft Total Length Surveyed

Scores

Structural:	Pipe Rating 31	Pipe Ratings Index 4.4	Peak 7	Mean Pipe 0.6
O&M:	Pipe Rating 0	Pipe Ratings Index 0	Peak 0	Mean Pipe 0

* Collapse has been repaired

Tabular Report of PSR SMH2209

A for City of Salem

Setup 11 Surveyor Craig Medwid Certificate # U-213-17284 System Owner

Drainage	Survey Customer				
P/O #	Date	2016/08/03	Time	14:12	Street
City	Salem	Further location details			
Start	SMH2210	Rim to invert	Grade to invert	Rim to grade	Ft
Finish	SMH2209	Rim to invert	Grade to invert	Rim to grade	Ft
Use	Sanitary	Direction	Up	Flow control	Media No
Shape	Circular	Height	8	Width	ins
Material	Vitrified Clay Pipe	Joint length	Ft	Total length	Ft
Lining		Year laid		Year rehabilitated	Weather
Purpose		Cat			Pressure
Additional info				Reverse set up on sheet:6	
Location				<div> <div>Structural</div> <div>Miscellaneous</div> </div> <div> <div>O&M</div> <div>Hydraulic</div> </div> <div> <div>Constructional</div> </div>	
Project				witchcraft heights	
Northing				Easting	
Coordinate System				GPS Accuracy	

Count	Video	CD	Code	In1	In2	%	JntFr	To	ImRef	Remarks
0.0			ST Start of Survey							
0.0			AMH Manhole							SMH2210
0.0			MWL Water Level			5				
9.5			FC Fracture Circumferential				12	12		
14.3			FC Fracture Circumferential				12	12		
16.2			FC Fracture Circumferential				12	12		
32.5			TF Tap Factory	6.000			03			
36.7			FC Fracture Circumferential				12	12		
43.2			B Broken				02	11		
48.2			B Broken				01	07		
51.9			B Broken				12	12		
62.6			B Broken				12	12		
69.6			TF Tap Factory	6.000			10			
75.3			B Broken				12	12		
81.3			B Broken				12	12		
96.0			XP Collapse Pipe Sewer			50				
97.0			MSA Abandoned Survey							CANNOT PASS COLLAPSE

97.0 Ft Total Length Surveyed

Scores

Structural:	Pipe Rating 43	Pipe Ratings Index 3.9	Peak 5	Mean Pipe 0.4
O&M:	Pipe Rating 0	Pipe Ratings Index 0	Peak 0	Mean Pipe 0

Tabular Report of PSR SMH2210

A

for City of Salem

Setup 17 Surveyor Craig Medwid Certificate # U-213-17284 System Owner

Drainage		Survey Customer			
P/O #	Date	2016/08/05	Time	7:56	Street
City	Salem	Further location details			
Start	SMH2210	Rim to invert	Grade to invert	Rim to grade	Ft
Finish	SMH2211	Rim to invert	Grade to invert	Rim to grade	Ft
Use	Sanitary	Direction	Down	Flow control	Media No
Shape	Circular	Height	8	Width	ins
Material	Vitrified Clay Pipe	Joint length	Ft	Total length	148.6
Lining		Year laid		Year rehabilitated	
Purpose		Cat		Weather	Pressure
Additional info				<div> <div>Structural</div> <div>O&M</div> <div>Constructional</div> </div>	
Location				<div> <div>Miscellaneous</div> <div>Hydraulic</div> </div>	
Project				witchcraft heights	
Northing				Easting	
Coordinate System				GPS Accuracy	

Count	Video	CD	Code	In1	In2	%	JntFr	To	ImRef	Remarks
0.0			ST Start of Survey							
0.0			AMH Manhole							SMH2210
0.0			MWL Water Level			5				
8.5			TF Tap Factory	6.000			03			
9.4			B Broken				12	12		
14.6			FM Fracture Multiple				12	12		
20.6			TF Tap Factory	6.000			09			
26.7			B Broken				12	12		
31.6			B Broken				12	12		
44.0			FC Fracture Circumferential				12	12		
48.8			FC Fracture Circumferential				12	12		
53.4			FC Fracture Circumferential				12	12		
62.2			B Broken				12	12		
66.9			FS Fracture Spiral				02	03		
68.1			TF Tap Factory	6.000			03			
71.0			FC Fracture Circumferential				12	12		
74.0			B Broken				12	12		
78.4			D Deformed			10				
80.6			CM Crack Multiple				12	12		
85.1			TF Tap Factory	6.000			09			
88.2			FC Fracture Circumferential				12	12		
92.9			FC Fracture Circumferential				12	12		
106.4			FM Fracture Multiple				12	12		
111.6			CM Crack Multiple				12	12		
116.5			B Broken				12	12		
127.9			CC Crack Circumferential				12	12		
133.9			FC Fracture Circumferential				12	12		
138.8			CC Crack Circumferential				12	12		
143.3			CC Crack Circumferential				12	12		
148.6			AMH Manhole							SMH2211
148.6			FH End of Survey							

Tabular Report of PSR SMH2211

A

for City of Salem

Setup 10 Surveyor Craig Medwid Certificate # U-213-17284 System Owner

Drainage		Survey Customer			
P/O #	Date	2016/08/03	Time	13:25	Street
City	salem	Further location details			
Start	SMH2222	Rim to invert	Grade to invert	Rim to grade	Ft
Finish	SMH2211	Rim to invert	Grade to invert	Rim to grade	Ft
Use	Sanitary	Direction	Up	Flow control	Media No
Shape	Circular	Height	8	Width	ins
Material	Vitrified Clay Pipe	Joint length	Ft	Total length	Ft
Lining		Year laid		Year rehabilitated	Weather
Purpose		Cat			Pressure
Additional info				<div> <div>Structural</div> <div>O&M</div> <div>Constructional</div> </div>	
Location				<div> <div>Miscellaneous</div> <div>Hydraulic</div> </div>	
Project				witchcraft heights	
Northing				Easting	
Coordinate System				GPS Accuracy	

Count	Video	CD	Code	In1	In2	%	JntFr	To	ImRef	Remarks
0.0			ST Start of Survey							
0.0			AMH Manhole							SMH2222
0.0			MWL Water Level			5				
2.8			CC Crack Circumferential				12	12		
7.9			TF Tap Factory	6.000			09			
18.9			B Broken				12	12		
35.2			TF Tap Factory	6.000			03			
40.9			FC Fracture Circumferential				12	12		
51.0			CM Crack Multiple				12	12		
59.4			FC Fracture Circumferential				12	12		
62.3			TF Tap Factory	6.000			09			
73.1			B Broken				12	12		
82.9			B Broken				12	12		
83.7			MSA Abandoned Survey							to much debris

83.7 Ft Total Length Surveyed

Scores

Structural:	Pipe Rating 23	Pipe Ratings Index 3.3	Peak 5	Mean Pipe 0.3
O&M:	Pipe Rating 0	Pipe Ratings Index 0	Peak 0	Mean Pipe 0

Tabular Report of PSR SMH2211

A

for City of Salem

Setup 18 Surveyor Craig Medwid

Certificate # U-213-17284

System Owner

Drainage		Survey Customer			
P/O #	Date	2016/08/05	Time	8:13	Street Sable RD
City	Salem	Further location details			
Start	SMH2211	Rim to invert	Grade to invert	Rim to grade	Ft
Finish	SMH2222	Rim to invert	Grade to invert	Rim to grade	Ft
Use	Sanitary	Direction	Down	Flow control	Media No
Shape	Circular	Height	8	Width	ins Preclean J
Material	Vitrified Clay Pipe	Joint length	Ft	Total length	Ft Length Surveyed 86.6
Lining		Year laid		Year rehabilitated	Weather
Purpose		Cat			Pressure
Additional info				<div> <div>Structural</div> <div>O&M</div> <div>Constructional</div> </div>	
Location				<div> <div>Miscellaneous</div> <div>Hydraulic</div> </div>	
Project witchcraft heights				Work Order	
Northing		Easting		Elevation	
Coordinate System		GPS Accuracy			

Count	Video	CD	Code	In1	In2	%	JntFr	To	ImRef	Remarks
0.0			ST Start of Survey							
0.0			AMH Manhole							SMH2211
0.0			MWL Water Level			0				
7.2			TF Tap Factory	6.000			03			
18.3			B Broken				12 12			
29.3			TF Tap Factory	6.000			09			
30.4			B Broken				12 12			
42.3			FC Fracture Circumferential				12 12			
47.1			CC Crack Circumferential				12 12			
53.4			FH4 Fracture Longitudinal Hinge, 4				12 12			
62.4			FC Fracture Circumferential				12 12			
65.5			B Broken				12 12			
75.6			B Broken				12 12			
86.6			TF Tap Factory	6.000			03			
86.6			MSA Abandoned Survey							reversal ends

86.6 Ft Total Length Surveyed

Scores

Structural:	Pipe Rating 30	Pipe Ratings Index 3.8	Peak 5	Mean Pipe 0.3
O&M:	Pipe Rating 0	Pipe Ratings Index 0	Peak 0	Mean Pipe 0

Tabular Report of PSR SMH2222 A for City of Salem
 Setup 8 Surveyor Craig Medwid Certificate # U-213-17284 System Owner

Drainage		Survey Customer			
P/O #	Date	2016/08/03	Time	12:29	Street
City	salem	Further location details			
Start	SMH2223	Rim to invert	Grade to invert	Rim to grade	Ft
Finish	SMH2222	Rim to invert	Grade to invert	Rim to grade	Ft
Use	Sanitary	Direction	Up	Flow control	Media No
Shape	Circular	Height	8	Width	ins
Material	Vitrified Clay Pipe	Joint length	Ft	Total length	98.0
Lining		Year laid		Year rehabilitated	
Purpose		Cat		Weather	Pressure
Additional info				Structural O&M Constructional Miscellaneous Hydraulic	
Location		Work Order			
Project		witchcraft heights			
Northing		Easting		Elevation	
Coordinate System		GPS Accuracy			

Count	Video	CD	Code	In1	In2	%	JntFr	To	ImRef	Remarks
0.0			ST Start of Survey							
0.0			AMH Manhole							SMH2223
0.0			MWL Water Level			5				
98.0			AMH Manhole							SMH2222
98.0			FH End of Survey							

98.0 Ft Total Length Surveyed

Scores

Structural:	Pipe Rating 0	Pipe Ratings Index 0	Peak 0	Mean Pipe 0
O&M:	Pipe Rating 0	Pipe Ratings Index 0	Peak 0	Mean Pipe 0

Tabular Report of PSR SMH2223

A for City of Salem

Setup 16 Surveyor Craig Medwid Certificate # U-213-17284 System Owner

Drainage		Survey Customer			
P/O #	Date	2016/08/05	Time	7:33	Street Sable Rd
City	Salem	Further location details			
Start	SMH2212	Rim to invert	Grade to invert	Rim to grade	Ft
Finish	SMH2223	Rim to invert	Grade to invert	Rim to grade	Ft
Use	Sanitary	Direction	Up	Flow control	Media No
Shape	Circular	Height	8	Width	ins Preclean J
Material	Vitrified Clay Pipe	Joint length	Ft	Total length	Ft Length Surveyed 7.4
Lining		Year laid	Year rehabilitated	Weather	
Purpose		Cat		Pressure	
Additional info				<div> <div>Structural</div> <div>O&M</div> <div>Constructional</div> </div>	
Location				<div> <div>Miscellaneous</div> <div>Hydraulic</div> </div>	
Project witchcraft heights				Work Order	
Northing		Easting		Elevation	
Coordinate System		GPS Accuracy			

Count	Video	CD	Code	In1	In2	%	JntFr	To	ImRef	Remarks
0.0			ST Start of Survey							
0.0			AMH Manhole							SMH2212
0.0			MWL Water Level			5				
4.0			B Broken				09	03		
7.4			MSA Abandoned Survey							cannot pass debris

7.4 Ft Total Length Surveyed

Scores

Structural:	Pipe Rating 5	Pipe Ratings Index 5	Peak 5	Mean Pipe 0.7
O&M:	Pipe Rating 0	Pipe Ratings Index 0	Peak 0	Mean Pipe 0

Tabular Report of PSR SMH2223

A

for City of Salem

Setup 19 Surveyor Craig Medwid

Certificate # U-213-17284

System Owner

Drainage		Survey Customer			
P/O #	Date 2016/08/05	Time 8:43	Street Sable RD		
City Salem	Further location details				
Start SMH2223	Rim to invert	Grade to invert	Rim to grade	Ft	
Finish SMH2212	Rim to invert	Grade to invert	Rim to grade	Ft	
Use Sanitary	Direction Down	Flow control	Media No		
Shape Circular	Height 8	Width ins	Preclean J	Year Cleaned	
Material Vitrified Clay Pipe	Joint length	Ft	Total length	Ft	Length Surveyed 91.2
Lining	Year laid	Year rehabilitated	Weather		
Purpose	Cat	Pressure			
Additional info			<div> <div>Structural</div> <div>O&M</div> <div>Constructional</div> </div>		
Location			<div> <div>Miscellaneous</div> <div>Hydraulic</div> </div>		
Project witchcraft heights			Work Order		
Northing		Easting	Elevation		
Coordinate System		GPS Accuracy			

Count	Video	CD	Code	In1	In2	%	JntFr	To	ImRef	Remarks
0.0			ST Start of Survey							
0.0			AMH Manhole							SMH2223
0.0			MWL Water Level			5				
8.3			B Broken				12	12		
13.4			B Broken				12	12		
37.0			RPPD Repair Patch Defective				12	08		brick and mortar
39.3			TF Tap Factory	6.000			03			
67.1			FC Fracture Circumferential				12	12		
84.7			B Broken				12	12		
90.8			B Broken				12	12		
91.2			MSA Abandoned Survey							reversal ends

91.2 Ft Total Length Surveyed

Scores

Structural:	Pipe Rating 26	Pipe Ratings Index 4.3	Peak 5	Mean Pipe 0.3
O&M:	Pipe Rating 0	Pipe Ratings Index 0	Peak 0	Mean Pipe 0

Tabular Report of PSR SMH2216

A

for City of Salem

Setup 21 Surveyor Craig Medwid

Certificate # U-213-17284

System Owner

Drainage		Survey Customer			
P/O #		Date	2016/08/05	Time	9:21
City	Salem	Street Circle Hill RD			
		Further location details			
Start	SMH2216	Rim to invert	Grade to invert	Rim to grade	Ft
Finish	SMH2219	Rim to invert	Grade to invert	Rim to grade	Ft
Use	Sanitary	Direction	Down	Flow control	Media No
Shape	Circular	Height	8	Width	ins
Material	Vitrified Clay Pipe	Joint length	Ft	Total length	106.3
Lining		Year laid		Year rehabilitated	
Purpose		Cat		Weather	
Additional info				Structural	O&M
Location				Miscellaneous	Hydraulic
Project		witchcraft heights		Work Order	
Northing		Easting		Elevation	
Coordinate System				GPS Accuracy	

Count	Video	CD	Code	In1	In2	%	JntFr	To	ImRef	Remarks
0.0			ST Start of Survey							
0.0			AMH Manhole							SMH2216
0.0			MWL Water Level			5				
2.3			CS Crack Spiral				08	12		
18.3			B Broken				12	12		
22.1			B Broken				03	09		
23.2			TF Tap Factory	6.000			03			
34.9			B Broken				12	12		
52.7			B Broken				12	12		
70.0			H Hole				05	07		
81.1			TF Tap Factory	6.000			03			
88.2			TF Tap Factory	6.000			09			
106.3			AMH Manhole							SMH2219
106.3			FH End of Survey							

106.3 Ft Total Length Surveyed

Scores

Structural:	Pipe Rating 27	Pipe Ratings Index 4.5	Peak 5	Mean Pipe 0.3
O&M:	Pipe Rating 0	Pipe Ratings Index 0	Peak 0	Mean Pipe 0

Tabular Report of PSR SMH2217

A

for City of Salem

Setup 20 Surveyor Craig Medwid

Certificate # U-213-17284

System Owner

Drainage		Survey Customer			
P/O #		Date 2016/08/05	Time 9:15	Street Circle Hill RD	
City Salem		Further location details			
Start SMH2217	Rim to invert	Grade to invert	Rim to grade	Ft	
Finish SMH2216	Rim to invert	Grade to invert	Rim to grade	Ft	
Use Sanitary	Direction Down	Flow control	Media No		
Shape Circular	Height 8	Width ins	Preclean J	Year Cleaned	
Material Vitrified Clay Pipe	Joint length	Ft	Total length 77.5	Ft	Length Surveyed 77.5
Lining	Year laid	Year rehabilitated	Weather		
Purpose	Cat	Pressure			
Additional info			<div> <div>Structural</div> <div>O&M</div> <div>Constructional</div> </div>		
Location			<div> <div>Miscellaneous</div> <div>Hydraulic</div> </div>		
Project witchcraft heights			Work Order		
Northing		Easting	Elevation		
Coordinate System		GPS Accuracy			

Count	Video	CD	Code	In1	In2	%	JntFr	To	ImRef	Remarks
0.0			ST Start of Survey							
0.0			AMH Manhole							SMH2217
0.0			MWL Water Level			5				
5.0			TF Tap Factory	6.000			09			
12.9			B Broken				12	12		
28.6			B Broken				12	12		
64.7			TF Tap Factory	6.000			10			
77.5			AMH Manhole							SMH2216
77.5			FH End of Survey							


77.5 Ft Total Length Surveyed

Scores

Structural:	Pipe Rating 10	Pipe Ratings Index 5	Peak 5	Mean Pipe 0.1
O&M:	Pipe Rating 0	Pipe Ratings Index 0	Peak 0	Mean Pipe 0

Maps are for graphical purposes only and do not represent a legal survey. NECE cannot assume liability for any damages caused by any errors or omissions in the data. Contractor to field verify and measure pipe size and material before bidding and beginning work.

MAP 7



Sanitary Sewer Repair Project - Wheatland Street Salem, MA

Thursday, August 17, 2017

0 20 40
Feet

1 inch = 40 feet



Tabular Report of PSR SMH 1938 A for NECE

Setup 57	Surveyor ZC	Certificate # U-614-06021733	System Owner
Drainage	Survey Customer		
P/O #	Date 2017/02/14	Time 7:29	Street Wheatland St.
City Salem	Further location details		
Up SMH 1938	Rim to invert	Grade to invert	Rim to grade Ft
Down SMH 1937	Rim to invert	Grade to invert	Rim to grade Ft
Use	Direction Up	Flow control	Media No
Shape Circular	Height 8 Width	ins Preclean N	Date Cleaned
Material Vitrified Clay Pipe	Joint length Ft	Total length 147.3 Ft	Length Surveyed 147.3 Ft
Lining	Year laid	Year rehabilitated	Weather
Purpose	Cat		Pressure
Additional info		<div> <div>Structural</div> <div>O & M</div> <div>Constructional</div> </div>	
Location		<div> <div>Miscellaneous</div> <div>Hydraulic</div> </div>	
Project Salem Utilities	Work Order		
Northing	Easting	Elevation	
Coordinate System	GPS Accuracy		

Count	Video	CD	Code	In1	In2	%	JntFr	To	ImRef	Remarks
0.0			ST Start of Survey							
0.0			AMH Manhole							SMH 1937
0.0			MWL Water Level			5				
12.6			CM Crack Multiple				07	12		
24.9			CC Crack Circumferential				06	12		
48.7			TFC Tap Factory Capped	6.000			03			
87.5			TFC Tap Factory Capped	6.000			09			
89.7			TFC Tap Factory Capped	6.000			03			
122.4			TF Tap Factory	6.000			09			
124.6			TFC Tap Factory Capped	6.000			03			
142.4			TB Tap Break-in	6.000			12			towards 3oclock
147.3			AMH Manhole							SMH 1938
147.3			FH End of Survey							










147.3 Ft Total Length Surveyed

Scores	Structural:	Pipe Rating 4	Pipe Ratings Index 2	Peak 3	Mean Pipe 0
	O&M:	Pipe Rating 0	Pipe Ratings Index 0	Peak 0	Mean Pipe 0

MAP 8

Legend

Repair Type

-  CIPP Spot Liner (3)
  Drain Manhole
  Uninspected Services
  Catchbasin
  Sanitary Service - Active
  Sewer Manhole
  Sanitary Service - Unknown if in use
  Sewer Pipes
  Sanitary Service - Capped

Services

- Uninspected Services
- Sanitary Service - Active
- Sanitary Service - Unknown if in use
- Sanitary Service - Capped



Sanitary Sewer Repair Project - Cleveland and Buchanan Road Salem, MA

Thursday, August 17, 2017

0 45 90 Feet

1 inch = 90 feet

Tabular Report of PSR SMH 3226 A for NECE

Setup 37	Surveyor ZC	Certificate # U-614-06021733	System Owner
Drainage	Survey Customer		
P/O #	Date 2016/09/22	Time 8:30	Street Grant st.
City Salem	Further location details		
Up SMH 3226	Rim to invert	Grade to invert	Rim to grade Ft
Down SMH 3225	Rim to invert	Grade to invert	Rim to grade Ft
Use	Direction Up	Flow control	Media No
Shape Circular	Height 8 Width	ins Preclean N	Date Cleaned
Material Vitrified Clay Pipe	Joint length Ft	Total length 174.1 Ft	Length Surveyed 174.1 Ft
Lining	Year laid	Year rehabilitated	Weather
Purpose	Cat	Pressure	
Additional info		<div>Structural</div> <div>O & M</div> <div>Constructional</div>	
Location		<div>Miscellaneous</div> <div>Hydraulic</div>	
Project Pre Paving Project		Work Order	
Northing		Elevation	
Coordinate System		GPS Accuracy	

Count	Video	CD	Code	In1	In2	%	JntFr	To	ImRef	Remarks
0.0			ST Start of Survey							
0.0			AMH Manhole							SMH 3225
0.0			MWL Water Level			40				
20.7			TFC Tap Factory Capped	6.000			12			
20.8			HSV Hole Soil Visible				08			
20.8			FM Fracture Multiple				07	03		
22.1			CL Crack Longitudinal				12			
52.0			JOM Joint Offset Medium							
63.0			TF Tap Factory	6.000			12			
71.1			TF Tap Factory	6.000			12			
87.0			JOM Joint Offset Medium							
96.3			JSM Joint Separated Medium							
100.5			TF Tap Factory	6.000			02			
104.1			TF Tap Factory	6.000			12			
115.3			TFC Tap Factory Capped	6.000			10			
139.0			TFC Tap Factory Capped	6.000			02			
142.7			TB Tap Break-in	6.000			02			
158.4			JSM Joint Separated Medium							
169.5			TF Tap Factory	6.000			10			
174.1			AMH Manhole							SMH 3226
174.1			FH End of Survey							

174.1 Ft Total Length Surveyed

Scores	Structural:	Pipe Rating 15	Pipe Ratings Index 2.1	Peak 9	Mean Pipe 0.1
	O&M:	Pipe Rating 0	Pipe Ratings Index 0	Peak 0	Mean Pipe 0

Tabular Report of PSR SMH 3230 A for NECE

Setup 47	Surveyor ZC	Certificate # U-614-06021733	System Owner
Drainage	Survey Customer NECE		
P/O #	Date 2016/09/27	Time 7:35	Street Buchanan Rd.
City Salem	Further location details		
Up SMH 3230	Rim to invert	Grade to invert	Rim to grade Ft
Down SMH 3231	Rim to invert	Grade to invert	Rim to grade Ft
Use Sanitary	Direction Up	Flow control	Media No
Shape Circular	Height 8 Width	ins Preclean N	Date Cleaned
Material Vitrified Clay Pipe	Joint length Ft	Total length 110.7 Ft	Length Surveyed 110.7 Ft
Lining	Year laid	Year rehabilitated	Weather
Purpose	Cat	Pressure	
Additional info		Structural	O & M
Location		Miscellaneous	Hydraulic
Project Pre Paving Project		Work Order	
Northing		Elevation	
Coordinate System		GPS Accuracy	

Count	Video	CD	Code	In1	In2	%	JntFr	To	ImRef	Remarks
0.0			ST Start of Survey							
0.0			AMH Manhole							SMH 3231
0.0			MWL Water Level			5				
4.0			HSV Hole Soil Visible				09			
4.0			BSV Broken Soil Visible				03			
4.0			IR Infil Runner				03			
4.5			TF Tap Factory	6.000			02			
20.6			TB Tap Break-in	6.000			10			
34.2			TFC Tap Factory Capped	6.000			10			roots in cap
35.5			RFJ Roots Fine Joint				J 03			
41.5			RFJ Roots Fine Joint				J 03			
41.9			CM Crack Multiple				08 10			
47.4			RFJ Roots Fine Joint				J 09 03			
50.8			RFJ Roots Fine Joint				J 08			
55.1			TB Tap Break-in	6.000			10			
85.8			TFC Tap Factory Capped	6.000			10			
98.6			TB Tap Break-in	6.000			10			
108.6			CM Crack Multiple				07 09			
109.0			CC Crack Circumferential				03 05			
110.7			AMH Manhole							SMH 3230
110.7			FH End of Survey							

110.7 Ft Total Length Surveyed

Scores	Structural:	Pipe Rating 17	Pipe Ratings Index 3.4	Peak 10	Mean Pipe 0.2
	O&M:	Pipe Rating 8	Pipe Ratings Index 1	Peak 4	Mean Pipe 0.1

Tabular Report of PSR SMH 3232 A for NECE

Setup 48	Surveyor ZC	Certificate # U-614-06021733	System Owner
Drainage	Survey Customer NECE		
P/O #	Date 2016/09/27	Time 8:13	Street Buchanan Rd.
City Salem	Further location details		
Up SMH 3232	Rim to invert	Grade to invert	Rim to grade Ft
Down SMH 3231	Rim to invert	Grade to invert	Rim to grade Ft
Use Sanitary	Direction Up	Flow control	Media No
Shape Circular	Height 8 Width	ins Preclean N	Date Cleaned
Material Vitrified Clay Pipe	Joint length Ft	Total length 96.9 Ft	Length Surveyed 96.9 Ft
Lining	Year laid	Year rehabilitated	Weather
Purpose	Cat	Pressure	
Additional info		<div>Structural</div> <div>O & M</div> <div>Constructional</div>	
Location		<div>Miscellaneous</div> <div>Hydraulic</div>	
Project Pre Paving Project		Work Order	
Northing		Elevation	
Coordinate System		GPS Accuracy	


Count	Video	CD	Code	In1	In2	%	JntFr	To	ImRef	Remarks
0.0			ST Start of Survey							
0.0			AMH Manhole							SMH 3231
0.0			MWL Water Level			10				
10.1			CC Crack Circumferential				09	12		
15.2			TFC Tap Factory Capped	6.000			02			
15.8			JSM Joint Separated Medium							
17.4			TB Tap Break-in	6.000			03			
17.8			CC Crack Circumferential				06	04		
39.8			CM Crack Multiple				06	01		
47.7			TFC Tap Factory Capped	6.000			09			
52.0			CM Crack Multiple				09	06		
52.0			JOM Joint Offset Medium							
55.6			HSV Hole Soil Visible				03			
55.6			TB Tap Break-in	6.000			09			
57.9			TB Tap Break-in	6.000			03			
76.6			JOM Joint Offset Medium							
80.7			JOM Joint Offset Medium							
84.8			JOM Joint Offset Medium							
96.9			AMH Manhole							SMH 3232
96.9			FH End of Survey							

96.9 Ft Total Length Surveyed

Scores	Structural:	Pipe Rating 18	Pipe Ratings Index 1.8	Peak 5	Mean Pipe 0.2
	O&M:	Pipe Rating 0	Pipe Ratings Index 0	Peak 0	Mean Pipe 0

Maps are for graphical purposes only and do not represent a legal survey. NECE cannot assume liability for any damages caused by any errors or omissions in the data. Contractor to field verify and measure pipe size and material before bidding and beginning work.

MAP 9




Sanitary Sewer Repair Project - Nichols and Butler Street Salem, MA

Thursday, August 17, 2017

0 40 80 Feet

1 inch = 80 feet





Location 41—(4-foot Repair) CIPP Spot Liner or Furnish and Install New Pipe Section



Location 42—(12-foot Drain Repair) CIPP Spot Liner or Furnish and Install New Pipe Section




Location 43—(4-foot Repair) CIPP Spot Liner or Furnish and Install New Pipe Section




Location 44—(4-foot Repair) CIPP Spot Liner or Furnish and Install New Pipe Section

Work Order	Setup 26	
Video	Survey Date	2016/08/16
Path to picture files	C:\FLEX6\Snaps\SALEM\	
Path to video files	C:\FLEX6\Movies\SALEM\	
Path to media files	C:\FLEX6\Media\SALEM\	



Video Index Count 48.9 Ft
 Code [Crack Multiple](#)
 Remarks
 File Name 361.jpg



Video Index Count 48.9 Ft
 Code [Crack Multiple](#)
 Remarks
 File Name 362.jpg



Video Index Count 51.3 Ft
 Code [Crack Multiple](#)
 Remarks
 File Name 363.jpg



Video Index Count 53.2 Ft
 Code [Broken Soil Visible](#)
 Remarks
 File Name 364.jpg



Video Index Count 59.5 Ft
 Code [Crack Multiple](#)
 Remarks
 File Name 365.jpg



Video Index Count 96.0 Ft
 Code [Fracture Multiple](#)
 Remarks
 File Name 366.jpg



Video Index Count 142.1 Ft
 Code [Crack Multiple](#)
 Remarks
 File Name 367.jpg

Tabular Report of PSR SMH 3071 A for NECE

Setup 26	Surveyor ZC	Certificate # U-614-06021733	System Owner
Drainage	Survey Customer		
P/O #	Date 2016/08/16	Time 12:22	Street Butler st.
City Salem	Further location details		
Up SMH 3071	Rim to invert	Grade to invert	Rim to grade Ft
Down SMH 3073	Rim to invert	Grade to invert	Rim to grade Ft
Use	Direction Down	Flow control	Media No
Shape Circular	Height 8 Width	ins Preclean N	Date Cleaned
Material Vitrified Clay Pipe	Joint length Ft	Total length 228.7 Ft	Length Surveyed 228.7 Ft
Lining	Year laid	Year rehabilitated	Weather
Purpose	Cat	Pressure	
Additional info		<div> <div>Structural</div> <div>O & M</div> <div>Constructional</div> </div>	
Location		<div> <div>Miscellaneous</div> <div>Hydraulic</div> </div>	
Project Witchcraft Heights	Work Order		
Northing	Easting	Elevation	
Coordinate System	GPS Accuracy		

Count	Video	CD	Code	In1	In2	%	JntFr	To	ImRef	Remarks
0.0			ST Start of Survey							
0.0			AMH Manhole							SMH 3071
0.0			MWL Water Level			5				
15.5			TF Tap Factory	6.000			11			
21.1			CM Crack Multiple				09	04		
22.9			CL Crack Longitudinal				09			
28.6			CM Crack Multiple				12	12		
31.0			CM Crack Multiple				09	03		
32.6			CL Crack Longitudinal				09			
35.2			CM Crack Multiple				09	03		
41.2			CM Crack Multiple				12	12		
46.0			TFC Tap Factory Capped	6.000			02			signs of activity
47.4			CH3 Crack Longitudinal Hinge, 3				09	03		
48.9			CM Crack Multiple				10	12		
51.3			CM Crack Multiple				12	04		
53.2			BSV Broken Soil Visible				06			
54.3			TF Tap Factory	6.000			11			
55.4			CM Crack Multiple				08	04		
59.5			CM Crack Multiple				08	04		
65.6			CM Crack Multiple				08	10		
65.6			HSV Hole Soil Visible				06			
67.8			CM Crack Multiple				08	04		
75.7			CM Crack Multiple				09	03		
84.6			TFC Tap Factory Capped	6.000			02			
92.1			CM Crack Multiple				02	08		
96.0			FM Fracture Multiple				09	11		
104.1			CM Crack Multiple				09	12		
104.9			TFC Tap Factory Capped	6.000			10			
106.8			TB Tap Break-in	6.000			12			
109.6			TB Tap Break-in	6.000			12			
109.6			ID Infil Dripper				12			

Tabular Report of PSR SMH 3071 A for NECE

Setup 26	Surveyor ZC	Certificate # U-614-06021733	System Owner
Drainage	Survey Customer		
P/O #	Date 2016/08/16	Time 12:22	Street Butler st.
City Salem	Further location details		
Up SMH 3071	Rim to invert	Grade to invert	Rim to grade Ft
Down SMH 3073	Rim to invert	Grade to invert	Rim to grade Ft
Use	Direction Down	Flow control	Media No
Shape Circular	Height 8 Width	ins Preclean N	Date Cleaned
Material Vitrified Clay Pipe	Joint length Ft	Total length 228.7 Ft	Length Surveyed 228.7 Ft
Lining	Year laid	Year rehabilitated	Weather
Purpose	Cat		Pressure
Additional info		<div> <div>Structural</div> <div>O & M</div> <div>Constructional</div> </div>	
Location		<div> <div>Miscellaneous</div> <div>Hydraulic</div> </div>	
Project Witchcraft Heights	Work Order		
Northing	Easting	Elevation	
Coordinate System	GPS Accuracy		

Count	Video	CD	Code	In1	In2	%	JntFr	To	ImRef	Remarks
121.4			TFC Tap Factory Capped	6.000			02			
139.6			CM Crack Multiple				09	03		
141.8			HSV Hole Soil Visible				02			
142.1			CM Crack Multiple				06	12		
142.6			TFC Tap Factory Capped	6.000			03			
146.6			TFC Tap Factory Capped	6.000			09			
170.9			TF Tap Factory	6.000			03			
177.9			FM Fracture Multiple				04	07		
189.0			TB Tap Break-in	6.000			09			
191.2			TFC Tap Factory Capped	6.000			03			
228.7			AMH Manhole							SMH 3073
228.7			FH End of Survey							

228.7 Ft Total Length Surveyed

Scores	Structural:	Pipe Rating 80	Pipe Ratings Index 3.3	Peak 8	Mean Pipe 0.3
	O&M:	Pipe Rating 3	Pipe Ratings Index 0.8	Peak 3	Mean Pipe 0

Tabular Report of PSR SMH 877 A for NECE

Setup 64	Surveyor ZC	Certificate # U-614-06021733	System Owner
Drainage	Survey Customer		
P/O #	Date 2016/08/24	Time 12:04	Street Nichols st.
City Salem	Further location details		
Up SMH 877	Rim to invert	Grade to invert	Rim to grade Ft
Down SMH 880	Rim to invert	Grade to invert	Rim to grade Ft
Use	Direction Down	Flow control	Media No
Shape Circular	Height 6 Width	ins Preclean N	Date Cleaned
Material Vitrified Clay Pipe	Joint length Ft	Total length 123.9 Ft	Length Surveyed 123.9 Ft
Lining	Year laid	Year rehabilitated	Weather
Purpose	Cat		Pressure
Additional info	Reverse set up on sheet:41	Structural	O & M
Location		Miscellaneous	Hydraulic
Project Witchcraft Heights		Work Order	
Northing	Easting	Elevation	
Coordinate System		GPS Accuracy	

Count	Video	CD	Code	In1	In2	%	JntFr	To	ImRef	Remarks
0.0			ST Start of Survey							
0.0			AMH Manhole							SMH 877
0.0			MWL Water Level			5				
11.6			JOM Joint Offset Medium							
12.6			TF Tap Factory	6.000			03			
18.9			TFC Tap Factory Capped	6.000			09			
34.6			CM Crack Multiple				11 02			
36.0			CM Crack Multiple				07 12			
63.9			TF Tap Factory	6.000			03			
70.1			TFC Tap Factory Capped	6.000			09			
70.7			TB Tap Break-in	6.000			12			
96.9			TFC Tap Factory Capped	6.000			09			
109.4			TF Tap Factory	6.000			03			
123.9			AMH Manhole							SMH 880
123.9			FH End of Survey							

123.9 Ft Total Length Surveyed

Scores	Structural:	Pipe Rating 7	Pipe Ratings Index 2.3	Peak 3	Mean Pipe 0.1
	O&M:	Pipe Rating 0	Pipe Ratings Index 0	Peak 0	Mean Pipe 0

Work Order			Setup 10
Video	Survey Date	2016/08/15	
Path to picture files	C:\FLEX6\Snaps\SALEM\		
Path to video files	C:\FLEX6\Movies\SALEM\		
Path to media files	C:\FLEX6\Media\SALEM\		



Video Index Count 77.6 Ft
Code [Fracture Multiple](#)
Remarks
File Name 338.jpg



Video Index Count 81.1 Ft
Code [Fracture Longitudinal Hinge, 4](#)
Remarks
File Name 339.jpg

Tabular Report of PSR DMH 4936 A for NECE

Setup 10	Surveyor ZC	Certificate # U-614-06021733	System Owner
Drainage	Survey Customer		
P/O #	Date 2016/08/15	Time 9:48	Street Nichols st.
City Salem	Further location details		
Up DMH 4936	Rim to invert	Grade to invert	Rim to grade Ft
Down DMH 4935	Rim to invert	Grade to invert	Rim to grade Ft
Use	Direction Down	Flow control	Media No
Shape Circular	Height 12 Width	ins Preclean N	Date Cleaned
Material Vitrified Clay Pipe	Joint length Ft	Total length 85.8 Ft	Length Surveyed 85.8 Ft
Lining	Year laid	Year rehabilitated	Weather
Purpose	Cat	Pressure	
Additional info		<div>Structural</div> <div>O & M</div> <div>Constructional</div>	
Location		<div>Miscellaneous</div> <div>Hydraulic</div>	
Project Witchcraft Heights	Work Order		
Northing	Easting	Elevation	
Coordinate System	GPS Accuracy		

Count	Video	CD	Code	In1	In2	%	JntFr	To	ImRef	Remarks
0.0			ST Start of Survey							
0.0			AMH Manhole							DMH 4936
0.0			MWL Water Level			5				
9.2			CL Crack Longitudinal				12			
17.0			OBJ Obstacle In Joint			15	J 12			pvc pipe
18.1			CL Crack Longitudinal				01			
18.5			RPP Repair Patch				11			brick
47.9			CM Crack Multiple				11	02		
49.0			CH4 Crack Longitudinal Hinge, 4				12	12		
67.6			CM Crack Multiple				11	01		
77.6			FM Fracture Multiple				12	12		
81.1			FH4 Fracture Longitudinal Hinge, 4				12	12		
85.8			AMH Manhole							DMH 4935
85.8			FH End of Survey							


85.8 Ft Total Length Surveyed

Scores	Structural:	Pipe Rating 24	Pipe Ratings Index 3	Peak 5	Mean Pipe 0.3
	O&M:	Pipe Rating 3	Pipe Ratings Index 3	Peak 3	Mean Pipe 0

Maps are for graphical purposes only and do not represent a legal survey. NECE cannot assume liability for any damages caused by any errors or omissions in the data. Contractor to field verify and measure pipe size and material before bidding and beginning work.

MAP 10

New structure installed after CCTV. Footage on CCTV will be off slightly due to new structure location.



Legend

Repair Type	Services		
CIPP Liner (2)	Sanitary Service - Active	Sewer Manhole	Drain Manhole
Sanitary Service - Unknown if in use	Rehab Planned (4)	Sewer Pipe (14)	Drain Pipe
Sanitary Service - Capped		Plugged Drain Pipe	Catchbasin

Sanitary Sewer Repair Project - Pope Street Easement Salem, MA

Wednesday, August 16, 2017

0 20 40
Feet

1 inch = 40 feet



Tabular Report of PSR SMH 904A A for City of Salem

Setup 2 Surveyor ZC Certificate # U-614-06021733 System Owner

Drainage		Survey Customer			
P/O #		Date 2015/10/16	Time 9:16	Street Proctor st.	
City Salem		Further location details			
Start	SMH 904	Rim to invert	Grade to invert	Rim to grade	Ft
Finish	SMH 904A	Rim to invert	Grade to invert	Rim to grade	Ft
Use		Direction Up	Flow control	Media No	
Shape	Circular	Height 18	Width ins	Preclean N	Year Cleaned
Material	Vitrified Clay Pipe	Joint length	Ft	Total length	Ft Length Surveyed 50.0
Lining		Year laid	Year rehabilitated	Weather	
Purpose		Cat		Pressure	
Additional info				<div> <div>Structural</div> <div>O&M</div> <div>Constructional</div> </div>	
Location				<div> <div>Miscellaneous</div> <div>Hydraulic</div> </div>	
Project Pope & Proctor				Work Order	
Northing		Easting		Elevation	
Coordinate System		GPS Accuracy			

Count	Video	CD	Code	In1	In2	%	JntFr	To	ImRef	Remarks
0.0			ST Start of Survey							
0.0			AMH Manhole							SMH 904
0.0			MWL Water Level			10				
14.6			RFJ Roots Fine Joint				J 08			
28.1			MWL Water Level			25				
34.2			IS Infil Stain				03			
48.7			CL Crack Longitudinal				08			
49.3			FL Fracture Longitudinal				12			
50.0			FL Fracture Longitudinal				12			
50.0			MGO General Observation							possible hole or cap at 12ocl...
50.0			MSA Abandoned Survey							

50.0 Ft Total Length Surveyed

Scores

Structural:	Pipe Rating 8	Pipe Ratings Index 2.7	Peak 3	Mean Pipe 0.2
O&M:	Pipe Rating 1	Pipe Ratings Index 0.5	Peak 1	Mean Pipe 0

Tabular Report of PSR SMH 904B

A

for City of Salem

Setup 3 Surveyor ZC

Certificate # U-614-06021733 System Owner

Drainage		Survey Customer			
P/O #	Date	2015/10/16	Time	10:09	Street Pope st.
City	Salem	Further location details			
Start	SMH 904	Rim to invert	Grade to invert	Rim to grade	Ft
Finish	SMH 904B	Rim to invert	Grade to invert	Rim to grade	Ft
Use	Direction	Up	Flow control	Media No	
Shape	Circular	Height 12	Width ins	Preclean N	Year Cleaned
Material	Vitrified Clay Pipe	Joint length	Ft	Total length	Ft Length Surveyed 36.2
Lining	Year laid	Year rehabilitated	Weather		
Purpose	Cat			Pressure	
Additional info			<div> <div>Structural</div> <div>O&M</div> <div>Constructional</div> </div>		
Location			<div> <div>Miscellaneous</div> <div>Hydraulic</div> </div>		
Project Pope & Proctor			Work Order		
Northing		Easting	Elevation		
Coordinate System		GPS Accuracy			

Count	Video	CD	Code	In1	In2	%	JntFr	To	ImRef	Remarks
0.0			ST Start of Survey							
0.0			AMH Manhole							SMH 904
0.0			MWL Water Level			5				
27.7			TB Tap Break-in	6.000			09			
29.5			TB Tap Break-in	6.000			10			
30.6			RMJ Roots Medium Joint			10	J 09			
36.2			MSA Abandoned Survey							

36.2 Ft Total Length Surveyed

Scores

Structural:	Pipe Rating 0	Pipe Ratings Index 0	Peak 0	Mean Pipe 0
O&M:	Pipe Rating 3	Pipe Ratings Index 1	Peak 3	Mean Pipe 0.1

Tabular Report of PSR SMH 911

A

for City of Salem

Setup 4 Surveyor ZC

Certificate # U-614-06021733 System Owner

Drainage		Survey Customer				
P/O #	Date	2015/10/16	Time	12:14	Street	Pope st.
City	Salem	Further location details				
Start	SMH 904	Rim to invert	Grade to invert	Rim to grade	Ft	
Finish	SMH 911	Rim to invert	Grade to invert	Rim to grade	Ft	
Use		Direction	Up	Flow control	Media No	
Shape	Circular	Height	12	Width	ins	Preclean N
Material	Vitrified Clay Pipe	Joint length	Ft	Total length	142.0	Ft
Lining		Year laid		Year rehabilitated		Weather
Purpose		Cat				Pressure
Additional info				<div> <div>Structural</div> <div>O&M</div> <div>Constructional</div> </div>		
Location				<div> <div>Miscellaneous</div> <div>Hydraulic</div> </div>		
Project				Pope & Proctor		
Northing				Easting		
Coordinate System				GPS Accuracy		
				Work Order		

Count	Video	CD	Code	In1	In2	%	JntFr	To	ImRef	Remarks
0.0			ST Start of Survey							
0.0			AMH Manhole							SMH 904
0.0			MWL Water Level			5				
25.0			IS Infil Stain				03			
27.0			IS Infil Stain				08			
29.4			IS Infil Stain				02			
31.5			IS Infil Stain				08			
39.1			TFC Tap Factory Capped	6.000			02			
41.8			IS Infil Stain				08			
48.1			IS Infil Stain				09			
50.1			IS Infil Stain				09			
52.2			IS Infil Stain				09			
52.2			IS Infil Stain				03			
54.4			IS Infil Stain				04			
56.2			IS Infil Stain				08			
58.4			IS Infil Stain				12			
68.6			IS Infil Stain				12			
70.9			IS Infil Stain				10			
72.8			IS Infil Stain				03			
78.6			RMJ Roots Medium Joint			10	J 03			
88.2			RMJ Roots Medium Joint			5	J 12			
94.9			TFC Tap Factory Capped	6.000			02			
123.9			TF Tap Factory	6.000			09			
133.9			TFC Tap Factory Capped	6.000			03			
142.0			AMH Manhole							SMH 911
142.0			FH End of Survey							

142.0 Ft Total Length Surveyed

Scores

Structural:	Pipe Rating 0	Pipe Ratings Index 0	Peak 0	Mean Pipe 0
O&M:	Pipe Rating 6	Pipe Ratings Index 0.4	Peak 3	Mean Pipe 0

Tabular Report of PSR SMH 2484

A

for City of Salem

Setup 1 Surveyor ZC

Certificate # U-614-06021733 System Owner

Drainage		Survey Customer			
P/O #	Date	2015/10/16	Time	8:24	Street
City	Salem	Further location details			
Start	SMH 2484	Rim to invert	Grade to invert	Rim to grade	Ft
Finish	SMH 904A	Rim to invert	Grade to invert	Rim to grade	Ft
Use	Direction	Down	Flow control	Media No	
Shape	Circular	Height	18	Width	ins
Material	Vitrified Clay Pipe	Joint length	Ft	Total length	119.8
Lining	Year laid	Year rehabilitated	Weather	Length Surveyed	119.8
Purpose	Cat			Pressure	
Additional info			<div> <div>Structural</div> <div>O&M</div> <div>Constructional</div> </div>		
Location			<div> <div>Miscellaneous</div> <div>Hydraulic</div> </div>		
Project			Work Order		
Northing			Elevation		
Coordinate System			GPS Accuracy		

Count	Video	CD	Code	In1	In2	%	JntFr	To	ImRef	Remarks
0.0			ST Start of Survey							
0.0			AMH Manhole							SMH 2484
0.0			MWL Water Level			10				
18.1			CM Crack Multiple				11	03		
18.1			MMC Material change							clay
21.9			CL Crack Longitudinal				12			
29.4			ID Infil Dripper				01			
35.0			IS Infil Stain				03			
37.2			IS Infil Stain				03			
39.8			IS Infil Stain				03			
41.5		S01	IS Infil Stain				03			
45.3			IS Infil Stain				03			
55.1			IS Infil Stain				03			
66.2			ID Infil Dripper				11			
103.0			CM Crack Multiple				11	02		
103.0			RFJ Roots Fine Joint				J 12			
105.1			CM Crack Multiple				01	03		
106.2			CL Crack Longitudinal				12			
108.8			CL Crack Longitudinal				03			
108.8			IS Infil Stain				03			
108.8		F01	IS Infil Stain				03			
110.5			CM Crack Multiple				09	03		
112.4			MWL Water Level			50				
113.3			CM Crack Multiple				11	02		
116.8			MWL Water Level			80				
119.8			AMH Manhole							SMH 904
119.8			FH End of Survey							

119.8 Ft Total Length Surveyed

Scores

Structural:	Pipe Rating 21	Pipe Ratings Index 2.6	Peak 3	Mean Pipe 0.2
O&M:	Pipe Rating 7	Pipe Ratings Index 0.3	Peak 3	Mean Pipe 0.1

Legend

Repair Type

- CIPP Spot Liner (1)
- SMH Rebuild (1)


Services

- Sanitary Service - Unknown if in use
- Sanitary Service - Capped

- Sewer Manhole
- Sewer Pipe (20)
- Drain Manhole
- Catchbasin
- Drain Pipe

Maps are for graphical purposes only and do not represent a legal survey. NECE cannot assume liability for any damages caused by any errors or omissions in the data. Contractor to field verify and measure pipe size and material before bidding and beginning work.

MAP 11



Sanitary Sewer Repair Project - Washington Street Salem, MA

Thursday, August 17, 2017

0 15 30
Feet

1 inch = 30 feet



Tabular Report of PSR SMH 4047 X for NECE

Setup	2	Surveyor	JAW	Certificate #	U-105-597	System Owner
Drainage		Survey Customer	NECE			
P/O #		Date	2015/11/13	Time	10:41	Street
City	Salem	Further location details				
Up	SMH 4047	Rim to invert		Grade to invert		Rim to grade
Down	SMH 289	Rim to invert		Grade to invert		Rim to grade
Use		Direction	Down	Flow control		Media No
Shape	Circular	Height	12	Width	ins	Preclean J
Material	Vitrified Clay Pipe	Joint length	Ft	Total length	Ft	Date Cleaned
Lining		Year laid		Year rehabilitated		Length Surveyed
Purpose		Cat				Weather
Additional info	Reverse set up on sheet:1				<div>Structural</div> <div>O & M</div> <div>Constructional</div>	
Location					<div>Miscellaneous</div> <div>Hydraulic</div>	
Project	Salem siphons					Work Order
Northing		Easting				Elevation
Coordinate System					GPS Accuracy	

Count	Video	CD	Code	In1	In2	%	JntFr	To	ImRef	Remarks
0.0			ST Start of Survey							
0.0			AMH Manhole							SMH 4047
0.0			MWL Water Level			60				
6.9			FM Fracture Multiple				J	09	03	
9.8			JSM Joint Separated Medium							
22.7			MWLS Water Level Sag			100				
57.5			MWL Water Level			10				
109.2			TFC Tap Factory Capped	6.000				10		
118.5			TF Tap Factory	6.000				09		
134.8			MMC Material change							CMP
134.8			MSA Abandoned Survey							No bottom on cmp, crushed hor...

134.8 Ft Total Length Surveyed

Scores	Structural:	Pipe Rating 9	Pipe Ratings Index 3	Peak 4	Mean Pipe 0.1
	O&M:	Pipe Rating 0	Pipe Ratings Index 0	Peak 0	Mean Pipe 0

Tabular Report of PSR SMH 4047 X for NECE

Setup 1	Surveyor JAW	Certificate # U-105-597	System Owner
Drainage	Survey Customer NECE		
P/O #	Date 2015/11/13	Time 9:58	Street Washington St.
City Salem	Further location details		
Up SMH 4047	Rim to invert	Grade to invert	Rim to grade Ft
Down SMH 289	Rim to invert	Grade to invert	Rim to grade Ft
Use	Direction Up	Flow control	Media No
Shape Circular	Height 12 Width	ins Preclean J	Date Cleaned 2015/11/13
Material Vitrified Clay Pipe	Joint length Ft	Total length Ft	Length Surveyed 35.0 Ft
Lining	Year laid	Year rehabilitated	Weather
Purpose	Cat	Pressure	
Additional info		<div> <div>Structural</div> <div>O & M</div> <div>Constructional</div> </div>	
Location		<div> <div>Miscellaneous</div> <div>Hydraulic</div> </div>	
Project Salem siphons	Work Order		
Northing	Easting	Elevation	
Coordinate System	GPS Accuracy		


Count	Video	CD	Code	In1	In2	%	JntFr	To	ImRef	Remarks
0.0			ST Start of Survey							
0.0			AMH Manhole							SMH 289
0.0			MWL Water Level			10				
31.0			MMC Material change							CMP
31.0			HSV Hole Soil Visible				J 06			
35.0			MSA Abandoned Survey							No bottom to cmp

35.0 Ft Total Length Surveyed

Scores	Structural:	Pipe Rating 5	Pipe Ratings Index 5	Peak 5	Mean Pipe 0.1
	O&M:	Pipe Rating 0	Pipe Ratings Index 0	Peak 0	Mean Pipe 0

Maps are for graphical purposes only and do not represent a legal survey. NECE cannot assume liability for any damages caused by any errors or omissions in the data. Contractor to field verify and measure pipe size and material before bidding and beginning work.

MAP 12



Sanitary Sewer Repair Project - Buena Vista Avenue (Cross Country Sewer) Salem, MA


Thursday, August 17, 2017

0 60 120 Feet


1 inch = 120 feet



Work Order			Setup 204
Video	Survey Date	2017/07/27	
Path to picture files	F:\Snaps\SALEM 2\		
Path to video files	F:\Movies\SALEM 2\		
Path to media files	F:\Media\SALEM 2\		



Video Index Count 86.7 Ft
 Code **Infil Gusher**
 Remarks
 File Name 386.jpg



Video Index Count 86.7 Ft
 Code **Infil Gusher**
 Remarks
 File Name 387.jpg



Video Index Count 87.6 Ft
 Code **Crack Longitudinal**
 Remarks
 File Name 388.jpg

Tabular Report of PSR SMH 1830A C for NECE

Setup 204	Surveyed By ZC	Certificate # 614-06021733	Owner
Reviewed By	Reviewer #	Work Order	
Customer		P/O #	
Media Label	Project Salem Utilities		
Date 2017/07/27	Time 13:25	Weather	Pre-Cleaning N
Flow control	Survey Purpose		Date Cleaned 2017/02/28
Inspection Status	Complete Inspection	Consequence Of Failure	Pressure
Inspection Technology Used	<input checked="" type="checkbox"/> CCTV <input type="checkbox"/> Laser <input type="checkbox"/> Sonar <input type="checkbox"/> Sidewall <input type="checkbox"/> Zoom <input type="checkbox"/> Other		
Street Mooney Rd. Easement	City Salem	Drainage area	
Location Code		Pipe Use	Sanitary Sewage Pipe
Location details		Height 18	Width ins
Shape Circular	Material Asbestos Cement	Lining	
Coating	Pipe Joint length	Ft	Total length 127.4 Ft
Length Surveyed	127.4 Ft	Year Constructed	Year Renewed
Up SMH 1830A	Rim to invert	Grade to invert	Rim to grade Ft
Northing	Easting	Elevation	
Down SMH 1831	Rim to invert	Grade to invert	Rim to grade Ft
Northing	Easting	Elevation	
Coordinate System	Vertical Datum		
GPS Accuracy	<div> Structural O & M </div>		
Additional info	<div> Miscellaneous Constructional </div>		

Count	Video	CD	Code	Val1	Val2	%	Jnt	Fr	To	ImRef	Remarks
0.0			ST Start of Survey								
0.0			AMH Manhole								SMH 1831
0.0			MWL Miscellaneous Water Level			10.000					
83.9			CL Crack Longitudinal					12			
86.7			IG Infil Gusher					03			
87.6			CL Crack Longitudinal					12			
127.4			AMH Manhole								SMH 1830
127.4			FH End of Survey								

127.4 Ft Total Length Surveyed

Scores	Structural:	Pipe Rating 4	Pipe Ratings Index 2	Quick Rating 2200
	O&M:	Pipe Rating 5	Pipe Ratings Index 5	Quick Rating 5100
	Overall	Pipe Rating 9	Pipe Ratings Index 7	Quick Rating 5122



CHARLES D. BAKER
Governor

KARYN E. POLITO
Lt. Governor

THE COMMONWEALTH OF MASSACHUSETTS
EXECUTIVE OFFICE OF LABOR AND WORKFORCE DEVELOPMENT
DEPARTMENT OF LABOR STANDARDS

Prevailing Wage Rates

As determined by the Director under the provisions of the
Massachusetts General Laws, Chapter 149, Sections 26 to 27H

ROSALIN ACOSTA
Secretary
WILLIAM D MCKINNEY
Director

Awarding Authority: City of Salem

Contract Number: **City/Town:** SALEM

Description of Work: T-09 Sewer Rehabilitation Project is for sewer rehabilitation including cured-in-place pipe lining, manhole reconstruction and waterproofing, and sewer pipe replacement and spot repairs.

Job Location: Various locations within city streets & easements

Information about Prevailing Wage Schedules for Awarding Authorities and Contractors

- This wage schedule applies only to the specific project referenced at the top of this page and uniquely identified by the "Wage Request Number" on all pages of this schedule.
- An Awarding Authority must request an updated wage schedule from the Department of Labor Standards ("DLS") if it has not opened bids or selected a contractor within 90 days of the date of issuance of the wage schedule. For CM AT RISK projects (bid pursuant to G.L. c.149A), the earlier of: (a) the execution date of the GMP Amendment, or (b) the bid for the first construction scope of work must be within 90-days of the wage schedule issuance date.
- The wage schedule shall be incorporated in any advertisement or call for bids for the project as required by M.G.L. c. 149, § 27. The wage schedule shall be made a part of the contract awarded for the project. The wage schedule must be posted in a conspicuous place at the work site for the life of the project in accordance with M.G.L. c. 149 § 27. The wages listed on the wage schedule must be paid to employees performing construction work on the project whether they are employed by the prime contractor, a filed sub-bidder, or any sub-contractor.
- All apprentices working on the project are required to be registered with the Massachusetts Department of Labor Standards, Division of Apprentice Standards (DLS/DAS). Apprentice must keep his/her apprentice identification card on his/her person during all work hours on the project. An apprentice registered with DAS may be paid the lower apprentice wage rate at the applicable step as provided on the prevailing wage schedule. **Any apprentice not registered with DLS/DAS regardless of whether or not they are registered with any other federal, state, local, or private agency must be paid the journeyworker's rate for the trade.**
- The wage rates will remain in effect for the duration of the project, except in the case of multi-year public construction projects. For construction projects lasting longer than one year, awarding authorities must request an updated wage schedule. Awarding authorities are required to request these updates no later than two weeks before the anniversary of the date the contract was executed by the awarding authority and the general contractor. For multi-year CM AT RISK projects, awarding authority must request an annual update no later than two weeks before the anniversary date, determined as the earlier of: (a) the execution date of the GMP Amendment, or (b) the execution date of the first amendment to permit procurement of construction services. Contractors are required to obtain the wage schedules from awarding authorities, and to pay no less than these rates to covered workers. The annual update requirement is not applicable to 27F "rental of equipment" contracts.
- Every contractor or subcontractor which performs construction work on the project is required to submit weekly payroll reports and a Statement of Compliance directly to the awarding authority by mail or email and keep them on file for three years. Each weekly payroll report must contain: the employee's name, address, occupational classification, hours worked, and wages paid. Do not submit weekly payroll reports to DLS. A sample of a payroll reporting form may be obtained at <http://www.mass.gov/dols/pw>.
- Contractors with questions about the wage rates or classifications included on the wage schedule have an affirmative obligation to inquire with DLS at (617) 626-6953.
- Employees not receiving the prevailing wage rate set forth on the wage schedule may report the violation to the Fair Labor Division of the office of the Attorney General at (617) 727-3465.
- Failure of a contractor or subcontractor to pay the prevailing wage rates listed on the wage schedule to all employees who perform construction work on the project is a violation of the law and subjects the contractor or subcontractor to civil and

Classification	Effective Date	Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
Construction						
(2 AXLE) DRIVER - EQUIPMENT <i>TEAMSTERS JOINT COUNCIL NO. 10 ZONE B</i>	12/01/2016	\$32.15	\$10.91	\$10.89	\$0.00	\$53.95
(3 AXLE) DRIVER - EQUIPMENT <i>TEAMSTERS JOINT COUNCIL NO. 10 ZONE B</i>	12/01/2016	\$32.22	\$10.91	\$10.89	\$0.00	\$54.02
(4 & 5 AXLE) DRIVER - EQUIPMENT <i>TEAMSTERS JOINT COUNCIL NO. 10 ZONE B</i>	12/01/2016	\$32.34	\$10.91	\$10.89	\$0.00	\$54.14
ADS/SUBMERSIBLE PILOT <i>PILE DRIVER LOCAL 56 (ZONE 1)</i>	08/01/2015	\$88.29	\$9.80	\$19.23	\$0.00	\$117.32
For apprentice rates see "Apprentice- PILE DRIVER"						
AIR TRACK OPERATOR <i>LABORERS - ZONE 2</i>	06/01/2017	\$33.15	\$7.60	\$13.50	\$0.00	\$54.25
	12/01/2017	\$33.78	\$7.60	\$13.50	\$0.00	\$54.88
	06/01/2018	\$34.62	\$7.60	\$13.50	\$0.00	\$55.72
	12/01/2018	\$35.46	\$7.60	\$13.50	\$0.00	\$56.56
	06/01/2019	\$36.33	\$7.60	\$13.50	\$0.00	\$57.43
	12/01/2019	\$37.19	\$7.60	\$13.50	\$0.00	\$58.29
For apprentice rates see "Apprentice- LABORER"						
ASBESTOS REMOVER - PIPE / MECH. EQUIPT. <i>HEAT & FROST INSULATORS LOCAL 6 (BOSTON)</i>	06/01/2017	\$34.90	\$11.50	\$7.10	\$0.00	\$53.50
	12/01/2017	\$35.90	\$11.50	\$7.10	\$0.00	\$54.50
	06/01/2018	\$36.90	\$11.50	\$7.10	\$0.00	\$55.50
	12/01/2018	\$37.90	\$11.50	\$7.10	\$0.00	\$56.50
	06/01/2019	\$38.90	\$11.50	\$7.10	\$0.00	\$57.50
	12/01/2019	\$39.90	\$11.50	\$7.10	\$0.00	\$58.50
	06/01/2020	\$40.90	\$11.50	\$7.10	\$0.00	\$59.50
	12/01/2020	\$41.90	\$11.50	\$7.10	\$0.00	\$60.50
ASPHALT RAKER <i>LABORERS - ZONE 2</i>	06/01/2017	\$32.65	\$7.60	\$13.50	\$0.00	\$53.75
	12/01/2017	\$33.28	\$7.60	\$13.50	\$0.00	\$54.38
	06/01/2018	\$34.12	\$7.60	\$13.50	\$0.00	\$55.22
	12/01/2018	\$34.96	\$7.60	\$13.50	\$0.00	\$56.06
	06/01/2019	\$35.83	\$7.60	\$13.50	\$0.00	\$56.93
	12/01/2019	\$36.69	\$7.60	\$13.50	\$0.00	\$57.79
For apprentice rates see "Apprentice- LABORER"						
ASPHALT/CONCRETE/CRUSHER PLANT-ON SITE <i>OPERATING ENGINEERS LOCAL 4</i>	06/01/2017	\$46.38	\$10.00	\$15.25	\$0.00	\$71.63
	12/01/2017	\$47.38	\$10.00	\$15.25	\$0.00	\$72.63
For apprentice rates see "Apprentice- OPERATING ENGINEERS"						
BACKHOE/FRONT-END LOADER <i>OPERATING ENGINEERS LOCAL 4</i>	06/01/2017	\$46.38	\$10.00	\$15.25	\$0.00	\$71.63
	12/01/2017	\$47.38	\$10.00	\$15.25	\$0.00	\$72.63
For apprentice rates see "Apprentice- OPERATING ENGINEERS"						
BARCO-TYPE JUMPING TAMPER <i>LABORERS - ZONE 2</i>	06/01/2017	\$32.65	\$7.60	\$13.50	\$0.00	\$53.75
	12/01/2017	\$33.28	\$7.60	\$13.50	\$0.00	\$54.38
	06/01/2018	\$34.12	\$7.60	\$13.50	\$0.00	\$55.22
	12/01/2018	\$34.96	\$7.60	\$13.50	\$0.00	\$56.06
	06/01/2019	\$35.83	\$7.60	\$13.50	\$0.00	\$56.93
	12/01/2019	\$36.69	\$7.60	\$13.50	\$0.00	\$57.79
For apprentice rates see "Apprentice- LABORER"						

Classification	Effective Date	Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
BLOCK PAVER, RAMMER / CURB SETTER <i>LABORERS - ZONE 2</i>	06/01/2017	\$33.15	\$7.60	\$13.50	\$0.00	\$54.25
	12/01/2017	\$33.78	\$7.60	\$13.50	\$0.00	\$54.88
	06/01/2018	\$34.62	\$7.60	\$13.50	\$0.00	\$55.72
	12/01/2018	\$35.46	\$7.60	\$13.50	\$0.00	\$56.56
	06/01/2019	\$36.33	\$7.60	\$13.50	\$0.00	\$57.43
	12/01/2019	\$37.19	\$7.60	\$13.50	\$0.00	\$58.29

For apprentice rates see "Apprentice- LABORER"

BOILER MAKER <i>BOILERMAKERS LOCAL 29</i>	01/01/2017	\$42.92	\$6.97	\$16.21	\$0.00	\$66.10
--	------------	---------	--------	---------	--------	---------

Apprentice - *BOILERMAKER - Local 29*

Effective Date - 01/01/2017

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	65	\$27.90	\$6.97	\$10.54	\$0.00	\$45.41
2	65	\$27.90	\$6.97	\$10.54	\$0.00	\$45.41
3	70	\$30.04	\$6.97	\$11.35	\$0.00	\$48.36
4	75	\$32.19	\$6.97	\$12.16	\$0.00	\$51.32
5	80	\$34.34	\$6.97	\$12.97	\$0.00	\$54.28
6	85	\$36.48	\$6.97	\$13.78	\$0.00	\$57.23
7	90	\$38.63	\$6.97	\$14.59	\$0.00	\$60.19
8	95	\$40.77	\$6.97	\$15.40	\$0.00	\$63.14

Notes:

Apprentice to Journeyworker Ratio:1:5

BRICK/STONE/ARTIFICIAL MASONRY (INCL. MASONRY WATERPROOFING) <i>BRICKLAYERS LOCAL 3 (LYNN)</i>	08/01/2017	\$52.06	\$10.75	\$19.35	\$0.00	\$82.16
	02/01/2018	\$52.74	\$10.75	\$19.35	\$0.00	\$82.84
	08/01/2018	\$54.09	\$10.75	\$19.48	\$0.00	\$84.32
	02/01/2019	\$54.73	\$10.75	\$19.48	\$0.00	\$84.96
	08/01/2019	\$56.08	\$10.75	\$19.62	\$0.00	\$86.45
	02/01/2020	\$56.72	\$10.75	\$19.62	\$0.00	\$87.09
	08/01/2020	\$58.07	\$10.75	\$19.77	\$0.00	\$88.59
	02/01/2021	\$58.71	\$10.75	\$19.77	\$0.00	\$89.23
	08/01/2021	\$60.11	\$10.75	\$19.93	\$0.00	\$90.79
	02/01/2022	\$60.70	\$10.75	\$19.93	\$0.00	\$91.38

Classification	Effective Date	Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
----------------	----------------	-----------	--------	---------	------------------------------	------------

Apprentice - BRICK/PLASTER/CEMENT MASON - Local 3 Lynn

Effective Date - 08/01/2017

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	50	\$26.03	\$10.75	\$19.35	\$0.00	\$56.13
2	60	\$31.24	\$10.75	\$19.35	\$0.00	\$61.34
3	70	\$36.44	\$10.75	\$19.35	\$0.00	\$66.54
4	80	\$41.65	\$10.75	\$19.35	\$0.00	\$71.75
5	90	\$46.85	\$10.75	\$19.35	\$0.00	\$76.95

Effective Date - 02/01/2018

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	50	\$26.37	\$10.75	\$19.35	\$0.00	\$56.47
2	60	\$31.64	\$10.75	\$19.35	\$0.00	\$61.74
3	70	\$36.92	\$10.75	\$19.35	\$0.00	\$67.02
4	80	\$42.19	\$10.75	\$19.35	\$0.00	\$72.29
5	90	\$47.47	\$10.75	\$19.35	\$0.00	\$77.57

Notes:

Apprentice to Journeyworker Ratio:1:5

BULLDOZER/GRADER/SCRAPER <i>OPERATING ENGINEERS LOCAL 4</i>	06/01/2017	\$45.93	\$10.00	\$15.25	\$0.00	\$71.18
For apprentice rates see "Apprentice- OPERATING ENGINEERS"	12/01/2017	\$46.92	\$10.00	\$15.25	\$0.00	\$72.17
CAISSON & UNDERPINNING BOTTOM MAN <i>LABORERS - FOUNDATION AND MARINE</i>	12/01/2016	\$37.45	\$7.60	\$14.35	\$0.00	\$59.40
For apprentice rates see "Apprentice- LABORER"						
CAISSON & UNDERPINNING LABORER <i>LABORERS - FOUNDATION AND MARINE</i>	12/01/2016	\$36.30	\$7.60	\$14.35	\$0.00	\$58.25
For apprentice rates see "Apprentice- LABORER"						
CAISSON & UNDERPINNING TOP MAN <i>LABORERS - FOUNDATION AND MARINE</i>	12/01/2016	\$36.30	\$7.60	\$14.35	\$0.00	\$58.25
For apprentice rates see "Apprentice- LABORER"						
CARBIDE CORE DRILL OPERATOR <i>LABORERS - ZONE 2</i>	06/01/2017	\$32.65	\$7.60	\$13.50	\$0.00	\$53.75
	12/01/2017	\$33.28	\$7.60	\$13.50	\$0.00	\$54.38
	06/01/2018	\$34.12	\$7.60	\$13.50	\$0.00	\$55.22
	12/01/2018	\$34.96	\$7.60	\$13.50	\$0.00	\$56.06
	06/01/2019	\$35.83	\$7.60	\$13.50	\$0.00	\$56.93
	12/01/2019	\$36.69	\$7.60	\$13.50	\$0.00	\$57.79
For apprentice rates see "Apprentice- LABORER"						
CARPENTER <i>CARPENTERS -ZONE 2 (Eastern Massachusetts)</i>	03/01/2017	\$38.77	\$9.90	\$17.00	\$0.00	\$65.67
	09/01/2017	\$39.28	\$9.90	\$17.50	\$0.00	\$66.68
	03/01/2018	\$40.28	\$9.90	\$17.50	\$0.00	\$67.68
	09/01/2018	\$41.32	\$9.90	\$17.50	\$0.00	\$68.72
	03/01/2019	\$42.35	\$9.90	\$17.50	\$0.00	\$69.75

Classification

Effective Date Base Wage Health Pension Supplemental Unemployment Total Rate

Apprentice - CARPENTER - Zone 2 Eastern MA

Effective Date - 03/01/2017

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	50	\$19.39	\$9.90	\$1.68	\$0.00	\$30.97
2	60	\$23.26	\$9.90	\$1.68	\$0.00	\$34.84
3	70	\$27.14	\$9.90	\$12.21	\$0.00	\$49.25
4	75	\$29.08	\$9.90	\$12.21	\$0.00	\$51.19
5	80	\$31.02	\$9.90	\$13.89	\$0.00	\$54.81
6	80	\$31.02	\$9.90	\$13.89	\$0.00	\$54.81
7	90	\$34.89	\$9.90	\$15.57	\$0.00	\$60.36
8	90	\$34.89	\$9.90	\$15.57	\$0.00	\$60.36

Effective Date - 09/01/2017

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	50	\$19.64	\$9.90	\$1.73	\$0.00	\$31.27
2	60	\$23.57	\$9.90	\$1.73	\$0.00	\$35.20
3	70	\$27.50	\$9.90	\$12.31	\$0.00	\$49.71
4	75	\$29.46	\$9.90	\$12.31	\$0.00	\$51.67
5	80	\$31.42	\$9.90	\$14.04	\$0.00	\$55.36
6	80	\$31.42	\$9.90	\$14.04	\$0.00	\$55.36
7	90	\$35.35	\$9.90	\$15.77	\$0.00	\$61.02
8	90	\$35.35	\$9.90	\$15.77	\$0.00	\$61.02

Notes:

Apprentice to Journeyworker Ratio:1:5

CEMENT MASONRY/PLASTERING
BRICKLAYERS LOCAL 3 (LYNN)

07/01/2017	\$47.40	\$12.20	\$19.41	\$1.30	\$80.31
01/01/2018	\$48.17	\$12.20	\$19.41	\$1.30	\$81.08
07/01/2018	\$49.56	\$12.20	\$19.41	\$1.30	\$82.47
01/01/2019	\$50.30	\$12.20	\$19.41	\$1.30	\$83.21
07/01/2019	\$51.69	\$12.20	\$19.41	\$1.30	\$84.60
01/01/2020	\$52.44	\$12.20	\$19.41	\$1.30	\$85.35

Classification
Effective Date
Base Wage
Health
Pension
**Supplemental
Unemployment**
Total Rate
Apprentice - CEMENT MASONRY/PLASTERING - Eastern Mass (Lynn)
Effective Date - 07/01/2017

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	50	\$23.70	\$12.20	\$12.41	\$0.00	\$48.31
2	60	\$28.44	\$12.20	\$14.41	\$1.30	\$56.35
3	65	\$30.81	\$12.20	\$15.41	\$1.30	\$59.72
4	70	\$33.18	\$12.20	\$16.41	\$1.30	\$63.09
5	75	\$35.55	\$12.20	\$17.41	\$1.30	\$66.46
6	80	\$37.92	\$12.20	\$18.41	\$1.30	\$69.83
7	90	\$42.66	\$12.20	\$19.41	\$1.30	\$75.57

Effective Date - 01/01/2018

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	50	\$24.09	\$12.20	\$12.41	\$0.00	\$48.70
2	60	\$28.90	\$12.20	\$14.41	\$1.30	\$56.81
3	65	\$31.31	\$12.20	\$15.41	\$1.30	\$60.22
4	70	\$33.72	\$12.20	\$16.41	\$1.30	\$63.63
5	75	\$36.13	\$12.20	\$17.41	\$1.30	\$67.04
6	80	\$38.54	\$12.20	\$18.41	\$1.30	\$70.45
7	90	\$43.35	\$12.20	\$19.41	\$1.30	\$76.26

Notes:

Steps 3,4 are 500 hrs. All other steps are 1,000 hrs.

Apprentice to Journeyworker Ratio:1:3

CHAIN SAW OPERATOR	06/01/2017	\$32.65	\$7.60	\$13.50	\$0.00	\$53.75
LABORERS - ZONE 2	12/01/2017	\$33.28	\$7.60	\$13.50	\$0.00	\$54.38
	06/01/2018	\$34.12	\$7.60	\$13.50	\$0.00	\$55.22
	12/01/2018	\$34.96	\$7.60	\$13.50	\$0.00	\$56.06
	06/01/2019	\$35.83	\$7.60	\$13.50	\$0.00	\$56.93
	12/01/2019	\$36.69	\$7.60	\$13.50	\$0.00	\$57.79
For apprentice rates see "Apprentice- LABORER"						
CLAM SHELLS/SLURRY BUCKETS/HEADING MACHINES	06/01/2017	\$47.38	\$10.00	\$15.25	\$0.00	\$72.63
OPERATING ENGINEERS LOCAL 4	12/01/2017	\$48.38	\$10.00	\$15.25	\$0.00	\$73.63
For apprentice rates see "Apprentice- OPERATING ENGINEERS"						
COMPRESSOR OPERATOR	06/01/2017	\$31.86	\$10.00	\$15.25	\$0.00	\$57.11
OPERATING ENGINEERS LOCAL 4	12/01/2017	\$32.55	\$10.00	\$15.25	\$0.00	\$57.80
For apprentice rates see "Apprentice- OPERATING ENGINEERS"						
DELEADER (BRIDGE)	01/01/2017	\$51.41	\$7.85	\$16.10	\$0.00	\$75.36
PAINTERS LOCAL 35 - ZONE 2						

Classification	Effective Date	Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
----------------	----------------	-----------	--------	---------	------------------------------	------------

Apprentice - PAINTER Local 35 - BRIDGES/TANKS

Effective Date - 01/01/2017

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	50	\$25.71	\$7.85	\$0.00	\$0.00	\$33.56
2	55	\$28.28	\$7.85	\$3.66	\$0.00	\$39.79
3	60	\$30.85	\$7.85	\$3.99	\$0.00	\$42.69
4	65	\$33.42	\$7.85	\$4.32	\$0.00	\$45.59
5	70	\$35.99	\$7.85	\$14.11	\$0.00	\$57.95
6	75	\$38.56	\$7.85	\$14.44	\$0.00	\$60.85
7	80	\$41.13	\$7.85	\$14.77	\$0.00	\$63.75
8	90	\$46.27	\$7.85	\$15.44	\$0.00	\$69.56

Notes:

Steps are 750 hrs.

Apprentice to Journeyworker Ratio:1:1

DEMO: ADZEMAN LABORERS - ZONE 2	06/01/2017	\$37.00	\$7.60	\$14.65	\$0.00	\$59.25
	12/01/2017	\$37.85	\$7.60	\$14.65	\$0.00	\$60.10
	06/01/2018	\$38.80	\$7.60	\$14.65	\$0.00	\$61.05
	12/01/2018	\$39.75	\$7.60	\$14.65	\$0.00	\$62.00
	06/01/2019	\$40.75	\$7.60	\$14.65	\$0.00	\$63.00
	12/01/2019	\$41.75	\$7.60	\$14.65	\$0.00	\$64.00
For apprentice rates see "Apprentice- LABORER"						
DEMO: BACKHOE/LOADER/HAMMER OPERATOR LABORERS - ZONE 2	06/01/2017	\$38.00	\$7.60	\$14.65	\$0.00	\$60.25
	12/01/2017	\$38.85	\$7.60	\$14.65	\$0.00	\$61.10
	06/01/2018	\$39.80	\$7.60	\$14.65	\$0.00	\$62.05
	12/01/2018	\$40.75	\$7.60	\$14.65	\$0.00	\$63.00
	06/01/2019	\$41.75	\$7.60	\$14.65	\$0.00	\$64.00
	12/01/2019	\$42.75	\$7.60	\$14.65	\$0.00	\$65.00
For apprentice rates see "Apprentice- LABORER"						
DEMO: BURNERS LABORERS - ZONE 2	06/01/2017	\$37.75	\$7.60	\$14.65	\$0.00	\$60.00
	12/01/2017	\$38.60	\$7.60	\$14.65	\$0.00	\$60.85
	06/01/2018	\$39.55	\$7.60	\$14.65	\$0.00	\$61.80
	12/01/2018	\$40.50	\$7.60	\$14.65	\$0.00	\$62.75
	06/01/2019	\$41.50	\$7.60	\$14.65	\$0.00	\$63.75
	12/01/2019	\$42.50	\$7.60	\$14.65	\$0.00	\$64.75
For apprentice rates see "Apprentice- LABORER"						
DEMO: CONCRETE CUTTER/SAWYER LABORERS - ZONE 2	06/01/2017	\$38.00	\$7.60	\$14.65	\$0.00	\$60.25
	12/01/2017	\$38.85	\$7.60	\$14.65	\$0.00	\$61.10
	06/01/2018	\$39.80	\$7.60	\$14.65	\$0.00	\$62.05
	12/01/2018	\$40.75	\$7.60	\$14.65	\$0.00	\$63.00
	06/01/2019	\$41.75	\$7.60	\$14.65	\$0.00	\$64.00
	12/01/2019	\$42.75	\$7.60	\$14.65	\$0.00	\$65.00
For apprentice rates see "Apprentice- LABORER"						

Classification	Effective Date	Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
DEMO: JACKHAMMER OPERATOR <i>LABORERS - ZONE 2</i>	06/01/2017	\$37.75	\$7.60	\$14.65	\$0.00	\$60.00
	12/01/2017	\$38.60	\$7.60	\$14.65	\$0.00	\$60.85
	06/01/2018	\$39.55	\$7.60	\$14.65	\$0.00	\$61.80
	12/01/2018	\$40.50	\$7.60	\$14.65	\$0.00	\$62.75
	06/01/2019	\$41.50	\$7.60	\$14.65	\$0.00	\$63.75
	12/01/2019	\$42.50	\$7.60	\$14.65	\$0.00	\$64.75
For apprentice rates see "Apprentice- LABORER"						
DEMO: WRECKING LABORER <i>LABORERS - ZONE 2</i>	06/01/2017	\$37.00	\$7.60	\$14.65	\$0.00	\$59.25
	12/01/2017	\$37.85	\$7.60	\$14.65	\$0.00	\$60.10
	06/01/2018	\$38.80	\$7.60	\$14.65	\$0.00	\$61.05
	12/01/2018	\$39.75	\$7.60	\$14.65	\$0.00	\$62.00
	06/01/2019	\$40.75	\$7.60	\$14.65	\$0.00	\$63.00
	12/01/2019	\$41.75	\$7.60	\$14.65	\$0.00	\$64.00
For apprentice rates see "Apprentice- LABORER"						
DIRECTIONAL DRILL MACHINE OPERATOR <i>OPERATING ENGINEERS LOCAL 4</i>	06/01/2017	\$45.93	\$10.00	\$15.25	\$0.00	\$71.18
	12/01/2017	\$46.92	\$10.00	\$15.25	\$0.00	\$72.17
For apprentice rates see "Apprentice- OPERATING ENGINEERS"						
DIVER <i>PILE DRIVER LOCAL 56 (ZONE 1)</i>	08/01/2015	\$58.86	\$9.80	\$19.23	\$0.00	\$87.89
For apprentice rates see "Apprentice- PILE DRIVER"						
DIVER TENDER <i>PILE DRIVER LOCAL 56 (ZONE 1)</i>	08/01/2015	\$42.04	\$9.80	\$19.23	\$0.00	\$71.07
For apprentice rates see "Apprentice- PILE DRIVER"						
DIVER TENDER (EFFLUENT) <i>PILE DRIVER LOCAL 56 (ZONE 1)</i>	08/01/2015	\$63.06	\$9.80	\$19.23	\$0.00	\$92.09
For apprentice rates see "Apprentice- PILE DRIVER"						
DIVER/SLURRY (EFFLUENT) <i>PILE DRIVER LOCAL 56 (ZONE 1)</i>	08/01/2015	\$88.23	\$9.80	\$19.23	\$0.00	\$117.26
For apprentice rates see "Apprentice- PILE DRIVER"						
DRAWBRIDGE OPERATOR (Construction) <i>ELECTRICIANS LOCAL 103</i>	03/01/2017	\$48.33	\$13.00	\$17.45	\$0.00	\$78.78
	09/01/2017	\$49.28	\$13.00	\$17.48	\$0.00	\$79.76
	03/01/2018	\$50.15	\$13.00	\$17.85	\$0.00	\$81.00
	09/01/2018	\$51.34	\$13.00	\$17.89	\$0.00	\$82.23
	03/01/2019	\$52.53	\$13.00	\$17.93	\$0.00	\$83.46
For apprentice rates see "Apprentice- ELECTRICIAN"						
ELECTRICIAN <i>ELECTRICIANS LOCAL 103</i>	03/01/2017	\$48.33	\$13.00	\$17.45	\$0.00	\$78.78
	09/01/2017	\$49.28	\$13.00	\$17.48	\$0.00	\$79.76
	03/01/2018	\$50.15	\$13.00	\$17.85	\$0.00	\$81.00
	09/01/2018	\$51.34	\$13.00	\$17.89	\$0.00	\$82.23
	03/01/2019	\$52.53	\$13.00	\$17.93	\$0.00	\$83.46

Classification
Effective Date
Base Wage
Health
Pension
**Supplemental
Unemployment**
Total Rate
Apprentice - ELECTRICIAN - Local 103
Effective Date - 03/01/2017

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	40	\$19.33	\$13.00	\$0.58	\$0.00	\$32.91
2	40	\$19.33	\$13.00	\$0.58	\$0.00	\$32.91
3	45	\$21.75	\$13.00	\$13.37	\$0.00	\$48.12
4	45	\$21.75	\$13.00	\$13.37	\$0.00	\$48.12
5	50	\$24.17	\$13.00	\$13.75	\$0.00	\$50.92
6	55	\$26.58	\$13.00	\$14.11	\$0.00	\$53.69
7	60	\$29.00	\$13.00	\$14.48	\$0.00	\$56.48
8	65	\$31.41	\$13.00	\$14.85	\$0.00	\$59.26
9	70	\$33.83	\$13.00	\$15.22	\$0.00	\$62.05
10	75	\$36.25	\$13.00	\$15.60	\$0.00	\$64.85

Effective Date - 09/01/2017

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	40	\$19.71	\$13.00	\$0.59	\$0.00	\$33.30
2	40	\$19.71	\$13.00	\$0.59	\$0.00	\$33.30
3	45	\$22.18	\$13.00	\$13.39	\$0.00	\$48.57
4	45	\$22.18	\$13.00	\$13.39	\$0.00	\$48.57
5	50	\$24.64	\$13.00	\$13.76	\$0.00	\$51.40
6	55	\$27.10	\$13.00	\$14.12	\$0.00	\$54.22
7	60	\$29.57	\$13.00	\$14.50	\$0.00	\$57.07
8	65	\$32.03	\$13.00	\$14.87	\$0.00	\$59.90
9	70	\$34.50	\$13.00	\$15.25	\$0.00	\$62.75
10	75	\$36.96	\$13.00	\$15.62	\$0.00	\$65.58

Notes: :

App Prior 1/1/03; 30/35/40/45/50/55/65/70/75/80

Apprentice to Journeyworker Ratio:2:3***

 ELEVATOR CONSTRUCTOR
 ELEVATOR CONSTRUCTORS LOCAL 4

01/01/2017

\$55.86

\$15.28

\$15.71

\$0.00

\$86.85

Classification	Effective Date	Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
Apprentice - ELEVATOR CONSTRUCTOR - Local 4						
Effective Date - 01/01/2017						
Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	50	\$27.93	\$15.28	\$0.00	\$0.00	\$43.21
2	55	\$30.72	\$15.28	\$15.71	\$0.00	\$61.71
3	65	\$36.31	\$15.28	\$15.71	\$0.00	\$67.30
4	70	\$39.10	\$15.28	\$15.71	\$0.00	\$70.09
5	80	\$44.69	\$15.28	\$15.71	\$0.00	\$75.68
Notes: Steps 1-2 are 6 mos.; Steps 3-5 are 1 year						
Apprentice to Journeyworker Ratio:1:1						
ELEVATOR CONSTRUCTOR HELPER <i>ELEVATOR CONSTRUCTORS LOCAL 4</i>	01/01/2017	\$39.10	\$15.28	\$15.71	\$0.00	\$70.09
For apprentice rates see "Apprentice - ELEVATOR CONSTRUCTOR"						
FENCE & GUARD RAIL ERECTOR <i>LABORERS - ZONE 2</i>	06/01/2017	\$32.65	\$7.60	\$13.50	\$0.00	\$53.75
	12/01/2017	\$33.28	\$7.60	\$13.50	\$0.00	\$54.38
	06/01/2018	\$34.12	\$7.60	\$13.50	\$0.00	\$55.22
	12/01/2018	\$34.96	\$7.60	\$13.50	\$0.00	\$56.06
	06/01/2019	\$35.83	\$7.60	\$13.50	\$0.00	\$56.93
	12/01/2019	\$36.69	\$7.60	\$13.50	\$0.00	\$57.79
For apprentice rates see "Apprentice- LABORER"						
FIELD ENG.INST.PERSON-BLDG,SITE,HVY/HWY <i>OPERATING ENGINEERS LOCAL 4</i>	05/01/2017	\$42.15	\$10.00	\$15.25	\$0.00	\$67.40
	11/01/2017	\$42.88	\$10.00	\$15.25	\$0.00	\$68.13
	05/01/2018	\$43.59	\$10.00	\$15.25	\$0.00	\$68.84
For apprentice rates see "Apprentice- OPERATING ENGINEERS"						
FIELD ENG.PARTY CHIEF-BLDG,SITE,HVY/HWY <i>OPERATING ENGINEERS LOCAL 4</i>	05/01/2017	\$43.61	\$10.00	\$15.25	\$0.00	\$68.86
	11/01/2017	\$44.34	\$10.00	\$15.25	\$0.00	\$69.59
	05/01/2018	\$45.06	\$10.00	\$15.25	\$0.00	\$70.31
For apprentice rates see "Apprentice- OPERATING ENGINEERS"						
FIELD ENG.ROD PERSON-BLDG,SITE,HVY/HWY <i>OPERATING ENGINEERS LOCAL 4</i>	05/01/2017	\$22.41	\$10.00	\$15.25	\$0.00	\$47.66
	11/01/2017	\$22.83	\$10.00	\$15.25	\$0.00	\$48.08
	05/01/2018	\$23.26	\$10.00	\$15.25	\$0.00	\$48.51
For apprentice rates see "Apprentice- OPERATING ENGINEERS"						
FIRE ALARM INSTALLER <i>ELECTRICIANS LOCAL 103</i>	03/01/2017	\$48.33	\$13.00	\$17.45	\$0.00	\$78.78
	09/01/2017	\$49.28	\$13.00	\$17.48	\$0.00	\$79.76
	03/01/2018	\$50.15	\$13.00	\$17.85	\$0.00	\$81.00
	09/01/2018	\$51.34	\$13.00	\$17.89	\$0.00	\$82.23
	03/01/2019	\$52.53	\$13.00	\$17.93	\$0.00	\$83.46
For apprentice rates see "Apprentice- ELECTRICIAN"						
FIRE ALARM REPAIR / MAINTENANCE <i>LOCAL 103</i> / COMMISSIONING <i>ELECTRICIANS</i>	03/01/2017	\$36.25	\$13.00	\$15.60	\$0.00	\$64.85
	09/01/2017	\$36.96	\$13.00	\$15.62	\$0.00	\$65.58
	03/01/2018	\$37.61	\$13.00	\$15.93	\$0.00	\$66.54
	09/01/2018	\$38.51	\$13.00	\$15.96	\$0.00	\$67.47
	03/01/2019	\$39.40	\$13.00	\$15.98	\$0.00	\$68.38

Issue Date: 08/24/2017	Wage Request Number:		20170824-010		Page 10 of 32	

Classification	Effective Date	Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
For apprentice rates see "Apprentice- TELECOMMUNICATIONS TECHNICIAN"						
FIREMAN (ASST. ENGINEER)	06/01/2017	\$38.49	\$10.00	\$15.25	\$0.00	\$63.74
OPERATING ENGINEERS LOCAL 4	12/01/2017	\$39.32	\$10.00	\$15.25	\$0.00	\$64.57
For apprentice rates see "Apprentice- OPERATING ENGINEERS"						
FLAGGER & SIGNALER	06/01/2017	\$20.50	\$7.60	\$13.50	\$0.00	\$41.60
LABORERS - ZONE 2	12/01/2017	\$21.50	\$7.60	\$13.50	\$0.00	\$42.60
	06/01/2018	\$21.50	\$7.60	\$13.50	\$0.00	\$42.60
	12/01/2018	\$22.50	\$7.60	\$13.50	\$0.00	\$43.60
	06/01/2019	\$22.50	\$7.60	\$13.50	\$0.00	\$43.60
	12/01/2019	\$23.50	\$7.60	\$13.50	\$0.00	\$44.60
For apprentice rates see "Apprentice- LABORER"						
FLOORCOVERER	03/01/2016	\$42.13	\$9.80	\$17.62	\$0.00	\$69.55
FLOORCOVERERS LOCAL 2168 ZONE I						

Apprentice - FLOORCOVERER - Local 2168 Zone I

Effective Date - 03/01/2016

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	50	\$21.07	\$9.80	\$1.79	\$0.00	\$32.66
2	55	\$23.17	\$9.80	\$1.79	\$0.00	\$34.76
3	60	\$25.28	\$9.80	\$12.25	\$0.00	\$47.33
4	65	\$27.38	\$9.80	\$12.25	\$0.00	\$49.43
5	70	\$29.49	\$9.80	\$14.04	\$0.00	\$53.33
6	75	\$31.60	\$9.80	\$14.04	\$0.00	\$55.44
7	80	\$33.70	\$9.80	\$15.83	\$0.00	\$59.33
8	85	\$35.81	\$9.80	\$15.83	\$0.00	\$61.44

Notes:

Steps are 750 hrs.

Apprentice to Journeyworker Ratio:1:1

FORK LIFT/CHERRY PICKER	06/01/2017	\$46.38	\$10.00	\$15.25	\$0.00	\$71.63
OPERATING ENGINEERS LOCAL 4	12/01/2017	\$47.38	\$10.00	\$15.25	\$0.00	\$72.63
For apprentice rates see "Apprentice- OPERATING ENGINEERS"						
GENERATOR/LIGHTING PLANT/HEATERS	06/01/2017	\$31.86	\$10.00	\$15.25	\$0.00	\$57.11
OPERATING ENGINEERS LOCAL 4	12/01/2017	\$32.55	\$10.00	\$15.25	\$0.00	\$57.80
For apprentice rates see "Apprentice- OPERATING ENGINEERS"						
GLAZIER (GLASS PLANK/AIR BARRIER/INTERIOR SYSTEMS)	01/01/2017	\$40.91	\$7.85	\$16.10	\$0.00	\$64.86
GLAZIERS LOCAL 35 (ZONE 2)						

Apprentice - GLAZIER - Local 35 Zone 2
Effective Date - 01/01/2017

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	50	\$20.46	\$7.85	\$0.00	\$0.00	\$28.31
2	55	\$22.50	\$7.85	\$3.66	\$0.00	\$34.01
3	60	\$24.55	\$7.85	\$3.99	\$0.00	\$36.39
4	65	\$26.59	\$7.85	\$4.32	\$0.00	\$38.76
5	70	\$28.64	\$7.85	\$14.11	\$0.00	\$50.60
6	75	\$30.68	\$7.85	\$14.44	\$0.00	\$52.97
7	80	\$32.73	\$7.85	\$14.77	\$0.00	\$55.35
8	90	\$36.82	\$7.85	\$15.44	\$0.00	\$60.11

Notes:
Steps are 750 hrs.

Apprentice to Journeyworker Ratio:1:1

HOISTING ENGINEER/CRANES/GRADALLS	06/01/2017	\$46.38	\$10.00	\$15.25	\$0.00	\$71.63
OPERATING ENGINEERS LOCAL 4	12/01/2017	\$47.38	\$10.00	\$15.25	\$0.00	\$72.63

Classification	Effective Date	Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
----------------	----------------	-----------	--------	---------	------------------------------	------------

Apprentice - OPERATING ENGINEERS - Local 4

Effective Date - 06/01/2017

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	55	\$25.51	\$10.00	\$0.00	\$0.00	\$35.51
2	60	\$27.83	\$10.00	\$15.25	\$0.00	\$53.08
3	65	\$30.15	\$10.00	\$15.25	\$0.00	\$55.40
4	70	\$32.47	\$10.00	\$15.25	\$0.00	\$57.72
5	75	\$34.79	\$10.00	\$15.25	\$0.00	\$60.04
6	80	\$37.10	\$10.00	\$15.25	\$0.00	\$62.35
7	85	\$39.42	\$10.00	\$15.25	\$0.00	\$64.67
8	90	\$41.74	\$10.00	\$15.25	\$0.00	\$66.99

Effective Date - 12/01/2017

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	55	\$26.06	\$10.00	\$0.00	\$0.00	\$36.06
2	60	\$28.43	\$10.00	\$15.25	\$0.00	\$53.68
3	65	\$30.80	\$10.00	\$15.25	\$0.00	\$56.05
4	70	\$33.17	\$10.00	\$15.25	\$0.00	\$58.42
5	75	\$35.54	\$10.00	\$15.25	\$0.00	\$60.79
6	80	\$37.90	\$10.00	\$15.25	\$0.00	\$63.15
7	85	\$40.27	\$10.00	\$15.25	\$0.00	\$65.52
8	90	\$42.64	\$10.00	\$15.25	\$0.00	\$67.89

Notes:

Apprentice to Journeyworker Ratio:1:6

HVAC (DUCTWORK) <i>SHEETMETAL WORKERS LOCAL 17 - A</i>	08/01/2017	\$43.83	\$11.45	\$24.03	\$2.38	\$81.69
	02/01/2018	\$44.98	\$11.45	\$24.03	\$2.38	\$82.84
For apprentice rates see "Apprentice- SHEET METAL WORKER"						
HVAC (ELECTRICAL CONTROLS) <i>ELECTRICIANS LOCAL 103</i>	03/01/2017	\$48.33	\$13.00	\$17.45	\$0.00	\$78.78
	09/01/2017	\$49.28	\$13.00	\$17.48	\$0.00	\$79.76
	03/01/2018	\$50.15	\$13.00	\$17.85	\$0.00	\$81.00
	09/01/2018	\$51.34	\$13.00	\$17.89	\$0.00	\$82.23
	03/01/2019	\$52.53	\$13.00	\$17.93	\$0.00	\$83.46
For apprentice rates see "Apprentice- ELECTRICIAN"						
HVAC (TESTING AND BALANCING - AIR) <i>SHEETMETAL WORKERS LOCAL 17 - A</i>	08/01/2017	\$43.83	\$11.45	\$24.03	\$2.38	\$81.69
	02/01/2018	\$44.98	\$11.45	\$24.03	\$2.38	\$82.84
For apprentice rates see "Apprentice- SHEET METAL WORKER"						
HVAC (TESTING AND BALANCING -WATER) <i>PIPEFITTERS LOCAL 537 (Local 138)</i>	03/01/2017	\$48.86	\$9.70	\$16.14	\$0.00	\$74.70
For apprentice rates see "Apprentice- PIPEFITTER" or "PLUMBER/PIPEFITTER"						
HVAC MECHANIC <i>PIPEFITTERS LOCAL 537 (Local 138)</i>	03/01/2017	\$48.86	\$9.70	\$16.14	\$0.00	\$74.70
For apprentice rates see "Apprentice- PIPEFITTER" or "PLUMBER/PIPEFITTER"						

Classification	Effective Date	Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
HYDRAULIC DRILLS <i>LABORERS - ZONE 2</i>	06/01/2017	\$33.15	\$7.60	\$13.50	\$0.00	\$54.25
	12/01/2017	\$33.78	\$7.60	\$13.50	\$0.00	\$54.88
	06/01/2018	\$34.62	\$7.60	\$13.50	\$0.00	\$55.72
	12/01/2018	\$35.46	\$7.60	\$13.50	\$0.00	\$56.56
	06/01/2019	\$36.33	\$7.60	\$13.50	\$0.00	\$57.43
	12/01/2019	\$37.19	\$7.60	\$13.50	\$0.00	\$58.29

For apprentice rates see "Apprentice- LABORER"

INSULATOR (PIPES & TANKS) <i>HEAT & FROST INSULATORS LOCAL 6 (BOSTON)</i>	09/01/2016	\$45.09	\$11.75	\$14.20	\$0.00	\$71.04
	09/01/2017	\$47.09	\$11.75	\$14.20	\$0.00	\$73.04
	09/01/2018	\$49.34	\$11.75	\$14.20	\$0.00	\$75.29
	09/01/2019	\$51.84	\$11.75	\$14.20	\$0.00	\$77.79

Apprentice - ASBESTOS INSULATOR (Pipes & Tanks) - Local 6 Boston

Effective Date - 09/01/2016

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	50	\$22.55	\$11.75	\$10.45	\$0.00	\$44.75
2	60	\$27.05	\$11.75	\$11.20	\$0.00	\$50.00
3	70	\$31.56	\$11.75	\$11.95	\$0.00	\$55.26
4	80	\$36.07	\$11.75	\$12.70	\$0.00	\$60.52

Effective Date - 09/01/2017

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	50	\$23.55	\$11.75	\$10.45	\$0.00	\$45.75
2	60	\$28.25	\$11.75	\$11.20	\$0.00	\$51.20
3	70	\$32.96	\$11.75	\$11.95	\$0.00	\$56.66
4	80	\$37.67	\$11.75	\$12.70	\$0.00	\$62.12

Notes:

Steps are 1 year

Apprentice to Journeyworker Ratio:1:4

IRONWORKER/WELDER <i>IRONWORKERS LOCAL 7 (BOSTON AREA)</i>	03/16/2017	\$44.65	\$7.80	\$20.85	\$0.00	\$73.30
---	------------	---------	--------	---------	--------	---------

Apprentice - IRONWORKER - Local 7 Boston

Effective Date - 03/16/2017

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	60	\$26.79	\$7.80	\$20.85	\$0.00	\$55.44
2	70	\$31.26	\$7.80	\$20.85	\$0.00	\$59.91
3	75	\$33.49	\$7.80	\$20.85	\$0.00	\$62.14
4	80	\$35.72	\$7.80	\$20.85	\$0.00	\$64.37
5	85	\$37.95	\$7.80	\$20.85	\$0.00	\$66.60
6	90	\$40.19	\$7.80	\$20.85	\$0.00	\$68.84

Notes:

** Structural 1:6; Ornamental 1:4

Apprentice to Journeyworker Ratio:**

JACKHAMMER & PAVING BREAKER OPERATOR	06/01/2017	\$32.65	\$7.60	\$13.50	\$0.00	\$53.75
LABORERS - ZONE 2	12/01/2017	\$33.28	\$7.60	\$13.50	\$0.00	\$54.38
	06/01/2018	\$34.12	\$7.60	\$13.50	\$0.00	\$55.22
	12/01/2018	\$34.96	\$7.60	\$13.50	\$0.00	\$56.06
	06/01/2019	\$35.83	\$7.60	\$13.50	\$0.00	\$56.93
	12/01/2019	\$36.69	\$7.60	\$13.50	\$0.00	\$57.79

For apprentice rates see "Apprentice- LABORER"

LABORER	06/01/2017	\$32.40	\$7.60	\$13.50	\$0.00	\$53.50
LABORERS - ZONE 2	12/01/2017	\$33.03	\$7.60	\$13.50	\$0.00	\$54.13
	06/01/2018	\$33.87	\$7.60	\$13.50	\$0.00	\$54.97
	12/01/2018	\$34.71	\$7.60	\$13.50	\$0.00	\$55.81
	06/01/2019	\$35.58	\$7.60	\$13.50	\$0.00	\$56.68
	12/01/2019	\$36.44	\$7.60	\$13.50	\$0.00	\$57.54

Classification
Effective Date
Base Wage
Health
Pension
**Supplemental
Unemployment**
Total Rate
Apprentice - LABORER - Zone 2
Effective Date - 06/01/2017

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	60	\$19.44	\$7.60	\$13.50	\$0.00	\$40.54
2	70	\$22.68	\$7.60	\$13.50	\$0.00	\$43.78
3	80	\$25.92	\$7.60	\$13.50	\$0.00	\$47.02
4	90	\$29.16	\$7.60	\$13.50	\$0.00	\$50.26

Effective Date - 12/01/2017

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	60	\$19.82	\$7.60	\$13.50	\$0.00	\$40.92
2	70	\$23.12	\$7.60	\$13.50	\$0.00	\$44.22
3	80	\$26.42	\$7.60	\$13.50	\$0.00	\$47.52
4	90	\$29.73	\$7.60	\$13.50	\$0.00	\$50.83

Notes:
Apprentice to Journeyworker Ratio:1:5
LABORER: CARPENTER TENDER
LABORERS - ZONE 2

06/01/2017	\$32.40	\$7.60	\$13.50	\$0.00	\$53.50
12/01/2017	\$33.03	\$7.60	\$13.50	\$0.00	\$54.13
06/01/2018	\$33.87	\$7.60	\$13.50	\$0.00	\$54.97
12/01/2018	\$34.71	\$7.60	\$13.50	\$0.00	\$55.81
06/01/2019	\$35.58	\$7.60	\$13.50	\$0.00	\$56.68
12/01/2019	\$36.44	\$7.60	\$13.50	\$0.00	\$57.54

For apprentice rates see "Apprentice- LABORER"

LABORER: CEMENT FINISHER TENDER
LABORERS - ZONE 2

06/01/2017	\$32.40	\$7.60	\$13.50	\$0.00	\$53.50
12/01/2017	\$33.03	\$7.60	\$13.50	\$0.00	\$54.13
06/01/2018	\$33.87	\$7.60	\$13.50	\$0.00	\$54.97
12/01/2018	\$34.71	\$7.60	\$13.50	\$0.00	\$55.81
06/01/2019	\$35.58	\$7.60	\$13.50	\$0.00	\$56.68
12/01/2019	\$36.44	\$7.60	\$13.50	\$0.00	\$57.54

For apprentice rates see "Apprentice- LABORER"

LABORER: HAZARDOUS WASTE/ASBESTOS REMOVER
LABORERS - ZONE 2

06/01/2017	\$32.60	\$7.60	\$13.45	\$0.00	\$53.65
12/01/2017	\$33.23	\$7.60	\$13.45	\$0.00	\$54.28
06/01/2018	\$34.07	\$7.60	\$13.45	\$0.00	\$55.12
12/01/2018	\$34.91	\$7.60	\$13.45	\$0.00	\$55.96
06/01/2019	\$35.78	\$7.60	\$13.45	\$0.00	\$56.83
12/01/2019	\$36.64	\$7.60	\$13.45	\$0.00	\$57.69

For apprentice rates see "Apprentice- LABORER"

Classification	Effective Date	Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
LABORER: MASON TENDER <i>LABORERS - ZONE 2</i>	06/01/2017	\$32.65	\$7.60	\$13.50	\$0.00	\$53.75
	12/01/2017	\$33.28	\$7.60	\$13.50	\$0.00	\$54.38
	06/01/2018	\$34.12	\$7.60	\$13.50	\$0.00	\$55.22
	12/01/2018	\$34.96	\$7.60	\$13.50	\$0.00	\$56.06
	06/01/2019	\$35.83	\$7.60	\$13.50	\$0.00	\$56.93
	12/01/2019	\$36.69	\$7.60	\$13.50	\$0.00	\$57.79
For apprentice rates see "Apprentice- LABORER"						
LABORER: MULTI-TRADE TENDER <i>LABORERS - ZONE 2</i>	06/01/2017	\$32.40	\$7.60	\$13.50	\$0.00	\$53.50
	12/01/2017	\$33.03	\$7.60	\$13.50	\$0.00	\$54.13
	06/01/2018	\$33.87	\$7.60	\$13.50	\$0.00	\$54.97
	12/01/2018	\$34.71	\$7.60	\$13.50	\$0.00	\$55.81
	06/01/2019	\$35.58	\$7.60	\$13.50	\$0.00	\$56.68
	12/01/2019	\$36.44	\$7.60	\$13.50	\$0.00	\$57.54
For apprentice rates see "Apprentice- LABORER"						
LABORER: TREE REMOVER <i>LABORERS - ZONE 2</i>	06/01/2017	\$32.40	\$7.60	\$13.50	\$0.00	\$53.50
	12/01/2017	\$33.03	\$7.60	\$13.50	\$0.00	\$54.13
	06/01/2018	\$33.87	\$7.60	\$13.50	\$0.00	\$54.97
	12/01/2018	\$34.71	\$7.60	\$13.50	\$0.00	\$55.81
	06/01/2019	\$35.58	\$7.60	\$13.50	\$0.00	\$56.68
	12/01/2019	\$36.44	\$7.60	\$13.50	\$0.00	\$57.54
This classification applies to all tree work associated with the removal of standing trees, and trimming and removal of branches and limbs when the work is not done for a utility company for the purpose of operation, maintenance or repair of utility company equipment. For apprentice rates see "Apprentice- LABORER"						
LASER BEAM OPERATOR <i>LABORERS - ZONE 2</i>	06/01/2017	\$32.65	\$7.60	\$13.50	\$0.00	\$53.75
	12/01/2017	\$33.28	\$7.60	\$13.50	\$0.00	\$54.38
	06/01/2018	\$34.12	\$7.60	\$13.50	\$0.00	\$55.22
	12/01/2018	\$34.96	\$7.60	\$13.50	\$0.00	\$56.06
	06/01/2019	\$35.83	\$7.60	\$13.50	\$0.00	\$56.93
	12/01/2019	\$36.69	\$7.60	\$13.50	\$0.00	\$57.79
For apprentice rates see "Apprentice- LABORER"						
MARBLE & TILE FINISHERS <i>BRICKLAYERS LOCAL 3 - MARBLE & TILE</i>	02/01/2017	\$38.78	\$10.75	\$17.67	\$0.00	\$67.20

Apprentice - MARBLE & TILE FINISHER - Local 3 Marble & Tile

Effective Date - 02/01/2017

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	50	\$19.39	\$10.75	\$17.67	\$0.00	\$47.81
2	60	\$23.27	\$10.75	\$17.67	\$0.00	\$51.69
3	70	\$27.15	\$10.75	\$17.67	\$0.00	\$55.57
4	80	\$31.02	\$10.75	\$17.67	\$0.00	\$59.44
5	90	\$34.90	\$10.75	\$17.67	\$0.00	\$63.32

Notes:

Apprentice to Journeyworker Ratio:1:3

MARBLE MASONS, TILELAYERS & TERRAZZO MECH <i>BRICKLAYERS LOCAL 3 - MARBLE & TILE</i>	02/01/2017	\$50.80	\$10.75	\$19.22	\$0.00	\$80.77
---	------------	---------	---------	---------	--------	---------

Classification
Effective Date
Base Wage
Health
Pension
**Supplemental
Unemployment**
Total Rate
Apprentice - MARBLE-TILE-TERRAZZO MECHANIC - Local 3 Marble & Tile
Effective Date - 02/01/2017

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	50	\$25.40	\$10.75	\$19.22	\$0.00	\$55.37
2	60	\$30.48	\$10.75	\$19.22	\$0.00	\$60.45
3	70	\$35.56	\$10.75	\$19.22	\$0.00	\$65.53
4	80	\$40.64	\$10.75	\$19.22	\$0.00	\$70.61
5	90	\$45.72	\$10.75	\$19.22	\$0.00	\$75.69

Notes:
Apprentice to Journeyworker Ratio:1:5

MECH. SWEEPER OPERATOR (ON CONST. SITES)	06/01/2017	\$45.93	\$10.00	\$15.25	\$0.00	\$71.18
OPERATING ENGINEERS LOCAL 4	12/01/2017	\$46.92	\$10.00	\$15.25	\$0.00	\$72.17

For apprentice rates see "Apprentice- OPERATING ENGINEERS"

MECHANICS MAINTENANCE	06/01/2017	\$45.93	\$10.00	\$15.25	\$0.00	\$71.18
OPERATING ENGINEERS LOCAL 4	12/01/2017	\$46.92	\$10.00	\$15.25	\$0.00	\$72.17

For apprentice rates see "Apprentice- OPERATING ENGINEERS"

MILLWRIGHT (Zone 1)	04/01/2017	\$38.62	\$9.90	\$18.50	\$0.00	\$67.02
MILLWRIGHTS LOCAL 1121 - Zone 1	10/01/2017	\$39.52	\$9.90	\$18.50	\$0.00	\$67.92
	04/01/2018	\$40.42	\$9.90	\$18.50	\$0.00	\$68.82
	10/01/2018	\$41.32	\$9.90	\$18.50	\$0.00	\$69.72
	04/01/2019	\$42.22	\$9.90	\$18.50	\$0.00	\$70.62

Apprentice - MILLWRIGHT - Local 1121 Zone 1
Effective Date - 04/01/2017

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	55	\$21.24	\$9.90	\$5.31	\$0.00	\$36.45
2	65	\$25.10	\$9.90	\$15.13	\$0.00	\$50.13
3	75	\$28.97	\$9.90	\$16.10	\$0.00	\$54.97
4	85	\$32.83	\$9.90	\$17.06	\$0.00	\$59.79

Effective Date - 10/01/2017

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	55	\$21.74	\$9.90	\$5.31	\$0.00	\$36.95
2	65	\$25.69	\$9.90	\$15.13	\$0.00	\$50.72
3	75	\$29.64	\$9.90	\$16.10	\$0.00	\$55.64
4	85	\$33.59	\$9.90	\$17.06	\$0.00	\$60.55

Notes:

Steps are 2,000 hours

Apprentice to Journeyworker Ratio:1:5

Classification	Effective Date	Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
MORTAR MIXER <i>LABORERS - ZONE 2</i>	06/01/2017	\$32.65	\$7.60	\$13.50	\$0.00	\$53.75
	12/01/2017	\$33.28	\$7.60	\$13.50	\$0.00	\$54.38
	06/01/2018	\$34.12	\$7.60	\$13.50	\$0.00	\$55.22
	12/01/2018	\$34.96	\$7.60	\$13.50	\$0.00	\$56.06
	06/01/2019	\$35.83	\$7.60	\$13.50	\$0.00	\$56.93
	12/01/2019	\$36.69	\$7.60	\$13.50	\$0.00	\$57.79
For apprentice rates see "Apprentice- LABORER"						
OILER (OTHER THAN TRUCK CRANES,GRADALLS) <i>OPERATING ENGINEERS LOCAL 4</i>	06/01/2017	\$23.47	\$10.00	\$15.25	\$0.00	\$48.72
	12/01/2017	\$23.99	\$10.00	\$15.25	\$0.00	\$49.24
For apprentice rates see "Apprentice- OPERATING ENGINEERS"						
OILER (TRUCK CRANES, GRADALLS) <i>OPERATING ENGINEERS LOCAL 4</i>	06/01/2017	\$27.54	\$10.00	\$15.25	\$0.00	\$52.79
	12/01/2017	\$28.15	\$10.00	\$15.25	\$0.00	\$53.40
For apprentice rates see "Apprentice- OPERATING ENGINEERS"						
OTHER POWER DRIVEN EQUIPMENT - CLASS II <i>OPERATING ENGINEERS LOCAL 4</i>	06/01/2017	\$45.93	\$10.00	\$15.25	\$0.00	\$71.18
	12/01/2017	\$46.92	\$10.00	\$15.25	\$0.00	\$72.17
For apprentice rates see "Apprentice- OPERATING ENGINEERS"						
PAINTER (BRIDGES/TANKS) <i>PAINTERS LOCAL 35 - ZONE 2</i>	01/01/2017	\$51.41	\$7.85	\$16.10	\$0.00	\$75.36

Apprentice - PAINTER Local 35 - BRIDGES/TANKS

Effective Date - 01/01/2017

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	50	\$25.71	\$7.85	\$0.00	\$0.00	\$33.56
2	55	\$28.28	\$7.85	\$3.66	\$0.00	\$39.79
3	60	\$30.85	\$7.85	\$3.99	\$0.00	\$42.69
4	65	\$33.42	\$7.85	\$4.32	\$0.00	\$45.59
5	70	\$35.99	\$7.85	\$14.11	\$0.00	\$57.95
6	75	\$38.56	\$7.85	\$14.44	\$0.00	\$60.85
7	80	\$41.13	\$7.85	\$14.77	\$0.00	\$63.75
8	90	\$46.27	\$7.85	\$15.44	\$0.00	\$69.56

Notes:

Steps are 750 hrs.

Apprentice to Journeyworker Ratio:1:1

PAINTER (SPRAY OR SANDBLAST, NEW) *	01/01/2017	\$42.31	\$7.85	\$16.10	\$0.00	\$66.26
-------------------------------------	------------	---------	--------	---------	--------	---------

* If 30% or more of surfaces to be painted are new construction,
NEW paint rate shall be used.*PAINTERS LOCAL 35 - ZONE 2*

Classification

Effective Date Base Wage Health Pension Supplemental Unemployment Total Rate

Apprentice - PAINTER Local 35 Zone 2 - Spray/Sandblast - New
Effective Date - 01/01/2017

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	50	\$21.16	\$7.85	\$0.00	\$0.00	\$29.01
2	55	\$23.27	\$7.85	\$3.66	\$0.00	\$34.78
3	60	\$25.39	\$7.85	\$3.99	\$0.00	\$37.23
4	65	\$27.50	\$7.85	\$4.32	\$0.00	\$39.67
5	70	\$29.62	\$7.85	\$14.11	\$0.00	\$51.58
6	75	\$31.73	\$7.85	\$14.44	\$0.00	\$54.02
7	80	\$33.85	\$7.85	\$14.77	\$0.00	\$56.47
8	90	\$38.08	\$7.85	\$15.44	\$0.00	\$61.37

Notes:

Steps are 750 hrs.

Apprentice to Journeyworker Ratio:1:1

PAINTER (SPRAY OR SANDBLAST, REPAINT)	01/01/2017	\$40.37	\$7.85	\$16.10	\$0.00	\$64.32
<i>PAINTERS LOCAL 35 - ZONE 2</i>						

Apprentice - PAINTER Local 35 Zone 2 - Spray/Sandblast - Repaint
Effective Date - 01/01/2017

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	50	\$20.19	\$7.85	\$0.00	\$0.00	\$28.04
2	55	\$22.20	\$7.85	\$3.66	\$0.00	\$33.71
3	60	\$24.22	\$7.85	\$3.99	\$0.00	\$36.06
4	65	\$26.24	\$7.85	\$4.32	\$0.00	\$38.41
5	70	\$28.26	\$7.85	\$14.11	\$0.00	\$50.22
6	75	\$30.28	\$7.85	\$14.44	\$0.00	\$52.57
7	80	\$32.30	\$7.85	\$14.77	\$0.00	\$54.92
8	90	\$36.33	\$7.85	\$15.44	\$0.00	\$59.62

Notes:

Steps are 750 hrs.

Apprentice to Journeyworker Ratio:1:1

PAINTER (TRAFFIC MARKINGS)	06/01/2017	\$32.40	\$7.60	\$13.50	\$0.00	\$53.50
<i>LABORERS - ZONE 2</i>						
	12/01/2017	\$33.03	\$7.60	\$13.50	\$0.00	\$54.13
	06/01/2018	\$33.87	\$7.60	\$13.50	\$0.00	\$54.97
	12/01/2018	\$34.71	\$7.60	\$13.50	\$0.00	\$55.81
	06/01/2019	\$35.58	\$7.60	\$13.50	\$0.00	\$56.68
	12/01/2019	\$36.44	\$7.60	\$13.50	\$0.00	\$57.54

For Apprentice rates see "Apprentice- LABORER"

PAINTER / TAPER (BRUSH, NEW) *	01/01/2017	\$40.91	\$7.85	\$16.10	\$0.00	\$64.86
--------------------------------	------------	---------	--------	---------	--------	---------

* If 30% or more of surfaces to be painted are new construction,
NEW paint rate shall be used.*PAINTERS LOCAL 35 - ZONE 2*

Classification	Effective Date	Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
----------------	----------------	-----------	--------	---------	------------------------------	------------

Apprentice - PAINTER - Local 35 Zone 2 - BRUSH NEW

Effective Date - 01/01/2017

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	50	\$20.46	\$7.85	\$0.00	\$0.00	\$28.31
2	55	\$22.50	\$7.85	\$3.66	\$0.00	\$34.01
3	60	\$24.55	\$7.85	\$3.99	\$0.00	\$36.39
4	65	\$26.59	\$7.85	\$4.32	\$0.00	\$38.76
5	70	\$28.64	\$7.85	\$14.11	\$0.00	\$50.60
6	75	\$30.68	\$7.85	\$14.44	\$0.00	\$52.97
7	80	\$32.73	\$7.85	\$14.77	\$0.00	\$55.35
8	90	\$36.82	\$7.85	\$15.44	\$0.00	\$60.11

Notes:

Steps are 750 hrs.

Apprentice to Journeyworker Ratio:1:1

PAINTER / TAPER (BRUSH, REPAINT)	01/01/2017	\$38.97	\$7.85	\$16.10	\$0.00	\$62.92
----------------------------------	------------	---------	--------	---------	--------	---------

PAINTERS LOCAL 35 - ZONE 2

Apprentice - PAINTER Local 35 Zone 2 - BRUSH REPAINT

Effective Date - 01/01/2017

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	50	\$19.49	\$7.85	\$0.00	\$0.00	\$27.34
2	55	\$21.43	\$7.85	\$3.66	\$0.00	\$32.94
3	60	\$23.38	\$7.85	\$3.99	\$0.00	\$35.22
4	65	\$25.33	\$7.85	\$4.32	\$0.00	\$37.50
5	70	\$27.28	\$7.85	\$14.11	\$0.00	\$49.24
6	75	\$29.23	\$7.85	\$14.44	\$0.00	\$51.52
7	80	\$31.18	\$7.85	\$14.77	\$0.00	\$53.80
8	90	\$35.07	\$7.85	\$15.44	\$0.00	\$58.36

Notes:

Steps are 750 hrs.

Apprentice to Journeyworker Ratio:1:1

PANEL & PICKUP TRUCKS DRIVER	12/01/2012	\$30.28	\$9.07	\$8.00	\$0.00	\$47.35
------------------------------	------------	---------	--------	--------	--------	---------

TEAMSTERS JOINT COUNCIL NO. 10 ZONE B

PIER AND DOCK CONSTRUCTOR (UNDERPINNING AND DECK)	08/01/2015	\$42.04	\$9.80	\$19.23	\$0.00	\$71.07
---	------------	---------	--------	---------	--------	---------

PILE DRIVER LOCAL 56 (ZONE 1)

For apprentice rates see "Apprentice- PILE DRIVER"

PILE DRIVER	08/01/2015	\$42.04	\$9.80	\$19.23	\$0.00	\$71.07
-------------	------------	---------	--------	---------	--------	---------

PILE DRIVER LOCAL 56 (ZONE 1)

Classification	Effective Date	Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
----------------	----------------	-----------	--------	---------	------------------------------	------------

Apprentice - PILE DRIVER - Local 56 Zone 1

Effective Date - 08/01/2015

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	50	\$21.02	\$9.80	\$19.23	\$0.00	\$50.05
2	60	\$25.22	\$9.80	\$19.23	\$0.00	\$54.25
3	70	\$29.43	\$9.80	\$19.23	\$0.00	\$58.46
4	75	\$31.53	\$9.80	\$19.23	\$0.00	\$60.56
5	80	\$33.63	\$9.80	\$19.23	\$0.00	\$62.66
6	80	\$33.63	\$9.80	\$19.23	\$0.00	\$62.66
7	90	\$37.84	\$9.80	\$19.23	\$0.00	\$66.87
8	90	\$37.84	\$9.80	\$19.23	\$0.00	\$66.87

Notes:

Apprentice to Journeyworker Ratio:1:3

PIPEFITTER & STEAMFITTER	03/01/2017	\$48.86	\$9.70	\$16.14	\$0.00	\$74.70
<i>PIPEFITTERS LOCAL 537 (Local 138)</i>						

Apprentice - PIPEFITTER Local 537 (Local 138)

Effective Date - 03/01/2017

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	40	\$19.54	\$9.70	\$5.50	\$0.00	\$34.74
2	45	\$21.99	\$9.70	\$16.14	\$0.00	\$47.83
3	60	\$29.32	\$9.70	\$16.14	\$0.00	\$55.16
4	70	\$34.20	\$9.70	\$16.14	\$0.00	\$60.04
5	80	\$39.09	\$9.70	\$16.14	\$0.00	\$64.93

Notes:

** 1:3; 3:15; 1:10 thereafter / Steps are 1 yr.

Refrig/AC Mechanic **1:1;1:2;2:4;3:6;4:8;5:10;6:12;7:14;8:17;9:20;10:23(Max)

Apprentice to Journeyworker Ratio:**

PIPELAYER	06/01/2017	\$32.65	\$7.60	\$13.50	\$0.00	\$53.75
<i>LABORERS - ZONE 2</i>						
	12/01/2017	\$33.28	\$7.60	\$13.50	\$0.00	\$54.38
	06/01/2018	\$34.12	\$7.60	\$13.50	\$0.00	\$55.22
	12/01/2018	\$34.96	\$7.60	\$13.50	\$0.00	\$56.06
	06/01/2019	\$35.83	\$7.60	\$13.50	\$0.00	\$56.93
	12/01/2019	\$36.69	\$7.60	\$13.50	\$0.00	\$57.79

For apprentice rates see "Apprentice- LABORER"

PLUMBER	03/01/2017	\$48.61	\$11.32	\$15.46	\$0.00	\$75.39
<i>PLUMBERS & GASFITTERS LOCAL 12 (Local 138)</i>						

Classification	Effective Date	Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
Apprentice - PLUMBER/GASFITTER - Local 12 (Local 138)						
Effective Date - 03/01/2017						
Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	35	\$17.01	\$11.32	\$5.74	\$0.00	\$34.07
2	40	\$19.44	\$11.32	\$6.49	\$0.00	\$37.25
3	55	\$26.74	\$11.32	\$8.73	\$0.00	\$46.79
4	65	\$31.60	\$11.32	\$10.23	\$0.00	\$53.15
5	75	\$36.46	\$11.32	\$11.72	\$0.00	\$59.50
Notes: Steps are 1 yr Step 4 with lic\$55.65 Step5 with lic\$61.89						
Apprentice to Journeyworker Ratio:1:5						
PNEUMATIC CONTROLS (TEMP.) <i>PIPEFITTERS LOCAL 537 (Local 138)</i>	03/01/2017	\$48.86	\$9.70	\$16.14	\$0.00	\$74.70
For apprentice rates see "Apprentice- PIPEFITTER" or "PLUMBER/PIPEFITTER"						
PNEUMATIC DRILL/TOOL OPERATOR <i>LABORERS - ZONE 2</i>	06/01/2017	\$32.65	\$7.60	\$13.50	\$0.00	\$53.75
	12/01/2017	\$33.28	\$7.60	\$13.50	\$0.00	\$54.38
	06/01/2018	\$34.12	\$7.60	\$13.50	\$0.00	\$55.22
	12/01/2018	\$34.96	\$7.60	\$13.50	\$0.00	\$56.06
	06/01/2019	\$35.83	\$7.60	\$13.50	\$0.00	\$56.93
	12/01/2019	\$36.69	\$7.60	\$13.50	\$0.00	\$57.79
For apprentice rates see "Apprentice- LABORER"						
POWDERMAN & BLASTER <i>LABORERS - ZONE 2</i>	06/01/2017	\$33.40	\$7.60	\$13.50	\$0.00	\$54.50
	12/01/2017	\$34.03	\$7.60	\$13.50	\$0.00	\$55.13
	06/01/2018	\$34.87	\$7.60	\$13.50	\$0.00	\$55.97
	12/01/2018	\$35.71	\$7.60	\$13.50	\$0.00	\$56.81
	06/01/2019	\$36.58	\$7.60	\$13.50	\$0.00	\$57.68
	12/01/2019	\$37.44	\$7.60	\$13.50	\$0.00	\$58.54
For apprentice rates see "Apprentice- LABORER"						
POWER SHOVEL/DERRICK/TRENCHING MACHINE <i>OPERATING ENGINEERS LOCAL 4</i>	06/01/2017	\$46.38	\$10.00	\$15.25	\$0.00	\$71.63
	12/01/2017	\$47.38	\$10.00	\$15.25	\$0.00	\$72.63
For apprentice rates see "Apprentice- OPERATING ENGINEERS"						
PUMP OPERATOR (CONCRETE) <i>OPERATING ENGINEERS LOCAL 4</i>	06/01/2017	\$46.38	\$10.00	\$15.25	\$0.00	\$71.63
	12/01/2017	\$47.38	\$10.00	\$15.25	\$0.00	\$72.63
For apprentice rates see "Apprentice- OPERATING ENGINEERS"						
PUMP OPERATOR (DEWATERING, OTHER) <i>OPERATING ENGINEERS LOCAL 4</i>	06/01/2017	\$31.86	\$10.00	\$15.25	\$0.00	\$57.11
	12/01/2017	\$32.55	\$10.00	\$15.25	\$0.00	\$57.80
For apprentice rates see "Apprentice- OPERATING ENGINEERS"						
READY-MIX CONCRETE DRIVER <i>TEAMSTERS LOCAL 42</i>	05/01/2017	\$24.21	\$8.49	\$11.54	\$0.00	\$44.24
	04/30/2018	\$24.21	\$8.49	\$11.96	\$0.00	\$44.66
	05/01/2018	\$24.24	\$8.49	\$12.46	\$0.00	\$45.19
	04/30/2019	\$24.24	\$8.49	\$12.92	\$0.00	\$45.65
RECLAIMERS <i>OPERATING ENGINEERS LOCAL 4</i>	06/01/2017	\$45.93	\$10.00	\$15.25	\$0.00	\$71.18
	12/01/2017	\$46.92	\$10.00	\$15.25	\$0.00	\$72.17
For apprentice rates see "Apprentice- OPERATING ENGINEERS"						

Issue Date:	08/24/2017	Wage Request Number:	20170824-010	Page 23 of 32		

Classification	Effective Date	Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
RESIDENTIAL WOOD FRAME (All Other Work) <i>CARPENTERS -ZONE 2 (Residential Wood)</i>	06/01/2016	\$25.32	\$9.80	\$16.82	\$0.00	\$51.94
RESIDENTIAL WOOD FRAME CARPENTER **	04/01/2017	\$26.31	\$7.07	\$7.18	\$0.00	\$40.56
** The Residential Wood Frame Carpenter classification applies only to the construction of new, wood frame residences that do not exceed four stories including the basement. <i>CARPENTERS -ZONE 2 (Residential Wood)</i>	10/01/2017	\$26.93	\$7.07	\$7.18	\$0.00	\$41.18
	04/01/2018	\$27.35	\$7.07	\$7.18	\$0.00	\$41.60
	10/01/2018	\$27.77	\$7.07	\$7.18	\$0.00	\$42.02
	04/01/2019	\$28.20	\$7.07	\$7.18	\$0.00	\$42.45
	10/01/2019	\$28.63	\$7.07	\$7.18	\$0.00	\$42.88

As of 9/1/09 Carpentry work on wood-frame residential WEATHERIZATION projects shall be paid the RESIDENTIAL WOOD FRAME CARPENTER rate.

Apprentice - CARPENTER (Residential Wood Frame) - Zone 2

Effective Date - 04/01/2017

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	60	\$15.79	\$7.07	\$0.00	\$0.00	\$22.86
2	60	\$15.79	\$7.07	\$0.00	\$0.00	\$22.86
3	65	\$17.10	\$7.07	\$7.18	\$0.00	\$31.35
4	70	\$18.42	\$7.07	\$7.18	\$0.00	\$32.67
5	75	\$19.73	\$7.07	\$7.18	\$0.00	\$33.98
6	80	\$21.05	\$7.07	\$7.18	\$0.00	\$35.30
7	85	\$22.36	\$7.07	\$7.18	\$0.00	\$36.61
8	90	\$23.68	\$7.07	\$7.18	\$0.00	\$37.93

Effective Date - 10/01/2017

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	60	\$16.16	\$7.07	\$0.00	\$0.00	\$23.23
2	60	\$16.16	\$7.07	\$0.00	\$0.00	\$23.23
3	65	\$17.50	\$7.07	\$7.18	\$0.00	\$31.75
4	70	\$18.85	\$7.07	\$7.18	\$0.00	\$33.10
5	75	\$20.20	\$7.07	\$7.18	\$0.00	\$34.45
6	80	\$21.54	\$7.07	\$7.18	\$0.00	\$35.79
7	85	\$22.89	\$7.07	\$7.18	\$0.00	\$37.14
8	90	\$24.24	\$7.07	\$7.18	\$0.00	\$38.49

Notes:

Apprentice to Journeyworker Ratio:1:5

RIDE-ON MOTORIZED BUGGY OPERATOR <i>LABORERS - ZONE 2</i>	06/01/2017	\$32.65	\$7.60	\$13.50	\$0.00	\$53.75
	12/01/2017	\$33.28	\$7.60	\$13.50	\$0.00	\$54.38
	06/01/2018	\$34.12	\$7.60	\$13.50	\$0.00	\$55.22
	12/01/2018	\$34.96	\$7.60	\$13.50	\$0.00	\$56.06
	06/01/2019	\$35.83	\$7.60	\$13.50	\$0.00	\$56.93
	12/01/2019	\$36.69	\$7.60	\$13.50	\$0.00	\$57.79

For apprentice rates see "Apprentice- LABORER"

ROLLER/SPREADER/MULCHING MACHINE <i>OPERATING ENGINEERS LOCAL 4</i>	06/01/2017	\$45.93	\$10.00	\$15.25	\$0.00	\$71.18
	12/01/2017	\$46.92	\$10.00	\$15.25	\$0.00	\$72.17

Classification	Effective Date	Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
For apprentice rates see "Apprentice- OPERATING ENGINEERS"						
ROOFER (Inc.Roofer Waterproofing &Roofer Damproofg) ROOFERS LOCAL 33	08/01/2017	\$41.36	\$11.20	\$14.80	\$0.00	\$67.36
	02/01/2018	\$42.51	\$11.20	\$14.80	\$0.00	\$68.51
	08/01/2018	\$43.61	\$11.20	\$14.80	\$0.00	\$69.61
	02/01/2019	\$44.76	\$11.20	\$14.80	\$0.00	\$70.76
Apprentice - ROOFER - Local 33						
Effective Date - 08/01/2017						
Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	50	\$20.68	\$11.20	\$3.44	\$0.00	\$35.32
2	60	\$24.82	\$11.20	\$14.80	\$0.00	\$50.82
3	65	\$26.88	\$11.20	\$14.80	\$0.00	\$52.88
4	75	\$31.02	\$11.20	\$14.80	\$0.00	\$57.02
5	85	\$35.16	\$11.20	\$14.80	\$0.00	\$61.16
Effective Date - 02/01/2018						
Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	50	\$21.26	\$11.20	\$3.44	\$0.00	\$35.90
2	60	\$25.51	\$11.20	\$14.80	\$0.00	\$51.51
3	65	\$27.63	\$11.20	\$14.80	\$0.00	\$53.63
4	75	\$31.88	\$11.20	\$14.80	\$0.00	\$57.88
5	85	\$36.13	\$11.20	\$14.80	\$0.00	\$62.13
Notes: ** 1:5, 2:6-10, the 1:10; Reroofing: 1:4, then 1:1 Step 1 is 2000 hrs.; Steps 2-5 are 1000 hrs. (Hot Pitch Mechanics' receive \$1.00 hr. above ROOFER)						
Apprentice to Journeyworker Ratio:**						
ROOFER SLATE / TILE / PRECAST CONCRETE ROOFERS LOCAL 33	08/01/2017	\$41.61	\$11.20	\$14.80	\$0.00	\$67.61
	02/01/2018	\$42.76	\$11.20	\$14.80	\$0.00	\$68.76
	08/01/2018	\$43.86	\$11.20	\$14.80	\$0.00	\$69.86
	02/01/2019	\$45.01	\$11.20	\$14.80	\$0.00	\$71.01
For apprentice rates see "Apprentice- ROOFER"						
SHEETMETAL WORKER SHEETMETAL WORKERS LOCAL 17 - A	08/01/2017	\$43.83	\$11.45	\$24.03	\$2.38	\$81.69
	02/01/2018	\$44.98	\$11.45	\$24.03	\$2.38	\$82.84

Classification

Effective Date Base Wage Health Pension Supplemental
Unemployment Total Rate

Apprentice - SHEET METAL WORKER - Local 17-A
Effective Date - 08/01/2017

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	40	\$17.53	\$11.45	\$5.61	\$0.00	\$34.59
2	40	\$17.53	\$11.45	\$5.61	\$0.00	\$34.59
3	45	\$19.72	\$11.45	\$10.76	\$1.26	\$43.19
4	45	\$19.72	\$11.45	\$10.76	\$1.26	\$43.19
5	50	\$21.92	\$11.45	\$11.71	\$1.35	\$46.43
6	50	\$21.92	\$11.45	\$11.96	\$1.36	\$46.69
7	60	\$26.30	\$11.45	\$13.61	\$1.54	\$52.90
8	65	\$28.49	\$11.45	\$14.56	\$1.64	\$56.14
9	75	\$32.87	\$11.45	\$16.47	\$1.82	\$62.61
10	85	\$37.26	\$11.45	\$17.87	\$2.00	\$68.58

Effective Date - 02/01/2018

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	40	\$17.99	\$11.45	\$5.24	\$0.00	\$34.68
2	40	\$17.99	\$11.45	\$5.24	\$0.00	\$34.68
3	45	\$20.24	\$11.45	\$10.31	\$1.27	\$43.27
4	45	\$20.24	\$11.45	\$10.31	\$1.27	\$43.27
5	50	\$22.49	\$11.45	\$11.21	\$1.37	\$46.52
6	50	\$22.49	\$11.45	\$11.46	\$1.38	\$46.78
7	60	\$26.99	\$11.45	\$13.02	\$1.56	\$53.02
8	65	\$29.24	\$11.45	\$13.93	\$1.67	\$56.29
9	75	\$33.74	\$11.45	\$15.74	\$1.85	\$62.78
10	85	\$38.23	\$11.45	\$17.05	\$2.03	\$68.76

Notes:

Steps are 6 mos.

Apprentice to Journeyworker Ratio:1:4

SIGN ERECTOR	06/01/2013	\$25.81	\$7.07	\$7.05	\$0.00	\$39.93
PAINTERS LOCAL 35 - ZONE 2						

Classification
Effective Date
Base Wage
Health
Pension
**Supplemental
Unemployment**
Total Rate
Apprentice - SIGN ERECTOR - Local 35 Zone 2
Effective Date - 06/01/2013

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	50	\$12.91	\$7.07	\$0.00	\$0.00	\$19.98
2	55	\$14.20	\$7.07	\$2.45	\$0.00	\$23.72
3	60	\$15.49	\$7.07	\$2.45	\$0.00	\$25.01
4	65	\$16.78	\$7.07	\$2.45	\$0.00	\$26.30
5	70	\$18.07	\$7.07	\$7.05	\$0.00	\$32.19
6	75	\$19.36	\$7.07	\$7.05	\$0.00	\$33.48
7	80	\$20.65	\$7.07	\$7.05	\$0.00	\$34.77
8	85	\$21.94	\$7.07	\$7.05	\$0.00	\$36.06
9	90	\$23.23	\$7.07	\$7.05	\$0.00	\$37.35

Notes:

Steps are 4 mos.

Apprentice to Journeyworker Ratio:1:1

SPECIALIZED EARTH MOVING EQUIP < 35 TONS TEAMSTERS JOINT COUNCIL NO. 10 ZONE B	12/01/2016	\$32.44	\$10.91	\$10.89	\$0.00	\$54.24
---	------------	---------	---------	---------	--------	---------

SPECIALIZED EARTH MOVING EQUIP > 35 TONS TEAMSTERS JOINT COUNCIL NO. 10 ZONE B	12/01/2016	\$32.73	\$10.91	\$10.89	\$0.00	\$54.53
---	------------	---------	---------	---------	--------	---------

SPRINKLER FITTER SPRINKLER FITTERS LOCAL 550 - (Section B) Zone 2	03/01/2017	\$50.47	\$8.77	\$17.20	\$0.00	\$76.44
--	------------	---------	--------	---------	--------	---------

Apprentice - SPRINKLER FITTER - Local 550 (Section B) Zone 2
Effective Date - 03/01/2017

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	35	\$17.66	\$8.77	\$8.70	\$0.00	\$35.13
2	40	\$20.19	\$8.77	\$8.70	\$0.00	\$37.66
3	45	\$22.71	\$8.77	\$8.70	\$0.00	\$40.18
4	50	\$25.24	\$8.77	\$8.70	\$0.00	\$42.71
5	55	\$27.76	\$8.77	\$8.70	\$0.00	\$45.23
6	60	\$30.28	\$8.77	\$10.20	\$0.00	\$49.25
7	65	\$32.81	\$8.77	\$10.20	\$0.00	\$51.78
8	70	\$35.33	\$8.77	\$10.20	\$0.00	\$54.30
9	75	\$37.85	\$8.77	\$10.20	\$0.00	\$56.82
10	80	\$40.38	\$8.77	\$10.20	\$0.00	\$59.35

Notes:

 Apprentice entered prior 9/30/10:
40/45/50/55/60/65/70/75/80/85
Steps are 850 hours

Apprentice to Journeyworker Ratio:1:3

STEAM BOILER OPERATOR OPERATING ENGINEERS LOCAL 4	06/01/2017	\$45.93	\$10.00	\$15.25	\$0.00	\$71.18
--	------------	---------	---------	---------	--------	---------

	12/01/2017	\$46.92	\$10.00	\$15.25	\$0.00	\$72.17
--	------------	---------	---------	---------	--------	---------

For apprentice rates see "Apprentice- OPERATING ENGINEERS"

Classification	Effective Date	Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
TAMPERS, SELF-PROPELLED OR TRACTOR DRAWN <i>OPERATING ENGINEERS LOCAL 4</i>	06/01/2017	\$45.93	\$10.00	\$15.25	\$0.00	\$71.18
	12/01/2017	\$46.92	\$10.00	\$15.25	\$0.00	\$72.17
For apprentice rates see "Apprentice- OPERATING ENGINEERS"						
TELECOMMUNICATION TECHNICIAN <i>ELECTRICIANS LOCAL 103</i>	03/01/2017	\$36.25	\$13.00	\$15.60	\$0.00	\$64.85
	09/01/2017	\$36.96	\$13.00	\$15.62	\$0.00	\$65.58
	03/01/2018	\$37.61	\$13.00	\$15.93	\$0.00	\$66.54
	09/01/2018	\$38.51	\$13.00	\$15.96	\$0.00	\$67.47
	03/01/2019	\$39.40	\$13.00	\$15.98	\$0.00	\$68.38

Apprentice - TELECOMMUNICATION TECHNICIAN - Local 103

Effective Date - 03/01/2017

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	40	\$14.50	\$13.00	\$0.44	\$0.00	\$27.94
2	40	\$14.50	\$13.00	\$0.44	\$0.00	\$27.94
3	45	\$16.31	\$13.00	\$12.54	\$0.00	\$41.85
4	45	\$16.31	\$13.00	\$12.54	\$0.00	\$41.85
5	50	\$18.13	\$13.00	\$12.81	\$0.00	\$43.94
6	55	\$19.94	\$13.00	\$13.09	\$0.00	\$46.03
7	60	\$21.75	\$13.00	\$13.37	\$0.00	\$48.12
8	65	\$23.56	\$13.00	\$13.65	\$0.00	\$50.21
9	70	\$25.38	\$13.00	\$13.93	\$0.00	\$52.31
10	75	\$27.19	\$13.00	\$14.21	\$0.00	\$54.40

Effective Date - 09/01/2017

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	40	\$14.78	\$13.00	\$0.44	\$0.00	\$28.22
2	40	\$14.78	\$13.00	\$0.44	\$0.00	\$28.22
3	45	\$16.63	\$13.00	\$12.55	\$0.00	\$42.18
4	45	\$16.63	\$13.00	\$12.55	\$0.00	\$42.18
5	50	\$18.48	\$13.00	\$12.82	\$0.00	\$44.30
6	55	\$20.33	\$13.00	\$13.10	\$0.00	\$46.43
7	60	\$22.18	\$13.00	\$13.39	\$0.00	\$48.57
8	65	\$24.02	\$13.00	\$13.66	\$0.00	\$50.68
9	70	\$25.87	\$13.00	\$13.95	\$0.00	\$52.82
10	75	\$27.72	\$13.00	\$14.22	\$0.00	\$54.94

Notes:

Apprentice to Journeyworker Ratio:1:1

TERRAZZO FINISHERS <i>BRICKLAYERS LOCAL 3 - MARBLE & TILE</i>	02/01/2017	\$49.70	\$10.75	\$19.22	\$0.00	\$79.67
--	------------	---------	---------	---------	--------	---------

Classification	Effective Date	Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
----------------	----------------	-----------	--------	---------	------------------------------	------------

Apprentice - TERRAZZO FINISHER - Local 3 Marble & Tile

Effective Date - 02/01/2017

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	50	\$24.85	\$10.75	\$19.22	\$0.00	\$54.82
2	60	\$29.82	\$10.75	\$19.22	\$0.00	\$59.79
3	70	\$34.79	\$10.75	\$19.22	\$0.00	\$64.76
4	80	\$39.76	\$10.75	\$19.22	\$0.00	\$69.73
5	90	\$44.73	\$10.75	\$19.22	\$0.00	\$74.70

Notes:

Apprentice to Journeyworker Ratio:1:3

TEST BORING DRILLER <i>LABORERS - FOUNDATION AND MARINE</i>	12/01/2016	\$37.70	\$7.60	\$14.35	\$0.00	\$59.65
For apprentice rates see "Apprentice- LABORER"						
TEST BORING DRILLER HELPER <i>LABORERS - FOUNDATION AND MARINE</i>	12/01/2016	\$36.42	\$7.60	\$14.35	\$0.00	\$58.37
For apprentice rates see "Apprentice- LABORER"						
TEST BORING LABORER <i>LABORERS - FOUNDATION AND MARINE</i>	12/01/2016	\$36.30	\$7.60	\$14.35	\$0.00	\$58.25
For apprentice rates see "Apprentice- LABORER"						
TRACTORS/PORTABLE STEAM GENERATORS <i>OPERATING ENGINEERS LOCAL 4</i>	06/01/2017	\$45.93	\$10.00	\$15.25	\$0.00	\$71.18
	12/01/2017	\$46.92	\$10.00	\$15.25	\$0.00	\$72.17
For apprentice rates see "Apprentice- OPERATING ENGINEERS"						
TRAILERS FOR EARTH MOVING EQUIPMENT <i>TEAMSTERS JOINT COUNCIL NO. 10 ZONE B</i>	12/01/2016	\$33.02	\$10.91	\$10.89	\$0.00	\$54.82
TUNNEL WORK - COMPRESSED AIR <i>LABORERS (COMPRESSED AIR)</i>	12/01/2016	\$48.58	\$7.60	\$14.75	\$0.00	\$70.93
For apprentice rates see "Apprentice- LABORER"						
TUNNEL WORK - COMPRESSED AIR (HAZ. WASTE) <i>LABORERS (COMPRESSED AIR)</i>	12/01/2016	\$50.58	\$7.60	\$14.75	\$0.00	\$72.93
For apprentice rates see "Apprentice- LABORER"						
TUNNEL WORK - FREE AIR <i>LABORERS (FREE AIR TUNNEL)</i>	12/01/2016	\$40.65	\$7.60	\$14.75	\$0.00	\$63.00
For apprentice rates see "Apprentice- LABORER"						
TUNNEL WORK - FREE AIR (HAZ. WASTE) <i>LABORERS (FREE AIR TUNNEL)</i>	12/01/2016	\$42.65	\$7.60	\$14.75	\$0.00	\$65.00
For apprentice rates see "Apprentice- LABORER"						
VAC-HAUL <i>TEAMSTERS JOINT COUNCIL NO. 10 ZONE B</i>	12/01/2016	\$32.44	\$10.91	\$10.89	\$0.00	\$54.24
WAGON DRILL OPERATOR <i>LABORERS - ZONE 2</i>	06/01/2017	\$32.65	\$7.60	\$13.50	\$0.00	\$53.75
	12/01/2017	\$33.28	\$7.60	\$13.50	\$0.00	\$54.38
	06/01/2018	\$34.12	\$7.60	\$13.50	\$0.00	\$55.22
	12/01/2018	\$34.96	\$7.60	\$13.50	\$0.00	\$56.06
	06/01/2019	\$35.83	\$7.60	\$13.50	\$0.00	\$56.93
	12/01/2019	\$36.69	\$7.60	\$13.50	\$0.00	\$57.79
For apprentice rates see "Apprentice- LABORER"						

Classification	Effective Date	Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
WASTE WATER PUMP OPERATOR <i>OPERATING ENGINEERS LOCAL 4</i>	06/01/2017	\$46.38	\$10.00	\$15.25	\$0.00	\$71.63
	12/01/2017	\$47.38	\$10.00	\$15.25	\$0.00	\$72.63
For apprentice rates see "Apprentice- OPERATING ENGINEERS"						
WATER METER INSTALLER <i>PLUMBERS & GASFITTERS LOCAL 12 (Local 138)</i>	03/01/2017	\$48.61	\$11.32	\$15.46	\$0.00	\$75.39
For apprentice rates see "Apprentice- PLUMBER/PIPEFITTER" or "PLUMBER/GASFITTER"						
Outside Electrical - East						
CABLE TECHNICIAN (Power Zone) <i>OUTSIDE ELECTRICAL WORKERS - EAST LOCAL 104</i>	08/28/2016	\$26.61	\$7.50	\$1.80	\$0.00	\$35.91
	09/03/2017	\$27.14	\$7.75	\$1.81	\$0.00	\$36.70
For apprentice rates see "Apprentice- LINEMAN"						
CABLEMAN (Underground Ducts & Cables) <i>OUTSIDE ELECTRICAL WORKERS - EAST LOCAL 104</i>	08/28/2016	\$37.70	\$7.50	\$8.87	\$0.00	\$54.07
	09/03/2017	\$38.45	\$7.75	\$9.53	\$0.00	\$55.73
For apprentice rates see "Apprentice- LINEMAN"						
DRIVER / GROUNDMAN CDL <i>OUTSIDE ELECTRICAL WORKERS - EAST LOCAL 104</i>	08/28/2016	\$31.05	\$7.50	\$8.89	\$0.00	\$47.44
	09/03/2017	\$31.66	\$7.75	\$9.44	\$0.00	\$48.85
For apprentice rates see "Apprentice- LINEMAN"						
DRIVER / GROUNDMAN -Inexperienced (<2000 Hrs) <i>OUTSIDE ELECTRICAL WORKERS - EAST LOCAL 104</i>	08/28/2016	\$24.39	\$7.50	\$1.73	\$0.00	\$33.62
	09/03/2017	\$24.88	\$7.75	\$1.75	\$0.00	\$34.38
For apprentice rates see "Apprentice- LINEMAN"						
EQUIPMENT OPERATOR (Class A CDL) <i>OUTSIDE ELECTRICAL WORKERS - EAST LOCAL 104</i>	08/28/2016	\$37.70	\$7.50	\$12.95	\$0.00	\$58.15
	09/03/2017	\$38.45	\$7.75	\$13.61	\$0.00	\$59.81
For apprentice rates see "Apprentice- LINEMAN"						
EQUIPMENT OPERATOR (Class B CDL) <i>OUTSIDE ELECTRICAL WORKERS - EAST LOCAL 104</i>	08/28/2016	\$33.26	\$7.50	\$9.63	\$0.00	\$50.39
	09/03/2017	\$33.92	\$7.75	\$10.21	\$0.00	\$51.88
For apprentice rates see "Apprentice- LINEMAN"						
GROUNDMAN <i>OUTSIDE ELECTRICAL WORKERS - EAST LOCAL 104</i>	08/28/2016	\$24.39	\$7.50	\$1.73	\$0.00	\$33.62
	09/03/2017	\$24.88	\$7.75	\$1.75	\$0.00	\$34.38
For apprentice rates see "Apprentice- LINEMAN"						
GROUNDMAN -Inexperienced (<2000 Hrs.) <i>OUTSIDE ELECTRICAL WORKERS - EAST LOCAL 104</i>	08/28/2016	\$19.96	\$7.50	\$1.60	\$0.00	\$29.06
	09/03/2017	\$20.35	\$7.75	\$1.61	\$0.00	\$29.71
For apprentice rates see "Apprentice- LINEMAN"						
JOURNEYMAN LINEMAN <i>OUTSIDE ELECTRICAL WORKERS - EAST LOCAL 104</i>	08/28/2016	\$44.35	\$7.50	\$15.83	\$0.00	\$67.68
	09/03/2017	\$45.23	\$7.75	\$16.61	\$0.00	\$69.59

Classification	Effective Date	Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
----------------	----------------	-----------	--------	---------	---------------------------	------------

Apprentice - LINEMAN (Outside Electrical) - East Local 104

Effective Date - 08/28/2016

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	60	\$26.61	\$7.50	\$3.30	\$0.00	\$37.41
2	65	\$28.83	\$7.50	\$3.36	\$0.00	\$39.69
3	70	\$31.05	\$7.50	\$3.43	\$0.00	\$41.98
4	75	\$33.26	\$7.50	\$5.00	\$0.00	\$45.76
5	80	\$35.48	\$7.50	\$5.06	\$0.00	\$48.04
6	85	\$37.70	\$7.50	\$5.13	\$0.00	\$50.33
7	90	\$39.92	\$7.50	\$7.20	\$0.00	\$54.62

Effective Date - 09/03/2017

Step	percent	Apprentice Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
1	60	\$27.14	\$7.75	\$3.31	\$0.00	\$38.20
2	65	\$29.40	\$7.75	\$3.38	\$0.00	\$40.53
3	70	\$31.66	\$7.75	\$3.45	\$0.00	\$42.86
4	75	\$33.92	\$7.75	\$5.02	\$0.00	\$46.69
5	80	\$36.18	\$7.75	\$5.09	\$0.00	\$49.02
6	85	\$38.45	\$7.75	\$5.15	\$0.00	\$51.35
7	90	\$40.71	\$7.75	\$7.22	\$0.00	\$55.68

Notes:

Apprentice to Journeyworker Ratio:1:2

TELEDATA CABLE SPLICER OUTSIDE ELECTRICAL WORKERS - EAST LOCAL 104	01/01/2016	\$28.98	\$4.25	\$3.12	\$0.00	\$36.35
---	------------	---------	--------	--------	--------	---------

TELEDATA LINEMAN/EQUIPMENT OPERATOR OUTSIDE ELECTRICAL WORKERS - EAST LOCAL 104	01/01/2016	\$27.31	\$4.25	\$3.07	\$0.00	\$34.63
--	------------	---------	--------	--------	--------	---------

TELEDATA WIREMAN/INSTALLER/TECHNICIAN OUTSIDE ELECTRICAL WORKERS - EAST LOCAL 104	01/01/2016	\$27.31	\$4.25	\$3.07	\$0.00	\$34.63
--	------------	---------	--------	--------	--------	---------

TREE TRIMMER OUTSIDE ELECTRICAL WORKERS - EAST LOCAL 104	01/31/2016	\$18.51	\$3.55	\$0.00	\$0.00	\$22.06
---	------------	---------	--------	--------	--------	---------

This classification applies only to tree work done: (a) for a utility company, R.E.A. cooperative, or railroad or coal mining company, and (b) for the purpose of operating, maintaining, or repairing the utility company's equipment, and (c) by a person who is using hand or mechanical cutting methods and is not on the ground. This classification does not apply to wholesale tree removal.

TREE TRIMMER GROUNDMAN OUTSIDE ELECTRICAL WORKERS - EAST LOCAL 104	01/31/2016	\$16.32	\$3.55	\$0.00	\$0.00	\$19.87
---	------------	---------	--------	--------	--------	---------

This classification applies only to tree work done: (a) for a utility company, R.E.A. cooperative, or railroad or coal mining company, and (b) for the purpose of operating, maintaining, or repairing the utility company's equipment, and (c) by a person who is using hand or mechanical cutting methods and is on the ground. This classification does not apply to wholesale tree removal.

Classification	Effective Date	Base Wage	Health	Pension	Supplemental Unemployment	Total Rate
----------------	----------------	-----------	--------	---------	------------------------------	------------

Additional Apprentice Information:

Minimum wage rates for apprentices employed on public works projects are listed above as a percentage of the pre-determined hourly wage rate established by the Commissioner under the provisions of the M.G.L. c. 149, ss. 26-27D. Apprentice ratios are established by the Division of Apprenticeship Training pursuant to M.G.L. c. 23, ss. 11E-11L.

All apprentices must be registered with the Division of Apprenticeship Training in accordance with M.G.L. c. 23, ss. 11E-11L.

All steps are six months (1000 hours.)
Ratios are expressed in allowable number of apprentices to journeymen or fraction thereof, unless otherwise specified.

- ** Multiple ratios are listed in the comment field.
- *** APP to JM; 1:1, 2:2, 2:3, 3:4, 4:4, 4:5, 4:6, 5:7, 6:7, 6:8, 6:9, 7:10, 8:10, 8:11, 8:12, 9:13, 10:13, 10:14, etc.
- **** APP to JM; 1:1, 1:2, 2:3, 2:4, 3:5, 4:6, 4:7, 5:8, 6:9, 6:10, 7:11, 8:12, 8:13, 9:14, 10:15, 10:16, etc.