

City of Salem, MA
FY18 Roadway Pavement Rehabilitation Project
List of Streets

ward	street	from	to
3	JEFFERSON AVE	MARGIN ST	CLEVELAND ST
2	BROWN ST	WASHINGTON SQ W	ST PETERS ST
2	KIMBALL CT	BROWN ST	END
2	MALL ST	WASHINGTON SQR N	BRIDGE ST
1	ESSEX ST	WASHINGTON SQR E	WASHINGTON SQR W
1	HODGES CT	DERBY ST	ESSEX ST
1	HERBERT ST	DERBY ST	ESSEX ST
2	BOARDMAN ST	WEBB ST	WASHINGTON SQR E
2	BRIGGS ST	WEBB ST	WASHINGTON SQR E
2	ANDREW ST	WEBB ST	WASHINGTON SQR E
2	PLEASANT ST AVE	PLEASANT ST	WINTER ST
6	TREMONT ST	GROVE ST	PEABODY CL
2	GIFFORD CT	CARPENTER ST	DEAD END
6	FRANKLIN CT	FOSTER ST	FRANKLIN ST
4	OBER ST	BUTLER ST	WALL ST
4	UGO RD	BUENA VISTA AVE	OUTLOOK AVE
5	CLIFF STREET	CLIFTON AVE	OCEAN AVE
5	GENEVA ST	ROSLYN ST	HANCOCK ST
3	HORTON ST	OLD RD	LAURENT RD
7	KELLEY RD	CEDARCREST RD	END
7	RAYMOND RD	LORING AVE	RAYMOND AVE
7	RAYMOND RD	RAYMOND AVE	LAFAYETTE
6	EVERETT ST	DEARBORN ST	END
1	PRINCE ST	HARBOR ST	LEAVITT ST
1	PEABODY ST	LAFAYETTE ST	CONGRESS ST
4	PROCTOR ST	LANGDON ST	POPE ST
2	MONROE ST	ESSEX ST	FEDERAL ST
1	HARDY ST	ESSEX ST	END
1	BENTLEY ST	ESSEX ST	DERBY ST
1	DANIELS ST	DANIELS ST CT	DERBY ST
1	DANIELS ST CT	KOSCIUSKO ST	DANIELS ST
1	KOSCIUSKO ST	DERBY ST	DANIELS ST CT
1	COLLINS ST	WEBB ST	ARBELLA ST
5	SUMMIT AVE	CLIFTON AVE	WILLOW AVE
5	SUMMIT AVE	WILLOW AVE	LEACH ST
1	DERBY	ORANGE ST	FORT AVE
4	CHERRY HILL AVE	CROWDIS ST	HIGHLAND AVE
7	CEDARCREST RD	CEDAR HILL RD	CEDARCREST AVE
7	CEDAR HILL RD	INTERVALE RD	CEDARCREST RD

typical squence of work for paving:

1. work starts with the existing top 2-inches of pavement removed by grinding.
2. leveling (thin layer of pavement) course installed to make roadway smooth for vehicular traffic.
3. structures (manhole frames and covers and water/gas boxes) are adjusted to final pavement grades
4. if necessary, utility services (gas, electric, water, sewer) are repaired or replaced
5. work is completed with the installation of the final top coarse of pavement.
6. work is typically completed within 4 weeks of starting, weather permitting.